

A TREATISE ON  
ANALYTICAL STATICS

Symington

CAMBRIDGE UNIVERSITY PRESS WAREHOUSE,

C. F. CLAY, MANAGER.

London: FETTER LANE, E.C.

Edinburgh: 100, PRINCES STREET.



Berlin: A. ASHER AND CO.

Leipzig: F. A. BROCKHAUS.

New York: G. P. PUTNAM'S SONS.

Bombay and Calcutta: MACMILLAN AND CO., LTD.

[*All Rights reserved*]

# ANALYTICAL STATICS

WITH NUMEROUS EXAMPLES

BY

EDWARD JOHN ROUTH,

Sc.D., LL.D., M.A., F.R.S., &c.

VOLUME I

*SECOND EDITION*

RECEIVED  
PHYSICAL DEPARTMENT OF TECHNOLOGY  
JAN 10 1909

Cambridge:  
at the University Press

1909

531.2.

656

v. 1

*First Edition* 1891

*Second Edition* 1896

*Reprinted* 1909

CAMBRIDGE: PRINTED BY JOHN CLAY, M.A.  
AT THE UNIVERSITY PRESS.



## PREFACE

**D**URING many years it has been my duty and pleasure to give courses of lectures on various Mathematical subjects to successive generations of students. The course on Statics has been made the groundwork of the present treatise. It has however been necessary to make many additions; for in a treatise all parts of the subject must be discussed in a connected form, while in a series of lectures a suitable choice has to be made.

A portion only of the science of Statics has been included in this volume. It is felt that such subjects as Attractions, Astatics, and the Bending of rods could not be adequately treated at the end of a treatise without either making the volume too bulky or requiring the other parts to be unduly curtailed. These remaining portions appear in the second volume.

In order to learn Statics it is essential to the student to work numerous examples. Besides some of my own construction, I have collected a large number from the University and College Examination papers. Some of these are so good as to deserve to rank among the theorems of the science rather than among the examples. Solutions have been given to many of the examples, sometimes at length and in other cases in the form of hints when these appeared sufficient.

I have endeavoured to refer each result to its original author. I have however found that it is a very difficult task to effect this

with any completeness. The references will show that I have searched many of the older books and memoirs as well as some of those of recent date to discover the first mention of a theorem.

In this edition I have made many additions and have also omitted several things which on after consideration appeared to be of minor importance. The explanations also have been simplified wherever there appeared to be any obscurity. For the convenience of reference I have retained the order of the articles as far as that was possible.

The latter part of the chapter on forces in three dimensions has been enlarged by the addition of several theorems and the portions on five and six forces re-arranged. The chapter on graphical statics also has been almost entirely rewritten.

An index has been added which it is hoped will be found useful.

EDWARD J. ROUTH.

PETERHOUSE,  
*May*, 1896.

# CONTENTS

## CHAPTER I.

### THE PARALLELOGRAM OF FORCES.

PARTS.		PAGES
1—12.	Elementary considerations on forces, &c. . . . .	1—7
13—18.	Dynamical and statical laws . . . . .	7—11
19—21.	Rigid bodies . . . . .	12
22—23.	Resultant forces . . . . .	13
24—30.	Parallelogram of forces . . . . .	14—17
31.	Historical summary . . . . .	17—18

## CHAPTER II.

### FORCES ACTING AT A POINT.

2—40.	Geometrical Method. Triangle, Polygon and Parallelepiped of forces. Three methods of resolution . . . . .	19—23
41—46.	Method of analysis. Resultant of any number of forces . . . . .	23—26
47.	Forces which act normally to the faces of a polyhedron . . . . .	26
48—49.	Theorems on Determinants . . . . .	26—27
50.	Oblique axes . . . . .	27
51—53.	The mean centre. Its use in resolving and compounding forces . . . . .	27—31
54—61.	Equilibrium of a particle. Smooth curves and surfaces . . . . .	31—34
62—69.	The principle of Work . . . . .	34—38
70—74.	Astatic equilibrium. The astatic triangle of forces . . . . .	38—40
75—77.	Stable and unstable equilibrium. A free body under two and three forces . . . . .	40—42

## CHAPTER III.

### PARALLEL FORCES.

ARTS.		PAGES
78—81.	Resultant of two and any number of parallel forces . . . . .	43—45.
82—84.	The centre of parallel forces . . . . .	45—46.
85—86.	Conditions of equilibrium . . . . .	46—48.
87.	A body suspended from a fixed point . . . . .	48—50.
88.	A body resting on a plane . . . . .	50—51.
89—103.	Theory of couples . . . . .	51—60.

## CHAPTER IV.

### FORCES IN TWO DIMENSIONS.

104—108.	Resultant of any number of forces . . . . .	61—63.
109—115.	Conditions of equilibrium . . . . .	63—65.
116—117.	Varignon's theorem . . . . .	65—66.
118—120.	The single resultant force or couple . . . . .	66—68.
121—129.	The solution of problems. Constrained rods, discs, spheres, &c. See also note at page 376 . . . . .	68—77.
130.	Equilibrium of four repelling or attracting particles . . . . .	77.
131—133.	Reactions at joints. Theorems of Euler, Fuss, &c. A note on a property of triangles . . . . .	77—84.
134—140.	Polygon of heavy rods. Funicular polygon. See also Arts. 356—357 . . . . .	84—87.
141.	Examples . . . . .	87—89.
142—147.	Reactions at rigid connections. Bending moment. Beam with weights, diagram of stress. Various examples . . . . .	89—94.
148—149.	Indeterminate problems . . . . .	94—97.
150—152.	Frameworks Conditions of stiffness . . . . .	97—99.
153.	Equations of equilibrium of a body or framework derived from those of a single particle. See foot-note . . . . .	99.
154—155.	Sufficiency of the equations to find the reactions when the frame is just stiff. Exceptional cases. See also Arts. 235, 236. *Supplementary equations when the frame is over stiff . . . . .	99—101.
156—163.	Astatics. Astatic resultant. Centre of forces, &c. . . . .	101—104.

## CHAPTER V.

### ON FRICTION.

164—171.	Laws of friction. The friction force and friction couple. The angle of friction and limiting friction . . . . .	105—110.
172—175.	Particle constrained by a rough curve, surface, &c. The cone of friction . . . . .	110—112.

ARTS.	PAGES
176—178. Problems on friction when the direction is known. Different methods of solution. Various examples . . .	112—120
179. Wheel and axle with friction . . . . .	120—122
180—187. Friction in unknown directions. Two methods . . .	122—127
188—190. Examples. Rotation of bodies on a finite and an infinite number of supports. String of particles, &c. . . .	127—134

## CHAPTER VI.

### THE PRINCIPLE OF WORK.

191—195. Proof of the principle . . . . .	135—138
196. The forces which do not appear in the equation of work . . .	138—140
197. Work of a bent string. See also Art. 493 . . . . .	140—142
198. Infinite forces . . . . .	142
199. Converse of the principle of work . . . . .	142—143
200—201. Initial motion . . . . .	143
202—204. Equations of equilibrium derived from work . . . .	143—146
205. Examples on the principle . . . . .	146—148
206—213. The work function . . . . .	148—152
214—225. Stable and unstable equilibrium. Analytical method . .	153—159
226—228. Attracting or repelling atoms . . . . .	159—161
229—234. Determination of stress in a simply stiff frame. Examples	161—168
235—236. Abnormal deformations . . . . .	168—169
237—238. Indeterminate tensions. Theorems of Crofton and Lévy. See also Art. 368 . . . . .	169—170
239—243. Geometrical method of determining the stability of a body. The circle of stability . . . . .	170—174
244—246. Rocking stones. Examples . . . . .	175—177
247—254. Rocking stones, spherical and not spherical to a second approximation in two and three dimensions . . . .	177—182
255—256. Lagrange's proof of the principle of virtual work . . .	182—183

## CHAPTER VII.

### FORCES IN THREE DIMENSIONS.

257—259. Resultants of a system of forces. Conditions of equilibrium. See also Art. 331 . . . . .	184—186
260—262. Components of a force . . . . .	186—187
263—267. Moment of a force . . . . .	188—190
268—269. Problems on equilibrium. Pressures on an axis, rods, spheres, rod on wall, curtain ring, &c. . . . .	190—194
270. Poincot's central axis . . . . .	194—195
271—278. The equivalent wrench. Analytical method . . . .	195—199
279—283. The Invariants . . . . .	199—201

ARTS.		PAGES
284—286.	Equivalent wrench of two wrenches or forces . . . . .	202—203
287—291.	The Cylindroid . . . . .	203—205
292—293.	Work of a wrench . . . . .	205—207
294—297.	Reciprocal screws . . . . .	207—208
298—302.	The Nul plane . . . . .	208—209
303—314.	Conjugate forces . . . . .	209—214
315.	Theorems on three forces . . . . .	214
316—319.	Four forces. The hyperboloid. Forces acting normally to the faces of a tetrahedron. Forces normal to a surface . . . . .	214—218
320—323.	Five forces. The two directors . . . . .	218—220
324—330.	Six Forces, <i>analytical view</i> . The polar plane. Lines in involution and the two determinants. Resolution of a force along six arbitrary lines . . . . .	220—224
331—333.	The sufficiency of the general conditions of equilibrium . . . . .	224—225
334—338.	Six Forces, <i>geometrical view</i> . The transversals. Theorems on the fifth and sixth force . . . . .	225—227
339.	Tetrahedral coordinates . . . . .	227—228

## CHAPTER VIII.

### GRAPHICAL STATICS.

340.	<i>Analytical view</i> . Reciprocal figures . . . . .	229—230
341—342.	Theorems of Maxwell and Cremona . . . . .	230—231
343—345.	Example of Maxwell's theorem . . . . .	231—232
346—348.	Mechanical property of reciprocal figures. Figures which have no reciprocals . . . . .	232—233
349—350.	Methods of lettering and drawing reciprocal figures . . . . .	233—234
351.	Euler's theorems . . . . .	235
352—355.	<i>Statical view</i> . Construction of the resultant force. Conditions of equilibrium . . . . .	236—239
356.	Parallel forces. Funicular polygon. See also Arts. 134—140 . . . . .	239
357—360.	Various graphical constructions . . . . .	239—241
361—362.	Graphical construction of stress problems . . . . .	241—242
363—365.	Frameworks . . . . .	243—245
366—367.	Method of sections . . . . .	245—246
368.	Indeterminate tensions. See Arts. 237, 238 . . . . .	246—247
369—371.	Line of pressure. Theorems . . . . .	247—249
372.	Examples . . . . .	249—250

## CHAPTER IX.

### CENTRE OF GRAVITY.

373—379.	Definitions and fundamental equations . . . . .	251—253
380—382.	Working rule. Examples . . . . .	254—255
383—386.	Area and perimeter of a triangle . . . . .	255—257
387—388.	Quadrilateral and pentagonal areas . . . . .	257—259

389—395.	Tetrahedron. Volume, faces, and edges. Pyramid, cone and double tetrahedra. Isosceles tetrahedron . . . . .	259—263
396—399.	Centres of gravity of arcs. Circle, catenary, cycloid, &c. . . . .	263—264
400—402.	Centres of gravity of circular areas . . . . .	264—265
403—408.	Geometrical and analytical projection of areas . . . . .	265—268
409—412.	Centre of gravity of any area . . . . .	268—271
413—417.	Theorems of Pappus . . . . .	271—274
418—419.	Areas on the surface of a right cone . . . . .	274—276
420—424.	Areas on a sphere. Theory of maps . . . . .	276—279
425—427.	Surfaces and solids of revolution. Moments and products of inertia . . . . .	279—281
428—430.	Ellipsoidal volumes and shells . . . . .	281—283
431—432.	Any surfaces and volumes . . . . .	283—285
433—434.	Heterogeneous bodies. Octant of ellipsoid. Triangular area, &c. . . . .	285—287
435—438.	Lagrange's two theorems . . . . .	287—289
439—441.	Applications to pure geometry . . . . .	289—291

## CHAPTER X.

### ON STRINGS.

442—445.	Catenary. Equations and properties . . . . .	292—295
446—448.	Problems on free and constrained catenaries . . . . .	295—301
449.	Stability of catenaries . . . . .	302
450—453.	Heterogeneous chains. Cycloid, parabola, and the catenary of equal strength . . . . .	302—306
454.	String under any forces. General intrinsic equations . . . . .	306—307
455—456.	General Cartesian equations . . . . .	308—309
457—458.	Constrained strings. Light string on a smooth curve. Problem of Bernoulli . . . . .	309—310
459—462.	Heavy string on a smooth curve. The anti-centre and statical directrix. Examples . . . . .	310—314
463—466.	Light string on a rough curve. Rough pegs . . . . .	315—317
467—471.	Heavy string on a rough curve . . . . .	317—320
472—473.	Endless strings. Strings which just fit a curve . . . . .	321—323
474—477.	Central forces. Various laws of force. Kinetic analogy. Two centres . . . . .	323—328
478—480.	String on a smooth surface. Cartesian and Intrinsic equations. Various theorems. Case of no forces . . . . .	328—331
481.	String on a surface of revolution . . . . .	331—332
482.	Spherical catenary . . . . .	332—333
483.	String on a cylinder . . . . .	333—335
484.	String on a right cone . . . . .	335
485—486.	String on a rough surface . . . . .	335—337
487.	Minimum force to move a heavy circular string on a rough plane, and other problems . . . . .	337—338

ARTS.		PAGES
488.	Calculus of variations . . . . .	338—339
489—491.	Elastic string. Hooke's law . . . . .	339—340
492.	Heavy elastic string suspended by one end . . . . .	341—342
493.	Work of an elastic string . . . . .	342—343
494.	Heavy elastic string on a smooth curve. The statical directrix . . . . .	343—344
495.	Light elastic string on a rough curve. Rough pegs . . . . .	344—345
496—499.	Elastic string under any forces . . . . .	345—346
500—501.	Elastic catenary . . . . .	346—347

## CHAPTER XI.

### THE MACHINES.

502—505.	Mechanical advantage. Efficiency . . . . .	348—349
506—516.	The Lever. Conditions of equilibrium. Pressure on axis. Various kinds of Levers. For lever under any forces see Art. 268; rough axis Art. 179 . . . . .	349—353
517.	Roberval's balance . . . . .	353—354
518—520.	The common balance . . . . .	354—355
521—524.	The common and Danish Steelyard . . . . .	356—358
525—528.	The single pulley . . . . .	358—359
529—530.	The system of pulleys with one rope . . . . .	359—361
531.	Rigidity of cords . . . . .	361
532—536.	Systems of pulleys with several ropes . . . . .	361—365
537—539.	The inclined plane . . . . .	366—368
540—543.	The wheel and axle. The differential axle . . . . .	368—369
544—546.	Toothed wheels . . . . .	369—371
547—549.	The wedge . . . . .	371—373
550—553.	The screw . . . . .	373—375

NOTE ON TWO THEOREMS IN CONICS ASSUMED IN ARTS. 126, 127 . . . . .	376—378
--	---------

INDEX . . . . .	379—391
-----------------	---------

## CONTENTS OF VOLUME II.

### ATTRACTIONS.

### THE BENDING OF RODS.

### ASTATICS.



## CHAPTER I

### THE PARALLELOGRAM OF FORCES

1. THE science of Mechanics treats of the action of forces on bodies. Under the influence of these forces the bodies may either be in motion or remain at rest. That part of mechanics which treats of the motion of bodies is called Dynamics. That part of mechanics in which the bodies are at rest is called Statics.

If the determination of the motion of bodies under given forces could be completely and easily solved, there would be no obvious advantage in this division of the subject into two parts. It is clear that statics is only that particular case of dynamics in which the motions of the bodies are equated to zero. But the particular case in which the motion is zero presents itself as a much easier problem than the general one. At the same time this particular case is one of great importance. It is important not merely for the intrinsic value of its own results but because these are found to assist in the solution of the general case by the help of a theorem due to D'Alembert. It has therefore been generally found convenient to lead up to the general problem of dynamics by considering first the particular case of statics.

2. Since statics is a particular case of dynamics we may begin by discussing the first principles of the more general science. We should consider how the mass of a body is measured, how the velocity and acceleration of any particle are affected by the action of forces. The general principles having been obtained we may then descend to the particular case by putting these velocities equal to zero. In this way the relationship of the two great branches of mechanics is clearly seen and their results are founded on a common basis.

3. There is another way of studying statics which has its own advantages. We might begin by assuming some simple axioms relating to the action of forces on bodies without introducing any properties of motion. In this method we introduce no terms or principles but those which are continually used in statics, leaving to dynamics the study of those terms which are peculiar to it.

Whether this is an advantageous method of studying statics or not depends on the choice of the fundamental axioms. In the first place they must be simple in character. In the second place they must be easily verified by experiment. For example we might take as an axiom the proposition usually called the parallelogram of forces or we might, after Lagrange, start from the principle of work. But neither of these principles satisfies the conditions just mentioned, for they do not seem sufficiently obvious on first acquaintance to command assent.

If we found the two parts of mechanics on a common basis, that basis must be broader than that which is necessary to support merely the principles of statics. We have to assume at once all the experimental results required in mechanics instead of only those required in statics. Now there is an advantage in introducing the fundamental experiments in the order in which they are wanted. We thus more easily distinguish the special necessity for each, we see more clearly what results are deduced from each experiment. The order of proceeding would be to begin with such elementary axioms about forces as will enable us to study their composition and resolution. Presently other experimental results are introduced as they are required and finally when the general problem of dynamics is reached, the whole of the fundamental axioms are summed up and consolidated.

In a treatise on statics it is necessary to consider both these methods. We shall examine first how the elementary principles of statics are connected with the axioms required for the more general problem of dynamics, and secondly how they may be made to stand on a base of their own.

4. In mechanics we have to treat of the action of forces on bodies. The term force is defined by Newton in the following terms.

An impressed force is an action exerted on a body in order to

change its state either of rest or of uniform motion in a straight line.

**5. Characteristics of a Force.** When a force acts on a body the action exerted has (1) a point of application, (2) a direction in space, (3) magnitude.

Two forces are said to be equal in magnitude when, if applied to the same particle in opposite directions, they balance each other. The magnitudes of forces are measured by taking some one force as a unit, then a force which will balance two unit forces is represented by two units and so on.

**6.** The simplest appeal to our experience will convince us that many at least of the ordinary forces of nature possess these three characteristics. If force be exerted on a body by pulling a string attached to it, the point of attachment of the string is the point of application, and the direction of the string is the direction of the force. The existence of the third element of a force is shown by the fact that we may exert different pulls on the string.

All the causes which produce or tend to produce motion in a body are not known. But as they are studied, it is found that they can be analysed into simpler causes, and these simpler causes are seen to have the three characteristics of a force. If there be any causes of motion which cannot be thus analysed, such causes are not considered as forces whose effects are to be discussed in the science of statics.

**7.** There are other things besides forces which possess these three characteristics. These other things may be used to help us in our arguments about forces so far as their other properties are common also to forces.

The most important of these analogies is that of a finite straight line. Let this finite straight line be  $AB$ . One extremity  $A$  will represent the point of application. The direction in space of the straight line will represent the direction of the force and the length of the line will represent the magnitude of the force.

Other things besides forces may also be represented graphically by a finite straight line. Thus in dynamics it will be seen that both the velocity and the momentum of a particle have direction and magnitude and may in the same way be represented by a finite straight line. One extremity  $A$  is placed at the particle,

the direction of the straight line represents the direction of the velocity and the length represents the magnitude. Generally this analogy is useful whenever the things considered obey what we shall presently call the *parallelogram law*.

8. In order to represent completely the direction of a force by the direction of the straight line  $AB$ , it is necessary to have some convention to determine whether the force pulls  $A$  in the direction  $AB$  or pushes  $A$  in the direction  $BA$ . This convention is supplied by the use of the terms positive and negative. The positive and negative directions of straight lines being defined by some convention or rule, the forces which act in the positive directions of their lines of action are called positive and those in the opposite directions are called negative. These conventions are often indicated by the conditions of the problem under consideration, but they usually agree with the rules adopted in the differential calculus. Thus the direction of the radius vector drawn from the origin is usually taken as the positive direction, and so on for all lines.

Sometimes instead of using the term positive, the direction or sense of a force is indicated by the order of the letters, thus a force  $AB$  is a force acting in the direction  $A$  to  $B$ , a force  $BA$  is a force acting from  $B$  towards  $A$ .

9. The third element of a force is its magnitude. This is represented by the length of the representative straight line. A unit of force is represented by a unit of length on any scale we please; a force of  $n$  such units of force is then represented by a straight line of  $n$  units of length.

10. **Measure of a force.** A force must be measured by its effects. Since a force may produce many effects there are several methods open to us. If we wish the measure of two equal forces acting together to be twice that of a single force equal to either, the effect which is to measure the force must be properly chosen.

We may measure a force by the weight of the mass which it will support. Placing two equal masses side by side, they will be supported by equal forces. Joining these together we see that a double force will support a double mass. Thus the effect is proportional to the magnitude of the cause.

We may also measure a force by the motion it will produce in a given body in a given time. If by motion is here meant velocity

then it may be shown by the experiments usually quoted to prove the second law of motion that a double force will produce a double velocity. So here also the effect chosen as the measure is proportional to the magnitude of the cause. This measure requires some experimental results, necessary for dynamics, but not used afterwards in statics.

If we agree to measure a force by the weight it will support the unit will depend on the force of gravity at the place where the experiment is made. Such a unit will therefore present several inconveniences. If also we measure a force by the velocity generated in a unit of mass in a unit of time, it is necessary to discuss how these other units are to be chosen.

It is not necessary for us, at this stage of our argument, to decide on the best method of measuring a force. It will be presently seen that our equations are concerned for the most part with the ratios of forces rather than with the forces themselves. The choice of the actual unit is therefore unimportant at present, and we can leave this choice until the proper occasion arrives. The comparative effects of forces will then have been discussed, and the reader will the better understand the reasons why any particular choice is made.

When therefore we speak of several forces equal to the weight of one, two or three pounds &c., acting on a body and determine the conditions of equilibrium, we shall find that the same conditions are true for forces equal to the weight of one, two or three oz. &c., and generally of all forces in the same ratio.

11. One system of units is that based on the foot, pound, and second as the three fundamental units of length, mass, and time. The unit force is that force which acting on a pound of matter for one second generates a velocity of one foot per second. This unit of force is called the poundal.

The foot and the pound are defined by certain standards kept in a place of security for reference. Thus the imperial yard is the distance between two marks on a certain bar, preserved in the Tower of London, when the whole bar has a temperature of 62° Fah. The unit of time is a certain known fraction of a mean solar day.

The units committee of the British Association recommended the general adoption of the centimetre the gramme and the second as the three fundamental units of space, mass and time. These they proposed should be distinguished from absolute units, otherwise derived, by the letters c. g. s. prefixed, these being the initial letters of the names of the three fundamental units. The c. g. s. unit of force is called a dyne. This is the force which

acting on a gramme for a second generates the velocity of a centimetre per second.

It is found by experiment that a body, say a unit of mass, falling in vacuo for one second acquires very nearly a velocity of 32.19 feet per second. This velocity is the same as 981.17 centimetres per second. It follows therefore that a poundal is about  $\frac{1}{32}$ nd part of the weight of one pound, and a dyne is the weight of  $\frac{1}{981}$ st part of a gramme. These numerical relations strictly apply only to the place of observation, for the force of gravity is not the same at all places on the earth. The difference between the greatest and least values of gravity is about  $\frac{1}{100}$ th of its mean value.


The relations which exist between these and other units in common use are given at length in Everett's treatise on *units and Physical Constants* and in Lupton's *numerical tables*. We have nearly

one inch = 2.54 centimetres,      one pound = 453.59 grammes.

It follows from what precedes that one poundal = 13825 dynes.

**12. The parallelogram of velocities.** This proposition is preliminary to Newton's laws of motion.

The velocity of a particle when uniform is measured by the space described in a given time. A straight line whose length is equal to this space will represent the velocity in direction and magnitude; Art. 8. Suppose a particle to be carried uniformly in the given time from  $O$  to  $C$ , then  $OC$  represents its velocity. This change of place may be effected by moving the particle in the same time from  $O$  to  $A$  along the straight line  $OA$ , if while this is being done we move the straight line  $OA$  (with the particle sliding on it) parallel to itself from the position  $OA$  to the position  $BC$ . The uniform motion of the particle from  $O$  to  $A$  is expressed by the statement that its velocity is represented by  $OA$ . The displacement produced by the uniform motion of the straight line is expressed by the statement that the particle has a velocity represented in direction and magnitude by either of the sides  $OB$  or  $AC$ . It is evident by the properties of similar figures that the path of the particle in space is the straight line  $OC$ .



*It follows that when a particle moves with two simultaneous velocities represented in direction and magnitude by the straight lines  $OA$ ,  $OB$  its motion is the same as if it were moved with a single velocity represented in direction and magnitude by the diagonal  $OC$  of the parallelogram described on  $OA$ ,  $OB$  as sides. This proposition is usually called the parallelogram of velocities.*

Let a particle move with three simultaneous velocities represented in direction and magnitude by the three straight lines  $OA_1$ ,  $OA_2$ ,  $OA_3$ . We may replace the two velocities  $OA_1$ ,  $OA_2$  by the single velocity represented in direction and magnitude by the diagonal  $OB_1$  of the parallelogram described on  $OA_1$ ,  $OA_2$  as sides. The particle now moves with the two simultaneous velocities represented by  $OB_1$  and  $OA_3$ . We may again use the same rule. We replace these two velocities by the single velocity represented in direction and magnitude by the diagonal  $OB_2$  described on  $OB_1$  and on  $OA_3$  as sides. We have thus replaced the three given simultaneous velocities by a single velocity.

In the same way any number of simultaneous velocities may be replaced by a single velocity.

If the simultaneous velocities represented by  $OA_1$ ,  $OA_2$  &c. were all altered in the same ratio, it is evident from the properties of similar figures that the resulting single velocity will also be altered in the same ratio.

Let the simultaneous velocities  $OA_1$ ,  $OA_2$  &c. be such that their resulting velocity is zero. It follows that if all the velocities  $OA_1$ ,  $OA_2$  &c. are altered in any, the same, ratio the resulting velocity is still zero.

**13. Newton's laws of Motion.** These are given in the introduction to the Principia.

1. Every body continues in its state of rest or of uniform motion in a straight line, except in so far as it may be compelled by force to change that state.

2. Change of motion is proportional to the force applied and takes place in the direction of the straight line in which the force acts.

3. To every action there is always an equal and contrary reaction; or the mutual actions of any two bodies are always equal and oppositely directed.

The full significance of these laws cannot be understood until the student takes up the subject of dynamics. The experiments which suggest these laws, and their further verification, are best studied in connection with that branch of the science, and are to be found in books on elementary dynamics. The student who has not already read some such treatise is advised to assume the truth of these laws for the present. We shall accordingly not enter into a full discussion of them in this treatise, but we shall confine our remarks to those portions which are required in statical problems.

14. *The first law asserts the inertness of matter.* A body at rest will continue at rest unless acted on by some external force. At first sight this may appear to be a repetition of the definition of force, since any cause which tends to move a body at rest is called a force. But it is not so. Here we assert as the result of observation or experiment the inertness of each particle of matter. It has no tendency to move itself, it is moved only by the action of causes *external* to itself.

15. *In the second law of motion the independence of forces which act on a particle is asserted.* If the effect of a force is always proportional to the force impressed it is clearly meant that each force must produce its own effect in direction and magnitude as if it acted singly on the particle placed at rest.

Let us consider the meaning of this statement a little more fully. Let a given force act on a given particle placed at rest at a point  $O$  and generate in a given time a velocity which we may represent graphically by the straight line  $OA$ . Let a second force act on the same particle again placed at rest at  $O$  and generate in the same time a velocity which we may represent by  $OB$ . If both forces act simultaneously on the particle both these velocities are generated. The actual velocity of the particle is then represented by the diagonal  $OC$  of the parallelogram described on  $OA$ ,  $OB$  as sides, Art. 12. In the same way, if any number of forces act simultaneously on a particle at rest, the law directs that we are to determine the velocity generated by each as if it acted alone for a given time. These separate velocities are then to be combined into a single velocity in the manner described in Art. 12. This single velocity is asserted to be the effect of the simultaneous action of the forces.

Let a system of forces be such that when they act simul-



taneously on a particle placed at rest the resulting velocity of the particle is zero. These forces are then in equilibrium. Let a second system of forces be also such that when they act on the particle placed at rest, the resulting velocity of the particle is again zero. Then this second system of forces is also in equilibrium. Let these two systems act simultaneously, then since the forces do not interfere with each other, the resulting velocity of the particle is still zero. We thus arrive at the following important proposition.

*Let us suppose that there are two systems of forces each of which when acting alone on a particle would be in equilibrium. Then when both systems act simultaneously there will still be equilibrium.*

This is sometimes called *the principle of the superposition of forces in equilibrium*. When we are trying to find the conditions of equilibrium of some system of forces, the principle enables us to simplify the problem by adding on or removing any particular forces which by themselves are in equilibrium.

Let the forces  $P_1$ ,  $P_2$  &c. acting on a given particle for a given time generate velocities  $v_1$ ,  $v_2$  &c. respectively. If the same or equal forces were made to act on a different particle the velocities generated in the same time may be different. But since the effect of each force is proportional to its magnitude the velocities generated by the several forces are to each other in the ratios of  $v_1$  to  $v_2$  to  $v_3$  &c. If then a system of forces is in equilibrium when acting on any one particle, that system will also be in equilibrium when applied to any other particle (Art. 12).

**16.** We notice also that it is *the change of motion* which is the effect of force. A given force produces the same change of motion in a particle whether that particle is in motion or at rest.

In this way we can determine whether a moving particle is acted on by any external force or not. If the velocity is uniform and the path rectilinear there is no force acting on the particle. If either the velocity is not uniform, or the path not rectilinear, there must be some force acting to produce that change.

Let two equal forces act one on each of two particles and generate in the same time equal changes of velocity; these particles are said to have equal mass. If the force acting on one particle must be  $n$  times that on the other in order to generate equal changes of velocity in equal times, the mass of the first particle is  $n$  times that of the second. It follows that the mass of a particle is proportional to the force required to generate in it a given change of velocity in a given time. Now all bodies falling from rest in a vacuum under the attraction of the earth are found to have the same velocity at the end of the first second of time, Art. 11. We therefore infer that the masses of bodies are proportional to their weights. The units of mass and

force are so chosen that the unit of force acting on the unit of mass will generate a unit of velocity in a unit of time.

The product of the mass of a particle into its velocity is called its *momentum*. It follows from what has just been said that the expression "change of motion" means change of momentum produced in a given time.

These results are peculiarly important in dynamics, but in statics, where the particles acted on are all initially at rest and remain so, they have not the same significance.

17. *In the third law the principle of the transmissibility of force is implied.* The principle is more clearly stated in the remarks which Newton added to his laws of motion. The law asserts the equality of action and reaction. If a force acting at a point  $A$  pull a body which has some point  $B$  held at rest, the reaction at  $B$  is asserted to be equal and opposite to the force acting at  $A$ . In general, when two forces act at different points of a body there will be equilibrium if the lines of action coincide, the directions of the forces are opposite, and their magnitudes equal.

From this we deduce that *when a force acts on a body, its effect is the same whatever point of its line of action is taken as the point of application, provided that point is connected with the rest of the body in some invariable manner.*

For let a force  $P$  act at  $A$  and let  $B$  be another point in its line of action. We have just seen that the force  $P$  acting at  $A$  may be balanced by an equal force  $Q$  acting at  $B$  in the opposite direction. But the force  $Q$  acting at  $B$  may also be balanced by an equal force  $P'$  acting at  $B$  in the same direction as  $P$  (Art. 15). Thus the two equal forces  $P$  and  $P'$  acting respectively at  $A$  and  $B$  in the same directions can be balanced by the same force  $Q$ . Thus the force  $P$  acting at  $A$  is equivalent to an equal force  $P'$  acting at  $B$ .

18. **Statistical Axioms.** If we wish to found the science of statics on a basis independent of the ideas of motion we require some elementary axioms concerning matter and force.

In the first place we assume as before the principle of the inertness of matter.


We also require the two principles of the independence and transmissibility of force.

The first of these principles is regarded as a matter of common experience. When our attention is called to the fact, we notice

that bodies at rest do not begin to move unless urged to do so by some external causes.

The other two require some elementary experiments.

Let a body be acted on by two forces, each equal to  $P$ , and having  $A, A'$  for their points of application. We may suppose these to be applied by means of strings attached to the body at  $A$  and  $A'$  and pulled by forces each of the given magnitude. Let us also suppose the body to be removed from the action of gravity and all other forces. This may be partially effected by trying the experiment on a disc placed on a smooth table or by suspending the body by a string attached at the proper point, or the experiment might be tried on some body floating in a vessel of water.



It is a matter of common experience that when the strings are pulled there cannot be equilibrium unless the lines of action of the forces acting at  $A$  and  $A'$  are on the same straight line. The body acted on will move unless this coincidence of the lines of action is exact.

This result is not to be regarded as obvious apart from experiment. In the diagram the points of application  $A$  and  $A'$  are separated by a space not occupied by the body. The forces have therefore to counterbalance each other by acting, if we may so speak, round the corner  $E$ . As the manner in which force is transmitted across a body is not discussed in this part of statics, it is necessary to have an experimental result on which to found our arguments.

Let us now suppose that two other forces each equal to  $Q$  are applied at  $B$  and  $B'$  and have their lines of action in the same straight line. These if they acted alone on the body without the forces  $P, P'$  would be in equilibrium. Then it will be seen, on trying the experiment, that equilibrium is still maintained when both the systems act. Thus it appears that the introduction of the two forces  $Q, Q'$  does not disturb the two forces  $P, P'$  so as to destroy the equilibrium.

From the results of this experiment we may deduce exactly as in Art. 17, the principle of the transmissibility of force.

**19. Rigid bodies.** Let two or more bodies act and react on each other and be in equilibrium under the action of any forces. The principle of the transmissibility of force asserts that any one of these forces may be applied at any point of its line of action. If the line of action of any force acting on one of the bodies be produced to cut another, it does not follow that equilibrium will be maintained if the force is transferred from a point on the first body to a point on the second.

It is therefore to be understood that when a force is transferred from any point in its line of action to another the two points are supposed to be rigidly connected together. When the points of application of the forces are connected in some invariable manner, the body acted on is said to be rigid. Such are the bodies we shall in general speak of, though for the sake of brevity we shall often refer to them simply as bodies.

**20.** It is sometimes convenient to form the conditions of equilibrium of the whole system (or any part of it) as if it were one body. That this may be done is evident, since the mutual actions and reactions of the several bodies are equal and opposite. But we may also reason thus; the system being in a position of equilibrium, we may suppose the points of application of the forces to be joined in some invariable manner. This will not disturb the equilibrium. The system being now made rigid we may form the conditions of equilibrium. These are generally necessary and sufficient for the equilibrium of the system regarded as a rigid body, but though *necessary* they are *not generally sufficient* for its equilibrium when regarded as a collection of bodies.

**21.** When a force acts on a rigid body, the principle of the transmissibility of force asserts that the body transmits its action from one point of application to another, but does not itself alter the magnitude of the force. It appears, therefore, that so far as this principle and that of the independence of forces are concerned the conditions of equilibrium depend on the forces and not on the body.

If a system of forces be in equilibrium when acting on any body, that system will also be in equilibrium when transferred to act on any other body, provided always the points of application are connected by some kind of invariable relations.

It follows that no definition of the body acted on is necessary when the forces in equilibrium are given. The forces must have something to act on, but all we assume here about this something, is that it transmits the force so that the axioms enunciated may be taken as true. For this reason, it is sometimes said that *statics is the science which treats of the equilibrium and action of forces apart from the subject matter acted on.*

**22. Resultant force.** When two forces act simultaneously on a particle and are not in equilibrium, they will tend to move the particle. We infer that there is always some one force which will keep the particle at rest.

A force equal and opposite to this force is called the resultant of the two forces and is equivalent to the forces. It is obvious that the resultant of two forces acting on a particle must also act on that particle. It is also clear that its line of action is intermediate between those of the two forces.

Let  $P_1, P_2, \dots P_n$  be any number of forces acting on the same particle. The two forces  $P_1, P_2$  have a resultant, say  $Q_1$ . We may remove  $P_1$  and  $P_2$  and replace them by  $Q_1$ . Again  $Q_1$  and  $P_3$  may be replaced by their resultant  $Q_2$  and so on. We finally have all the forces replaced by a single force. This single force is called their resultant.

If the forces of a system do not all act at the same point, it may happen that there is no single force which could balance the system. If so, the system is not equivalent to any single resultant force.

**23.** *To find the resultant of any number of forces acting at a point and having their lines of action in the same straight line.*

Let  $O$  be the point of application, and first let all the forces act in the same direction  $Ox$ . Since each acts independently of the others, the resultant is clearly the sum of the separate forces and it acts in the direction  $Ox$ .

If some of the forces act in one direction  $Ox$  and others in the opposite direction say  $Ox'$ , we sum the forces in these two directions separately. Let  $X$  and  $X'$  be these separate sums, and let  $X$  be the greater. Then by Art. 15 we can remove the force  $X'$  from both sets of forces. The whole system is therefore equivalent to the single force  $X - X'$  acting in the direction of  $X$ .

By the rule of signs this is also equivalent to a single force represented by the negative quantity  $X' - X$  acting in the opposite direction, viz. that of  $X'$ .

The necessary and sufficient condition that a system of forces acting at a point and having their lines of action in the same straight line should be in equilibrium is that the algebraic sum of the forces should be zero.

**24. Parallelogram of forces.** To find the resultant of two forces acting at a given point and inclined to each other at an angle. Let the two forces act at the point  $O$  and let them be represented in direction and magnitude by two straight lines  $OA$ ,  $OB$  drawn from the point  $O$  (Art. 7). Let us now construct a parallelogram having  $OA$ ,  $OB$  for two adjacent sides and let  $OC$  be the diagonal which passes through the point  $O$ . Then the resultant of the two forces will be represented in direction and magnitude by the diagonal  $OC$ .

Several proofs of this important theorem have been given. As the "parallelogram law" is the foundation of the whole theory of the composition and resolution of forces, it will be useful to consider more than one proof, though the student at first reading should confine his attention to one of them.

**25. Newton's proof of the parallelogram of forces** This proof is founded on the dynamical measure of force. Its principle has already been explained in Art. 15. It is repeated here on account of its importance. The figure is the same as that used in Art. 12 for the parallelogram of velocities.


**26.** Suppose two forces to act on the particle placed at  $O$  in the directions  $OA$ ,  $OB$ . Let the lengths  $OA$ ,  $OB$  be such that they represent the velocities these forces could separately generate in the particle by acting for a given time. Since each force acts independently of the other, it will generate the same velocity whether the other acts or does not act. When both act the particle has at the end of the given time both the velocities represented by  $OA$  and  $OB$ . These are together equivalent to the single velocity  $OC$ . But this is also the measure of the force which would generate that velocity. Thus the two forces measured by  $OA$ ,  $OB$  are together equivalent to the single force measured by  $OC$ .

**27. Duchayla's proof of the parallelogram of forces** This proof is founded on the principle of the transmissibility of force, Art. 17. It has been shown in Art. 18 that this principle can be made to depend only on statical axioms.

To prove the proposition we shall use the *inductive proof*. We shall assume that the theorem is true for forces of  $p$  and  $m$  units inclined at any angle, and also for forces of  $p$  and  $n$  units inclined

at the same angle; we shall then prove that the theorem must be true for forces of  $p$  and  $m + n$  units inclined at the same angle.

Let the forces  $p$  and  $m$  act at the point  $O$  and be represented in direction and magnitude by the straight lines  $OA$  and  $OB$ . On the same scale let  $BD$  represent the force  $n$  in direction and magnitude. Let  $BD$  be in the same straight line with  $OB$ , then the length  $OD$  will represent the force  $m + n$  in direction and magnitude, Art. 23. Let the two parallelograms  $OBAC$ ,  $BDFC$  be constructed and let  $OC$ ,  $OF$ ,  $BF$  be the diagonals.



By hypothesis the resultant of the two forces  $p$  and  $m$  acts along  $OC$ . By Art. 18, we transfer the point of application to  $C$ . We now replace this resultant force by its two components  $p$  and  $m$ . These act at  $C$ , viz.  $p$  along  $BC$  produced and  $m$  along  $CF$ . Transfer the force  $p$  to act at  $B$  and the force  $m$  to act at  $F$ .

Since  $BC$  is equal and parallel to  $OA$ , the force  $p$  acting at  $B$  is represented by  $BC$ . The force  $n$  may be supposed also to act at  $B$  and is represented by  $BD$ . Hence by our hypothesis the resultant of these two acts along  $BF$ . Transfer the point of application to the point  $F$ .


The two forces  $p$  and  $m + n$  are therefore equivalent to two forces acting at  $F$ . Their resultant must therefore pass through  $F$ , Art. 22. For the same reason the resultant passes through  $O$ , and the forces have but one resultant, Art. 22. Hence the resultant must act along  $OF$ . But this is the diagonal of the parallelogram constructed on the sides  $OA$ ,  $OD$  which represent the forces  $p$  and  $m + n$ .

It is clear that the resultant of two equal forces makes equal angles with each of these forces. The resultant of two equal forces therefore acts along the diagonal of the parallelogram constructed on the equal forces in the manner already described. Thus the hypothesis is true for the equal forces  $p$  and  $p$ . By what has just been proved it is true for the forces  $p$  and  $2p$  and therefore for  $p$  and  $3p$  and so on. Thus it is true for forces  $p$  and  $rp$  where  $r$  is any integer. Again the hypothesis has just been proved true for

forces  $rp$  and  $p$ ; hence it is true for  $rp$  and  $2p$  and so on. Thus the hypothesis is true for forces  $rp$  and  $sp$ , where  $r$  and  $s$  are any integers. Thus the proposition so far as the *direction* of the resultant is concerned is established for any commensurable force

**28.** *We have now to find the direction of the resultant when the forces are incommensurable.* Let  $OA, OB$  represent in direction and magnitude any two incommensurable forces  $p$  and  $q$ , then the diagonal  $OC$  does not represent the resultant, let  $OG$  be the direction of the resultant. The straight line  $OG$  must lie within the angle  $AOB$  and will cut either  $BC$  between  $B$  and  $C$  or  $A$  between  $A$  and  $C$ ; Art. 22. Let it cut  $BC$  between  $B$  and  $C$ .

Divide  $OB$  into a number of equal parts each less than  $GC$  and measure off from  $OA$  beginning at  $O$  portions equal to these until we arrive at a point  $K$  where  $AK$  is less than  $GC$ . Draw  $GH, KL$  parallel to  $AC$ . Since  $OB$  and  $OK$  are commensurable the forces represented by these have a resultant which acts along the diagonal  $OL$ . Thus the forces  $p$  and  $q$  acting at  $O$  are equivalent to two forces, one of which acts along  $OL$  and the other is the force represented by  $KA$ . The resultant of these two must act at  $O$  in a direction lying between  $OL$  and  $OA$ . But  $OG$  lies outside the angle  $AOL$ , hence the assumption that the direction of the resultant is  $OG$  is impossible. But  $OG$  represents any direction other than  $OC$  for then only is it impossible to divide  $OB$  into equal parts each less than  $GC$ . Thus the resultant force must act along the diagonal whether the forces be commensurable or incommensurable.




We have given a separate proof for incommensurable forces. But this is unnecessary. The theorem has been proved for forces whose ratio can be expressed by a fraction. In the case of incommensurable forces we can still find a fraction which differs from their true ratio by a quantity less than any assignable difference. In the limit the theorem must be true for incommensurable forces.



**29.** To prove that the diagonal represents the magnitude of the resultant as well as its direction.

Let  $OA$  and  $OB$  represent the two forces, and let  $OC$  be the diagonal of the parallelogram  $OACB$ . Take  $OD$  in  $CO$  produced of such length as to represent the resultant in magnitude. Then the three forces  $OA$ ,  $OB$ ,  $OD$  are in equilibrium and each of them is equal and opposite to the resultant of the other two.



Construct on  $OB$ ,  $OD$  the parallelogram  $OBED$ . Since  $OA$  is equal and opposite to the resultant of  $OB$  and  $OD$ ,  $OE$  is in the same straight line with  $OA$  and therefore  $OE$  is parallel to  $CB$ . By construction  $OC$  is in the same straight line with  $OD$  and is therefore parallel to  $EB$ . Thus  $EC$  is a parallelogram. Hence  $OC$  is equal to  $EB$  and therefore to  $DO$ .

Thus the diagonal  $OC$  represents the resultant of the two forces  $OA$ ,  $OB$  in magnitude.

**30. Ex.** Assuming that the diagonal represents the *magnitude* of the resultant, show that it also represents the *direction*.

As before, let  $OA$ ,  $OB$ ,  $OD$  represent forces in equilibrium. It is given that  $OA = OE$ ,  $OC = OD$ , and it is to be proved that  $AOE$ ,  $DOC$  are straight lines. Since  $AB$  and  $BD$  are parallelograms,  $OA = BC$ ,  $OD = BE$ . Hence in the quadrilateral  $EOCB$  the opposite sides are equal in length. The quadrilateral is therefore a parallelogram. (For the triangles  $OEB$ ,  $BCO$  have their sides equal each to each.) It follows that  $OE$  is parallel to  $BC$ , and is therefore in the same straight line with  $OA$ .

**31. Historical summary.** The principles on which the science of statics has been founded in former times may be reduced to three.

There is first the principle used by Archimedes, viz., that of the lever. It is assumed as self-evident or as the result of an obvious experiment, (1) that a straight horizontal lever charged at its extremities with equal weights will balance about a support placed at its middle point, (2) that the pressure on the support is the sum of the equal weights. Starting with this elementary principle, and measuring forces by the weights they would support, the conditions of equilibrium of a straight lever acted on by unequal forces were deduced. From this result by the addition of some simple axioms the other proposition of statics may be made to follow. The truth of the first elementary principle named above is perhaps evident from the symmetry of the figure, but Lagrange points out that the second is not equally evident with the first.

The second principle which has been used as the foundation of statics is that

of the parallelogram of forces. In 1586, Stevinus enunciated the theorem of the triangle of forces. Till this time the science of statics had rested on the theory of the lever, but then a new departure became possible. The simplicity of the principle and the ease with which it may be applied to the problems of mechanics caused it to be generally adopted. The principle finally became the basis of modern statics. For an account of its gradual development we refer the reader to *A Short History of Mathematics*, by W. W. R. Ball.

Many writers have given or attempted to give proofs of this principle which are independent of the idea of motion. One of these, that of Duchayla, has been reproduced above, as that is the one which seems to have been best received. There is another, that of Laplace, which has attracted considerable attention. This is founded on principles similar to the proofs of Bernoulli and D'Alembert. It is assumed as evident that if two forces be increased in any, the same, ratio the magnitude of their resultant will be increased in the same ratio, but its direction will be unaltered.

In comparing these proofs with that founded on the idea of motion, we must admit the force of a remark of Lagrange. He says that, in separating the principle of the composition of forces from the composition of motions, we deprive that principle of its chief advantages. It loses its simplicity and its self-evidence, and it becomes merely a result of some constructions of geometry or analysis.

The third fundamental principle which has been used is that of virtual velocities. This principle had been used by the older writers, but Lagrange gave, or attempted to give, an elementary proof and then made it the basis of the whole science of mechanics. This proof has not been generally received as presenting the simplicity and evidence which he had admired in the principle of the composition of forces.


## CHAPTER II

### FORCES ACTING AT A POINT

#### *The triangle of forces*

32. IN the last chapter we arrived at a fundamental proposition, usually called the parallelogram of forces, which we shall be continually using. Experience shows it is not always convenient to draw the parallelogram, for this complicates the figure and makes the solution cumbersome. Several artifices have been invented to enable us to use the principle with facility and quickness. In this chapter we shall consider these in turn.

33. If  $OA$ ,  $OB$  represent two forces  $P$  and  $Q$  acting at a point  $O$ , we know that their resultant is represented by the



diagonal  $OC$  of the parallelogram constructed on those sides. Now it is evident that  $AC$  will represent the force  $Q$  in direction and magnitude as well as  $OB$ , though it will not represent the point of application. This however is unimportant if the point of application is otherwise indicated. Thus the triangle  $OAC$  may be used instead of the parallelogram  $OACB$ .

As the points of application are supposed to be given independently it is no longer necessary to represent the forces by straight lines passing through  $O$ . Thus we may represent the

forces  $P, Q, R$  acting at  $O$  both in direction and magnitude by the sides of a triangle  $DEF$  provided these sides are parallel to the forces and proportional to them in magnitude.

It is clear that all theorems about the parallelogram of forces may be immediately transferred to the triangle. We therefore infer the following proposition called the *triangle of forces*.

*If two forces acting at some point are represented in direction and magnitude by the sides  $DE, EF$  of any triangle, the third side  $DF$  will represent their resultant.*

*If three forces acting at some point are represented in direction and magnitude by the three sides of any triangle taken in order viz.,  $DE, EF, FD$ , the three forces are in equilibrium.*

**34.** When three forces in one plane are given and we wish to determine whether they are in equilibrium or not, we see that there are two conditions to be satisfied.

1. If they are not all parallel two of them must meet in some point  $O$ . The resultant of these two will also pass through the same point. The third force must be equal and opposite to this resultant and must therefore also pass through the same point. Hence the lines of action of the three forces must meet in one point or be parallel.

2. If the forces are not all parallel, straight lines can be drawn parallel to the forces so as to form a triangle. The magnitudes of the forces must be proportional to the sides of that triangle taken in order.

The case in which the forces are all parallel will be considered in the next chapter.

**35.** We may evidently extend this proposition further. Suppose we turn the triangle  $DEF$  through a right angle into the position  $D'E'F'$ , the sides will then be perpendicular instead of parallel to the forces. Also if the forces act in the directions  $DE, EF, FD$  they now act all three outwards with regard to the triangle  $D'E'F'$ . If the forces were reversed they would all act inwards. We have thus a new proposition.


*If three forces acting at some point be represented in magnitude by the sides of a triangle, and if the directions of the forces be perpendicular to those sides and if they act all inwards or all outwards, the three forces are in equilibrium.*

Instead of turning the triangle through a right angle, we might turn it through any acute angle. We thus obtain another theorem. If three forces acting at a point be represented in magnitude by the sides of a triangle and if their directions make equal angles with the sides taken in order, the three forces are in equilibrium.

In using this theorem, it is sometimes found to be inconvenient to sketch the triangle. We then put the theorem into another form. The sides of the triangle are proportional to the sines of the opposite angles. This relation must therefore also hold for the forces. Hence we infer the following theorem.

*Three forces acting on a body in one plane are in equilibrium if (1) their lines of action all meet in one point, (2) their directions are all towards or all from that point, (3) the magnitude of each is proportional to the sine of the angle between the other two.*

**36. Polygon of forces.** We may further extend the triangle of forces into a polygon of forces. If several forces act at a point  $O$  we may represent these in magnitude and direction by the sides of an unclosed polygon  $DE, EF, FG, GH$  &c. taken in order. The resultant of  $DE, EF$  is represented by  $DF$ . That of  $DF$  and  $FG$  is  $DG$  and so on. Thus the resultant is represented by the straight line closing the polygon. It is clear that the sides of the polygon need not all be in the same plane.



If several forces acting at one point be represented in direction and magnitude by the sides of a closed polygon taken in order, they are in equilibrium.

**37. Ex. 1.** Forces in one plane, whose magnitudes are proportional to the sides of a closed polygon, act perpendicularly to those sides at their middle points all inwards or all outwards. Prove that they are in equilibrium.

Let  $ABCD$  &c. be the polygon. Join one corner  $A$  to the others  $C, D$  &c. Consider the triangle  $ABC$  thus formed. The forces across  $AB, BC$  meet in the centre of the circumscribing circle, and have therefore for resultant a force proportional to  $AC$  acting perpendicularly to it at its middle point. Taking the triangles  $ACD, ADE$  &c. in turn, the final resultant is obviously zero.

**Ex. 2.** Forces in one plane, whose magnitudes are proportional to the cosines of half the internal angles of a closed polygon, act inwards at the corners in directions bisecting the angles. Prove that they are in equilibrium.

therefore be in equilibrium.

✓ **38. Ex. 1.** Forces represented by the numbers 4, 5, 6 are in equilibrium; find the tangents of the halves of the angles between the forces.

By drawing parallels to these forces we construct a triangle of the forces. The angles of this triangle can be found by the ordinary rules of trigonometry.

✓ **Ex. 2.** Forces represented by 6, 8, 10 lbs. are in equilibrium; find the angle between the two smaller forces. How must the least force be altered that the angle between the other two may be halved?

✓ **Ex. 3.** If  $OA$ ,  $OB$  represent two forces, show that their resultant is represented by twice  $OM$ , where  $M$  is the middle point of  $AB$ .

✓ **Ex. 4.** Two constant equal forces act at the centre of an ellipse parallel to the directions  $SP$  and  $PH$ , where  $S$  and  $H$  are the foci and  $P$  is any point on the curve. Show that the extremity of the line which represents their resultant lies on a circle.

[Math. Tripos, 1883.]

✓ **Ex. 5.** Forces  $P$ ,  $Q$  act at a point  $O$ , and their resultant is  $R$ ; if any transversal cut the directions of the forces in the points  $L$ ,  $M$ ,  $N$  respectively, show that

$$\frac{P}{OL} + \frac{Q}{OM} = \frac{R}{ON}. \quad [\text{Math. Tripos, 1881.}]$$

Clear of fractions and the equation reduces to the statement that the area  $LOM$  is the sum of the areas  $LON$ ,  $MON$ .

✓ **Ex. 6.** A particle  $O$  is in equilibrium under three forces, viz., a force  $F$  given in magnitude, a force  $F'$  given in direction, and a force  $P$  given in magnitude and direction. Find the lines of action of  $F'$  by a geometrical construction.


If  $OA$  represent  $P$ , draw  $AB$  parallel to  $F'$ , and describe a circle whose centre is  $O$  and whose radius represents  $F'$  in magnitude.

**Ex. 7.**  $ABCD$  is a tetrahedron,  $P$  is any point in  $BC$ , and  $Q$  any point in  $AD$ . Prove that a force represented in magnitude, direction, and position by  $PQ$ , can be replaced by four components in  $AB$ ,  $BD$ ,  $DC$ ,  $CA$  in one and in only one way, and find the ratios of these components. [St John's Coll., 1887.]

**Ex. 8.** Lengths  $BD$ ,  $CE$ ,  $AF$  are drawn from the corners along the sides  $BC$ ,  $CA$ ,  $AB$  of a triangle  $ABC$ ; each length being proportional to the side along which it is drawn. If forces represented in magnitude and direction by  $AD$ ,  $BE$ ,  $CF$  acted on a point, show that they would be in equilibrium. Conversely if the forces  $AD$ ,  $BE$ ,  $CF$  act at a point and are in equilibrium, then  $BD$ ,  $CE$ ,  $AF$  are proportional to the sides.

**39. Parallelepiped of forces.** Three forces acting at a point  $O$  are represented in direction and magnitude by three straight lines  $OA$ ,  $OB$ ,  $OC$  not in one plane. To show that the resultant is represented in direction and magnitude by the diagonal of the parallelepiped constructed on the three straight lines as sides.

Consider the parallelogram constructed on  $OA$ ,  $OB$ , the resultant of these two forces is represented by  $OD$ . If  $CE$  be the parallel diagonal of the opposite face, it is clear by geometry that  $OCED$  will be a parallelogram. The resultant of the forces represented by  $OC$ ,  $OD$  will therefore be  $OE$ , i.e. the diagonal of the parallelepiped.



We may also deduce the theorem from Art. 36. The resultant of the three forces represented by  $OA$ ,  $AD$ ,  $DE$  is represented by the straight line which closes the polygon  $OADE$ , i.e. it is  $OE$ .

#### 40. Three methods of oblique resolution.

(1) Any three directions (not all in one plane) being given, a force  $R$  represented by  $OE$  may be replaced by three forces  $X$ ,  $Y$ ,  $Z$ , acting in the given directions. The force  $R$  is then said to be resolved in these directions and the forces  $X$ ,  $Y$ ,  $Z$  are called its components. The magnitudes of the components are found geometrically by constructing the parallelepiped whose diagonal is  $R$  and whose sides  $OA$ ,  $OB$ ,  $OC$  have the given directions.

(2) *When the resultant  $OE$  is given, each component may be found by resolving perpendicularly to the plane containing the other two.* Thus suppose the component along  $OC$  of a force  $R$  acting along  $OE$  is required. Let  $OC$ ,  $OE$  make angles  $\theta$ ,  $\gamma$  respectively with the plane  $AOB$ , then, since the perpendiculars from  $C$  and  $E$  on that plane are equal,  $OC \sin \theta = OE \sin \gamma$ . The component  $Z$  along  $OC$  is therefore given by  $Z \sin \theta = R \sin \gamma$ .

(3) A third method of effecting an oblique resolution is given in Arts. 51 and 53.

Ex. 1. If six forces, acting on a particle, be represented in magnitude and direction by the edges of a tetrahedron, the particle cannot be at rest. [Math. T., 1859.]

Ex. 2. Four forces acting at a point  $O$  are in equilibrium, and equal straight lines are drawn from  $O$  along their directions. Prove that each force is proportional to the volume of the tetrahedron described on the lines drawn along the other three forces.

#### *Method of Analysis.*

41. We have seen that any force may be replaced by two others, called its components, which are inclined at any angle to

is meant, unless it is otherwise stated, that the other component is at right angles to it. By referring to the figure of Art. 33, we see that the parallelogram  $OACB$  becomes a rectangle. The two components of the force  $OC$  are  $OC \cdot \cos COA$  and  $OC \cdot \sin COA$ .

We may put this result into the form of a working rule. *If a force  $R$  act at  $O$  in the direction  $OC$ , its component in any direction  $Ox$  is  $R \cos COx$ . Its component in the opposite direction  $Ox'$  is  $R \cos COx'$ . In the same way the component of  $R$  perpendicular to  $Ox$  is  $R \sin COx$ .*

It is convenient to have some short name to distinguish the rectangular components of a force from its oblique components. The name *resolute* for the components in the first case has been suggested in Lock's *Elementary Statics*.

**42.** *Two forces  $P_1, P_2$  act at a point  $O$ . To find the position and magnitude of their resultant.*

Let  $Ox, Oy$  be any two rectangular axes, and let  $\alpha_1, \alpha_2$  be the angles the forces  $P_1, P_2$  make with the axis of  $x$ . The sums of the components parallel to the axes are

$$X = P_1 \cos \alpha_1 + P_2 \cos \alpha_2,$$

$$Y = P_1 \sin \alpha_1 + P_2 \sin \alpha_2.$$

If these are the components of a force  $R$  whose line of action makes an angle  $\bar{\alpha}$  with the axis of  $x$ , we have

$$X = R \cos \bar{\alpha}, \quad Y = R \sin \bar{\alpha}.$$

We easily find by adding together the squares of  $X$  and  $Y$  that

$$R^2 = P_1^2 + P_2^2 + 2P_1P_2 \cos \theta,$$

where  $\theta = \alpha_1 - \alpha_2$ , so that  $\theta$  is the angle between the directions of the forces  $P_1, P_2$ . This result also follows from the parallelogram of forces. For the right-hand side is evidently the square of the diagonal of the parallelogram whose sides are  $P_1$  and  $P_2$ .

The direction of the resultant is also easily found, for we have

$$\tan \bar{\alpha} = \frac{Y}{X} = \frac{P_1 \sin \alpha_1 + P_2 \sin \alpha_2}{P_1 \cos \alpha_1 + P_2 \cos \alpha_2}.$$



✓ 43. Ex. 1. Two forces  $P, Q$  act at an angle  $\alpha$  and have a resultant  $R$ . If each force be increased by  $R$ , prove that the new resultant makes with  $R$  an angle whose tangent is  $\frac{(P-Q) \sin \alpha}{P+Q+R+(P+Q) \cos \alpha}$ . [St John's Coll., 1880.]

Take the line of action of the resultant  $R$  for the axis of  $x$ .

✓ Ex. 2. Forces each equal to  $F$  act at a point parallel to the sides of a triangle  $ABC$ . If  $R$  be their resultant, prove that  $R^2 = F^2(3 - 2 \cos A - 2 \cos B - 2 \cos C)$ .

✓ Ex. 3. The resultant of  $P$  and  $Q$  is  $R$ , if  $Q$  be doubled  $R$  is doubled, if  $Q$  be reversed,  $R$  is also doubled; show that  $P : Q : R :: \sqrt{2} : \sqrt{3} : \sqrt{2}$ . [St John's Coll.]

44. Any number of forces act at a point  $O$  in any directions. It is required to find their resultant.

Take any rectangular axes  $Ox, Oy, Oz$ . Let  $P_1, P_2, P_3$  &c. be the forces,  $(\alpha_1 \beta_1 \gamma_1), (\alpha_2 \beta_2 \gamma_2)$  &c. their direction angles. The sums of the components of these parallel to the axes are

$$X = P_1 \cos \alpha_1 + P_2 \cos \alpha_2 + \dots = \Sigma P \cos \alpha,$$

$$Y = P_1 \cos \beta_1 + P_2 \cos \beta_2 + \dots = \Sigma P \cos \beta,$$

$$Z = P_1 \cos \gamma_1 + P_2 \cos \gamma_2 + \dots = \Sigma P \cos \gamma.$$

If these are the components of a force  $R$  whose direction angles are  $(\bar{\alpha} \bar{\beta} \bar{\gamma})$  we have

$$R \cos \bar{\alpha} = X, \quad R \cos \bar{\beta} = Y, \quad R \cos \bar{\gamma} = Z.$$

By a known theorem in solid geometry

$$\cos^2 \bar{\alpha} + \cos^2 \bar{\beta} + \cos^2 \bar{\gamma} = 1.$$

Hence

$$\frac{R^2 \cos^2 \bar{\alpha}}{X^2} = \frac{R^2 \cos^2 \bar{\beta}}{Y^2} = \frac{R^2 \cos^2 \bar{\gamma}}{Z^2} = \frac{1}{(X^2 + Y^2 + Z^2)^{\frac{1}{2}}}.$$

Thus both  $R$  and its direction cosines have been found.

If the conditions of equilibrium are required it is sufficient and necessary that  $R = 0$ . This gives the three conditions

$$X = \Sigma P \cos \alpha = 0, \quad Y = \Sigma P \cos \beta = 0, \quad Z = \Sigma P \cos \gamma = 0.$$

45. If the resolved parts of the forces  $P_1, P_2$  &c. along any three directions  $OA, OB, OC$  not all in one plane are zero, they are in equilibrium.

Let the axis  $Oz$  coincide with  $OC$  and let the plane  $xOz$  contain  $OA$ . Since the resolved part along  $Oz$  is zero, we have  $Z = 0$ . Since the resolved part along  $OA$  is zero, we have  $X \cos xOA = 0$ . Since  $xOA$  cannot be a right angle without making  $OA, OC$  coincide, we have  $X = 0$ . Lastly since the resolved part along  $OB$  is zero we find  $Y \cos yOB = 0$ . This gives  $Y = 0$ .  $\therefore R = 0$ .

46. The magnitude and direction of  $R$  may also be expressed in a form independent of coordinates in the following manner.

By a known theorem in solid geometry if  $\theta_{12}$  be the angle between the straight lines whose direction angles are  $(\alpha_1, \beta_1, \gamma_1)$ ,  $(\alpha_2, \beta_2, \gamma_2)$  with the usual convention as to direction, then

$$\cos \theta_{12} = \cos \alpha_1 \cos \alpha_2 + \cos \beta_1 \cos \beta_2 + \cos \gamma_1 \cos \gamma_2.$$

Adding together the squares of the expressions for  $X, Y, Z$  we have  $R^2 = P_1^2 (\cos^2 \alpha_1 + \cos^2 \beta_1 + \cos^2 \gamma_1) + \&c.$

$$+ 2P_1P_2 (\cos \alpha_1 \cos \alpha_2 + \cos \beta_1 \cos \beta_2 + \cos \gamma_1 \cos \gamma_2) + \&c.$$

$$= P_1^2 + P_2^2 + \&c. + 2P_1P_2 \cos \theta_{12} + \&c.$$

This gives the *magnitude* of  $R$ .

To determine the *line of action* of  $R$ , we shall find the angles  $\phi_1, \phi_2$  &c. which its direction makes with the directions of the forces  $P_1, P_2$  &c. The axes of coordinates being perfectly arbitrary; let us take the axis of  $x$  to be coincident with the line of action of the force  $P_1$ . Then  $\bar{\alpha} = \phi_1, \alpha_1 = 0, \alpha_2 = \theta_{12}$  &c., the equations

$$R \cos \bar{\alpha} = X = \sum P \cos \alpha$$

$$\text{become} \quad R \cos \phi_1 = P_1 + P_2 \cos \theta_{12} + P_3 \cos \theta_{13} + \&c.$$

In the same way by taking the axis of  $x$  along the force  $P_2$  we find  $R \cos \phi_2 = P_1 \cos \theta_{12} + P_2 + P_3 \cos \theta_{23} + \dots$  and so on. Thus the direction of  $R$  has been found.

**47. Polyhedron of forces.** The equations of Art. 44 have a geometrical meaning which is often useful. Let any closed polyhedron be constructed, let  $A_1, A_2$  &c. be the areas of its faces. Let normals be drawn to these faces, each from a point in the face all outwards or all inwards, and let  $\theta_1, \theta_2$  &c. be the angles these normals make with any straight line which we may call the axis of  $z$ . Let us now project orthogonally all these areas on the plane of  $xy$ . The several projections are  $A_1 \cos \theta_1, A_2 \cos \theta_2$  &c. Since the polyhedron is closed the total projected area which is positive is equal to the total negative projected area. We therefore have

$$A_1 \cos \theta_1 + A_2 \cos \theta_2 + \dots = 0.$$

Similar results hold for the projection on the other coordinate planes. Thus we obtain three equations which are the same as the equations of equilibrium already found, except that we have  $A_1, A_2$  &c. written for  $P_1, P_2$  &c. We therefore have the following theorem. *If forces acting at a point be represented in magnitude by the areas of the faces of a closed polyhedron and if the directions of the forces be perpendicular to those faces respectively, acting all inwards or all outwards, then these forces are in equilibrium.*

**48.** By using the theory of determinants we may put the results of Art. 46 into a more convenient form. Let it be required to find the resultant of any three forces acting at a point. To obtain a symmetrical result we shall reverse the resultant and speak of four forces in equilibrium.

Let  $P_1, P_2, P_3, P_4$  be four forces in equilibrium. Putting  $R=0$ , we have found

in Art. 46 four linear equations connecting these. Eliminating the forces, we have the determinantal equation

$$\begin{vmatrix} 1 & \cos \theta_{12} & \cos \theta_{13} & \cos \theta_{14} \\ \cos \theta_{21} & 1 & \cos \theta_{23} & \cos \theta_{24} \\ \cos \theta_{31} & \cos \theta_{32} & 1 & \cos \theta_{34} \\ \cos \theta_{41} & \cos \theta_{42} & \cos \theta_{43} & 1 \end{vmatrix} = 0.$$

This is the relation connecting the mutual inclinations of any four straight lines in space\*. If all these angles except one (say  $\theta_{12}$ ) are given, we have a quadratic to find the two possible values which  $\cos \theta_{12}$  could then have. If three of the angles say  $\theta_{12}$ ,  $\theta_{23}$ ,  $\theta_{31}$  are right angles this determinant reduces to the well-known form

$$\cos^2 \theta_{14} + \cos^2 \theta_{24} + \cos^2 \theta_{34} = 1.$$

If the angles between the four directions in which the forces act are given, the ratios of the forces are found from any three of the four linear equations above mentioned. It follows that the forces are in the ratio of the minors of the constituents in any row of the determinant.

**49.** Ex. Show that the squares of the forces are in the ratio of the minors of the constituents in the leading diagonal.

For let  $I_{rs}$  be the minor of the  $r$ th row and  $s$ th column, then by a theorem in Salmon's *Higher Algebra*  $I_{11}I_{22} = I_{12}^2$ . But we have shown above that

$$P_1 : P_2 = I_{11} : I_{12};$$

hence we deduce at once  $P_1^2 : P_2^2 = I_{11} : I_{22}$ .

For the sake of reference we state at length the minor of the leading constituent.

It is  $I_{11} = 1 - \cos^2 \theta_{23} - \cos^2 \theta_{34} - \cos^2 \theta_{42} + 2 \cos \theta_{23} \cos \theta_{34} \cos \theta_{42}$ .

This expression is easily recognized as one which occurs in many formulæ in spherical trigonometry. For example, if unit lengths are drawn from any point  $O$  parallel to the directions of any three of the forces (say  $P_2$ ,  $P_3$ ,  $P_4$ ) the volume of the tetrahedron so formed is one sixth of the square root of the corresponding minor (viz.  $I_{11}$ ).

**50.** Sometimes it is necessary to refer the forces to oblique axes. In this case we replace the direction cosines of each force by its direction ratios. Let the direction ratios of  $P_1$ ,  $P_2$  &c. be  $(a_1b_1c_1)$ ,  $(a_2b_2c_2)$  &c. Then by the same reasoning as before, the sums of the components of the forces parallel to the axes are

$$X = \Sigma Pa, \quad Y = \Sigma Pb, \quad Z = \Sigma Pc.$$

If these are the components of a force  $R$  with direction ratios  $(l, m, n)$  we have

$$Rl = X, \quad Rm = Y, \quad Rn = Z.$$

The relations between the direction ratios of a straight line and the angles that straight line makes with the axes are given in treatises on solid geometry or on spherical trigonometry. They are not nearly so simple as when the axes of reference are rectangular. For this reason oblique axes are seldom used.

### *The mean centre*

**51.** There is another method of expressing the magnitude and direction of the resultant of any number of forces acting at

\* Another proof is given in Salmon's *Solid Geometry*, Ed. iv., Art. 54.

a point which will be found very useful both in geometrical and analytical reasoning.

Let us represent the forces  $P_1, P_2$  &c. in direction by the straight lines  $OA_1, OA_2$  &c. To represent their magnitudes we shall take lengths measured along these straight lines, thus the force along  $OA_1$  is represented by  $p_1.OA_1$ , that along  $OA_2$  by  $p_2.OA_2$ , and so on. The advantage of introducing the numerical multipliers  $p_1, p_2$  &c. is that the extremities  $A_1, A_2$  &c. of the straight lines may be chosen so as to suit the figure of the problem under consideration. It is evident that this is equivalent to representing the forces by straight lines on different scales, viz. the scales  $p_1, p_2$  &c. of force to each unit of length.

Taking  $O$  for origin, let  $(x_1y_1z_1), (x_2y_2z_2)$  &c. be the coordinates of the points  $A_1, A_2$  &c. We have already proved that the components of the resultant are

$$\left. \begin{aligned} X &= \Sigma P \cos \alpha = \Sigma p . OA_1 \cos \alpha = \Sigma px \\ Y &= \Sigma P \cos \beta &= \Sigma py \\ Z &= \Sigma P \cos \gamma &= \Sigma pz \end{aligned} \right\} \dots\dots\dots (1).$$

Let us take a point  $G$  whose coordinates  $(\bar{x}\bar{y}\bar{z})$  are given by the equations  $\bar{x} = \frac{\Sigma px}{\Sigma p}, \quad \bar{y} = \frac{\Sigma py}{\Sigma p}, \quad \bar{z} = \frac{\Sigma pz}{\Sigma p} \dots\dots\dots (2).$

It follows at once that

$$X = \bar{x}\Sigma p, \quad Y = \bar{y}\Sigma p, \quad Z = \bar{z}\Sigma p.$$

These equations imply that the resultant of the forces is represented in direction and magnitude by  $OG . \Sigma p$ .

This point  $G$  is known by a variety of names. It is called the *centre of gravity*, or *centroid* or *mean centre* of a system of particles placed at  $A_1, A_2, \dots$  whose masses or weights are proportional to  $p_1, p_2$  &c.

The result is, *if forces acting at a point  $O$  be represented in direction by the straight lines  $OA_1, OA_2$  &c. and in magnitude by  $p_1.OA_1, p_2.OA_2$  &c., then their resultant is represented in direction by  $OG$  and in magnitude by  $\Sigma p . OG$ , where  $G$  is the centroid of masses proportional to  $p_1, p_2$  &c. placed at  $A_1, A_2$  &c.* This theorem is commonly ascribed to Leibnitz.

We notice that *forces represented in magnitude and direction by  $p_1.OA_1, p_2.OA_2$  &c., are in equilibrium when  $O$  is the centroid of masses proportional to  $p_1, p_2$  &c., placed at  $A_1, A_2$  &c.*

Conversely, a force  $R$ , acting along  $OG$ , may be resolved into three forces  $P_1, P_2, P_3$ , which act along three given straight lines passing through  $O$ , by making  $G$  to be the mean centre of masses placed at convenient points  $A_1, A_2, A_3$ , on those straight lines. If  $p_1, p_2, p_3$  are those masses, the components  $P_1, P_2, P_3$  are given by

$$\frac{P_1}{p_1 \cdot OA_1} = \frac{P_2}{p_2 \cdot OA_2} = \frac{P_3}{p_3 \cdot OA_3} = \frac{R}{(p_1 + p_2 + p_3) OG}.$$

In using this theorem we may draw some or all of the straight lines  $OA_1, OA_2$  &c. in the opposite directions to the forces. If this be done we simply regard the  $p$ 's of those straight lines as negative.

When some of the  $p$ 's are negative, it may happen that  $\Sigma p = 0$ . In this case the centroid is at infinity and this representation of the resultant though correct is not convenient. The components along the axes are still given by the expressions  $X = \Sigma px, Y = \Sigma py, Z = \Sigma pz$  which do not contain any infinite quantities.

**52.** The utility of this proposition depends on the ease with which the point  $G$  can be found when  $A_1, A_2$ , &c., are given. The working rule is that the distance of  $G$  from any plane of reference, taken as the plane of  $xy$ , is given by the formula  $\bar{z} = \frac{\Sigma pz}{\Sigma p}$ . The properties of this point and its positions in various cases are discussed in the chapter on the centre of gravity.

**53.** Ex. 1. The centroid  $G$  of two particles  $p_1, p_2$ , placed at two given points  $A_1, A_2$ , lies in the straight line  $A_1A_2$  and divides it so that  $p_1 \cdot A_1G = p_2 \cdot A_2G$ .

Take  $A_1A_2$  as the axis of  $x$ ,  $A_1$  as origin and let  $A_1A_2 = a$ . Then  $x_1 = 0, x_2 = a, y_1 = 0, y_2 = 0$ . Using the working rule we have

$$\bar{x} = \frac{p_1 x_1 + p_2 x_2}{p_1 + p_2} = \frac{p_2 a}{p_1 + p_2}, \quad \bar{y} = \frac{p_1 y_1 + p_2 y_2}{p_1 + p_2} = 0.$$

Hence  $G$  lies in  $A_1A_2$  and since  $\bar{x} = A_1G$  we find  $p_1 \cdot A_1G = p_2 (A_1A_2 - A_1G) = p_2 \cdot A_2G$ .

This theorem enables us to resolve a force  $P$  which acts along a given straight line  $OG$  into two directions  $OA_1, OA_2$ , which are not necessarily at right angles. The components  $P_1, P_2$  are given by

$$\frac{P_1}{p_1 \cdot OA_1} = \frac{P_2}{p_2 \cdot OA_2} = \frac{P}{(p_1 + p_2) OG}$$

where  $p_1, p_2$  are the distances of  $G$  from  $A_2, A_1$  taken positively when measured inwards.

**Ex. 2.** Prove that the centroid of three masses  $p_1, p_2, p_3$ , placed at the corners of a triangle is the point whose areal coordinates are proportional to  $p_1, p_2, p_3$ . When the masses are equal this point is briefly called the centroid of the triangle.

If  $\alpha, \beta, \gamma$  are the distances of a point  $G$  from the sides  $BC, CA, AB$  of a triangle taken positively when measured inwards, and  $p, q, r$  are the perpendiculars from the corners on the same sides, the ratios  $x = \alpha/p, y = \beta/q, z = \gamma/r$  are called the

areal coordinates of  $G$ . It is evident that  $x, y, z$  are also proportional to the areas of the triangles  $BGC, CGA, AGB$  respectively. Also  $x + y + z = 1$ .

✓ Taking any side  $AB$  as the axis of reference we deduce from the working rule (Art. 52) that the distance of the centroid from it is  $\gamma = p_3/s$  where  $s = p_1 + p_2 + p_3$ . Similarly  $\alpha = p_1/s, \beta = p_2/s$ . It follows that  $x, y, z$  are proportional to  $p_1, p_2, p_3$ .

✓ Ex. 3. A force  $P$  acting at the corner  $D$  of a tetrahedron intersects the opposite face  $ABC$  in a point  $G$  whose areal coordinates referred to the triangle  $ABC$  are  $(x/yz)$ . If the components of  $P$  along the edges  $DA, DB, DC$  are  $P_1, P_2, P_3$

prove 
$$\frac{P_1}{x \cdot DA} = \frac{P_2}{y \cdot DB} = \frac{P_3}{z \cdot DC} = \frac{P}{DG}.$$

✓ Ex. 4. Any number of forces are represented in magnitude and direction by straight lines  $A_1A'_1, A_2A'_2, \dots, A_nA'_n$  and  $G, G'$  are the centroids of the points  $A_1, A_2, \dots, A_n$  and  $A'_1, A'_2, \dots, A'_n$ . Show that these forces transferred parallel to themselves to act at a point have a resultant which is represented in magnitude and direction by  $n \cdot GG'$ . [Coll. Ex., 1889.]

The group of forces  $AA'$  is equivalent to the three groups  $AG, GG', G'A'$ , Art. 36. The first and last are separately in equilibrium, Art. 51.

Ex. 5. Three forces in one plane, acting at  $A, B, C$ , are represented by  $AD, BE, CF$  where  $D, E, F$  are their intersections with the sides of the triangle  $ABC$ . Show that these are equivalent to three forces acting along the sides  $AB, BC, CA$  of the triangle represented by  $\left(\frac{CD}{a} - \frac{CE}{b}\right)c, \left(\frac{AE}{b} - \frac{AF}{c}\right)a$  and  $\left(\frac{BF}{c} - \frac{BD}{a}\right)b$ .

Thence show that if  $BD/a = CE/b = AF/c = \kappa$ , these three forces are statically equivalent to the three forces  $(1 - 2\kappa)c, (1 - 2\kappa)a, (1 - 2\kappa)b$  acting along the sides of the triangle.

Prove that the centroid of equal particles placed at  $D, E, F$ , coincides with that of the triangle. Thence show that the forces represented by  $OD, OE, OF$ , (where  $O$  is any point) have a resultant whose magnitude and line of action are independent of the value of  $\kappa$ .

✓ Ex. 6. A particle in the plane of a triangle is acted on by forces directed to the mid-points of the sides whose magnitudes are proportional directly to the distances from those points and inversely to the radii of the circles escribed to those sides. Find the position of equilibrium. [Math. Tripos, 1890.]

The point is the centre of the inscribed circle.

✓ Ex. 7.  $A, B, C, D$  are four small holes in a vertical lamina, and four elastic strings of natural lengths  $OA, OB, OC, OD$  are attached to a point  $O$  in the lamina, their other ends being passed through  $A, B, C, D$  respectively and attached to a small heavy ring  $P$ . Assuming that the tension of an elastic string is a given multiple of its extension, prove that when the lamina is turned in its own plane about  $O$  the locus of  $P$  in the lamina will be a circle. [Coll. Ex., 1888.]

✓ Ex. 8. A quadrilateral  $ABCD$  is inscribed in a circle whose centre is  $O$ , forces proportional to  $\triangle BCD \pm 2\triangle OBD, \triangle ACD \pm 2\triangle OAC, \triangle ABD \pm 2\triangle OBD, \triangle ABC \pm 2\triangle OAC$ , act along  $OA, OB, OC, OD$  respectively, the signs being determined according to a certain convention, show that the forces are in equilibrium. [Math. Tripos, 1889.]

✓ Ex. 9. Three forces  $P, Q, R$  act along three straight lines  $DA, DB, DC$  not in one plane; if their resultant is parallel to the plane  $ABC$ , prove that

$$P/DA + Q/DB + R/DC = 0. \quad [\text{St John's Coll., 1882.}]$$

✓ Ex. 11.  $ABCDEF$  is a regular hexagon, and at  $A$  forces act represented in magnitude and direction by  $AB, 2AC, 3AD, 4AE, 5AF$ . Show that the length of the line representing their resultant is  $\sqrt{351}AB$ . [Math. Tripos, 1880.]

### *Equilibrium of a particle under constraint*

54. *Distinction between smooth and rough bodies.* Let a particle under the influence of any forces be constrained to slide along an infinitely thin fixed wire. There is an action between the particle and the curve. Let this force be resolved into two components, one acting along a normal to the curve and the other along the tangent. The latter of these is called friction. By common experience it is found to depend on the nature of the materials of which the wire and particle are made. When this component is zero or so small that it can be neglected the bodies are said to be *smooth*. When it cannot be neglected the conditions of equilibrium are more complicated and will be found in another chapter. For the present we shall confine our attention to smooth bodies. Similar remarks apply when a particle is constrained to remain on a surface. In all such cases the constraining curve or surface is called smooth when the action between it and the particle is along the normal to that curve or surface.

55. If the particle be a bead slung on the curve, the bead can only move in the direction of a tangent drawn to the curve at the point occupied by the bead. *The necessary and sufficient condition of equilibrium is that the component of the forces along the tangent to the curve at the point occupied by the particle is zero.*

If the particle rest on one side of the curve the action of the curve on the particle will only prevent motion in one direction along the normal. It is therefore also *necessary for equilibrium that the external forces should press the particle against the curve.*

If a particle rest on a smooth surface at any point, the component of the forces along every tangent to the surface at that point must be zero. In other words, *the resultant force at a position of equilibrium must act normally to the surface in such a direction as to press the particle against the surface.*

56. *The form of a curve being given by its equations; to find the positions on it at which a particle would rest in equilibrium under the action of any given forces.*

Suppose the curve to be given by its Cartesian equations, and let the axes of reference be rectangular. Let  $x, y, z$  be the coordinates of the particle when in a position of equilibrium. Let  $X, Y, Z$  be the components of the forces parallel to these axes. Let  $s$  be the arc measured from some fixed point on the curve up to the point occupied by the particle. Then resolving the forces  $X, Y, Z$  along the tangent, we have by Art. 41,

$$X \frac{dx}{ds} + Y \frac{dy}{ds} + Z \frac{dz}{ds} = 0.$$

If the equations of the curve are given in the form

$$\phi(x, y, z) = 0, \quad \psi(x, y, z) = 0,$$

we have with the usual notation for partial differential coefficients

$$\phi_x dx + \phi_y dy + \phi_z dz = 0, \quad \psi_x dx + \psi_y dy + \psi_z dz = 0.$$

Eliminating the ratios  $dx:dy:dz$ , we have the determinant

$$J = \begin{vmatrix} X & Y & Z \\ \phi_x & \phi_y & \phi_z \\ \psi_x & \psi_y & \psi_z \end{vmatrix} = 0.$$

This determinantal equation, joined to the two equations of the curve, suffice in general to find the values of  $x, y, z$ . There may be several sets of values of these coordinates, and these give all the positions of equilibrium.

57. *The form of a surface being given by its equation; to find the point or points on it at which a particle would rest in equilibrium under the action of given forces.*

Let the surface be given by its Cartesian equation  $f(x, y, z) = 0$  when referred to rectangular axes. By Art. 55 the direction cosines of the resultant force must be proportional to those of the normal to the surface. We therefore have

$$X/f_x = Y/f_y = Z/f_z.$$

Joining these two equations to the given equation of the surface, we have three equations to find  $(x, y, z)$ .

58. *Pressure on the curve or surface.* It follows from Art. 54 that in the position of equilibrium the resultant force acts normally



and is equal to the pressure. If then  $R$  be the pressure on the curve or surface, its magnitude is given by  $R^2 = X^2 + Y^2 + Z^2$  and its direction is determined by the direction cosines  $X/R$ ,  $Y/R$ ,  $Z/R$ .

**59.** In these propositions the components  $X$ ,  $Y$ ,  $Z$  are supposed to be given functions of the coordinates  $x$ ,  $y$ ,  $z$ . In many cases these components are respectively partial differential coefficients with regard to  $x$ ,  $y$ ,  $z$  of some function  $V$  called the potential of the forces. Thus  $X = \frac{dV}{dx}$ ,  $Y = \frac{dV}{dy}$ ,  $Z = \frac{dV}{dz}$  .....(1).

The condition of equilibrium of a particle resting on a smooth curve defined by its Cartesian equations  $\phi=0$ ,  $\psi=0$  has been found above and is equivalent to the assertion that the Jacobian of  $(V, \phi, \psi)$  vanishes at the points of equilibrium.

If we equate the potential  $V$  to an arbitrary constant  $c$  we obtain a system of surfaces. Each of these is called a level surface. By equations (1)  $X$ ,  $Y$ ,  $Z$  are proportional to the direction-cosines of the normal to a level surface. The resultant force at any point, therefore, acts along the normal to the level surface which passes through that point. *If then a particle is constrained to rest on any smooth curve or surface, the positions of equilibrium are those points at which the curve or surface touches a level surface.*

A curve or surface may be such that every point of it is a position of equilibrium. In this case the resultant force is everywhere normal to the curve or surface. If then the particle be constrained by a curve, the curve must lie on one of the level surfaces, if by a surface, ~~that surface~~ must be a level surface.

**60.** Another interpretation may be found for the condition of equilibrium

$$Xdx + Ydy + Zdz = 0.$$

Substituting for  $X$ ,  $Y$ ,  $Z$  from (1), this is equivalent to  $dV=0$ , i.e. at a position of equilibrium the potential of the forces is a maximum or minimum.

**61.** Ex. 1. A heavy particle is constrained to slide on a smooth circle whose plane is vertical. A string, attached to the particle, passes through a small ring placed at the highest point of the circle and supports an equal weight at its other end. Prove that the system is in equilibrium when the string between the ring and the particle makes an angle  $60^\circ$  with the vertical.

Ex. 2. The ends of a string are attached to two heavy rings of masses  $m$ ,  $m'$ , and the string carries a third ring of mass  $M$  which can slide on it; the rings  $m$ ,  $m'$  are free to slide on two smooth fixed rigid bars inclined at angles  $\alpha$  and  $\beta$  to the horizontal. Prove that if  $\phi$  be the angle which either part of the string makes with the vertical, then  $\cot \phi : \cot \beta : \cot \alpha = M : M + 2m' : M + 2m$ . [St John's, 1890.]

Ex. 3. A weight  $P$ , attached by a cord to a fixed point  $O$ , rests against a smooth curve in the same vertical plane with  $O$ ; show that, (1) if the pressure on the curve is to be independent of the position of the weight on it, the curve must be a circle; (2) if the tension in the cord is to be independent of the position of the weight, the curve must be a conic section with  $O$  as focus. [Math. Tripos, 1886.]

The vertical  $OA$  drawn through  $O$ , the normal  $PA$  to the curve and the string  $PO$  form a triangle whose sides are proportional to the forces which act along them. In case (1) the ratio of  $OA$  to  $AP$  is constant; it follows that  $P$  lies on a circle or on a straight line passing through  $O$ . In case (2) the ratio of  $OA$  to  $OP$  is constant; it follows that  $P$  lies on a conic or on a horizontal straight line through  $O$ .

Ex. 4. Two small rings without weight slide on the arc of a smooth vertical circle; a string passes through both rings and has three equal weights attached to it, one at each end and one between the pegs. Show that in equilibrium the rings must be  $30^\circ$  distant from the highest point of the circle. [Math. Tripos, 1853.]

Ex. 5. A smooth elliptic wire is placed with its major axis vertical, and a bead of given weight  $W$  is capable of sliding on the wire but is maintained in equilibrium by two strings passing over smooth pegs at the foci and sustaining given weights, of which the higher exceeds the lower by  $W/c$ , where  $c$  is the eccentricity. Prove that the pressure on the curve will be a maximum or minimum when the bead is at the extremities of the major axis or when the focal distances have between them the same ratio as the two sustained weights. [Christ's Coll., 1865.]

Ex. 6. If four equal particles, attracting each other with forces which vary as the distance, slide along the arc of a smooth ellipse, they cannot be in equilibrium unless placed at the extremities of the axes; but if a fifth equal particle be fixed at any point and attract the other four according to the same law, there will be equilibrium if the distances of the four particles from the semi-axis major be the roots of the equation

$$(y^2 - b^2) \left( y + \frac{b^2 q}{5a^2 - 3b^2} \right)^2 = - \frac{a^2 b^2 p^2}{(3a^2 - 5b^2)^2 y^2}$$




where  $p$  and  $q$  are the distances of the fifth particle from the axis minor and axis major respectively.

Ex. 7. A surface is such that the product of the distances of any point on it from two fixed points  $A$  and  $B$  is equal to the sum of those distances multiplied by a constant. A particle constrained to remain on the surface is acted on by two equal centres of repulsive force situated at  $A$  and  $B$ . If each force varies as the inverse square of the distance, show that the particle is in equilibrium in all positions.

Ex. 8. A heavy smooth tetrahedron rests with three of its faces against three fixed pegs and the fourth face horizontal: prove that the pressures on the pegs are proportional to the areas of the corresponding faces. [Math. Tripos, 1869.]

### Work.

62. Let a force  $P$  act at a point  $A$  of a body in the direction  $AB$  and let us suppose the point  $A$  to move into any other position  $A'$  very near  $A$ . Let  $\phi$  be the angle the direction  $AB$  of the



force makes with the direction  $AA'$  of the displacement of the point of application, then the product  $P \cdot AA' \cdot \cos \phi$  is called the work done by the force. If for  $\phi$  we write the angle the direction  $AB$  of the force makes with the direction  $A'A$  opposite to the displacement, the product is called the work done against the force.

Let us drop a perpendicular  $A'M$  on  $AB$ ; *the work done by the force is also equal to the product  $P \cdot AM$ , where  $AM$  is to be estimated positive when in the direction of the force.* Let  $P'$  be the resolved part of  $P$  in the direction of the displacement; *the work is also equal to  $P' \cdot AA'$ .* These expressions for the work of a force are clearly equivalent, and all three are in continual use.

63. The forces which act on a particle generally depend on the position of that particle. Thus if the particle be moved from  $A$  to any point  $A'$  at a *finite distance* from  $A$ , the force  $P$  will not generally remain the same either in direction or magnitude. For this reason it is necessary to suppose the displacement  $AA'$  to be so small a quantity that we may regard the force as fixed in direction and magnitude. Taking the phraseology of the differential calculus this is expressed by saying that the displacement  $AA'$  is of the first order of small quantities.

We may suppose any finite displacement of the point  $A$  to be made along a curve beginning at  $A$  and ending at some point  $C$ . Let  $ds$  be any element of this curve, and when the particle has reached this element let  $P'$  be the resolved part of the force along  $ds$  in the direction in which  $s$  is measured. Then by the above definition  $\int P' ds$  is the sum of the separate works done by the force  $P$  as the particle travels along each element in turn. *This sum is defined to be the whole work in any finite displacement.* If  $s$  be measured from any point  $O$  on the curve, the limits of this integral will evidently be  $s = OA$  and  $s = OC$ .

64. The resolved displacement  $AA' \cos \phi$  is sometimes called the *virtual velocity of the point of application*. The product  $P \cdot AA' \cos \phi$  is called the *virtual moment* or *virtual work* of the force. But these terms are restricted to infinitely small displacements. When the displacement is finite, the integral of the virtual works is called the work.

65. It is often convenient to construct a proposed displacement by several steps. Thus a displacement  $AA'$  may be constructed by moving  $A$  first to  $D$  and then from  $D$  to  $A'$  (see figure in Art. 62). Supposing  $AD$  and  $DA'$  to be infinitely small so that the direction and magnitude of the force  $P$  continue constant throughout, it is easy to see *that the work due to the whole displacement  $AA'$  is the sum of the works due to the displacements  $AD$  and*

$DA'$ . For if we drop the perpendiculars  $DN$  and  $A'M$  on the direction of the force, the separate works *with their proper signs* will be  $P \cdot AN$  and  $P \cdot NM$ . The sum of these is  $P \cdot AM$ , which is the work due to the whole displacement  $AA'$ .

If the displacement  $AA'$  is finite, and the force  $P$  remains unaltered in direction and magnitude, the work due to the resultant displacement is equal to the sum of the works due to the partial displacements  $AD$ ,  $DA'$ .

66. Suppose next that several forces act at the point  $A$ ; then as  $A$  moves to  $A'$  each of these will do work. The sum of the works done by each separately is defined to be the work done by all the forces collectively.

*If any number of forces act at a point  $A$ , the sum of the works due to any small displacement  $AA'$  is equal to the work done by their resultant.*

The work done by any one force  $P$  is equal, by definition, to the product of  $AA'$  into the resolved part of  $P$  in the direction of  $AA'$ . The work done by all the forces is therefore the product  $AA'$  into the sum of their resolved parts. By Art. 44 this is equal to  $AA'$  into the resolved part of the resultant, i.e. is equal to the work done by the resultant.

67. This theorem leads to another method of stating the conditions of equilibrium of any number of forces  $P_1$ ,  $P_2$  &c. acting at the same point  $A$ .

Case 1. If the particle at  $A$  is free to move in all directions it is necessary for equilibrium that the resultant force should vanish. The virtual work of the forces  $P_1$ ,  $P_2$  &c. must therefore be zero in whatever direction the particle is displaced.

Conversely, if the virtual work for any displacement  $AA'$  is zero it immediately follows that the resolved part of the resultant in that direction is also zero. If then the virtual work of  $P_1$ ,  $P_2$  &c. is zero for any three different displacements not all in one plane, the three resolved parts of the resultant in those directions are zero. The particle is therefore in equilibrium.

68. Case 2. If the particle is constrained to move on some curve or surface, then besides the forces  $P_1$ ,  $P_2$  &c. the particle is acted on by a pressure  $R$  which is normal to the curve or surface. The forces which maintain equilibrium are therefore  $P_1$ ,  $P_2$  &c.

and  $R$ . Then by Case 1 their virtual work is zero for all small displacements.

If the displacement given to  $A$  is along a tangent to the curve or is situated in the tangent plane to the surface, the angle  $\phi$  between the reaction  $R$  and the displacement is a right angle. The virtual work of that force is therefore zero. It immediately follows that for all such displacements the virtual work of  $P_1, P_2$  &c. is zero.

Conversely, suppose the particle constrained to move on a *curve*; then if the virtual work for a displacement along the tangent is zero the resolved part of the resultant force in that direction is also zero. The particle is therefore in equilibrium.

Next, suppose the particle constrained to move on a *surface*; then if the virtual works for any two displacements, not in the same straight line, are each zero, the resolved parts of the resultant force in those directions are each zero. The particle is therefore in equilibrium.

69. Ex. 1. Deduce from the principle of virtual velocities the conditions of equilibrium obtained in Art. 56, for a particle constrained to rest on a curve.

The forces on the particle are  $X, Y, Z$ ; the displacement is  $ds$ , the projections of  $ds$  on the forces are  $dx, dy, dz$ . Multiplying each force by the corresponding projection, we see at once that the condition of equilibrium is  $Xdx + Ydy + Zdz = 0$ .

Ex. 2. Two small smooth rings of equal weight slide on a fixed elliptical wire, of which the axis major is vertical, and are connected by a string passing over a smooth peg at the upper focus; prove that the rings will rest in whatever position they may be placed. [Math. Tripos, 1858.]

Let  $P, Q$  be the two rings,  $W$  the weight of either. Let  $T$  be the tension of the string,  $l$  its length. Let  $S$  be the peg, let  $x, x'$  be the abscissæ of  $P, Q$  measured vertically downwards from  $S$ ; let  $r = SP, r' = SQ$ , then  $r + r' = l$ . Since the ring  $P$  is in equilibrium, we have by the principle of virtual work  $Wdx - Tdr = 0$ . The positive sign is given to the first term because  $x$  is measured in the direction in which  $W$  acts; the negative sign is given to the second term because  $T$  acts in the opposite direction to that in which  $r$  is measured. In the same way we find for the other ring  $Wdx' - Tdr' = 0$ . Since  $dr = -dr'$  this gives as the condition of equilibrium  $Wdx + Wdx' = 0$ . As yet we have not introduced the condition that the wire has the form of an ellipse. If  $2c$  be its latus rectum and  $e$  its eccentricity, we have  $r = c + ex, r' = c + ex'$ . It easily follows that  $dx + dx' = 0$ , so that the condition of equilibrium is satisfied in whatever position the rings are placed.

Ex. 3. A small ring movable along an elliptic wire is attracted towards a given centre of force which varies as the distance: prove that the positions of equilibrium of the ring lie in a hyperbola, the asymptotes of which are parallel to the axes of the ellipse. [Math. Tripos, 1865.]

Ex. 4. Two small rings of the same weight attracting one another with a force varying as the distance, slide on a smooth parabolic shaped wire, whose axis is

vertical and vertex upwards: show that if they are in equilibrium in *any* symmetrical position, they are so in *every* one. [Coll. Ex., 1887.]

Ex. 5. Two mutually attracting or repelling particles are placed in a parabolic groove, and connected by a thread which passes through a small ring at the focus; prove that if the particles be at rest, the line joining the vertex to the focus will be a mean proportional between the abscissæ measured from the vertex. [Math. T. 1852.]


X Ex. 6. A weight  $W$  is drawn up a rough conical hill of height  $h$  and slope  $\alpha$  and the path cuts all the lines of greatest slope at an angle  $\beta$ . If the friction be  $\mu$  times the normal pressure prove that the work done in attaining the summit will be  $Wh(1 + \mu \cot \alpha \sec \beta)$ . [St John's Coll., 1887.]

### Astatic Equilibrium

70. Suppose that three forces  $P, Q, R$  acting at a point are in equilibrium. We may clearly turn the forces round that point through any angle without disturbing the equilibrium if only the magnitudes of the forces and the angles between them are unaltered. Since a force may be supposed to act at any point of its line of action these three forces may act at any points  $A, B, C$  in their respective initial lines of action. If now we turn the forces supposed to act at  $A, B, C$ , each round its own point of application, through the same angle it is clear the equilibrium will be disturbed unless these points are so chosen that the lines of action of the forces continue to intersect in some point (Art. 34).

It is evident that instead of turning the forces round their points of application we may turn the body round any point through any angle. In this case each force preserves its magnitude unaltered, continues to act parallel to its original direction supposed fixed in space, while the point of application remains fixed in the body and moves with it. *When equilibrium is undisturbed by this rotation, it is called Astatic.*

71. Let  $A$  and  $B$  be the points of application of the forces  $P$  and  $Q$ . Let their lines of action intersect in  $O$ . Then as the forces turn round  $A$  and  $B$ , in the plane  $AOB$ , the angle between them is to remain unaltered. Hence  $O$  will trace out a circle passing through  $A$  and  $B$ . The resultant of these two forces passes through  $O$  and makes constant angles with both  $OA$  and  $OB$ . It therefore will cut the circle in a fixed point  $C$ . This resultant is equal and opposite to the force called  $R$ .



If therefore three forces  $P, Q, R$ , acting at three points  $A, B, C$ , intersect on the circle circumscribing  $ABC$ , and be in equilibrium, the equilibrium will not be disturbed by turning the forces round their points of application through any angle in the plane of the forces. This proof is given in Moigno's *Statics*, p. 228.

If the forces  $P$  and  $Q$  are parallel, the circle of construction becomes the straight line  $AB$ . The point  $C$  lies on  $AB$ , and the sines of the angles  $AOC, BOC$  are ultimately proportional to  $AC$  and  $CB$ . Hence  $AC$  is to  $CB$  inversely in the ratio of the forces tending to  $A$  and  $B$ . If the forces  $P, Q$ , besides being parallel, are equal and opposite, the force  $R$  acts at a point on the straight line at infinity.

**72.** When two forces  $P_1, P_2$  act at given points  $A, B$  the point at which the resultant acts, however the forces are turned round, is called the *centre of the forces*. If a third force  $P_3$  act at a third given point  $C$ , we may combine the resultant of the first two with this force and thus obtain a resultant acting at another fixed point in the body. This is the centre of the three forces. Thus we may proceed through any number of forces. We see that we can obtain a single force acting at a fixed point of the body which is the resultant of any number of given forces acting at any given fixed points in one plane. This single force will continue to be the resultant and to act at the same point when all the forces are turned round their points of application through any angle. This force is called their *astatic resultant*.

**73. Astatic triangle of forces.** This proposition leads us to another method of using the triangle of forces. Referring to the figure of Art. 71, we see that the angles  $ABC, AOC$  and  $BAC, BOC$  being angles in the same segment are equal each to each. If therefore  $P, Q, R$  are in equilibrium, they are proportional to the sines of the angles of the triangle  $ABC$ . It follows that  $P, Q, R$  are also proportional to the sides of the triangle  $ABC$ . Thus

$$P : BC = Q : CA = R : AB.$$

The points  $A, B, C$  divide the circle into three segments  $AB, BC, CA$ . If  $O$  be taken on any one of the segments, say  $AB$ , then the forces whose lines of action pass through  $A$  and  $B$  must act both to or both from  $A$  and  $B$ . The third force acts from or to  $C$  according as the first two act towards or from  $A$  and  $B$ . We deduce the following proposition.

Let three forces act at the corners of a triangle  $ABC$ ; they will be in equilibrium if (1) their magnitudes are proportional to the opposite sides, (2) their lines of action meet in any point  $O$  on the circumscribing circle, (3) their directions obey the rule given above. Also the equilibrium will not be disturbed by turning all the forces round their points of application through any, the same angle, but without altering their magnitudes. The forces are supposed to act in the plane of the triangle.

**74. Ex. 1.** Any number of forces  $P, Q, R, S$  &c. in one plane are in equilibrium, and their lines of action meet in one point  $O$ . Through  $O$  describe any circle

cutting the lines of action of the forces in  $A, B, C, D$  &c. If these points are regarded as the points of application of the forces, prove that the equilibrium is astatic.

Ex. 2. If  $CC'$  is drawn parallel to the opposite side  $AB$  to cut the circle in  $C'$ , prove that the forces  $P, Q, R$  make equal angles with the sides  $BC', C'A, AB$  of the triangle  $BC'A$ . Thence deduce from Art. 35 the conditions of equilibrium.

Ex. 3. If  $\alpha, \beta$  are the angles the forces  $P$  and  $Q$  make with their resultant  $R$ , prove that the position of the centres of the forces is given by

$$CE = \frac{AE}{\cot \beta} = \frac{BE}{\cot \alpha} = \frac{AB}{\cot \alpha + \cot \beta},$$

where  $CED$  is drawn from  $C$  perpendicular to  $AB$ .

Ex. 4. Let the forces act from a point  $O$  towards  $A$  and  $B$  where  $O$  is on the left or negative side of  $AB$  as we look from  $A$  towards  $B$ . If  $p, q$  are the coordinates of  $A, p', q'$  of  $B$  referred to any rectangular axes, prove that the coordinates of the central point of  $A$  and  $B$  are given by

$$\begin{aligned} (\cot \alpha + \cot \beta)x &= p \cot \alpha + p' \cot \beta + (q' - q) \\ (\cot \alpha + \cot \beta)y &= q \cot \alpha + q' \cot \beta - (p' - p) \end{aligned}$$

If the forces  $P$  and  $Q$  are at right angles, prove also that

$$\begin{aligned} (P^2 + Q^2)x &= pP^2 + p'Q^2 + (q' - q)PQ \\ (P^2 + Q^2)y &= qP^2 + q'Q^2 - (p' - p)PQ \end{aligned}$$

These are obtained by projecting  $AE, EC$  on the coordinate axes.

### *Stable and Unstable Equilibrium*

75. Let us suppose a body to be in equilibrium in any position, which we may call  $A$ , under the action of any forces. If the body be now moved into some neighbouring position  $B$  and placed there at rest, it may either remain in equilibrium in its new position (as in Art. 71) or the body may begin to move under the action of the forces. In the first case the position  $A$  is called one of *neutral equilibrium*. In the second case the equilibrium in the position  $A$  is called *unstable* or *stable* according as the body during its subsequent motion does or does not deviate from the position  $A$  beyond certain limits. The magnitude of these limits will depend on the circumstances of the case. Sometimes they are very restricted, so that the deviation permitted must be infinitesimal; in other cases greater latitude may be admissible.

The determination of the stability of a state of equilibrium is a dynamical problem. We must according to this definition examine the whole of the subsequent motion to determine the extent of the deviations of the body from the position of equilibrium. But sometimes we may settle this question from statical considerations. If the conditions of the problem are such that for all displacements of the body from the position  $A$  within certain




limits, the forces tend to bring the body back to that position, then the position may be regarded as stable for displacements within those limits. If on the other hand the forces tend to remove the body further from the position  $A$ , that position may be regarded as unstable. This cannot however be strictly proved to be a sufficient condition until we have some dynamical equations at our disposal. Properly we should, for the present, distinguish this as the criterion of statical stability or statical instability. But for the sake of brevity we shall omit this distinction, except when we wish to draw special attention to it.

**76.** Two equal given forces  $P$ ,  $Q$  act on a body at two given points  $A$ ,  $B$ , and are in equilibrium. They therefore act along the straight line  $AB$ . Let the body be now turned round through any angle less than two right angles and let the forces continue to act at these points in directions fixed in space. It is required to find the condition of stability.

Referring to the figure, it is evident that the forces tend to restore the body to its former position if *each force acts from the point of application of the other force*, while they tend to move the body further from that position if *each force acts towards the point of application of the other*. In the first case the equilibrium is stable, in the second unstable.

If the body be turned round through two right angles, the forces will again be in equilibrium. The position of stable equilibrium will then be changed into one of unstable equilibrium and conversely.




**77. Ex. 1.** A smooth circular ring is fixed in a horizontal position, and a small ring sliding upon it is in equilibrium when acted on by two forces in the directions of the chords  $PA$ ,  $PB$ . Prove that, if  $PC$  be a diameter of the circle, the forces are in the ratio of  $BC$  to  $AC$ . If  $A$  and  $B$  be fixed points and the magnitude of the forces remain the same, show that the equilibrium is unstable. [Math. Tripos, 1854.]

**Ex. 2.** Three given forces  $P$ ,  $Q$ ,  $R$ , act on a body in one plane at three given points  $A$ ,  $B$ ,  $C$  and are in equilibrium. When the body is disturbed, the forces continue to act at these points parallel to directions fixed in space and their magnitudes are unaltered. Find the condition of stability. See also Art. 221.

In the given position of equilibrium the lines of action of the forces must meet in some point  $O$ . If this point lie on the circle circumscribing  $ABC$  we know by Art. 71 that the equilibrium is neutral.

Next let the point  $O$  lie *within* the segment of the circumscribing circle contained by the angle  $ACB$ . Let  $P$  and  $Q$  act towards  $A$ ,  $B$  while  $R$  acts from  $C$  towards  $O$ .

Describe a circle about  $OAB$  cutting  $OC$  in  $C'$ . Then since  $O$  is within the circumscribing circle,  $C'$  is without that circle. By Art. 71, the forces  $P$  and  $Q$  are statically equivalent to a force equal and opposite to  $R$  but acting at  $C'$ . Thus the whole system is equivalent to two equal forces acting at  $C$  and  $C'$  and each tending away from the point of application of the other. The equilibrium is therefore stable for all rotatory displacements less than two right angles. In the same way if the forces  $P, Q$  act respectively from  $A$  and  $B$  towards  $O$  the equilibrium is unstable.



If the point  $O$  lie *outside* the circumscribing circle, but within the angle  $ACB$ , the point  $C'$  is within that circle. The conditions are then reversed, and therefore if the forces  $P, Q$  tend from  $O$  towards  $A, B$  the equilibrium is unstable.

If the point  $O$  lie within the triangle  $ABC$ , all the three forces must act from  $O$  or all the three towards  $O$ . By the same reasoning as before we may show that in the former case the equilibrium is stable, in the latter unstable.

Summing up, we have the following result. If two at least of the forces in equilibrium act from the common point of intersection  $O$  towards their points of application  $A, B, C$ ; then the equilibrium is stable if  $O$  lie within the circle circumscribing  $ABC$  and unstable if  $O$  lie outside that circle. If two at least of the forces act from their points of application towards  $O$ , these conditions are reversed.

Ex. 3. A particle is in equilibrium at a point  $O$  on a smooth surface under the action of forces which have a potential, and  $Oz$  is the common normal to the surface of constraint and that level surface which passes through  $O$ . The particle being displaced through a small arc  $OP = ds$ , prove that the resolute  $F$  of the force of restitution in the direction of the tangent at  $P$  to  $OP$  is  $F = \left(\frac{1}{\rho} - \frac{1}{\rho'}\right) Z ds$ , where  $Z$  is the equilibrium pressure and  $\rho, \rho'$  are the radii of curvature of the normal sections of the two surfaces made by the plane  $zOP$ .

Let  $z = PN$  be a perpendicular on the plane of  $xy$ ;  $X', Y', Z'$  the resolved forces at  $P$ , and  $\phi$  the angle  $xON$ . Since  $ds/\rho$  is the angle the tangent at  $P$  to the normal section  $zOP$  makes with  $ON$ , we have when the squares of small quantities are neglected

$$F = -X' \cos \phi - Y' \sin \phi - Z' ds/\rho,$$

where we may write for  $Z'$  its equilibrium value. Since  $z$  is of the second order  $X', Y', Z'$  at  $P$  have the same values as at  $N$ ; hence the two first terms have the same values for all surfaces which touch the plane at  $O$ . But  $F = 0$  when the surface is a level surface, hence these terms  $= Z ds/\rho'$ .

It follows that when the level surface intersects the surface of constraint the equilibrium is stable for some displacements and unstable for others, the separating line being the intersection. If the level surface lies wholly on one side of the surface of constraint, the equilibrium is stable for all displacements or unstable for all.

We suppose that the particle is constrained, either to return to its position of equilibrium by the way it came, or to recede further on that course. The constraining force  $F'$  acts perpendicularly to the section  $zOP$ , and by considering the angle of torsion at  $P$ , we find that its magnitude is  $F' = Z ds \sin \phi \cos \phi \left(\frac{1}{\rho_1} - \frac{1}{\rho_2} - \frac{1}{\rho'_1} + \frac{1}{\rho'_2}\right)$ , where  $\rho_1, \rho_2; \rho'_1, \rho'_2$  are the principal radii of curvature of the two surfaces.

## CHAPTER III

### PARALLEL FORCES

78. *To find the resultant of two parallel forces.*

Let the two parallel forces be  $P, Q$  and let them act at  $A, B$ , which of course are any points in their lines of action. In order to obtain a point of intersection of the forces at a finite distance let us impress at  $A, B$  in opposite directions two equal forces of any magnitude, each of which we may represent by  $F$ , Art. 15. The resultants of  $P, F$  and  $Q, F$  act respectively along some straight lines  $AO, BO$  which intersect in  $O$ .

Thus we have replaced the two given forces by two others, each of which may be supposed to act at  $O$ . Draw  $OC$  parallel to  $AP, BQ$  to cut  $AB$  in  $C$ . Consider the force acting at  $O$  along  $OA$ . We may resolve this force (as in Duchayla's proof of the parallelogram of forces) into two forces, one equal to  $P$  acting along  $OC$  and the other equal to  $F$  acting parallel to  $CA$ . In the same way the other force acting at  $O$  along  $OB$  is equivalent to  $Q$  acting along  $OC$  and  $F$  acting at  $O$  parallel to  $CB$ .

The two forces each equal to  $F$  balance each other and may be removed. The whole system is therefore reduced to the single force  $P + Q$  acting along  $OC$ .


The sides of the triangle  $OCA$  are parallel to  $P, F$  and their resultant. Hence  $\frac{OC}{CA} = \frac{P}{F}$ . In the same way  $\frac{OC}{CB} = \frac{Q}{F}$ . We

therefore have 
$$\frac{AC}{Q} = \frac{BC}{P} = \frac{AB}{P + Q}.$$

*The resultant of the parallel forces  $P, Q$  is  $P + Q$ , and its line of action divides every straight line  $AB$  which intersects the forces in the inverse ratio of the forces.*

If the forces  $P, Q$  act in opposite directions the proof is the

same, but the figure is somewhat different. If  $Q$  be greater than  $P$ ,  $BO$  will make a smaller angle with the force  $Q$  than  $OA$  makes



with the force  $P$ . Hence  $O$  will lie within the angle  $QBC$ . In this case the magnitude of the resultant is  $Q - P$  and its line of action divides  $AB$  externally in the inverse ratio of  $P$  to  $Q$ .

We also notice that,  $A, B$  being any two points in the lines of action of the parallel forces  $P, Q$ , the point  $C$  through which the resultant acts is the centroid of two particles placed at  $A$  and  $B$  whose masses are proportional to the forces which act at those points (Art. 53).

**79.** Conversely any given force  $R$  acting at a given point  $C$  may be replaced by two parallel forces acting at two arbitrary points  $A$  and  $B$ , where  $A, B, C$  are in one straight line. Let us represent these forces by  $P$  and  $Q$ .

Let  $CA = a$ ,  $CB = b$ , and let these be regarded as positive when measured from  $C$  in the same direction. We then find

$$P + Q = R, \quad P = \frac{b}{b-a} R, \quad Q = \frac{a}{a-b} R.$$

If  $A$  and  $B$  lie on the same side of  $C$ ,  $a$  and  $b$  are positive; in this case the force nearer  $R$  acts in the same direction as  $R$ , the other force acts in the opposite direction and is therefore negative. If  $C$  lie between  $A$  and  $B$ , one of the two distances  $a, b$  is negative; in this case both forces act in the same direction as  $R$ .

**80.** To find the resultant of any number of parallel forces  $P_1, P_2$  &c. acting at any points  $A_1, A_2$  &c. when referred to any axes.

Let  $(x_1 y_1 z_1), (x_2 y_2 z_2)$  &c. be the Cartesian coordinates of the points  $A_1, A_2$  &c. The forces  $P_1, P_2$  acting at  $A_1, A_2$  are equivalent to a single force  $P_1 + P_2$  acting at a point  $C_1$  situated in  $A_1 A_2$  such that  $P_1 \cdot A_1 C_1 = P_2 \cdot A_2 C_1$  (Art. 78). Let  $(\xi_1 \eta_1 \zeta_1)$  be the coordinates of  $C_1$ . Since  $A_1 C_1, A_2 C_1$  are in the ratio of their projections on the axes of coordinates we have

$$P_1 (\xi_1 - x_1) = P_2 (x_2 - \xi_1) \\ \therefore (P_1 + P_2) \xi_1 = P_1 x_1 + P_2 x_2.$$

Similar results apply for the other coordinates of  $C_1$ .

The force  $P_1 + P_2$  acting at  $C_1$  and a third force  $P_3$  acting at  $A_3$  are in the same way equivalent to  $P_1 + P_2 + P_3$  acting at a point  $C_2$  whose coordinates  $(\xi_2, \eta_2, \zeta_2)$  are given by

$$\begin{aligned}(P_1 + P_2 + P_3) \xi_2 &= (P_1 + P_2) \xi_1 + P_3 x_3 \\ &= P_1 x_1 + P_2 x_2 + P_3 x_3\end{aligned}$$

with similar expressions for  $\eta_2$  and  $\zeta_2$ .

Proceeding in this way we see that the resultant of all the forces is  $P_1 + P_2 + \dots$  and if  $(\xi, \eta, \zeta)$  be the coordinates of its point of application, we have

$$(P_1 + P_2 + \&c.) \xi = P_1 x_1 + P_2 x_2 + \&c.$$

$$(P_1 + P_2 + \&c.) \eta = P_1 y_1 + P_2 y_2 + \&c.$$

$$(P_1 + P_2 + \&c.) \zeta = P_1 z_1 + P_2 z_2 + \&c.$$

These equations are usually written

$$\xi = \frac{\sum Px}{\sum P}, \quad \eta = \frac{\sum Py}{\sum P}, \quad \zeta = \frac{\sum Pz}{\sum P}.$$

**81.** It might be supposed that this proof would either fail or require some modification if any one of the partial resultants  $P_1 + P_2$ ,  $P_1 + P_2 + P_3$  &c. were zero, for then some of the quantities  $\xi_1, \xi_2$  &c. would be infinite. The final result also might be thought to fail if  $\sum P = 0$ . But any proposition proved true for general values of the forces must be true for these limiting cases, though its interpretation may not be understood until we come to the theory of couples.

We may avoid this apparent difficulty by a slight modification of the proof. Let us separate the forces which act in one direction from those which act in the opposite direction, thus forming two groups. Let us suppose the sums of the forces in the two groups are unequal. If we compound together first all the forces in that group in which the sum is greatest and then join to these one by one the forces of the other group, it is clear that we shall never have any of the partial resultants equal to zero and no point of application of any such partial resultant will be at infinity. If the sums of the forces in the two groups are equal, the centre of parallel forces is infinitely distant.

**82.** The expressions for the coordinates  $(\xi, \eta, \zeta)$  are the same as those given in Art. 51 for the coordinates of the centroid; we therefore deduce the following rule.

*To find the resultant of the parallel forces  $P_1, P_2$  &c. we select convenient points  $A_1, A_2$  &c. on their respective lines of action and place at these points particles whose masses are proportional to the forces  $P_1, P_2$  &c. The line of action of the resultant passes through the centroid of these particles, its direction is parallel to that of the forces, and its magnitude is  $\sum P$ .*

Conversely, any given force can be replaced by parallel forces acting at arbitrary points  $A_1, A_2$  &c. provided the forces are such that the centroid lies on the given force.

This proposition is really the limiting case of Leibnitz's theorem. If concurrent forces act along  $OA_1, OA_2$  &c. their resultant may be found by any of the methods considered in the last chapter. By regarding  $O$  as a point very distant from  $A_1, A_2$  &c., the forces acting along  $OA_1, OA_2$  &c. become parallel and the corresponding theorem follows at once. Thus in Art. 51 it is shown that the resultant of forces proportional to  $P_1 \cdot OA_1, P_2 \cdot OA_2$  &c. is a force proportional to  $\Sigma P \cdot OC$  acting along  $OC$  where  $C$  is the centroid of particles  $P_1, P_2$  &c. placed at  $A_1, A_2$  &c. In the limit  $OA, OB, OC$  are all equal; hence the resultant of parallel forces proportional to  $P_1, P_2$  &c. is proportional to  $\Sigma P$  and acts at  $C$ .

83. The point  $(\xi\eta\zeta)$  determined by the equations of Art. 80 has one important property. Its position is the same whatever be the magnitudes of the angles made by the forces with the co-ordinate axes. If then *the points of application of the given parallel forces viz.  $A_1, A_2$  &c. are regarded as fixed in the body, the point of application of their resultant is also fixed in the body however the forces are turned round their points of application provided they remain parallel and unaltered in magnitude.*

This point of application of the resultant is called the "*centre of parallel forces.*"

84. Ex. 1. Parallel forces, each equal to  $P$ , act at the corners  $A, B, C, D$  of a re-entrant plane quadrilateral and a fifth force equal to  $-P$  acts at the intersection  $H$  of the diagonals  $HCA, BHD$ . If the centre of the five parallel forces coincide with a corner  $C$  of the quadrilateral, prove that  $HC=CA$ .

Ex. 2.  $ABC$  is a triangle;  $APD, BPE, CPF$ , the perpendiculars from  $A, B, C$  on the opposite sides. Prove that the resultant of six equal parallel forces, acting at the middle points of the sides of the triangle and of the lines  $PA, PB, PC$ , passes through the centre of the circle which goes through all of these middle points.

[Math. Tripos, 1877.]

Ex. 3.  $ABCD$  is a quadrilateral whose diagonals intersect in  $O$ . Parallel forces act at the middle points of  $AB, BC, CD, DA$  respectively proportional to the areas  $AOB, BOC, COD, DOA$ . Prove that the centre of parallel forces is at the fourth angular point, viz.  $G$ , of the parallelogram described on  $OE, OF$  as adjacent sides where  $E, F$  are the middle points of the diagonals  $AC, BD$  of the quadrilateral.

[Coll. Ex., 1885.]

Taking  $BD$  as the axis of  $x$  we find  $\eta = \frac{1}{2}(p-p')$  where  $p, p'$  are the perpendiculars from  $A$  and  $C$  on  $BD$ . It follows that the centre of parallel forces lies on  $EG$ . Similarly it lies on  $FG$ .

85. *To find the conditions of equilibrium of a system of parallel forces.*

Let the forces be  $P_1, \dots P_n$ ; then by Art. 80 they will have a resultant unless  $\Sigma P = 0$ . This, though a necessary condition of equilibrium, is not sufficient.

We can find the resultant of  $n-1$  of the forces by Art. 80 without introducing any forces whose lines of action are at infinity, because the sum of these  $n-1$  forces is equal to  $-P_n$  and therefore is not zero. It is sufficient for equilibrium that the point of application of this resultant should be situated on the line of action of  $P_n$ .

Let  $(\xi\eta\zeta)$  be the coordinates of that point of application of this resultant which is found in Art. 80, then

$$\xi = \frac{P_1x_1 + \dots + P_{n-1}x_{n-1}}{P_1 + \dots + P_{n-1}}$$

with similar expressions for  $\eta$  and  $\zeta$ . Let  $(\alpha\beta\gamma)$  be the direction angles of the forces.

Since  $\xi - x_n$ ,  $\eta - y_n$ ,  $\zeta - z_n$  are the projections on the axes of the straight line joining the point  $(\xi\eta\zeta)$  to the point of application of the force  $P_n$ , viz.  $(x_ny_nz_n)$ , we have

$$\frac{\xi - x_n}{\cos \alpha} = \frac{\eta - y_n}{\cos \beta} = \frac{\zeta - z_n}{\cos \gamma}.$$

Substituting for  $(\xi\eta\zeta)$  and remembering that the denominator of  $\xi$  is equal to  $-P_n$ , this reduces to

$$\frac{\Sigma Px}{\cos \alpha} = \frac{\Sigma Py}{\cos \beta} = \frac{\Sigma Pz}{\cos \gamma} \dots\dots\dots(1).$$

Joining these two equations to the condition  $\Sigma P = 0$ , we have *the three necessary and sufficient conditions of equilibrium.*

If the equilibrium is to exist however the forces are turned round their points of application, the point of application of the resultant of the first  $n-1$  forces as found by Art. 80 must coincide with the given point of application of the force  $P_n$ . We have therefore

$$\xi = x_n, \quad \eta = y_n, \quad \zeta = z_n.$$

These give  $\Sigma Px = 0, \quad \Sigma Py = 0, \quad \Sigma Pz = 0 \dots\dots\dots(2).$

Joining these three equations to  $\Sigma P = 0$  we have *the four necessary and sufficient conditions that a system of parallel forces should be astatically in equilibrium.*

**86. Ex. 1.** Prove that any system of parallel forces can be replaced by three parallel forces acting at the corners of an arbitrary triangle  $ABC$ .

Let  $P$  be any one of the forces, intersecting the plane of the triangle in a point whose areal coordinates are  $x, y, z$ , Art. 53, Ex. 2. We may replace  $P$  by the parallel forces  $Px, Py, Pz$ , acting at the corners, Art. 82. All the forces are therefore equivalent to  $\Sigma Px, \Sigma Py, \Sigma Pz$  acting at  $A, B, C$ , respectively.

**Ex. 2.** If four parallel forces balance each other, let their lines of action be intersected by a plane, and let the four points of intersection be joined by six

straight lines so as to form four triangles; each force will be proportional to the area of the triangle whose corners are in the lines of action of the other three.

[Rankine's *Applied Mathematics*, Art. 143.]

87. A heavy body is suspended from a fixed point without any other constraint. It is required to find the position of equilibrium.


The body is in equilibrium under the action of the weights of all its elements and the reaction at the point of support. The weights of the elements form a system of parallel forces and are equivalent to the whole weight of the body acting vertically downwards at the centre of gravity. It easily follows that *in equilibrium, the centre of gravity must be vertically under the point of support*. It is also clear that the pressure on the point of support is equal to the weight of the body.

In applying this principle to examples, the positions of the centres of gravity of the elementary bodies are assumed to be known. The positions of these points will be stated as they are required. If the reader is not already acquainted with them, he may either assume the results given or refer to the chapter on the centre of gravity where their proofs may be found.

Ex. 1. A uniform triangular area  $ABC$  is suspended from a fixed point  $O$  by three strings attached to its corners. Prove that the tensions of the strings are proportional to their lengths.

To find the centre of gravity  $G$  of the triangle  $ABC$ , we draw the median line  $AM$  bisecting  $BC$  in  $M$ . Then  $G$  lies in  $AM$ , so that  $AG = \frac{2}{3}AM$ .

The three tensions acting along  $AO$ ,  $BO$ ,  $CO$  and the weight acting along  $OG$  are in equilibrium. The resultant of the tension  $AO$  and the weight is therefore equal and opposite to that of the tensions  $BO$ ,  $CO$ . Since each resultant acts in the plane of the forces of which it is the resultant, their common line of action is  $OM$ .



Draw through  $B$  and  $C$  parallels to  $OC$  and  $OB$ , and let  $D$  be their point of intersection. Then, since  $OM$  bisects  $BC$ ,  $OM$  passes through  $D$ . Hence the sides of the triangle  $OCD$  are parallel to the tensions  $CO$ ,  $BO$  and their resultant. The tensions are therefore proportional to  $OC$ ,  $CD$ , i.e. to  $OC$ ,  $OB$ .

Another proof may be deduced from Art. 51. The centre of gravity of the triangular area coincides with the centre of gravity of three equal weights placed one at each corner. The components along  $OA$ ,  $OB$ ,  $OC$  of the force represented by 3.  $OG$  are therefore represented by the lengths of those lines.

Ex. 2. A heavy triangle  $ABC$  is hung up by the angle  $A$ , and the opposite side is inclined at an angle  $\alpha$  to the horizon. Show that  $2 \tan \alpha = \cot B \sim \cot C$ .

[Math. Tripos, 1865.]

Ex. 3. Two uniform heavy rods  $AB$ ,  $BC$  are rigidly united at  $B$ , the rods are then hung up by the end  $A$ : show that  $BC$  will be horizontal if  $\sin C = \sqrt{2} \sin \frac{1}{2}B$ ,  $B$  and  $C$  being angles of the triangle  $ABC$ .

[Coll. Ex., 1883.]



Ex. 4. A heavy equilateral triangle, hung up on a smooth peg by a string, the ends of which are attached to two of its angular points, rests with one of its sides vertical; show that the length of the string is double the altitude of the triangle.

[Math. Tripos, 1857.]

Ex. 5. A piece of uniform wire is bent into three sides of a square  $ABCD$ , of which the side  $AD$  is wanting; prove that if it be hung up by the two points  $A$  and  $B$  successively, the angle between the two positions of  $BC$  is  $\tan^{-1} 18$ .

The distance of the centre of gravity  $G$  from  $BC$  can be shown to be equal to one third of  $AB$ . When hung up from  $A$  and  $B$ ,  $AG$  and  $BG$  respectively are vertical. The angle required is therefore equal to  $AGB$ . [Math. Tripos, 1854.]

Ex. 6. A triangle  $ABC$  is successively suspended from  $A$  and  $B$ , and the two positions of any side are at right angles to each other; prove that  $5c^2 = a^2 + b^2$ .

[Coll. Ex.]

Ex. 7. A uniform circular disc of weight  $nW$  has a heavy particle of weight  $W$  attached to a point on its rim. If the disc be suspended from a point  $A$  on its rim,  $B$  is the lowest point; and if suspended from  $B$ ,  $A$  is the lowest point. Show that the angle subtended by  $AB$  at the centre is  $2 \sec^{-1} 2(n+1)$ . [Math. Tripos, 1883.]

Ex. 8. The altitude of a right cone is  $h$  and the radius of its base is  $r$ ; a string is fastened to the vertex and to a point on the circumference of the circular base and is then put over a smooth peg: prove that if the cone rests with its axis horizontal the length of the string is  $\sqrt{(h^2 + 4r^2)}$ . [Math. Tripos, 1865.]

If  $V$  be the vertex and  $C$  the centre of gravity of the base of a cone (either right or oblique), the centre of gravity of the solid cone lies in  $VC$ , so that  $VG = \frac{3}{4}VC$ .

Ex. 9. A string nine feet long has one end attached to the extremity of a smooth uniform heavy rod two feet in length, and at the other end carries a light ring which slides upon the rod. The rod is suspended by means of the string from a smooth peg; prove that if  $\theta$  be the angle which the rod makes with the horizon, then  $\tan \theta = 3 - \frac{1}{3} - 3 - \frac{2}{3}$ . [Math. Tripos, 1852.]

Ex. 10. A heavy uniform rod of length  $2a$  turns freely on a pivot at a point in it, and suspended by a string of length  $l$  fastened to the ends of the rod hangs a bead of equal weight which slides on the string. Prove that the rod cannot rest in an inclined position unless the distance of the pivot from the middle point of the rod be less than  $a^2/l$ . [Math. Tripos, 1882.]

Ex. 11. Two equal rods  $AB, BC$  of length  $2a$  are connected by a free hinge at  $B$ ; the ends  $A$  and  $C$  are connected by an inextensible string of length  $l$ : the system is suspended from  $A$ : prove that, in order that the angle  $AB$  makes with the vertical may be the greatest possible,  $l$  must be equal to  $4a/\sqrt{3}$ . [St John's Coll., 1883.]

As  $l$  is varied the centre of gravity  $G$  of the system moves along the circle described on  $BE$  as diameter, where  $E$  is the middle point of  $AB$ . Hence the angle  $GAB$  is greatest when  $AG$  is a tangent to this circle.

Ex. 12. At the angular points  $A, B, C$  of a light rigid frame-work, three heavy particles of weights  $W_A, W_B, W_C$  are fixed and the whole is suspended from a point  $O$  by three strings  $OA, OB, OC$ ; if the tensions in equilibrium be  $T_A, T_B, T_C$  respectively, prove that  $\frac{T_A}{OA \cdot W_A} = \frac{T_B}{OB \cdot W_B} = \frac{T_C}{OC \cdot W_C}$ , and hence determine  $T_A, T_B, T_C$ . [St John's Coll., 1886.]

Ex. 13. A heavy triangular lamina is suspended from a fixed point by means of three elastic strings attached to its angular points: the strings when unstretched

are equal in length, but the moduli of their elasticities are different. that the tension of each is equal to the modulus multiplied by the extension to the unstretched length, prove that the strings will be equal be placed at a certain point on the lamina, provided the weight be not certain weight: prove also that the locus of its position for different  $m$  & the weight, is a straight line. [Coll.]

✓ Ex. 14. A uniform circular disc, whose weight is  $w$  and radius  $a$ , is supported by three vertical strings attached to three points on the circumference separated by equal intervals. A weight  $W$  may be put down anywhere concentric circle of radius  $ma$ ; prove that the strings will not break support a tension equal to  $\frac{1}{3}(2mW + W' + w)$ . [Trin.]

Ex. 15. A right circular cone rests with its elliptic base on a smooth table. A string fastened to the vertex and the other end of the longer passes round a smooth pulley above the cone, so that all parts of the string in contact with the pulley are vertical. If the string become contracted by dampness or other causes and tend to lift the cone, the end of the shortest generator will remain in contact with the table that the diameter of the pulley be less than three times the semi-major elliptic base. [Math. Tr.]

88. A heavy body is placed on either a smooth horizontal plane or a rough inclined plane, and its base is any polygonal area. Determine whether it will tumble over one side or remain in equilibrium.

The weights of the particles of the body constitute a system of parallel forces. These have a resultant whose position and magnitude may be found by the theorem of Art. 80 when the positions of the particles are known. This resultant acts vertically downwards through a point of the body called its centre of gravity. If equilibrium exists, this must be balanced by the pressure of the plane on the body. These pressures however distributed over the polygonal area must have a resultant which acts at some point within the polygonal area. It follows that equilibrium will exist unless the vertical through the centre of gravity of the body intersects the plane within the area of the base.

✓ Ex. 1. The distance between the heels of a man's feet is  $2b$ , and the length of each foot is  $a$ . As the body sways, the vertical through the centre of gravity should always pass through the area contained by the feet. Therefore the body is turned out at such an angle that the area contained by the feet is a maximum. Show (1) that a circle can be described about the feet with its centre on the straight line joining the toes, (2) that its diameter is  $b + (b^2 + 2a^2)^{1/2}$ .

✓ Ex. 2. A heavy right cone whose height is  $h$  and semi-angle  $\alpha$  is placed on its base on a perfectly rough plane; prove that the cone will tumble over one side of its base if the angle  $\theta$  at which the plane is inclined to the horizontal is greater than that given by  $\tan \theta = 4 \tan \alpha$ .

Ex. 3. A hemispherical cup of weight  $W$  is loaded by two weights  $w, w'$  attached to its rim and is then placed on a smooth horizontal plane; show that the angle  $\theta$  which the principal radius of the cup makes with the vertical when the cup is in equilibrium is given by the equation

$$W \tan \theta = 2 \{ (w - w')^2 + 4ww' \cos^2 \beta \}^{\frac{1}{2}},$$

where  $2\beta$  is the angle between the radii through the weights  $w, w'$ , and it is assumed that the centre of gravity of the cup is at the middle point of its principal radius.

[King's Coll., 1889.]

Ex. 4. Two equal heavy particles are at the extremities of the latus rectum of a parabolic arc without weight, which is placed with its vertex in contact with that of an equal parabola, whose axis is vertical and concavity downwards. Prove that the parabolic arc may be turned through any angle without disturbing the equilibrium, provided no sliding be possible between the curves.

[Watson's Problem, Math. Tripos, 1860.]

### Theory of Couples

89. There is one case in which the theorem of Art. 80 leads to a remarkable result. Let us suppose that the parallel forces  $P, Q$  are equal and act in opposite directions. According to the theorem the magnitude of the resultant is zero, and the point of application is infinitely distant.

Two equal and opposite forces acting at two points  $A$  and  $B$  cannot balance each other unless these points are in the same straight line with the forces. Yet we have just seen that these two forces are not equivalent to any one single force at a finite distance. They therefore supply a new method of analysing forces. When a number of forces act on a body we simplify the system by reducing the forces to as few as we can. Sometimes we can reduce them to a single force acting at some point of the body. In other cases (as in the case considered in this article) the point of application is at infinity and the reduction to a single force is no longer convenient. By using a couple of equal forces, as a new elementary term, we obtain a simple method of expressing this infinitely distant force. We now have two elementary quantities, viz. a force and a couple. It may be possible to reduce a given system of forces to either or both of these constituents. With the help of both these, we may analyse a system of forces with greater completeness than with one alone.

If we regard a couple as a new element in analysis, it becomes necessary to consider the properties of such an element apart from all other combinations of forces. Since a couple can itself be

analysed into two forces we can deduce the properties of a couple from those which belong to a combination of forces. No new axiom is necessary in addition to those already given in the beginning of this treatise. We proceed in the following articles to investigate the elementary properties of a couple.

The theory of couples is due to Poinot. In his *Elements of Statics* published in 1803 he discusses the composition of parallel forces and deduces his new theory of couples. On this theory he founds the general laws of equilibrium.


**90. Definitions.** A system of two equal and parallel forces acting in opposite directions is called a *couple*.

The perpendicular distance between these two forces is called its *arm*. It should be noticed that the arm of a couple has length, but has no definite position in space. From any point  $A$  in the line of action of one force, a perpendicular  $AB$  can be drawn on the other force. Then  $AB$  is the arm. If in any case it is convenient to regard the forces as acting at  $A$  and  $B$ , then we might regard  $AB$ , if perpendicular to the forces, as representing the arm in position as well as in length.

✱✱ The product of the magnitude of either force into the length of the arm is called the *moment of the couple*.

✱✱ **91.** *The effect of a couple is not altered if it be moved parallel to itself to any other position in its own plane or in a parallel plane, the arm remaining parallel to itself.*

Let  $P, Q$  be the equal forces of the given couple,  $AB$  its arm. Let  $A'B'$  be equal and parallel to  $AB$ , we shall prove that the couple may be moved so that the same forces act at  $A', B'$ .




At each of the points  $A', B'$  apply two equal and opposite forces, each force being equal in magnitude to  $P$ . These are represented in the figure by  $P', P'', Q', Q''$ . Then because  $AB$  is equal and parallel to  $A'B'$ ,  $AA'B'B'$  is a parallelogram and therefore the diagonals  $AB', A'B$  bisect each other in some point  $O$ . The resultant of the forces  $P$  and  $Q''$  is  $2P$  acting at  $O$ , the resultant of  $P'$  and  $Q$  is  $2P$  also acting at  $O$ ,

but in the opposite direction. These two resultants neutralise each other. Removing them, the whole system of forces is equivalent to the couple of forces, which act at  $A'$  and  $B'$ .


**92.** The effect of a couple is not altered by turning the whole couple through any angle in its own plane about the middle point of any arm.

Let the arm  $AB$  be turned round its middle point  $C$  and let it take any position  $A'B'$ . At each of the points  $A'$ ,  $B'$  apply as before equal and opposite forces  $P'$ ,  $P''$ ,  $Q'$ ,  $Q''$ , each force being equal to  $P$ . The equal forces  $P$  and  $P''$  acting at  $A$  and  $A'$  have a resultant which acts along  $CE$  and bisects the angle  $ACA'$ . The forces  $Q$  and  $Q''$  have an equal resultant which acts along  $CF$  and bisects the angle  $BCB'$ . These neutralise each other and may be removed. The forces remaining are the equal forces  $P'$ ,  $Q'$  acting



at  $A'$ ,  $B'$ . These together constitute a couple, which is the same as the original couple except that it has been turned round  $C$  through the angle  $ACA'$ .

**93.** The effect of a couple is not altered if we replace it by another couple having the same moment, the plane remaining the same, the arms being in the same straight line and their middle points coincident.



Let  $P$ ,  $Q$  be the equal forces,  $AB$  the arm of the given couple. Let  $A'B'$  be the new arm,  $P'$ ,  $Q'$  the new forces. Apply at each

of the points  $A', B'$  equal and opposite forces, each equal to  $P'$ . Then by the conditions of the proposition,  $P \cdot AB = P' \cdot A'B'$ . Hence if  $C$  be the middle point of both  $AB$  and  $A'B'$ , we have  $P \cdot AC = P' \cdot A'C$ .

The forces  $P$  and  $P''$  have a resultant  $P - P''$  which by Art. 78 acts at  $C$ . In the same way  $Q$  and  $Q''$  have an equal resultant, also acting at  $C$  in the opposite direction. Removing these two, it follows that the given couple is equivalent to the couple of forces  $\pm P'$  acting at  $A', B'$ .

94. It follows from Arts. 91 and 92 that a couple may be transferred without altering its effect from one given position to any other given position in a parallel plane. Thus by Art. 92 we may turn a couple round the middle point of its arm until the forces become parallel to their directions in the second given position. Then by Art. 91 we may move the couple parallel to itself into the required position.

It follows from Art. 93 that the forces and the arm may also be changed without altering the effect of the couple, provided its moment is kept the same.

Summing up these results, we see that *a couple is to be regarded as given when we know, (1) the position of some plane parallel to the plane of the couple, (2) the direction of rotation of the couple in its plane, and (3) the moment of the couple.*

95. *To find the resultant of any number of couples acting in parallel planes.*

Let  $P_1, P_2$  &c. be the magnitudes of the forces,  $a_1, a_2$  &c. the arms of the couples. Let us first suppose the couples all tend to produce rotation in the same direction.

By Art. 94 we may move these couples into one plane and turn them about until their arms are in the same straight line. We may then alter the arms and forces of each until they all have a common arm  $AB$  whose length is, say, equal to  $b$ . The forces of the couples now act at the extremities of  $AB$ , and are respectively equal to  $P_1 a_1/b, P_2 a_2/b$  &c. All these together constitute a single couple each of whose forces is  $(P_1 a_1 + P_2 a_2 + \text{&c.})/b$  and whose arm is  $b$ . This single couple is equivalent to any other couple in the same plane with the same direction of rotation whose moment is

$P_1a_1 + P_2a_2 + \&c.$ , i.e. whose moment is the sum of the moments of the separate couples.

If some of the couples tend to produce rotation in the opposite direction to the others, we may represent this by regarding the forces of these couples as negative. The same result follows as before.

We thus obtain the following theorem; *the resultant of any number of couples whose planes are parallel is a couple whose moment is the algebraic sum of the moments of the separate couples and whose plane is parallel to those of the given couples.*

**96. Measure of a couple.** We may use the proposition just established to show that the magnitude of a couple regarded as a single element is properly measured by its moment. To prove this we assume as a unit the couple whose force is the unit of force and whose arm is the unit of length. The moment of this couple is unity. By this proposition a couple whose moment is  $n$  times as great is equivalent to  $n$  such couples and its magnitude is therefore properly represented by the symbol  $n$ .

**97. Axis of a couple.** A couple may tend to produce rotation in one direction or the opposite according to the circumstances of the couple. One of these is usually called the positive direction and the other the negative. Just as in choosing axes of coordinates sometimes one direction is taken as the positive one and sometimes the other, so in couples the choice of the positive direction is not always the same. In trigonometry the direction of rotation opposite to the hands of a watch is taken as the positive direction. In most treatises on conics the same choice is made. In solid geometry the opposite direction is generally chosen. Having however chosen one of these two directions as the positive one it is usual to indicate the direction of rotation of a given couple in the following manner.


From any point  $C$  in the plane of the couple draw a straight line  $CD$  at right angles to the plane and on one side of it. The straight line is to be so drawn that if an observer stand with his feet at  $C$  on the plane and his back along  $CD$ , the couple will appear to him to produce rotation in what has been chosen as the positive direction. The straight line  $CD$  is called the *positive direction of the axis of the couple*.

To indicate the direction of rotation of a couple it is sufficient to give the direction in space of  $CD$  as distinguished from  $DC$ . This is effected by the convention usually employed in solid geometry. A finite straight line having one extremity at the origin of coordinates is drawn parallel to  $CD$ . The position of this straight line is defined by the angles it makes with the *positive directions* of the axes of coordinates.

The position of the straight line  $CD$ , when given, indicates at once the plane of the couple and the direction of rotation. We may also use a length measured along  $CD$  to represent the magnitude of the moment of the couple, in just the same way as a straight line was used in Art. 7 to represent the magnitude of a force.

We therefore infer that all the circumstances of a couple may be properly represented by a finite straight line measured from a fixed point in a direction perpendicular to its plane. This finite straight line is called the *axis of the couple*.

98. To find the resultant of two couples whose planes are inclined to each other.



Let the two couples be moved, each in its own plane, until they have a common arm  $AB$ , which of course must lie in the intersection of the two planes. In effecting this change of arm it may have been necessary to alter the forces of the couples, but the moments of the couples must remain unaltered. Let the forces thus altered be  $P$  and  $Q$ .

At the point  $A$  we have two forces  $P$  and  $Q$ ; these are equivalent to some resultant  $R$  found by the parallelogram of forces. At the point  $B$  there are two forces equal and opposite to those at  $A$ ; their resultant is equal, parallel and opposite to  $R$ . Thus the two couples are equivalent to a single couple, each of



whose forces is equal to  $R$ , and whose arm is  $AB$ . Let the length of  $AB$  be  $b$ .

From any point  $C$  (which we may conveniently take in  $AB$ ) draw  $Cp, Cq$  in the directions of the axes of the given couples, and measure lengths along them proportional to their moments, viz. to  $Pb$  and  $Qb$ . These axes are perpendicular to the planes of the couples, and their lengths are also proportional to  $P$  and  $Q$ . If we compound these two by the parallelogram law we evidently obtain an axis perpendicular to the plane of the forces  $\pm R$ , whose length is proportional to  $R$ . It is evident that the parallelogram  $Cpqr$  is similar to that contained by the forces  $PQR$ , but the sides of one parallelogram are perpendicular to the sides of the other.

We therefore infer the following construction for the resultant of any two couples. *Draw two finite straight lines from any point  $C$  to represent the axes of the couples in direction and magnitude. The resultant of these two obtained by the parallelogram law represents in direction and magnitude the axis of the resultant couple.*

The rule to compound couples is therefore the same as that already given for compounding forces. It follows that all the theorems for compounding forces deduced from the parallelogram law also apply to couples. The working rule is that *if we represent the couples by their axes, we may compound and resolve these as if they were forces acting at a point.*

X 99. Ex. 1. A system of couples is represented in position and magnitude by the areas of the faces of a polyhedron, and their axes are turned all inwards or all outwards. Show that they are in equilibrium. Art. 47. *Möbius.*

Ex. 2. Four straight lines are given in space, prove that four couples can be found, having these for the directions of their axes, which are in equilibrium. Find also their moments and discuss the case in which three of the given straight lines are parallel to a plane, Arts. 40, 48.


X Ex. 3. Three couples are represented in position and magnitude by the areas of three faces  $OBC, OCA, OAB$  of the tetrahedron  $OABC$ , the axes of the first two being turned inwards and that of the third outwards. Prove that the resultant couple acts in the plane  $ODE$  bisecting the sides  $BC, CA$  and is represented by four times the area of the triangle  $ODE$ .

Soln. Replace each couple by another, one of whose forces passes through  $O$  and the other acts along a side of  $ABC$ . The forces represented by  $BC, CA$  and  $BA$  have evidently a resultant  $4DE$ .

100. A force  $P$  acting at any point  $A$  may be transferred parallel to itself, to act at any other point  $B$ , by introducing a couple

whose moment is  $Pp$ , where  $p$  is the perpendicular distance of  $B$  from the line of action  $AF$  of  $P$ . This couple acts to turn the body in the direction  $AFB$ .

Apply at  $B$  two equal and opposite forces  $P'$ ,  $P''$ , each equal to  $P$ . One of these, viz.  $P'$ , is the force  $P$  transferred to act at  $B$ . The two forces  $P''$  and  $P$  then constitute the couple whose moment is  $Pp$ .



101. Summing up the various propositions just proved on forces and couples, we find that they fall into three classes. These may be briefly stated thus:

1. Forces may be combined together according to the parallelogram law.
2. Couples may be combined together according to the parallelogram law.
3. A force is equivalent to a parallel force together with a couple.

The theorems in the subsequent chapters are obtained by continual applications of these three classes of propositions. It is therefore evident that theorems thus obtained will apply also to any other vectors for which these three classes of propositions are true. Thus in dynamics we find that the elementary relations of linear and angular velocities are governed by these three sets of propositions. We therefore apply to these, without further proof, all the theorems found to be true for couples and forces.

102. **Initial motion of the body.** If a single couple act on a body at rest, it is clear that the body will not remain in equilibrium. It is proved in treatises on dynamics that the body will begin to turn about a certain axis. Since a couple can be moved about in its own plane without altering its effect, this axis cannot depend on the position of the couple in its plane. The dynamical results are (1) the initial axis of rotation passes through the centre of gravity of the body, (2) the axis of rotation is not necessarily perpendicular to the plane of the couple, though this may sometimes be the case. The construction to find the axis is somewhat complicated, and its discussion would be out of place in a treatise on statics.

We may show by an elementary experiment that the axis of rotation is independent of the position of the couple in its plane. Let a disc of wood be made to float on the surface of water contained in a box. At any two points  $A$ ,  $B$  attach to the disc two fine threads and hang these over two small pulleys, fixed in the sides of the vessel at  $C$  and  $D$ , with equal weights suspended at

the other extremities. Let the strings  $AC, BD$  be parallel so that their tensions form a couple. Under the influence of this couple the body will begin to turn round. However eccentrically the points  $A, B$  are situated the body *begins* to turn round its centre of gravity. The body may not *continue* to turn round this axis for, as the body moves, the strings cease to be parallel. For this and other reasons the motion of rotation is altered.

**103.** Ex. 1. Forces  $P, 2P, 4P, 2P$  act along the sides of a square taken in order; find the magnitude and position of their resultant. [St John's, 1880.]

Ex. 2. A triangular lamina  $ABC$  is moveable in its own plane about a point in itself: forces act on it along and proportional to  $BC, CA, BA$ . Prove that if these do not move the lamina, the point must lie in the straight line which bisects  $BC$  and  $CA$ . [Math. Tripos, 1874.]

Ex. 3. Forces are represented in magnitude, direction, and position by the sides of a triangle taken in order; prove that they are equivalent to a couple whose moment is twice the area of the triangle.

If the sides taken in order represent the axes of three couples, prove that these couples are in equilibrium.

Ex. 4. If six forces acting on a body be completely represented three by the sides of a triangle taken in order and three by the sides of the triangle formed by joining the middle points of the sides of the original triangle, prove that they will be in equilibrium if the parallel forces act in the same direction and the scale on which the first three forces are represented be four times as large as that on which the last three are represented. [Math. Tripos.]

✓ Ex. 5. Four forces  $\alpha \cdot AB, \beta \cdot BC, \gamma \cdot CD, \delta \cdot DA$  act along the sides  $AB, BC, CD, DA$  of a skew quadrilateral  $ABCD$ ; show that (1) they cannot be in equilibrium, (2) if  $\alpha = \beta = \gamma = \delta$  they form a single couple whose plane is parallel to the diagonals  $AC, BD$ , (3) if  $\alpha\gamma = \beta\delta$  they reduce to a single resultant whose line of action intersects the diagonals. Find also the magnitudes of the couple and resultant. [Coll. Ex., 1892.]

The forces at the corners  $B$  and  $D$  have respectively resultants acting along some lines  $BE, DF$  cutting  $AC$  in  $E$  and  $F$ . Since the planes  $ABC, ADC$  do not coincide, these two partial resultants cannot act in the same straight line, and therefore cannot be in equilibrium.

If the forces are equivalent to a couple, the sum of their resolved parts along the perpendicular from  $B$  on the plane  $ADC$  is zero. This requires  $BE$  to be parallel to  $AC$  and gives  $\alpha = \beta$ ; similarly  $\beta = \gamma$  and  $\gamma = \delta$ . The partial resultants at  $B$  and  $D$  are  $\pm \alpha \cdot AC$ , and act parallel to  $AC$  and  $CA$ . The plane of the couple is therefore parallel to  $AC$ , similarly it is parallel to  $BD$ . The moment of the couple is  $4\alpha$  times the area of the parallelogram whose vertices are the middle points of the sides.

If the forces are equivalent to a single resultant the points  $E$  and  $F$  on  $AC$  must coincide; but  $E$  is the mean centre of  $-a$  and  $\beta$  at  $A$  and  $C$ , while  $F$  is the mean centre of  $\delta$  and  $-\gamma$  at the same points, Art. 51, hence  $\alpha\gamma = \beta\delta$ . The partial resultants now intersect in the point  $E$  on the diagonal  $AC$  and are represented by  $(\alpha - \beta)EB$  and  $(\gamma - \delta)ED$ . The single resultant therefore passes through  $E$  and a point  $H$  on the other diagonal  $BD$  and its magnitude is  $(\alpha - \beta + \gamma - \delta) \cdot EH$ .

If the quadrilateral is plane the four forces are equivalent to a single resultant

except when  $\alpha, \beta, \gamma, \delta$  are equal. The forces are in equilibrium when the partial resultants are equal and opposite, i.e. when

$$\alpha\gamma = \beta\delta, \quad \alpha \cdot AO + \beta \cdot OC = 0, \quad \beta \cdot BO + \gamma \cdot OD = 0,$$

where  $O$  is the intersection of the diagonals.

Ex. 6. Forces are represented in magnitude, direction, and position by the sides of a skew polygon taken in order; show that they are equivalent to a couple.

If the corners of the skew polygon are projected on any plane, prove that the resolved part of the resultant couple in that plane is represented by twice the area of the projected polygon.

Ex. 7.  $AC, BD$  are two non-intersecting straight lines of constant length; prove that the effect of forces represented in every respect by  $AB, BC, CD, DA$  is the same, so long as  $AC, BD$  remain parallel to the same plane, and the angle between their projections on that plane is constant. [Coll. Ex., 1881.]

Ex. 8. If two equal lengths  $Aa, Bb$ , are marked off in the same direction along a given straight line, and two equal lengths  $Cc, Dd$  along another given line, prove that forces represented in every respect by  $AC, ca, CB, bc, BD, db, DA, ad$  are in equilibrium. [Trin. Coll.]

Ex. 9. Forces proportional to the sides  $a_1, a_2, \dots$  of a closed polygon act at points dividing the sides taken in order in the ratios  $m_1:n_1, m_2:n_2, \dots$  and each makes the same angle  $\theta$  in the same sense with the corresponding side; prove that there will be equilibrium if  $\Sigma \left( \frac{m-n}{m+n} a^2 \right) = 4\Delta \cot \theta$ , where  $\Delta$  is the area of the polygon. [Math. Tripos, 1869.]

Resolve each force along and perpendicular to the corresponding side and transfer the latter component to act at the middle point by introducing a couple, Art. 100. The couples balance the components along the sides, Ex. 3. The other components are in equilibrium, Art. 37.

## CHAPTER IV


### FORCES IN TWO DIMENSIONS

**104.** *To find the resultant of any number of forces which act on a body in one plane, i.e. to reduce these forces to a force and a couple.*

Let the forces  $P_1, P_2$  &c. act at the points  $A_1, A_2$  &c. of the body. Let  $O$  be any point arbitrarily chosen in the plane of the forces, it is proposed to reduce all these forces to a single force acting at  $O$  and a couple.

Let the point  $O$  be taken as the origin of coordinates. Let the coordinates of  $A_1, A_2$  &c. be  $(x_1, y_1), (x_2, y_2)$  &c. Let the directions of the forces make angles  $\alpha_1, \alpha_2$  &c. with the positive side of the axis of  $x$ .

Referring to Art. 100 of the chapter on parallel forces, we see that any one of these forces as  $P$  may be transferred parallel to itself, to act at the point  $O$ , by introducing into the system a couple whose moment is  $Pp$ , where  $p$  is the length of the perpendicular  $ON$  drawn from  $O$  on the line of action of the force  $P$ . In this way all the given forces  $P_1, P_2$  &c. may be transferred to act at  $O$  parallel to their original directions, provided we introduce into the system the proper couples.



These forces, by Art. 44, may be compounded together so as to make a single resultant force. The couples also may be added together with their proper signs so as to make a single couple whose moment is  $\Sigma Pp$ .

This method of compounding forces is due to Poinsot (*Éléments de Statique*, 1803).

105. It should be noticed that the argument in Art. 104 is in no way restricted to forces in two dimensions. If we refer the system to three rectangular axes  $Ox, Oy, Oz$ , having an arbitrary origin  $O$ , we may transfer the forces  $P_1, P_2$  &c. to the point  $O$  by introducing the proper couples. The forces acting at  $O$  may be compounded into a single force, which we may call  $R$ . The couples also may be compounded, by help of the parallelogram of couples, into a single couple which we may call  $G$ . Thus the forces  $P_1, P_2$  &c. can always be reduced to a single force  $R$  acting at an arbitrary point, together with the appropriate couple  $G$ .

106. To find the magnitude and the line of action of the resultant force we follow the rules given in Art. 44. The resolved parts of the resultant force parallel to the axes are

$$X = \Sigma P \cos \alpha, \quad Y = \Sigma P \sin \alpha.$$

Let  $R$  be the resultant force, and let  $\theta$  be the angle which its line of action makes with the axis of  $x$ , then

$$R^2 = (\Sigma P \cos \alpha)^2 + (\Sigma P \sin \alpha)^2, \quad \tan \theta = \frac{\Sigma (P \sin \alpha)}{\Sigma (P \cos \alpha)}.$$

107. To find the moment of the resultant couple, we must find the value of  $Pp$ . By projecting the coordinates  $(xy)$  of  $A$  on  $ON$  we have

$$\begin{aligned} p &= x \cos NOx - y \sin NOx \\ &= x \sin \alpha - y \cos \alpha. \end{aligned}$$

Let  $G$  be the resultant couple, estimated positive when it tends to turn the body from the positive end of  $Ox$  to the positive end of  $Oy$ . Then  $G = \Sigma Pp = \Sigma (xP \sin \alpha - yP \cos \alpha)$

$$= \Sigma (xP_y - yP_x),$$

where  $P_x$  and  $P_y$  are the axial components of  $P$ .

108. The arbitrary point  $O$  to which the forces have been transferred may be called the *base of reference*, or more briefly the *base*. It need not necessarily be the origin, though usually it is convenient to take that point as origin.

Let some point  $O'$ , whose coordinates are  $(\xi\eta)$ , be the base. The resultant force and the resultant couple for this new base may be deduced from those for the origin  $O$  by writing  $x - \xi$  and  $y - \eta$  for  $x$  and  $y$ .

The expressions in Art. 106, for the resultant force do not contain  $x$  or  $y$ . Hence the resultant force is the same in magnitude and direction whatever base is chosen.

The expression for the resultant couple is

$$\begin{aligned} G' &= \Sigma P \{ (x - \xi) \sin \alpha - (y - \eta) \cos \alpha \} \\ &= G - \xi Y + \eta X. \end{aligned}$$

Thus the magnitude of the couple is, in general, different at different bases.

**109.** *To find the conditions of equilibrium of a rigid body.*

Let the system of forces be reduced to a force  $R$  and a couple  $G$  at any arbitrary base  $O$ . Since by Art. 78 the resultant force of the couple  $G$  is a force zero acting along the line at infinity, a finite force  $R$  cannot balance a finite couple  $G$ . If it could, we should have two forces in equilibrium, though they are not equal and opposite. It is therefore necessary for equilibrium that the resultant force  $R$  and the couple  $G$  should separately vanish.

**110.** Since  $R = 0$  in equilibrium, we have as in Art. 44,

$$\Sigma P \cos \alpha = 0, \quad \Sigma P \sin \alpha = 0.$$

These equations are necessary and sufficient to make  $R$  vanish. But we may put this result into a more convenient form.

*In order to make the resultant force  $R$  zero, it is necessary and sufficient that the sum of the resolved parts or resolutes of the forces along each of any two non-parallel straight lines should be zero.*

It is obvious that these conditions are necessary, for each straight line in turn may be taken as the axis of  $x$ . To prove that the conditions are sufficient, let one of these straight lines be the axis of  $x$ , and let the other be  $Ox'$ . Let the angle  $xOx' = \beta$ . Equating to zero the resolved parts of the forces along these straight lines we have

$$\Sigma P \cos \alpha = 0, \quad \Sigma P \cos (\alpha - \beta) = 0.$$

These give  $X = 0, \quad X' = X \cos \beta + Y \sin \beta = 0.$

Unless  $\beta$  is zero or a multiple of  $\pi$ , these equations give  $X = 0$  and  $Y = 0$ , and therefore  $R = 0$ .

The two equations of equilibrium obtained by resolving in any two different directions are commonly called the *equations of resolution*.

**111.** Again, it is necessary for equilibrium that  $G = 0$ ; this gives  $\Sigma Pp = 0$ . The product  $Pp$  is called the *moment of the force  $P$  about  $O$* . In order then to make  $G = 0$ , it is necessary and sufficient that the sum of the moments of all the forces (taken with their proper signs) about some arbitrary point should be zero. The equation of equilibrium thus obtained is usually called briefly the *equation of moments*.

112. Thus for forces in one plane the conditions of equilibrium supply three equations, viz. two equations of resolution and one of moments. This will be better understood when we consider the different ways in which a body can move. It may be proved that every displacement of a body may be constructed by a combination of the following motions. *Firstly*, the body may be moved, without rotation, a distance  $h$  parallel to the axis of  $x$ . *Secondly*, the body may be moved, also without rotation, a distance  $k$  parallel to the axis of  $y$ . In this way some arbitrary point  $O$  of the body may be brought to another point  $O'$  whose coordinates referred to  $O$  are any given quantities  $h$  and  $k$ . *Thirdly*, the body may be turned round this point through any given angle. The two equations of resolution express the fact that the forces urging the body in the two directions of the axes are zero, and the equation of moments expresses the fact that the forces do not tend to turn the body round the origin.

113. As great use is made of moments of forces, it is important that the meaning of this term should be distinctly understood. Suppose a force  $P$  to act at any point  $A$  along any straight line  $AB$ , and let  $O$  be the point about which we wish to take the moment of  $P$ . To find this moment we multiply the force  $P$  by the length  $p$  of the perpendicular from  $O$  on its line of action, viz.  $AB$ . The product has already been defined to be the moment.

As we are now discussing the theory of forces in one plane, the line  $AB$  and the point  $O$  are all in the plane of reference. But when we speak of forces in three dimensions it will be seen that what has just been defined is the moment of the force *about a straight line* through  $O$  perpendicular to the plane  $OAB$ .

When several forces act on the body, and the sum of their moments is required, attention must be paid to their proper signs. Exactly as in elementary trigonometry we select either direction of rotation round  $O$  as the standard direction. This we call the positive direction. Thus in Art. 104 the direction opposite to that of the hands of a watch has been chosen as the positive direction. The moment of each force is to be taken positive or negative according as it tends to turn the body round  $O$  in the positive or negative direction.

114. The three equations of equilibrium may be expressed in other forms besides the three given above, viz.  $X = 0$ ,  $Y = 0$ ,  $G = 0$ .



Thus there will be equilibrium if the sum of the moments about each of any two different points (say  $O$  and  $C$ ) is zero, and the sum of the resolved parts of the forces in some one direction, not perpendicular to  $OC$ , is zero. To prove this, take  $O$  for origin, let  $Ox$  be parallel to the direction of resolution and let  $(\xi, \eta)$  be the coordinates of  $C$ . The given conditions are therefore

$$G=0, \quad G' = G - \xi Y + \eta X = 0, \quad X = 0.$$

These lead to  $G=0$ ,  $X=0$ , and  $Y=0$ , provided  $\xi$  is not zero.

In the same way it may be proved that there will be equilibrium if the sum of the moments about three different points  $O, C, C'$ , not all in the same straight line, are each zero.

**115.** We may also notice that we cannot obtain more than three independent equations of equilibrium by resolving in several other directions or taking moments about several other points. All the equations thus obtained may be deduced from some three equations of equilibrium. Thus if  $X, Y$  and  $G$  are zero it follows from Arts. 108 and 110 that  $G'$  and  $X'$  are also zero.

**116. Varignon's Theorem.** If a system of forces be transformed by the rules of statics into any other equivalent system, then (1) the sum of the resolved parts of the forces in any given direction, and (2) the sum of the moments of the forces about any given point are equal, each to each, in the two systems.

This theorem follows easily from the results of Art. 110. Let the two systems be  $P_1, P_2$  &c. and  $P'_1, P'_2$  &c. Let  $O$  be the point about which moments have to be taken, and  $Ox$  the direction in which the resolution is to be made. Then we have to prove (1)  $\sum P \cos \alpha = \sum P' \cos \alpha'$  and (2)  $G = G'$ . Since the two systems are equivalent, there will be equilibrium if all the forces of either system are reversed, and both systems, after this change, act simultaneously on the same body. Hence, resolving in the given direction and taking moments about the given point, we have, by Arts. 110 and 111

$$\sum (P \cos \alpha - P' \cos \alpha') = 0, \quad G - G' = 0.$$


The result follows at once.

**117.** We may also give an elementary proof of this theorem, derived from first principles.

According to the rules of statics one system of forces is transformed into another by the use of three processes. (1) We may transfer a force from one point of its line of action to another; (2) we may remove or add equal and opposite forces, as in Art. 78; (3) we may combine or resolve forces by the parallelogram of forces.

It is evident that neither the sum of the resolved parts in any direction nor the sum of the moments of the forces about any point is altered by the first two processes. We shall now prove in an elementary manner that they are not altered by the third.

Let the forces  $P, Q$ , acting at  $C$ , be represented in direction and magnitude by  $CA, CB$  respectively, and let their resultant  $R$  be represented by  $CD$ . (1) Because the sum of the projections of  $CA, AD$  on any straight line (say  $Cx$ ) is equal to that of  $CD$  (see Art. 65), it follows that the sum of the resolved parts of the forces  $P, Q$  along  $Cx$  is equal to the resolved part of their resultant  $R$ . (2) Let  $O$  be the point about which moments are to be taken. Draw  $OL, OM, ON$  perpendiculars on the forces. We have to prove



$$P \cdot OL + Q \cdot OM = R \cdot ON \dots\dots(1).$$

If  $O$  were on the other side of  $CA$ , say between  $CD$  and  $CA$ , the sign of the term  $P \cdot OL$  would have to be changed, see Art. 113. But this change is provided for by the law of continuity, since the perpendicular from any point, as  $O$ , on a straight line, as  $OA$ , changes sign when  $O$  passes across the straight line. Such cases need not therefore be separately considered.

Dividing the equation (1) by  $CO$ , we see that it is equivalent to

$$P \sin ACO + Q \sin BCO = R \sin DCO \dots\dots\dots(2).$$

This equation merely expresses that the sum of the resolved parts perpendicular to  $CO$  of the forces  $P, Q$  is equal to that of  $R$ . But if we take the arbitrary line  $Cx$  perpendicular to  $CO$ , this has just been proved true.

**118. The single resultant.** Any system of forces  $P_1, P_2$  &c. can be reduced to a single force  $R$  acting at an arbitrary base together with a couple  $G$ . We shall now show that they can be further reduced to either a single force or a single couple.

The force  $R$  is zero when

$$X = \sum P \cos \alpha = 0, \quad Y = \sum P \sin \alpha = 0.$$

When this is the case, the given system of forces reduces to a single couple. It is evident that this single couple must be the same in all respects, whatever base of reference is chosen.

Supposing  $R$  not to be zero, we may by properly choosing the base of reference make the couple vanish, so that the whole system is equivalent to a single force  $R$ . Taking any convenient axes  $Ox, Oy$ , let  $O'$  be a base so chosen that the corresponding couple  $G'$  is zero. If  $(\xi\eta)$  be the coordinates of  $O'$ , we have by Art. 108,

$$G' = G - \xi Y + \eta X = 0 \dots\dots\dots(1).$$

If then the base be chosen at any point of the straight line whose equation is (1), the resultant couple is zero. This straight line makes with  $Ox$  an angle whose tangent is  $Y/X$ ; it is therefore parallel to the direction of the resultant force  $R$ . Since  $R$  acts at the new base  $O'$ , this straight line is the line of action of  $R$ .

119. *Summing up*; if any set of forces be given by their resultant force and couple, viz.  $R$  and  $G$ , at any assumed base, we have the following results:

(1) The condition that the forces can be reduced to a single couple is  $R = 0$ . The condition that they can be reduced to a single force is that  $R$  should not be zero.

(2) If  $R$  be not zero, the given forces can be reduced to a single force whose magnitude is equal to  $R$ , and whose line of action is the straight line

$$G - \xi Y + \eta X = 0.$$

The direction in which the force acts along this straight line is indicated by the known signs of its components  $X$  and  $Y$ .

(3) Whatever system of coordinate axes is chosen this single resultant must be the same in magnitude and position. We therefore infer that this straight line is independent of all coordinates, *i.e.* is invariable in space.

120. Ex. 1. Prove that a given system of forces can be reduced to two forces acting one at each of two given points  $A$  and  $B$ , the force at  $A$  making a given angle (not zero) with  $AB$ .

Ex. 2. Show that a system of forces in one plane can be reduced to three forces which act along the sides of any triangle taken arbitrarily in that plane. Show also how to find these three forces.

(1) This resolution is possible. Let  $P$  be any one force of the system, and let it cut some one side, as  $AB$ , of the triangle  $ABC$  in  $M$ . Then  $P$  acting at  $M$  may be resolved into two forces, one acting along  $AB$  and the other along  $CM$ . The latter may be transferred to  $C$  and again resolved into two other forces acting along  $CA$ ,  $CB$  respectively. Since every force may be treated in the same way, the whole system may be replaced by three forces,  $F_1$ ,  $F_2$ ,  $F_3$  acting along  $BC$ ,  $CA$ ,  $AB$ .

(2) To find the forces  $F_1$ ,  $F_2$ ,  $F_3$ . Let  $G_1$ ,  $G_2$ ,  $G_3$  be the sums of the moments of the forces of the given system about the corners  $A$ ,  $B$ ,  $C$  respectively. Then if  $p_1$ ,  $p_2$ ,  $p_3$  be the three perpendiculars from the corners on the opposite sides we have

$$F_1 p_1 = G_1, \quad F_2 p_2 = G_2, \quad F_3 p_3 = G_3.$$

Ex. 3. Show that the trilinear equation to the single resultant of the forces  $F_1$ ,  $F_2$ ,  $F_3$  acting along the sides of a triangle taken in order is  $F_1 \alpha + F_2 \beta + F_3 \gamma = 0$ . What is the meaning of this result when  $F_1$ ,  $F_2$ ,  $F_3$  are proportional to the lengths of the sides along which they act?

Ex. 4. Two systems of three forces ( $P$ ,  $Q$ ,  $R$ ), ( $P'$ ,  $Q'$ ,  $R'$ ) act along the sides taken in order of a triangle  $ABC$ : prove that the two resultants will be parallel if  $(QR' - Q'R) \sin A + (RP' - R'P) \sin B + (PQ' - P'Q) \sin C = 0$ . [Math. Tripos, 1869.]

Ex. 5. Four forces in equilibrium act along tangents to an ellipse, the directions at adjacent points tending in opposite directions round the ellipse. Prove that the moment of each about the centre is proportional to the area of the triangle formed by joining the points of contact of the three other forces.

Ex. 6. A rigid polygon  $A_1A_2\dots$  is moved into a new position  $A_1'A_2'\dots$  and the mean centres of masses  $a_1, a_2, \dots$  placed at the corners in the two positions are  $G, G'$ . Prove that forces represented in direction and magnitude by  $a_1.A_1A_1', a_2.A_2A_2', \dots$  are equivalent to a force represented by  $\Sigma a.GG'$  together with a couple  $\sin \theta \Sigma (a.GA^2)$ , where  $\theta$  is the angle any side of the polygon  $A_1A_2\dots$  makes with the corresponding side of  $A_1'A_2'\dots$ .

### *Solution of Problems*

121. We shall now explain how the preceding theorems may be used to determine the positions of equilibrium of one or more rigid bodies in one plane. This can only be shown by examples. After some general remarks on the solution of statical problems a series of examples will be found arranged under different heads. The object is to separate the difficulties which occur in these applications and enable the reader to attack them one by one. A commentary is sometimes added to assist the reader in applying the same principles to other problems.

122. When the number of forces which act on a body is either three, or can be conveniently reduced to three, we can find the position of equilibrium by using the principle that these forces must meet in one point or be parallel. This is proved in Art. 34.

There are two advantages in this method, (1) the criterion that the three straight lines are concurrent may often be conveniently expressed by some *geometrical statement*, (2) the actual magnitudes of the forces are not brought into the process, so that if these are unknown, no further elimination is necessary. If the magnitudes of the forces are also required, they can be found afterwards from the principle that each is proportional to the sine of the angle between the other two. This is often called the geometrical method.

123. If there are more than three forces, or if we prefer to use an analytical method of solution even when there are only three forces, we use the results of Art. 109. We express the conditions of equilibrium (1) by resolving all the forces in some two convenient directions and equating the result of each resolution to zero, (2) by taking moments about some convenient point and equating the result to zero. Having thus obtained three equations, we must eliminate the unknown forces. Finally we shall obtain an equation expressing in an *algebraic manner* the position of equilibrium.

As we have to eliminate the unknown forces it will be convenient to *make one of the resolutions in the direction perpendicular to a force which we intend to eliminate, and to take moments about some point in its line of action.* This force will then appear only in the other resolution, which may therefore be omitted altogether. Thus by a proper choice of the directions of resolution and of the point about which moments are taken we may sometimes save much elimination.

124. When there are several bodies forming a system, we represent the mutual actions of these bodies by introducing forces called reactions at the points of contact. We may then regard each body as if it existed singly (all the others being removed) and were acted on by these reactions in addition to the given forces. We then form the equations for each body separately. Finally we must eliminate the reactions, if unknown, and the remaining equations will express the positions of equilibrium of the several bodies.

*These eliminations are sometimes avoided by expressing the conditions of equilibrium for two bodies taken together.* Afterwards we may form the equations for either separately in such a manner as to avoid introducing the mutual reaction.

When we come to the theory of virtual work we shall have a method of forming the equations of equilibrium free from these reactions.

✓125. Ex. 1. *A thin heavy uniform rod AB rests partly within and partly without a hemispherical smooth bowl, which is fixed in space. Find the position of equilibrium.*

Let  $G$  be the middle point of the rod, then the weight  $W$  of the rod may be collected at  $G$ . This should be evident from the theory of parallel forces, but it is strictly proved in the chapter on centre of gravity.

It follows from the remarks made in Art. 54, that, when two smooth surfaces touch each other, the pressure (if any exist) between the surfaces acts along the normal to the common tangent plane at the point of contact. If the rod be regarded as a very thin cylinder with its extremities rounded off, it is easy to see that the common tangent plane at  $A$  to the rod and the sphere coincides with the tangent plane to the sphere. The pressure at this point therefore acts along the normal  $AO$  to the sphere. We obtain the same result if we regard the rod as resting with a single terminal particle in contact with the sphere; it then follows immediately from Art. 54 that the pressure between the terminal particle and the sphere acts along the normal to the sphere.


Consider next the point  $C$ , at which the rod meets the rim of the bowl. The common tangent plane to the rod and the rim passes through both the rod and the tangent at  $C$  to the rim. The reaction is to be at right angles to both these, it

therefore acts along a straight line  $CI$  drawn perpendicularly to the rod in the vertical plane containing the rod.

It will be found useful to put these remarks into the form of a *working rule*. Since the tangent plane at any point of a surface contains all the tangent straight lines at that point, the pressure between two *smooth bodies* which touch each other must be normal to every line on the two bodies which passes through the point of contact. To find the direction of the reaction we select two lines which lie on the bodies and pass through the point of contact; the required direction is normal to both these lines. Thus, at  $A$ , any tangent to the sphere passes through the point of contact, the reaction is therefore normal to the bowl. At  $C$  both the rod and the rim pass through the point of contact, the reaction is therefore normal both to the rod and to the tangent to the rim.

Let  $a$  be the radius of the bowl,  $l$  half the length of the rod. Let the position of equilibrium be determined by the angle  $ACO = \theta$  which the rod makes with the horizon. It easily follows that  $CAO = \theta$ ,  $CA = 2a \cos \theta$ .

Since the rod is in equilibrium under three forces, viz.  $R$ ,  $R'$  and  $W$ , we use the geometrical method of solution. We have to express the condition that the three forces meet in some point  $I$ . To effect this we equate the projections of  $AG$  and  $AI$  on the horizontal. Since  $ICA$  is a right angle,  $I$  lies on the circumference produced, hence  $AI = 2a$ . Equating the projections, we have  $l \cos \theta = 2a \cos 2\theta$ ,



$$\therefore \cos \theta = \frac{l}{2a} \pm \sqrt{\left(\frac{1}{2} + \frac{l^2}{4a^2}\right)}.$$

If the negative sign is given to the radical,  $\cos \theta$  is negative and  $\theta$  is greater than a right angle. This is excluded by geometrical considerations. The position of equilibrium is therefore given by the value of  $\cos \theta$  with the positive sign prefixed to the radical.

There are however other geometrical limitations. Unless  $2l$  is greater than  $2a \cos \theta$  the rod will not be long enough to reach over the rim of the bowl, and unless  $l$  is less than  $2a \cos \theta$  the point  $G$  at which the weight acts will fall outside the bowl. Unless the first condition is satisfied the rod will slip into the bowl, and if the second be not true the rod will tumble out. These conditions require that  $l$  should lie between  $a/\sqrt{2}$  and  $2a$ . If the half-length of the rod is less than  $2a$ , it is easy to prove that the value of  $\cos \theta$  given above is never greater than unity.

For the sake of comparison, a solution of this problem by the analytical method is given here. We have to resolve in some directions, and take moments about some point. To avoid introducing the reaction  $R'$  into our equations, we shall resolve along  $AC$  and take moments about  $C$ . The resolution gives

$$R \cos \theta = W \sin \theta.$$

Since the perpendicular from  $C$  on  $AO$  is  $a \sin 2\theta$ , and  $CG = 2a \cos \theta - l$ , the equation of moments is  $Ra \sin 2\theta = W(2a \cos \theta - l) \cos \theta$ .

Eliminating  $R$ , we have the same equation to find  $\cos \theta$  as before.

The reader should notice that the value of  $\cos \theta$  given by the equation of equilibrium depends only on the lengths  $a$  and  $l$ , and not on the weight of the


rod. Thus all uniform rods of the same length, whatever their weights may be, will rest in equilibrium in a given bowl in the same position. This result might have been anticipated from the theory of dimensions, for a ratio like  $\cos \theta$  could not be equal to any multiple of a weight, though it could be equal to the ratio of two weights. Now the only weight which could appear in the result is  $W$ . There is therefore no other force to make a ratio with  $W$ . It follows that  $W$  could not appear in the result.

Ex. 2. Show, by taking moments about the intersection  $I$  of the two reactions  $R, R'$  in example (1), that we arrive at the equation to find  $\cos \theta$  without introducing any unknown force into the equation. Thence show that the equilibrium is stable.

If we slightly displace the rod by increasing its inclination  $\theta$  to the horizon, the extremity  $A$  slides down the interior of the bowl and the rod moves a little outwards. The new position of  $I$  is therefore to the left of the vertical through the new position of  $G$ . When therefore the rod is left to itself, we see, by taking moments about the new position of  $I$ , that the weight acting at  $G$  will tend to bring the rod back to its position of equilibrium. Similar remarks apply, if the rod be displaced by decreasing  $\theta$ . The equilibrium is therefore stable.

Ex. 3. A rod  $AB$ , placed with one extremity  $A$  inside a fixed wine glass, whose form is a right cone, with its axis vertical, rests over the rim of the glass at  $C$ : show that in the position of equilibrium  $l \sin^2 (\theta + \beta) \cos \theta = 2a \sin^2 \beta$ , where  $\theta$  is the inclination of the rod to the horizontal,  $a$  is the radius of the rim of the cone,  $\beta$  the complement of the semi-vertical angle, and  $2l$  the length of the rod.

Ex. 4. An open cylindrical jar, whose radius is  $a$  and weight  $nW$ , stands on a horizontal table. A heavy rod, whose length is  $2l$  and weight  $W$ , rests over its rim with one end pressing against the vertical interior surface of the jar. Prove (1) that in the position of equilibrium the inclination  $\theta$  of the rod to the horizon is given by  $l \cos^3 \theta = 2a$ ; (2) that the rod will tumble out of the jar if the inclination be less than this value of  $\theta$ ; (3) that the jar will tumble over unless  $l \cos \theta < (n+2)a$ . Is the position of equilibrium stable or unstable?



The rod will tumble out of the jar if  $G$  lies to the right of the vertical through  $I$  in the figure. The jar will tumble over  $D$  if the moment about  $D$  of the weight of the rod acting at  $G$  is greater than that of the weight of the jar acting at its centre of gravity.

Ex. 5. Prove that the length of the longest rod which can be in equilibrium with one extremity pressing against the smooth vertical interior surface of the jar described in the last example is given by  $2l^2 = a^2 (n+2)^3$ .

Ex. 6. A heavy rod  $AB$ , of length  $2l$ , rests over a fixed peg at  $C$ , while the end  $A$  presses against a smooth curve in the same vertical plane. The polar equation to the curve, referred to  $C$  as origin, is  $r = f(\theta)$ ,  $\theta$  being measured from the vertical. Show that the equilibrium value of  $\theta$  satisfies the equation  $(r-l) \tan \theta = dr/d\theta$ .

Show, by integrating this differential equation, that the form of the curve,


X when the rod rests against it in equilibrium in all positions, is  $(r-l) \cos \theta = a$ . Thence show that the middle point of the rod always lies in a fixed horizontal straight line, and that the curve is the conchoid of Nicomedes.

If we attack this problem with the help of the principle of virtual work we arrive first at the result that in equilibrium the middle point must begin to move horizontally. From this geometrical fact we must then deduce the other results given above.

X 126. Ex. 1. A uniform heavy rod  $PQ$  rests inside a smooth bowl formed by the revolution of an ellipse about its major axis, which is vertical. Show that in equilibrium the rod is either horizontal or passes through a focus.

The reactions at  $P$  and  $Q$  act along the normals to the bowl. In the position of equilibrium these normals must intersect in a point  $I$  which is vertically over the middle point  $G$  of the rod.

The following geometrical property of conics is a generalization of those given in Salmon's *Conics*, chap. XI, on the normal. See also the note at the end of this volume. Let  $CA$ ,  $CB$  be the semi-axes of the generating ellipse and let these be the axes of coordinates. Let  $(\bar{x}\bar{y})$  be the coordinates of the middle point  $G$  of any chord  $PQ$  of a conic, and let  $(\xi\eta)$  be the intersection  $I$  of the normals at  $P$  and  $Q$ . Then if  $p$ ,  $p'$  be the perpendiculars from the foci on the chord and  $q$  the perpendicular from the centre, we have



$$\frac{\eta - \bar{y}}{\bar{y}} \frac{b^2}{a^2} = - \frac{pp'}{q^2}.$$

Here  $p$  and  $p'$  are supposed to have the same sign when the two foci are on the same side of the chord.

In our problem we have in equilibrium  $\eta = \bar{y}$ . Hence we must have either, one of the two  $p$ ,  $p'$  equal to zero, or  $\bar{y} = 0$ . In the first case the rod passes through a focus, in the second case it is horizontal.

X Ex. 2. Show that the position of equilibrium in which the rod passes through the lower focus is stable.

This may be proved by finding the moment of the weight of the rod about  $I$ , tending to bring the rod back to its position of equilibrium when displaced. Another proof of this theorem, deduced from the principle of virtual work, is given in the second volume of the *Quarterly Journal* by H. G., late Bishop of Carlisle.

X Ex. 3. If the bowl be formed by the revolution of an ellipse about the minor axis, which is vertical, prove that the only position of equilibrium is horizontal.

To find the positions of equilibrium we make  $\xi = \bar{x}$ . Since the foci on the minor axis are imaginary, we cannot immediately derive the corresponding formula for  $\xi$  from that for  $\eta$  by interchanging  $a$  and  $b$ . Let the chord cut the axes in  $L$  and  $M$ , then by similar triangles

$$\frac{\eta - \bar{y}}{\bar{y}} \frac{b^2}{a^2} = - \frac{CL^2 - a^2 + b^2}{CL^2}, \quad \therefore \frac{\xi - \bar{x}}{\bar{x}} \frac{a^2}{b^2} = - \frac{CM^2 - b^2 + a^2}{CM^2}.$$

The condition  $\xi = \bar{x}$  gives  $\bar{x} = 0$  since the right-hand side cannot vanish.

? Ex. 4. A uniform heavy rod  $PQ$  rests inside a smooth bowl formed by the revolution of an ellipse about its major axis, which is inclined at an angle  $\alpha$  to the



vertical. If the rod when in equilibrium intersect the axes  $CA$ ,  $CB$  of the generating ellipse in  $L$  and  $M$ , prove that  $\frac{CM^2 + c^2}{CM} \cdot b^2 \sin \alpha = \frac{CL^2 - c^2}{CL} a^2 \cos \alpha$ , where  $c^2 = a^2 - b^2$ .

✓ Ex. 5. Two wires, bent into the forms of equal catenaries, are placed so as to have a common vertical directrix, and their axes in the same straight line. The extremities of a uniform rod are attached to two small rings which can freely slide on these catenaries. Show that in equilibrium the rod must be horizontal.

Ex. 6. A straight uniform rod has smooth small rings attached to its extremities, one of which slides on a fixed vertical wire and the other on a fixed wire in the form of a parabolic arc whose axis coincides with the former wire, and whose latus rectum is twice the length of the rod: prove that in the position of equilibrium the rod will make an angle of  $60^\circ$  with the vertical. [Math. Tripos, 1869.]

Ex. 7.  $AC$ ,  $BC$  are two equal uniform rods which are jointed at  $C$ , and have rings at the ends  $A$  and  $B$ , which slide on a smooth parabolic wire, whose axis is vertical and vertex upwards; prove that in the position of equilibrium the distance of  $C$  from  $AB$  is one fourth of the latus rectum. [Math. Tripos, 1871.]

Ex. 8. Two heavy uniform rods  $AB$ ,  $BC$  whose weights are  $P$  and  $Q$  are connected by a smooth joint at  $B$ . The ends  $A$  and  $C$  slide by means of smooth rings on two fixed rods each inclined at an angle  $\alpha$  to the horizon. If  $\theta$  and  $\phi$  be the inclinations of the rods to the horizon, show that  $P \cot \phi = Q \cot \theta = (P + Q) \tan \alpha$ . [Trin. Coll., 1882.]

Resolve horizontally and vertically for the two rods regarded as one system; then take moments for each singly about  $B$ .

Ex. 1. Two smooth rods  $OM$ ,  $ON$ , at right angles to each other are fixed in space. A uniform elliptic disc is supported in the same vertical plane by resting on these rods. If  $OM$  make an angle  $\alpha$  with the vertical, prove that either the axes of the ellipse are parallel to the rods, or the major axis makes an angle  $\theta$  with  $OM$ , given by


$$\tan^2 \theta = \frac{a^2 \tan^2 \alpha - b^2}{a^2 - b^2 \tan^2 \alpha}.$$

Let  $P$ ,  $Q$  be the points of contact and let the normals at  $P$ ,  $Q$  meet in  $I$ . Let  $C$  be the centre, then in equilibrium either  $C$  and  $I$  must coincide, or  $CI$  is vertical.

In the former case the tangents  $OM$ ,  $ON$  are parallel to the axes.

In the latter case, let  $D$  bisect  $PQ$ , then  $OD$  produced passes through  $C$ ; but because the tangents are at right angles  $OPIQ$  is a rectangle, therefore  $OD$  passes through  $I$ . Hence  $OCI$  is vertical.

These two results follow easily from a principle to be proved in the chapter on virtual work. As the ellipse is moved round, always remaining in contact with the rods, we know by conics that  $C$  describes an arc of a circle, whose centre is  $O$ , and whose radius is  $\sqrt{a^2 + b^2}$ . Hence when  $C$  is vertically over  $O$ , its altitude is a maximum. When the axes are parallel to the rods,  $C$  is at one of the extremities of its arc and its altitude is a minimum. It immediately follows from the principle of virtual work that the first of these is a position of unstable equilibrium, and that the other two are positions of stable equilibrium.



Resuming the solution, we have now to find  $\theta$  when  $CI$  is vertical. The perpendicular from  $C$  on  $OM$  makes with the major axis an angle equal to the complement of  $\theta$ , hence

$$a^2 \sin^2 \theta + b^2 \cos^2 \theta = OC^2 \sin^2 \alpha = (a^2 + b^2) \sin^2 \alpha.$$

The value of  $\tan^2 \theta$  follows immediately.

*R.*  $\times$  Ex. 2. An elliptic disc touches two rods  $OM$ ,  $ON$ , not necessarily at right angles, and is supported by them in a vertical plane. If  $(XY)$  be the coordinates of the intersection  $O$  of the rods, referred to the axes of the ellipse, prove that the major axis is inclined to the vertical at an angle  $\theta$  given by  $\tan \theta = -\frac{Y}{X} \frac{a^2 - X^2}{b^2 - Y^2}$ .

To prove this we may use a theorem deduced from two given by Salmon in his chapter on Central Conics, Art. 180, Sixth Edition. Let  $(XY)$  be a point from which two tangents are drawn to touch a conic at  $P$ ,  $Q$ . The normals at  $P$ ,  $Q$  meet in a point  $I$ , whose coordinates  $(xy)$  are given by

$$\frac{x}{X} = (a^2 - b^2) \frac{b^2 - Y^2}{a^2 Y^2 + b^2 X^2}, \quad \frac{y}{Y} = - (a^2 - b^2) \frac{a^2 - X^2}{a^2 Y^2 + b^2 X^2}.$$

The result follows, since  $CI$  must be vertical.

*R.*  $\times$  Ex. 3. An elliptic disc is supported in equilibrium in a vertical plane by resting on two smooth fixed points in a horizontal straight line. Prove that in equilibrium either a principal diameter is vertical, or these points are at the extremities of two conjugate diameters.

Let the principal diameters be the axes of coordinates. Let the fixed points  $P$ ,  $Q$  be  $(xy)$ ,  $(x'y')$ , and let  $(\xi\eta)$  be the intersection  $I$  of the normals at these points. In equilibrium  $IC$  must be perpendicular to  $PQ$ , hence  $(x - x')\xi + (y - y')\eta = 0$ . By writing down the equations to the normals at  $P$ ,  $Q$  we find  $\xi$ ,  $\eta$ , as is done in Salmon's *Conics*, Art. 180. This equation then becomes

$$(x - x')(y - y') \left( \frac{xx'}{a^2} + \frac{yy'}{b^2} \right) = 0.$$

One of these factors must vanish. These give the three positions of equilibrium.

That there should be equilibrium when  $P$ ,  $Q$  are at the extremities of two conjugate diameters is evident; for  $PI$ ,  $QI$  are perpendiculars from two of the corners of the triangle  $CPQ$  on the opposite sides, hence  $CI$  must be perpendicular to the side  $PQ$ . This is the condition of equilibrium. That there should be equilibrium when an axis is vertical is evident from symmetry.

$\times$  128. Ex. 1. A cone has attached to the edge of its base a string equal in length to the diameter of the base, and is suspended by the extremity of this string from a point in a smooth vertical wall, the rim of the base also touching the wall. If  $\alpha$  be the semi-angle of the cone,  $\theta$  the inclination of the string to the vertical, prove that in a position of equilibrium  $\tan \alpha \tan \theta = \frac{1}{\sqrt{3}}$ . Assume that the centre of gravity of the cone is in its axis at a distance from the base equal to one quarter of the altitude.

$\times$  Ex. 2. A square rests with its plane perpendicular to a smooth wall, one corner being attached to a point in the wall by a string whose length is equal to a side of the square. Prove that the distances of three of its angular points from the wall are as 1, 3 and 4. [Math. Tripos, 1853.]

By resolving vertically, and taking moments about the corner of the square which is in contact with the wall, we obtain two equations from which the inclination of any side to the wall and the tension may be found.

Ex. 3.  $AB$  is a uniform rod of length  $a$ ; a string  $APBC$  is fastened to the end  $A$  of the rod and passes through a smooth ring attached to the other end  $B$ ; the end  $C$  of the string is fastened to a peg  $C$ , and the portion  $APB$  is hung over a smooth peg  $P$  which is in the same horizontal plane as  $C$  at a distance  $2b$  from it ( $b < a$ ). If  $AP$  is vertical, find the angles which the other parts of the string make with the vertical, and show that the string must have one of the lengths  $\frac{2}{3}b\sqrt{3} \pm \sqrt{a^2 - b^2}$ . [King's Coll., 1889.]


Ex. 4. Two light elastic strings have their ends tied to a fixed point on the line joining two small smooth pegs which are in the same horizontal plane, so that when they are unstretched their ends just reach the pegs; they hang over the pegs and have their other ends fastened to the ends of a heavy uniform rod; show that the inclination of the rod to the horizon is independent of its length, being equal to  $\tan^{-1} (y_1 - y_2)/2a$ , where  $y_1$  and  $y_2$  are the extensions of the strings when they singly support the rod, and  $a$  is the distance between the pegs. Show also that the two strings and the rod are inclined to the horizon at angles whose tangents are in arithmetical progression. It may be assumed that the tension of each string is proportional to the ratio of its extension to its unstretched length.

[Math. Tripos, 1887.]

129. Ex. 1. A sphere rests on a string fastened at its extremities to two fixed points. Show that if the arc of contact of the sphere and plane be not less than  $2 \tan^{-1} \frac{4}{3}$ , the sphere may be divided into two equal portions by means of a vertical plane without disturbing the equilibrium. [Math. Tripos, 1840.]

It may be assumed that the centre of gravity of a solid hemisphere is on the middle radius at a distance  $\frac{3}{8}$ ths of that radius from the centre.

Consider the equilibrium of the hemisphere  $ABD$  and the portion  $AD$  of the string in contact with it. The mutual reactions of the string and the hemisphere may now be omitted. This compound body is acted on by (1) the tensions of the string, each equal to  $T$ , acting at  $A$  and  $D$ , (2) the weight  $W$  of the hemisphere acting at its centre of gravity  $G$ , (3) the mutual reaction  $R$  of the two hemispheres. The reaction  $R$  is the resultant of all the horizontal pressures between the elements of the plane bases and must act at some point within the area of contact. The two bases will separate unless the resultant of the remaining forces also passes inside the area of contact. The arc  $AD$  being as small as possible, this separation will take place by the hemispheres opening out at  $B$ , for the mutual pressures are then confined to the single point  $A$  at the lowest point of the sphere. The hemisphere  $ABD$  is then acted on by the three forces,  $T$  at  $D$ ,  $T - R$  at  $A$ , and  $W$  at  $G$ . These must intersect in a point  $I$ . Hence  $CG = CA \tan \frac{1}{2}ACD$ . This gives  $\tan \frac{1}{2}ACD = \frac{3}{4}$  and  $\tan ACD = \frac{4}{3}$ .



Ex. 2. Two equal heavy solid smooth hemispheres, placed so as to look like one sphere with the diametral plane vertical, rest on two pegs which are on the same horizontal line. Prove that the least distance apart of the pegs, so that the hemispheres may not fall asunder, is to the diameter of the circle as 3 to  $\sqrt{73}$ .

[Christ's Coll.]

Ex. 3. An elliptic lamina of eccentricity  $e$ , divided into two pieces along the minor axis, is placed with its major axis horizontal in a loop of string attached

extremities  $A$  and  $B$  of the axes. These have a resultant inclined at  $45^\circ$  to either axis. Let it cut the vertical through the centre of gravity  $G$  in the point  $H$ . The reaction between the semi-ellipses must pass through  $H$ . Hence the altitude of  $H$  above  $B$  must be less than the axis minor. If  $C$  be the centre, this gives at once  $a - CG < 2b$ . Granting that  $CG = \frac{4a}{3\pi}$ , this leads to the result.

✓ Ex. 4. A circular cylinder rests with its base on a smooth inclined plane; a string attached to its highest point, passing over a pulley at the top of the inclined plane, hangs vertically and supports a weight; the portion of the string between the cylinder and the pulley is horizontal; determine the conditions of equilibrium.

[Math. Tripos, 1843.]

Show that the ratio of the height of the cylinder to the diameter of its base must be less than the cotangent of the inclination of the plane to the horizon.

✓ Ex. 5. A uniform bar of length  $a$  rests suspended by two strings of lengths  $l$  and  $l'$  fastened to the ends of the bar and to two fixed points in the same horizontal line at a distance  $c$  apart. If the directions of the strings being produced meet at right angles, prove that the ratio of their tensions is  $al + cl' : al' + cl$ .

[Math. Tripos, 1874.]

✓ Ex. 6. A smooth vertical wall  $AB$  intersects a smooth plane  $BC$  so that the line of intersection is horizontal. Within the obtuse angle  $ABC$  a smooth sphere of weight  $W$  is placed and is kept in contact with the wall and plane by the pressure of a uniform rod of length  $l$  which is hinged at  $A$ , and rests in a vertical plane touching the sphere. Show that the weight of the rod must be greater than

$$\frac{Wh \cos \alpha \cos \frac{1}{2}\alpha}{2l \sin \frac{1}{2}\theta \sin \frac{1}{2}(\alpha - \theta) \cos^2 \frac{1}{2}(\alpha - \theta)},$$

where  $\alpha$  and  $\theta$  are the acute angles made by the plane and rod with the wall, and  $h = AB$ .

[Math. Tripos, 1890.]

Ex. 7. A set of equal frictionless cylinders, tied together by a fine string in a bundle whose cross section is an equilateral triangle, lies on a horizontal plane. Prove that, if  $W$  be the total weight of the bundle, and  $n$  the number of cylinders in a side of the triangle, the tension of the string cannot be less than  $\frac{W}{4\sqrt{3}} \left(1 + \frac{1}{n}\right)^{-1}$

or  $\frac{W}{4\sqrt{3}} \left(1 - \frac{1}{n}\right)$ , according as  $n$  is an even or an odd number, and that these values will occur when there are no pressures between the cylinders in any horizontal row above the lowest.

[Math. Tripos, 1886.]

Ex. 8. A number  $n$  of equal smooth spheres, of weight  $W$  and radius  $r$ , is placed within a hollow vertical cylinder of radius  $a$ , less than  $2r$ , open at both ends and resting on a horizontal plane. Prove that the least value of the weight  $W'$  of the cylinder, in order that it may not be upset by the balls, is given by

$$aW' = (n-1)(a-r)W \text{ or } aW' = n(a-r)W,$$

according as  $n$  is odd or even.

[Math. Tripos, 1884.]

Ex. 9. The circumference of a heavy rigid circular ring is attached to another concentric but larger ring in its own plane by  $n$  elastic strings ranged symmetrically round the centre along common radii. This second ring is attached to a third in a

similar manner by  $2n$  strings, and this to a fourth by  $3n$  strings and so on. Supposing all the rings to have the same weight, and the strings at first to be without tension, show that, if the last ring be lifted up and held horizontal, all the other rings will be on the surface of a right cone. [Pet. Coll., 1862.]

Ex. 10. Two spheres of densities  $\rho$  and  $\sigma$ , and whose radii are  $a$  and  $b$ , rest in a paraboloid of revolution whose axis is vertical and touch each other at the focus: prove that  $\rho^2 a^{10} = \sigma^2 b^{10}$ . [Curtis' problem. *Educational Times*, 5460.]

**130. Equilibrium of four repelling particles.** Ex. 1. Four free particles situated at the corners of a quadrilateral are in equilibrium under their mutual attractions or repulsions; the forces along the sides  $AB$ ,  $BC$ ,  $CD$ ,  $DA$  being attractive, those along the diagonals  $AC$ ,  $BD$  being repulsive. If the forces are proportional to the sides along which they act, prove that the quadrilateral is a parallelogram.

In this case the forces on the particle  $A$  are represented by the sides  $AB$ ,  $AD$  and the diagonal  $AC$ . The result follows at once from the parallelogram of forces.

Ex. 2. If the quadrilateral formed by joining the four particles can be inscribed in a circle, show that the attracting force along any side is proportional to the opposite side, and the repelling force along a diagonal to the other diagonal.

Ex. 3. If the quadrilateral be any whatever, prove that when the particles at the corners are in equilibrium

$$\frac{f(AB)}{AB \cdot OC \cdot OD} = \frac{f(BC)}{BC \cdot OD \cdot OA} = \&c. = \frac{f(BD)}{AC \cdot OB \cdot OD} = \frac{f(AC)}{BD \cdot OA \cdot OC},$$

where  $O$  is the intersection of the diagonals  $BD$ ,  $AC$ , and the mutual force along any line, as  $AB$ , is represented by  $f(AB)$ .

To prove this, consider the equilibrium of the particle  $A$ .

$$\frac{f(AC)}{f(AB)} = \frac{\sin DAB}{\sin DAO} = \frac{\text{area } DAB}{\text{area } DAO} \cdot \frac{AD \cdot AO}{AD \cdot AB} = \frac{DB}{DO} \cdot \frac{AO}{AB};$$

all the results follow by symmetry.

Ex. 4. Whatever be the form of the quadrilateral, prove that (1) the moments about  $O$  of the forces which act along the sides are equal, and (2),

$$ABf(AB) + BCf(BC) + CDf(CD) + DAf(DA) = ACf(AC) + BDf(BD).$$

### Reactions at Joints


**131.** When two beams are connected together by a smooth hinge-joint or are fastened together by a very short string, the mutual action between them will be equivalent to a single force acting at the point of junction. In some cases the direction of this force is at once apparent, in other cases its *direction as well as its magnitude* must be deduced from the equations of equilibrium.

There are two cases in which the direction is apparent. *Firstly* let the body and the external forces be both symmetrical about some straight line through the hinge. In this case the action and

reaction between the two beams must also be symmetrically situated. Since they are equal and opposite, they must each be perpendicular to the line of symmetry.

*Secondly*, let the body be hinged at two points  $A$  and  $B$ , and let it be acted on by no other forces except the reactions at  $A$  and  $B$ . Since the body is in equilibrium under these two reactions, they must act along the straight line joining the hinges and be equal and opposite.

- ✓ Ex. 1. Two equal beams  $AA'$ ,  $BB'$ , without weight, are hinged together at their common middle point  $C$ , and placed in a vertical plane on a smooth horizontal table. The upper ends  $A$ ,  $B$  of the rods are connected by a light string  $ADB$ , on which a small heavy ring can slide freely. Show that in equilibrium a horizontal line through the ring  $D$  will bisect  $AC$  and  $BC$ . [Coll. Ex.]




The action at  $C$  is horizontal, because the system is symmetrical about the vertical through  $C$ . The action at  $A'$  is vertical because, when the end of a rod rests on a surface, the action is normal to the surface (Art. 125). The tension of the string acts along  $AD$ . These three forces keep the rod  $AA'$  in equilibrium. They therefore meet in some point  $I$ . By similar triangles  $DC$  is half  $IA'$ . The result follows immediately.

- ✓ Ex. 2. If the weight of each rod in the last example be  $n$  times the weight of the ring, prove that in equilibrium a horizontal line through the ring will cut  $CA$  in a point  $P$  such that  $CP = (2n+1)PA$ .

- ✓ Ex. 3. Two equal heavy rods  $CA$ ,  $CB$  are hinged at  $C$ , and their extremities  $A$ ,  $B$  rest on a smooth horizontal table. A third rod, attached to their middle points  $E$ ,  $F$  by smooth hinges, prevents the rods  $CA$ ,  $CB$  from opening out. Find the reactions at the hinges (1) when the rod  $EF$  has no weight, and (2) when it has a weight  $W'$ .

The reaction  $R$  at  $C$  is horizontal by the rule of symmetry. If the weight of the rod  $EF$  is neglected, the reactions at  $E$  and  $F$  act along  $EF$  by the second rule of this Article. Let this be  $X$ . The reaction  $R'$  at  $A$  is vertical. The weight of the rod  $CA$  acts vertically at  $E$ . These are all the forces which act on the rod  $CA$ . By resolving horizontally and vertically, and by taking moments about  $E$  we easily find that  $R$  and  $-X$  are each equal to  $W \tan \alpha$ , where  $\alpha$  is half the angle  $ACB$ .



When the roof of a house is not high pitched, the angle  $ACB$  between the beams is nearly equal to two right angles, so that  $\tan \alpha$  is large. The reactions at  $C$  and  $E$  become therefore much greater than the weight of the beams. It is therefore necessary to give great strength to the mode of attachment of the beams.

If the weight  $W'$  of the beam  $EF$  cannot be neglected, the reactions at  $E$  and  $F$  will not be horizontal. Let the components of the action at  $E$  on the rod  $EF$  be

$X, Y$  when resolved horizontally to the right and vertically downwards. It will be noticed that they have been put in directions opposite to those in which we should expect them to act. This is done to avoid confusing the figure. They should therefore appear as negative quantities in the result. The reactions on the rod  $AC$  are of course exactly opposite. The equations of equilibrium are as follows:

Resolve ver. for $BF$ ,	$2Y + W' = 0$ ,
Res. ver. for the system,	$2R' = W' + 2W$ ,
Mts. about $E$ for $AC$ ,	$Ra \cos \alpha = R'a \sin \alpha$ ,
Res. hor. for $AC$ ,	$X + R = 0$ ,

where  $2a$  is the length of either  $CA$  or  $CB$ . These four equations determine  $X, Y, R, R'$ .

✓ Ex. 4. Two rods  $AB, BC$ , of equal weight but of unequal length, are hinged together at  $B$ , and their other extremities are attached to two fixed hinges  $A$  and  $C$  in the same vertical line. Prove that the line of action of the reaction at the hinge  $B$  bisects the straight line  $AC$ .

✓ Ex. 5. Two uniform rods  $AB, AC$ , freely jointed at  $A$ , rest with  $A$  capable of sliding on a fixed smooth horizontal wire.  $B$  and  $C$  are connected by small smooth rings with two vertical wires in the plane  $ABC$ . If the rods are perpendicular prove that  $a\sqrt{l+l'} = l\sqrt{l'+l'}\sqrt{l}$ , where  $l, l'$  are the lengths of the rods and  $a$  the distance between the vertical wires. [Coll. Ex., 1890.]

✓ 132. Ex. 1. Four rods, jointed at their extremities  $A, B, C, D$  form a parallelogram. The opposite corners are joined by strings along the two diagonals, each of which is tight. Show that their tensions are proportional to the diagonals along which they act.

Let four particles be added to the figure, one at each corner. Let the sides be jointed to the particles instead of to each other, and let the strings also be attached to the particles. By this arrangement each rod is acted on only by forces at its extremities; hence by the second rule of Art. 131 these forces act along the rod. We now proceed as in Art. 130, Ex. 1. The forces on the particle  $A$  are parallel to the sides of the triangle  $ABC$ , hence, by the parallelogram of forces, they are proportional to those sides. It follows that every side in the figure measures the force which acts along it.

*Another Solution.* We may also arrange the internal forces otherwise. Let the rods be jointed to each other, but let the strings be attached to the extremities of the rods  $AB, CD$ . Since  $AD$  is now acted on only by the actions at the hinges, these actions act along  $AD$  (Art. 131). In the same way the reactions at  $B$  and  $C$  act along  $BC$ . Thus the rod  $CD$  is acted on by the tensions  $T, T'$  along the diagonals  $DB$  and  $CA$ , and by the reactions along  $AD$  and  $BC$ . Resolving at right angles to the latter, we have  $T \sin OBC = T' \sin OCB$ , where  $O$  is the intersection of the diagonals. This gives  $T \cdot OC = T' \cdot OB$ , i.e. the tensions are as the diagonals along which they act.

It should be noticed that the mutual reactions on the rods obtained in the two solutions appear not to be the same. In the first solution, the conditions of equilibrium of the rod  $CD$  and the particles at  $C$  and  $D$  are separately considered; in the second solution, they are treated as one body and the conditions of equilibrium of this compound body are found to be sufficient to determine the ratio of the tensions of the strings. Consider the reactions at the corner  $D$ . In the first solution there are two reactions at this corner, viz. those between the particle at  $D$  and the two

rods  $AD$ ,  $CD$ . These are proved to act along  $AD$  and  $CD$ ; let them be called  $R_1$  and  $R_2$  respectively. In the second solution the only reaction at the corner  $D$  which is considered is  $R_1$ , the other reaction  $R_2$  not being required. If it had been asked, as part of the question, to find the reaction at the joint  $D$ , it would have been necessary to state in the enunciation how the rods were joined to each other and to the string. It is only when this mode of attachment is given that we can determine whether it is  $R_1$ ,  $R_2$  or some combination of both that can be properly called *the* reaction at the corner  $D$ .

Ex. 2. A parallelepiped, formed of twelve weightless rods freely jointed together at their extremities, is in equilibrium under the action of four stretched elastic strings connecting the four pairs of opposite vertices. Show that the tensions of the rods and strings are proportional to their lengths. [Coll. Ex., 1890.]

Ex. 3. Four rods are jointed at their extremities so as to form a quadrilateral  $ABCD$ , and the opposite corners  $A$ ,  $C$  and  $B$ ,  $D$  are joined by tight strings. If the tensions are represented by  $f(AC)$  and  $f(BD)$ , prove that

$$f(AC) \left( \frac{1}{AO} + \frac{1}{OC} \right) = f(BD) \left( \frac{1}{BO} + \frac{1}{OD} \right),$$

where  $O$  is the intersection of the diagonals.

By placing particles at the four corners as in the first solution to the last example, this problem is immediately reduced to that solved in Ex. 3, Art. 130. The result follows at once. This problem is due to Euler, who gives an equivalent result in *Acta Academiae Scientiarum Imperialis Petropolitanae*, 1779. From this he deduces the result given in Ex. 1 for a parallelogram.

Ex. 4. If the opposite sides  $AD$ ,  $BC$  (or  $CD$ ,  $BA$ ) are produced to meet in  $X$ , prove that the tensions of the strings are inversely proportional to the perpendiculars drawn from  $X$  on the strings.


To prove this we follow the second method of solution adopted in Ex. 1. Let the strings be attached to the extremities of the rods  $AB$ ,  $CD$ . The reactions at  $D$  and  $C$  now act along  $AD$  and  $BC$ . Considering the equilibrium of the rod  $CD$ , the result follows at once by taking moments about  $X$ .

Ex. 5. Four rods, jointed together at their extremities, form a quadrilateral  $ABCD$ . Points  $E$ ,  $F$  on the adjacent sides  $AB$ ,  $BC$  are joined by one string and points  $G$ ,  $H$  on the adjacent sides  $BC$ ,  $CD$  are joined by another string. Compare the tensions of the strings. This is a modification of a problem solved by Euler in 1779. *Acta Academiae Petropolitanae*. The following solution is founded on his.

*Lemma.* We may replace the string  $EF$  by a string joining any other two points  $E'$ ,  $F'$  taken in the same two sides  $AB$ ,  $BC$  without altering any reaction except the one at  $B$ , provided the moments about  $B$  of the tensions of  $EF$ ,  $E'F'$  are equal. To prove this, let the strings intersect in  $K$ . The tension  $T$ , acting at  $F$  on the rod  $BC$ , may be transferred to  $K$ , and then resolved into two, viz. one  $U$  which acts along  $KF'$ , and which may be transferred to  $F'$ , and another  $V$  which acts along  $KB$  and may be transferred to  $B$ . In the same way the tension  $T$  acting at  $E$  on the rod  $AB$  may be resolved into  $U$  acting at  $E'$  along  $E'K$ , and  $V$  acting at  $B$  along  $BK$ . Thus the equal forces  $T$ ,  $T$  at  $E$  and  $F$  are replaced by the equal forces  $U$ ,  $U$  at  $E'$ ,  $F'$ , i.e. by the tension  $U$  of a string  $E'F'$ . At the same time the mutual reactions at  $B$  are altered by the superposition of the two equal and opposite forces called  $V$ . The other forces and reactions of the system are unaffected by the change. Since  $T$  is the resultant of  $U$  and  $V$ , the moments of  $T$  and  $U$  about  $B$  must be equal.



By using this lemma we may transfer the strings  $EF, GH$  until they coincide with the diagonals  $AC, BD$ . Let  $T, T'$  be the tensions of  $EF, GH$ . Then  $U = nT$  is the tension of  $AC$ , where  $n$  is the ratio of the perpendiculars from  $B$  on  $EF$  and




$AC$ . So  $U' = n'T'$  is the tension of  $BD$ , where  $n'$  is the ratio of the perpendiculars from  $C$  on  $HG$  and  $BD$ . The ratio of the tensions along the diagonals has been found in Ex. 3. Using that result we have

$$nT \left( \frac{1}{AO} + \frac{1}{OC} \right) = n'T' \left( \frac{1}{BO} + \frac{1}{OD} \right).$$

Ex. 6. Four rods joined together at their extremities form a quadrilateral  $ABCD$ . Points  $E, F$  on the opposite sides  $AB, CD$  are joined by one string, and points  $G, H$  on the other two sides  $AD, BC$  are joined by a second string. If the opposite sides  $AD, BC$  meet in  $X$ , and the sides  $CD, BA$  in  $Y$ , and  $p, p'$  are the perpendiculars from  $X, Y$  on the strings  $EF, GH$ , prove that the tensions  $T, T'$  are connected by the equation

$$\frac{Tp \sin X}{AB \cdot CD} + \frac{T'p' \sin Y}{AD \cdot BC} = 0.$$

The perpendicular from  $X$  or  $Y$  on any string is to be regarded as positive when the string intersects  $XY$  at some point between  $X$  and  $Y$ .



It follows that in equilibrium one string must pass between  $X$  and  $Y$  and the other outside both, contrary to what is represented in the diagram. It also follows that, if one string as  $GH$  produced passes through  $Y$ , either the tension of the other string is zero, or that string produced passes through  $X$ .

Let the reactions at each of the corners of the quadrilateral be resolved into forces acting along the adjacent sides, viz.  $P', P$  at  $A$  along  $DA, AB$ ;  $Q', Q$  at  $B$

moments about  $D$  and  $C$  respectively,

$$P \cdot YD \sin Y = T' \cdot DH \sin H, \quad Q' \cdot YC \sin Y = T' \cdot CG \sin G.$$

Consider next the equilibrium of the rod  $AB$ , taking moments about  $X$ ,

$$(P - Q')XM = T_p,$$

where  $XM$  is a perpendicular from  $X$  on  $AB$ .

Substituting, and remembering that  $\sin H$ ,  $\sin G$ , and  $\sin X$  have the ratio of the opposite sides in the triangle  $XHG$ , we find

$$\frac{DH \cdot CY \cdot XG - DY \cdot CG \cdot HI}{YD \cdot YC} \cdot \frac{\sin X}{\sin Y} \cdot \frac{XM \cdot T'}{HG} = T_p.$$

Now the numerator of the first fraction on the left-hand side is minus the sum of the products of the segments (with their proper signs) into which the sides of the triangle  $DCX$  are divided by the points  $G$ ,  $H$ ,  $Y^*$ . The equation therefore reduces to

$$\frac{[GHY] \cdot DC \cdot CX \cdot XD}{[DCX] \cdot YD \cdot YC} \cdot \frac{\sin X}{\sin Y} \cdot \frac{XM \cdot T'}{HG} + T_p = 0,$$

where  $[GHY]$  and  $[DCX]$  represent the areas of the triangles  $GHY$  and  $DCX$ . These areas are equal to  $\frac{1}{2}HG \cdot p'$  and  $\frac{1}{2}DX \cdot CX \sin X$  respectively. Also  $AB \cdot XM$  is twice the area of the triangle  $AXB$ , and is therefore equal to  $XA \cdot XB \sin X$ . Again,

$$\frac{YD}{\sin A} = \frac{AD}{\sin Y}, \quad \frac{YC}{\sin B} = \frac{BC}{\sin Y}, \quad \frac{XA}{\sin B} = \frac{AB}{\sin X} = \frac{XB}{\sin A}.$$


Substituting we obtain the equation connecting  $T$ ,  $T'$  given in the enunciation.

\* Let  $D, E, F$  be three arbitrary points taken on the sides of a triangle  $ABC$ . If  $\Delta, \Delta'$  be the areas of the triangles  $ABC, DEF$ , it may be shown that

$$\frac{\Delta'}{\Delta} = \frac{AF \cdot BD \cdot CE + AE \cdot CD \cdot BF}{abc}.$$

To form the two products  $AF \cdot BD \cdot CE$  and  $AE \cdot CD \cdot BF$ , we start from any corner, say  $A$ , and travel round the triangle, first one way and then the other, taking on each circuit one length from each side. The sum of the two products so formed, each with its proper sign, is the expression in the numerator.

The signs of these factors may be determined by the following rule. Each length, being drawn from one of the corners of the triangle  $ABC$ , along one of the sides, is to be regarded as positive or negative according as it is drawn towards or from the other corner in that side. Thus,  $AF$  being drawn from  $A$  towards  $B$  is therefore positive,  $BF$  being drawn from  $B$  towards  $A$  is also positive. If  $F$  were taken on  $AB$  produced beyond  $B$ ,  $AF$  would still be positive, but  $BF$  would be negative. If  $F$  move along the side  $AB$ , in the direction  $AB$ , the area  $DEF$  vanishes and becomes negative when  $F$  passes the transversal  $ED$ .




In the same way, if we draw any three straight lines through the corners of the triangle, say  $AD, BE, CF$ , they will enclose an area  $PQR$ . If the area of the triangle  $PQR$  is  $\Delta''$ , it may be shown that

$$\frac{\Delta''}{\Delta} = \frac{(AF \cdot BD \cdot CE - AE \cdot CD \cdot BF)^2}{(ab - CE \cdot CD)(bc - AE \cdot AF)(ca - BF \cdot BD)}.$$

The author has not met with these expressions for the area of two triangles which often occur. He has therefore placed them here in order that the argument in the text may be more easily understood.

133. Ex. 1. A series of rods in one plane, jointed together at their extremities, form a *closed polygon*. Each rod is acted on at its middle point in a direction perpendicular to its length by a force whose magnitude is proportional to the length of the rod. These forces act all inwards or all outwards. Show that in equilibrium (1) the polygon can be inscribed in a circle, (2) the reactions at the corners act along the tangents to the circle, (3) the reactions are all equal.

Let  $AB, BC, CD, \&c.$  be the rods,  $L, M, N, \&c.$  their middle points. Let  $\alpha B\beta, \beta C\gamma, \&c.$  be the lines of action of the reactions at the corners  $B, C \&c.$  Since each rod is in equilibrium, the forces at the middle points of the rods must pass through  $\alpha, \beta, \gamma, \&c.$  respectively. Consider the rod  $BC$ ; the triangles  $BM\beta, CM\beta$  are equal and similar, also the reactions along  $B\beta$  and  $C\beta$  balance the force along  $M\beta$  which



bisects the angle  $B\beta C$ . Hence these reactions are equal. It follows that the reactions at all the corners are equal in magnitude.

Draw  $BO, CO$  perpendicular to the directions of the reactions at  $B$  and  $C$ . These must intersect in some point  $O$  on the perpendicular through  $M$  to  $BC$ . The sides of the triangle  $OBC$  are perpendicular to the directions of the three forces which act on the rod  $BC$ , and are in equilibrium. Hence  $CO$  represents the magnitude of the reaction at  $C$  on the same scale that  $BC$  represents the force at  $M$ .

In the same way if  $CO', DO'$  be drawn perpendicular to the reactions at  $C$  and  $D$ , they will meet in some point  $O'$  on the perpendicular through  $N$  to  $CD$ . Also  $CO'$  will measure the reaction at  $C$  on the same scale that  $CD$  measures the force at its middle point. Hence by the conditions of the question  $CO = CO'$ , and therefore  $O$  and  $O'$  coincide. Thus a circle, centre  $O$ , can be drawn to pass through all the angular points of the polygon and to touch the lines of action of all the reactions.

Ex. 2. A series of jointed rods form an *unclosed polygon*. The two extremities of the system are constrained, by means of two small rings, to slide along a smooth rod fixed in space. If each moveable rod is acted on, as in the last problem, by a force at its middle point perpendicular and proportional to its length, prove that the polygon can be inscribed in a circle having its centre on the fixed rod.

Let  $A$  and  $Z$  be the two extremities. We can attach to  $A$  and  $Z$  a second system of rods equal and similar to the first, but situated on the opposite side of the fixed rod. We can apply forces to the middle points of these additional rods acting in the same way as in the given system. With this symmetrical arrangement the fixed rod becomes unnecessary and may be removed. The results follow at once from those obtained in the last problem.

These two problems may be derived from Hydrostatical principles. Let a vessel be formed of plane vertical sides hinged together at their vertical intersections, and let this vessel be placed on a horizontal table. Let the interior be filled with fluid

which cannot escape either between the sides and the table or at the vertical joinings. The pressures of the fluid on each face will be proportional to that part of the area of each which is immersed in the fluid, and will act at a point on the median line. These pressures are represented in the two problems by the forces acting on the rods at their middle points. It will follow from a general principle, to be proved in the chapter on virtual work, that the vessel will take such a form that the altitude of the centre of gravity of the fluid above the table is the least possible. Hence the depth of the fluid is a minimum. Since the volume is given, it immediately follows that the area of the base is a maximum.

By a known theorem in the differential calculus, the area of a polygon formed of sides of given length is a maximum when it can be inscribed in either a circle or a semicircle, according as the polygon is closed or unclosed. (De Morgan's *Diff. and Int. Calculus*, 1842.) The results of the preceding problems follow at once.

We may also deduce the results from the principle of virtual work without the intervention of any hydrostatical principles.

We may notice that both these theorems will still exist if a great many consecutive sides of the polygon become very short. In the limit these may be regarded as the elementary arcs of a string acted on by normal forces proportional to their lengths. *If then a polygon be formed by rods and strings, and be in equilibrium under the action of a uniform normal pressure from within, the sides can be inscribed in a circle, and the strings will form arcs of the same circle.*

The first of these two problems was solved by N. Fuss in *Mémoires de l'Académie Impériale des Sciences de St Pétersbourg*, Tome VIII, 1822. His object was to determine the form of a polygonal jointed vessel when surrounded by fluid.

✓ **134. Ex. Polygon of heavy rods.**  *$n$  uniform heavy rods  $A_0A_1, A_1A_2$  &c.,  $A_{n-1}A_n$  are freely jointed together at  $A_1, A_2$  &c.  $A_{n-1}$  and the two extremities  $A_0$  and  $A_n$  are hinged to two points which are fixed in space; it is required to find the conditions of equilibrium.*

At each of the joints  $A_0, A_1$  &c. draw a vertical line upwards; let  $\theta_0, \theta_1$  &c. be the inclinations of the rods  $A_0A_1, A_1A_2$  &c. to these verticals, the angles being measured round each hinge from the vertical to the rod in the same direction of rotation. Let the weights of these rods be  $W_0, W_1$  &c.

*First Method.* The equilibrium will not be disturbed if we replace the weight  $W$  of any rod by two vertical forces, each equal to  $\frac{1}{2}W$ , acting at the extremities of the rod. In this way each rod may be regarded as separated into three parts, viz. the two terminal particles, each acted on by half the weight of the rod, and the intermediate portion thus rendered weightless. Let us first consider how these several parts act on each other. At any joint the two terminal particles of the adjacent rods are hinged together. Each particle is in equilibrium under the action of the force at the hinge, the half-weight of the rod of which it forms a part, and the reaction between itself and the intermediate portion of that rod. This last reaction is therefore a force. Since the intermediate portion of each rod has been rendered weightless, the reactions on it will act along the rod, Art. 131. Let the reactions along the intermediate portions of the rods  $A_0A_1, A_1A_2$  &c., be  $T_0, T_1$  &c., and let these be regarded as positive when they pull the terminal particles as if the rods were strings.


To avoid introducing the force at a hinge into our equations we shall consider the equilibrium of the two particles adjacent to that hinge as forming one system.

This compound particle is acted on by the half-weights of the adjacent rods and the reactions along the intermediate portions of those rods. The result of the argument is, that we may regard all the rods as being without weight, and suppose them to be hinged to heavy particles placed at the joints, the weight of each particle being equal to half the sum of the weights of the adjacent rods.

A system of weights joined, each to the next in order, by weightless rods or strings and suspended from two fixed points is usually called a *funicular polygon*.

Consider the equilibrium of any one of the compound particles, say that at the joint  $A_2$ . Resolving horizontally and vertically, we have

$$\left. \begin{aligned} T_1 \sin \theta_1 &= T_2 \sin \theta_2 \\ T_2 \cos \theta_2 - T_1 \cos \theta_1 &= \frac{1}{2} (W_1 + W_2) \end{aligned} \right\} \dots\dots\dots (1).$$



We easily find  $\frac{\frac{1}{2} (W_1 + W_2)}{\cot \theta_2 - \cot \theta_1} = T_1 \sin \theta_1.$

The right-hand side of this equation is the same for all the rods, being equal to the horizontal tension at any joint, we find therefore

$$\frac{\frac{1}{2} (W_1 + W_2)}{\cot \theta_2 - \cot \theta_1} = \frac{\frac{1}{2} (W_2 + W_3)}{\cot \theta_3 - \cot \theta_2} = \&c. \dots\dots\dots (2).$$

If  $A_r, A_s$  be any two joints we see that each of these fractions is equal to

$$\frac{\frac{1}{2} W_{r-1} + W_r + \dots + W_{s-1} + \frac{1}{2} W_s}{\cot \theta_s - \cot \theta_{r-1}}.$$

**135. Second Method.** In this method we consider the equilibrium of any two successive rods, say  $A_1A_2, A_2A_3$ , and take moments for each about the extremity remote from the other rod.

Let  $X_2, Y_2$  be the resolved parts of the reaction at the joint  $A_2$  on the rod  $A_2A_3$ . The two equations of moments give

$$\left. \begin{aligned} -X_2 \cos \theta_2 + Y_2 \sin \theta_2 + \frac{1}{2} W_2 \sin \theta_2 &= 0 \\ -X_2 \cos \theta_1 + Y_2 \sin \theta_1 - \frac{1}{2} W_1 \sin \theta_1 &= 0 \end{aligned} \right\} \dots\dots\dots (3).$$

Eliminating  $Y_2$  we find

$$X_2 (\cot \theta_2 - \cot \theta_1) = \frac{1}{2} (W_1 + W_2) \dots\dots\dots (4),$$

which is equivalent to equations (2).

**136.** Let  $l_0, l_1$  &c. be the lengths of the rods,  $h, k$  the horizontal and vertical coordinates of  $A_n$  referred to  $A_0$  as origin. We then have

$$\left. \begin{aligned} l_0 \cos \theta_0 + l_1 \cos \theta_1 + \dots + l_{n-1} \cos \theta_{n-1} &= k \\ l_0 \sin \theta_0 + l_1 \sin \theta_1 + \dots + l_{n-1} \sin \theta_{n-1} &= h \end{aligned} \right\} \dots\dots\dots (5).$$

The equations (2) supply  $n-2$  relations between the angles  $\theta_0, \theta_1$  &c. and the weights  $W_0, W_1$  &c. of the rods. Joining these to (5) we have sufficient equations to find the angles when the weights are known. When the angles and the weights of two of the rods are known, the  $n-2$  remaining weights may be found from (2).

**137.** It is evident that either of these methods may be used if the rods are not uniform or if other forces besides the weights act on them. The two equations of moments in the second method will be slightly more complicated, but they can be easily formed. In the first method the transference of the forces parallel to themselves to act at the joints is also only a little more complicated, see Art. 79.

**138.** *To find the reactions at the joints.* If we use the second method, these are easily found from equations (3). But if we use the first method we must transfer the weights  $\frac{1}{2}W_1$  and  $\frac{1}{2}W_3$  back to the extremities of the rods which meet at  $A_2$ . In the original arrangement of the rods when hinged to each other, let  $R_2$  be the action at the joint  $A_2$  on the rod  $A_2A_3$ . The terminal particle of the rod  $A_2A_3$  is then acted on by the three forces  $R_2$ ,  $\frac{1}{2}W_2$  and  $T_2$ . We therefore have

$$R_2^2 = T_2^2 + \frac{1}{4}W_2^2 - W_2T_2 \cos \theta_2 \dots \dots \dots (6).$$

The direction of the reaction is easily deduced from equations (2). Suppose that the rods  $A_1A_2$ ,  $A_2A_3$  are joined by a short rod or string without weight. The position of this rod is clearly the line of action of  $R_2$ . Treating this rod as if it were one of the rods of the polygon, we have, if  $\phi_2$  be its inclination to the vertical,


$$\frac{\frac{1}{2}W_1}{\cot \phi - \cot \theta_1} = \frac{\frac{1}{2}W_2}{\cot \theta_2 - \cot \phi} \dots \dots \dots (7),$$

$$\therefore (W_1 + W_2) \cot \phi = W_2 \cot \theta_1 + W_1 \cot \theta_2.$$

**139.** *The subsidiary polygon.* The lines of action of the reactions  $R_1$ ,  $R_2$  &c. at the joints will form a new polygon whose corners  $B_1$ ,  $B_2$  &c. are vertically under the centres of gravity of the rods  $A_1A_2$ ,  $A_2A_3$  &c. The weights of the rods may be supposed to act at the corners of this new polygon. Each weight will be in equilibrium with the reactions which act along the adjacent sides of the polygon.

If we suppose the corners  $B_1$ ,  $B_2$  &c. to be joined by weightless strings or rods we shall have a second funicular polygon. This funicular polygon may be treated in the same way as the former one, except that we have the weights  $W_1$ ,  $W_2$  &c. instead of  $\frac{1}{2}(W_1 + W_2)$ ,  $\frac{1}{2}(W_2 + W_3)$  &c.

**140.** Let  $B_0B_1B_2$  &c. be any funicular polygon;  $W_1$ ,  $W_2$ , &c., the weights suspended from the corners  $B_1$ ,  $B_2$  &c. From any arbitrary point  $O$  draw straight lines  $Ob_1$ ,  $Ob_2$ ,  $Ob_3$  &c. parallel to the sides  $B_0B_1$ ,  $B_1B_2$ ,  $B_2B_3$  &c. to meet any vertical straight line in the points  $b_1$ ,  $b_2$ ,  $b_3$  &c. Since a particle at the point  $B_1$  is in equilibrium under the action of the weight  $W_1$  and the tensions  $R_1$ ,  $R_2$  acting



along the sides  $B_1B_0$ ,  $B_1B_2$ , it follows, by the triangle of forces, that the sides of the triangle  $Ob_1b_2$  are proportional to these forces. In the same way, the sides of the triangle  $Ob_2b_3$  represent on the same scale the weight  $W_2$  and the tensions acting along  $B_2B_1$ ,  $B_2B_3$ . In general the straight lines  $Ob_1$ ,  $Ob_2$  &c. represent the tensions

acting along the sides of the funicular polygon to which they are respectively parallel; while any part of the vertical straight line as  $b_2b_6$  represents the sum of the weights at  $B_2$ ,  $B_3$  and  $B_4$ .

By using this figure we may find *geometrically* the relations between the tensions and the weights. If  $\phi_1$ ,  $\phi_2$  &c. be the inclinations of the sides  $B_0B_1$ ,  $B_1B_2$  &c. to the vertical, we have

$$ON (\cot \phi_1 - \cot \phi_2) = b_1b_2,$$

where  $ON$  is a perpendicular drawn from  $O$  on the vertical straight line. Since  $ON$  represents the horizontal tension  $X$  at any point of the funicular polygon, this

$$\text{equation gives } \frac{W_1}{\cot \phi_1 - \cot \phi_2} = \pm X = \frac{W_2}{\cot \phi_2 - \cot \phi_3} = \&c.$$

In the same way other relations may be established.

The use of this diagram is described in Rankine's *Applied Mechanics*. Such figures are usually called *force diagrams*. We have here only considered the simple case in which the forces are parallel to each other. In the chapter on Graphics this method of solving statical problems will be again considered and extended to forces which act in any directions.

✓ 141. Ex. 1. A chain consisting of a number of equal and in every respect similar uniform heavy rods, freely jointed at their ends, is hung up from two fixed points; prove that the tangents of the angles the rods make with the horizontal are in arithmetical progression, as are also the tangents of the angles the directions of the stresses at the joints make with the same, the common difference being the same for each series.

[Coll. Ex., 1881.]

✓ Ex. 2.  $OA$ ,  $OB$  are vertical and horizontal radii of a vertical circle,  $A$  being the lowest point. A string  $ACDB$  is fixed to  $A$  and  $B$  and divided into three equal parts in  $C$  and  $D$ . Weights  $W$ ,  $W'$  being hung on at  $C$  and  $D$ , it is found that in the position of equilibrium  $C$  and  $D$  both lie on the circle. Prove that  $W = W' \tan 15^\circ$ .

[Trin. Coll., 1881.]

✓ Ex. 3. Four equal heavy uniform rods  $AB$ ,  $BC$ ,  $CD$ ,  $DA$  are jointed at their extremities so as to form a rhombus, and the corners  $A$  and  $C$  are joined by a string. If the rhombus is suspended by the corner  $A$ , show that the tension of the string is  $2W$  and that the reaction at either  $B$  or  $D$  is  $\frac{1}{2}W \tan \frac{1}{2}BAD$ , where  $W$  is the weight of any rod.

✓ Ex. 4.  $AB$ ,  $BC$ ,  $CD$  are three equal rods freely jointed at  $B$  and  $C$ . The rods  $AB$ ,  $CD$  rest on two pegs in the same horizontal line so that  $BC$  is horizontal. If  $\alpha$  be the inclination of  $AB$ , and  $\beta$  the inclination of the reaction at  $B$  to the horizon, prove that  $3 \tan \alpha \tan \beta = 1$ .

[St John's Coll., 1881.]

Ex. 5. Three equal uniform rods are freely jointed at their extremities and rest in equilibrium over two smooth pegs, in a horizontal line at a distance apart equal to half the length of one rod. If the lowest side be horizontal, then the resultant action at the upper joint is  $\frac{1}{\sqrt{3}}\sqrt{3}W$  and at each of the lower  $\frac{1}{\sqrt{3}}\sqrt{57}W$ , where  $W$  is the aggregate weight of the rods.

[Coll. Ex., 1882.]

Ex. 6. Three rods, jointed together at their extremities, are laid on a smooth horizontal table; and forces are applied at the middle points of the sides of the triangle formed by the rods, and respectively perpendicular to them. Show that, if these forces produce equilibrium, the strains at the joints will be equal to one another, and their directions will touch the circle circumscribing the triangle.

[Math. Tripos, 1858.]

*See Rankine  
p. 250.*

Ex. 7. Three pieces of wire, of the same kind, and of proper lengths, are bent into the form of the three squares in the diagram of Euclid I., 47, and the angles of the squares which are in contact are hinged together, so that the smaller ones are supported by the larger square in a vertical plane. Show that in every position, into which the figure can be turned, the action, if any, between the angles of the smaller squares will be perpendicular to the hypotenuse of the right-angled triangle.

[Math. Tripos, 1867.]

Ex. 8. Three uniform rods, whose weights are proportional to their lengths  $a, b, c$ , are jointed together so as to form a triangle, which is placed on a smooth horizontal plane on its three sides successively, its plane being vertical: prove that the stresses along the sides  $a, b, c$  when horizontal are proportional to

$$(b+c) \operatorname{cosec} 2A, \quad (c+a) \operatorname{cosec} 2B, \quad (a+b) \operatorname{cosec} 2C. \quad [\text{Math. Tripos, 1870.}]$$

Ex. 9. Three uniform rods  $AB, BC, CD$  of lengths  $2c, 2b, 2c$  respectively rest symmetrically on a smooth parabolic arc, the axis being vertical and vertex upwards. There are hinges at  $B$  and  $C$ , and all the rods touch the parabola. If  $W$  be the weight of either of the slant rods, show that its pressure against the parabola is equal to  $W \frac{a^2}{(a^2+b^2)b}$ , where  $4a$  is the latus rectum of the parabola.

[Coll. Ex., 1883.]

Ex. 10.  $ABCD$  is a quadrilateral formed by four uniform rods of equal weight loosely jointed together. If the system be in equilibrium in a vertical plane with the rod  $AB$  supported in a horizontal position, prove that  $2 \tan \theta = \tan \alpha + \tan \beta$ , where  $\alpha, \beta$  are the angles at  $A$  and  $B$ , and  $\theta$  is the inclination of  $CD$  to the horizon; also find the stresses at  $C$  and  $D$ , and prove that their directions are inclined to the horizon at the angles  $\tan^{-1} \frac{1}{2} (\tan \beta - \tan \theta)$  and  $\tan^{-1} \frac{1}{2} (\tan \alpha + \tan \theta)$  respectively.

[Math. Tripos, 1879.]

Ex. 11. Four equal rods  $AB, BC, CD, DA$ , jointed at  $A, B, C, D$ , are placed on a horizontal smooth table to which  $BC$  is fixed, the middle points of  $AD, DC$  being connected by a string which is tight when the rods form a square. Show that, if a couple act on  $AB$  and produce a tension  $T$  in the string, its moment must be  $\frac{1}{2} T \cdot AB \sqrt{2}$ .

[Coll. Ex., 1888.]

Ex. 12. A weightless quadrilateral framework  $A_1A_2A_3A_4$  rests with its plane vertical and the side  $A_1A_2$  on a horizontal plane. Two weights  $W, W'$  are placed at the corners  $A_4, A_3$  respectively, while a string connecting the two corners  $A_1A_3$  prevents the frame from closing up. Show that the tension  $T$  of the string is given by

$$nT \sin \theta_2 \sin \theta_4 = W' \cos \theta_1 \sin \theta_3 - W' \cos \theta_2 \sin \theta_4,$$

where  $\theta_1, \theta_2, \theta_3, \theta_4$  are the internal angles of the quadrilateral, and  $n$  is the ratio of the side on the horizontal plane to the length of the string.

Ex. 13. A pentagon formed of five heavy equal uniform jointed bars is suspended from one corner, and the opposite side is supported by a string attached to its middle point of such length as to make the pentagon regular. Prove that the tension of the string is equal to  $4W \cos^2 \frac{1}{10} \pi$ , where  $W$  is the weight of any rod. Find also the reactions at the corners.

Ex. 14. A regular pentagon  $ABCDE$ , formed of five equal heavy rods jointed together, is suspended from the joint  $A$ , and the regular pentagonal form is maintained by a rod without weight joining the middle points  $K, L$  of  $BC$  and  $DE$ . Prove that the stress at  $K$  or  $L$  is to the weight of a rod in the ratio of  $2 \cot 18^\circ$  to unity.

[Math. Tripos, 1885.]



Ex. 15. The twelve edges of a regular octahedron are formed of rods hinged together at the angles, and the opposite angles are connected by elastic strings; if the tensions of the three strings are  $X, Y, Z$  respectively, show that the pressure along any of the rods connecting the extremities of the strings whose tensions are  $Y$  and  $Z$  is  $(Y+Z-X)/2\sqrt{2}$ . [Math. Tripos, 1867.]

Ex. 16. Any number of equal uniform heavy rods of length  $a$  are hinged together, and rotate with uniform angular velocity  $\omega$  about a vertical axis through one extremity of the system, which is fixed; if  $\theta, \theta', \theta''$  be the inclinations to the vertical of the  $n^{\text{th}}, (n+1)^{\text{th}}, (n+2)^{\text{th}}$  rods counting from the free end, and  $a\omega^2 = 3\kappa g$ , prove that


$$(2n+3) \tan \theta'' - (4n+2) \tan \theta' + (2n-1) \tan \theta + \kappa \{ \sin \theta'' + 4 \sin \theta' + \sin \theta \} = 0.$$

[Math. Tripos, 1877.]

### Reactions at rigid connections

142. Let  $AB$  be a horizontal rod fixed at the extremity  $A$  in a vertical wall, and let it support a weight  $W$  at its other extremity  $B$ . We may enquire what are the stresses across a section at any point  $C$ , by which the portion  $CB$  of the rod is supported.

It is evident that the reaction at  $C$  cannot consist of a single force, for then a force acting at  $C$  would balance a force  $W$  to which it could not be opposite. It is also clear that the resultant action across the section  $C$  (whatever it may be) must be equal and opposite to the force  $W$  acting at  $B$ . Let us transfer the force  $W$  from  $B$  to any point of the section  $C$  by help of Art. 100. We see that the reaction across the section is equivalent to a force equal to  $W$ , together with a couple whose moment is  $W \cdot BC$ .



If the portion  $CB$  of the rod is heavy, we may suppose its weight collected at the middle point of  $CB$ . Let  $W'$  be the weight of this part of the rod. Then we must transfer this weight also to the base of reference  $C$ . The whole reaction across the section of the rod will then consist of (1) a force  $W + W'$  and (2) a couple whose moment is  $W \cdot BC + \frac{1}{2} W' \cdot BC$ .

Various names have been given to the reaction force and reaction couple at different times. The components of the force along the length of the rod and transverse to it have been called the *tension* and *shear* respectively. The former being normal to a perpendicular section of the rod is sometimes called the *normal stress*. The magnitude of the couple has been called the tendency of the forces to break the rod, or briefly, the *tendency to break*. It

is also called the *moment of flexure*, or *bending stress*. See Rankine's *Applied Mechanics*. In what follows we shall restrict ourselves to the case in which the rod is so thin that we may speak of it as a line in discussing the geometry of the figure.

**143.** Generalizing this argument, we arrive at the following result: *the action across a section at any point  $C$  of a rod is equal and opposite to the resultant of all the forces which act on the rod on one side of that point  $C$ .*

The action across  $C$  on  $CB$  balances the forces on  $CB$ . The equal and opposite reaction on  $AC$  across the same section balances those on  $AC$ . Since the forces on one side of  $C$  balance those on the other side when there is equilibrium, it is a matter of indifference whether we consider the forces on the one side or the other of  $C$  provided we keep them distinct.


Thus the bending couple at  $C$  is equal to the sum of the moments of all the forces which act on one side of  $C$ . So also the shear at  $C$  is equal to the sum of the resolved parts of these forces along the normal to the rod at  $C$ .

If we regard the rod as slightly elastic we may explain otherwise the origin of the force and couple. The weight  $W$  will slightly bend the rod, and thus stretch the upper fibres and compress the lower ones. The action across the section at  $C$  will therefore consist of an infinite number of small tensions across its elements of area. By Art. 104 all these can be reduced to a single force and a single couple at a base of reference at  $C$ .

**144.** Ex. 1. A rod  $AB$ , of given length  $l$ , is supported in a horizontal position by two pegs, one at each end. A heavy particle  $M$ , whose weight is  $W$ , traverses the rod slowly from one end to the other. It is required to find the stresses at any point.

Let  $AM = \xi$ ,  $BM = l - \xi$ . Let  $R$  and  $R'$  be the pressures of the supports at  $A$  and  $B$  on the rod. These are evidently given by

$$R'l = W \cdot \xi, \quad Rl = W(l - \xi).$$



Let  $P$  be the point at which the stresses are required, and let  $AP = x$ . To find these we consider the equilibrium of either the portion  $AP$  or the portion  $BP$  of the rod. We choose the former, as the simpler of the two, because there is only

ting on it. The shear at  $P$  is therefore equal in magnitude to of the stress couple is equal to  $Rx$ .

rich the stresses are required is on the other side of  $M$  as at  $P'$ , s more convenient to consider the equilibrium of  $BP'$ . The to  $R'$ , and the bending moment to  $R'(l-x')$ .

ouple is generally more effective in breaking a rod than either sion, we shall at present turn our attention to the couple. If erect an ordinate  $PQ$  proportional to the bending couple at  $P$ , represent to the eye the magnitude of the bending couple at rod. In our case the locus of  $Q$  is clearly portions of two ented in the figure by the dotted lines. The maximum ordinate id is represented by either  $R\xi$  or  $R'(l-\xi)$ , according as we take or the sides  $AM$  or  $MB$  of the rod. Substituting for  $R$  or  $R'$ , at  $M$  becomes  $W\xi(l-\xi)/l$ . This is a maximum when  $M$  is at  $AB$ .


vs in a general way that, when a man stands on a stiff plank a, the bending couple is greatest at the point of the plank on ds. Also if he walks slowly along the plank, the bending couple is midway between the two supports.

rm heavy rod  $AB$  is supported at each end. If  $w$  be the weight ove that the bending couple at any point  $P$  will be  $\frac{1}{2}w \cdot AP \cdot BP$ .

veral forces act on a rod, the diagram by which the distribution s exhibited to the eye can be constructed in a similar manner. . act at the points  $A_1, A_2$  &c. of a rod in the directions indicated  $A_1A_2=a_2, A_1A_3=a_3$  and so on. Then the bending moment at etween  $A_3$  and  $A_4$ , is obtained by taking the moments of the t  $A_1, A_2, A_3$ , these being points on one side of  $P$ . Putting d bending moment is

$$y = R_1x - R_2(x-a_2) + R_3(x-a_3).$$

te  $PQ$  to represent  $y$ , it is clear that the locus of  $Q$  between  $A_3$  line.



$P$  moves beyond  $A_4$  we must add to this expression the moment  $-R_4(x-a_4)$ . The locus of  $Q$  is now a different straight line. mer at the point  $x=a_4$ , i.e. at the top of the ordinate corre- at  $A_4$ , but its inclination to the rod is different.

when a rod is acted on only by forces at isolated points, the g the bending couple will consist of a series of finite straight es an easy method of constructing the diagram. Calculate the ing the bending couples at these isolated points, and join their ght lines. In this case there can be no maximum ordinate d points  $A_1, A_2$  &c. at which the forces act. Hence the bending inum or minimum only at one of these points.

If the rod is heavy, its weight is distributed over the whole rod. The bending couple at  $P$  will contain not merely the moments of the forces which act at  $A_1, A_2$  &c., but also that of the weight of the portion  $A_1P$  of the rod. If  $w$  be the weight per unit of length, the bending couple at  $P$  will be

$$y = \Sigma R(x-a) - \frac{1}{2}wx^2,$$

for the weight of  $A_1P$  will be  $wx$ , and it may be collected at the middle point of  $A_1P$ .

This is the equation to a parabola. Hence the diagram will consist of a series of arcs of parabolas, each intersecting the next at the extremity of the ordinate along which an isolated force acts. All these parabolas have their axes vertical. If the different sections of the rod be of the same weight per unit of length, the intern recta of the parabolas will be equal.

This expression gives the bending moment by which the forces on the left or negative side of any point  $P$  tend to turn the portion of the rod on the positive side of  $P$  in the direction of rotation of the hands of a watch.

Suppose that any portion  $CD$  of a rod  $ACDB$  has no weight, and that no point of support lies between  $C$  and  $D$ . The remaining parts of the rod on each side of  $CD$  may have any weights and any number of points of support. The bending couple at any point between  $C$  and  $D$  is always proportional to the ordinate of some straight line. But if  $y_1, y_2$ , and  $y$  are ordinates of any straight line at  $C, D$  and  $P$ , and if the distances  $CP$  and  $PD$  are  $l_1$  and  $l_2$ , it is easy to see that

$$y(l_1 + l_2) = y_1l_2 + y_2l_1.$$

This equation therefore must also connect the bending couples  $y_1, y_2$ , and  $y$  at the points  $C, D$ , and any intermediate point  $P$ .

Let us next suppose that the portion  $CD$  of the rod is heavy. The bending couple at any point of this portion of the rod is now proportional to the ordinate of the parabola  $y = A + Bx - \frac{1}{2}wx^2$ , where  $A = -\Sigma Ra$  and  $B = \Sigma R$ . If  $y_1, y_2$  and  $y$  are the ordinates at  $C, D$  and any point  $P$ , where  $CP = l_1, PD = l_2$ , it is easy to prove that

$$y(l_1 + l_2) = y_1l_2 + y_2l_1 + \frac{1}{2}wl_1l_2(l_1 + l_2).$$

This equation connects the bending couples at any three points of a heavy rod provided there is no point of support within the length considered.

Ex. If  $y_1, y_2, y_3$  be the bending couples at three consecutive points of support of a heavy horizontal rod whose distances apart are  $l_1, l_2$ , then

$$y_2(l_1 + l_2) = y_1l_2 + y_3l_1 + \frac{1}{2}wl_1l_2(l_1 + l_2) - Rl_1l_2,$$

where  $R$  is the pressure at the middle point of support, and  $w$  is the weight of the rod per unit of length.

**146.** Since the bending couple at any point  $P$  is the sum of the moments of the several forces which act on one side of  $P$ , it is clear that each force contributes its share to the bending couple as if it acted alone on the rod. In this way it is sometimes convenient to consider the effects of the forces separately.

For example, if a heavy rod  $AB$ , supported at each end, has a weight  $W$  placed at a point  $M$ , the bending couple at any point  $P$  is the sum of the bending couples found in Art. 144 for the two cases in which (1) the rod is light and (2) there is no weight at  $M$ . The bending couple is therefore given by

$$ly = W \cdot BM \cdot AP + \frac{1}{2}wl \cdot AP \cdot BP.$$

**147.** Ex. 1. A heavy rod is supported in a horizontal position on two pegs, one at each end. A heavy particle, whose weight is  $n$  times that of the rod, is placed

at a point  $M$ . If  $C$  be the middle point of the rod, show that the bending couple will be greatest either at some point between  $M$  and  $C$  or at  $M$ , according as the distance of  $M$  from  $C$  is greater or less than  $n$  times its distance from the nearer end of the rod.

Ex. 2. A semicircular wire  $ACB$  is rotated with uniform angular velocity about a tangent at one extremity  $A$ . Show that the bending couple is zero at  $B$ , is a maximum at the middle point  $C$ , vanishes at some point between  $C$  and  $A$ , and is again a maximum with the opposite sign at  $A$ . Show also that the maximum at  $A$  is greater than that at  $C$ .

It may be assumed that the effect of rotation is represented by supposing the wire to be at rest, and each element to be acted on by a force tending directly from the axis of rotation and proportional to the mass of the element and its distance from the axis.

Ex. 3. A horizontal beam  $AB$ , without weight, supported but not fixed at both ends  $A$  and  $B$ , is traversed from end to end by a moving load  $W$  distributed equally over a segment of it, of constant length  $PQ$ . Show that the bending moment at any point  $X$  of the beam, as the load passes over it, is greatest when  $X$  divides  $PQ$  in the same ratio as that in which it divides  $AB$ . Show also that this maximum bending moment is equal to  $W \cdot AX \cdot BX (AB - \frac{1}{2}PQ) / AB^2$ . [Townsend.]

Let  $AX = a$ ,  $BX = b$ ,  $AB = a + b$ ,  $PQ = l$ ,  $AP = x$ ,  $BQ = \xi$ . Let  $R$  be the shear at  $X$ , and  $y$  the bending moment. Since the weight of  $PX$ , viz.  $w(a - x)$ , may be collected at its middle point we have by taking moments about  $A$  for the portion  $AX$  of the beam  $\frac{1}{2}w(a - x)(a + x) - y + Ra = 0$ , similarly, taking moments for  $BX$  about  $B$ ,  $\frac{1}{2}w(b - \xi)(b + \xi) - y - Rb = 0$ .

Eliminating  $R$ ,  $2l(a + b)y = W\{ab(a + b) - bx^2 - a\xi^2\}$ .

Making  $y$  a maximum with the condition  $x + \xi = a + b - l$ , the results follow at once.

Ex. 4. A uniform horizontal beam, which is to be equally loaded at all points of its length, is supported at one end and at some other point; find where the second support should be placed in order that the greatest possible load may be placed upon the beam without breaking it, and show that it will divide the beam in the ratio 1 to  $\sqrt{2} - 1$ . [Math. Tripos.]

Let  $ABC$  be the beam supported at  $A$  and  $B$ . Let  $w dx$  be the load placed on  $dx$ ;  $wR$ ,  $wR'$  the pressures at  $A$ ,  $B$ . Let  $l$  be the length of the beam,  $\xi = AB$ , then  $2\xi > l$ . We easily find  $R = l - \frac{l^2}{2\xi}$ ,  $R' = \frac{l^2}{2\xi}$ .

Let  $P$  and  $Q$  be two points in  $CB$  and  $BA$  respectively,  $x = CP$ ,  $x' = AQ$ . By taking moments about  $P$  and  $Q$  respectively the bending couples  $y$ ,  $y'$  at  $P$  and  $Q$  are found to be  $y = -\frac{1}{2}wx^2$ ,  $y' = wRx' - \frac{1}{2}wx'^2$ . The first parabola has its maximum ordinate at  $B$ , the second has a maximum ordinate at a point  $x' = R$  which must lie between  $A$  and  $B$ . The bending couples at these points are numerically equal to  $\frac{1}{2}w(l - \xi)^2$  and  $\frac{1}{2}w\left(l - \frac{l^2}{2\xi}\right)^2$ . If these are unequal, the support  $B$  can be moved so as to diminish the greater. The proper position is found by making these equal; hence  $\pm(l - \xi) = l - l^2/2\xi$ . Since  $\xi$  must be greater than  $\frac{1}{2}l$ , this gives  $\xi\sqrt{2} = l$ .

Ex. 5. Three beams  $AB$ ,  $BC$ ,  $CA$  are jointed at  $A$ ,  $B$ ,  $C$ ,  $B$  being an obtuse angle, and are placed with  $AB$  vertical, and  $A$  fixed to the ground, so as to form the

framework of a crane. There is a pulley at  $C$ , and the rope is fastened to  $AB$  near  $B$  and passes along  $BC$  and over the pulley. If it support a weight  $W$ , large in comparison with the weights of the framework and rope, find the couples which tend to break the crane at  $A$  and  $B$ . [Math. Tripos.]

Ex. 6. A gipsy's tripod consists of three uniform straight sticks freely hinged together at one end. From this common end hangs the kettle. The other ends of the sticks rest on a smooth horizontal plane, and are prevented from slipping by a smooth circular hoop which encloses them and is fixed to the plane. Show that there cannot be equilibrium unless the sticks be of equal length; and if the weights of the sticks be given (equal or unequal) the bending moment of each will be greatest at its middle point, will be independent of its length, and will not be increased on increasing the weight of the kettle. [Math. Tripos, 1878.]

Ex. 7. A brittle rod  $AB$ , attached to smooth hinges at  $A$  and  $B$ , is attracted towards a centre of force  $C$  according to the law of nature. Supposing the absolute force to be indefinitely augmented, prove that the rod will eventually snap at a point  $E$  determined by the equation  $\sin \frac{1}{2}(a + \beta) \cos \theta = \sin \frac{1}{2}(a - \beta)$ , where  $a$ ,  $\beta$  denote the angles  $BAC$ ,  $ABC$ , and  $\theta$  the angle  $AEC$ . *Math. Tripos*, 1854. See also the solutions for that year by the Moderators and Examiners.

### Indeterminate Problems

148. When a body is placed on a horizontal plane, the pressure exerted by its weight is distributed over the points of support. When there are more than three supports, or more than two in one vertical plane, this distribution appears to be indeterminate. Thus suppose the body to be a table with vertical legs, and let these legs intersect the plane horizontal surface of the table in the points  $A_1, A_2$  &c. Let the projection on this plane of the centre of gravity of the body be  $G$ . The weight  $W$  of the table will then be supported by certain pressures  $R_1, R_2$  &c. acting at  $A_1, A_2$  &c. Let  $Ox, Oy$  be any rectangular axes of reference in this plane and let  $Oz$  be vertical. Let  $(x_1y_1)$ ,  $(x_2y_2)$  &c. be the coordinates of  $A_1, A_2$  &c. and let  $(xy)$  be those of  $G$ . Since  $W$  is supported by a system of parallel forces we have by Arts. 110 and 111

$$W = R_1 + R_2 + \dots$$

$$Wx = R_1x_1 + R_2x_2 + \dots$$

$$Wy = R_1y_1 + R_2y_2 + \dots$$

These three equations suffice to determine  $R_1, R_2$  &c. if there are but three of them and these not all in one vertical plane, but if there are more than three, the problem appears to be indeterminate.

In this solution we have replaced the supporting power of the floor by forces  $R_1, R_2$  &c. acting upwards along the legs. What we

have really proved is that the table could be supported by such forces in a variety of different ways. Suppose there were four legs; we could choose one of these forces to be what we please, the others could then be found from these three equations. It is therefore evident that the problem of finding what forces could support the table must be indeterminate.


The actual pressures exerted by the table on the floor are not indeterminate, for in nature things are necessarily determinate. When anything appears to be indeterminate, it must be because we have omitted some of the data of the question, i.e. some property of matter on which the solution depends.

We notice that the elementary axioms relating to forces, which have been enunciated in Art. 18, make no reference to the nature of the materials of the body. We have found in the preceding Articles that the equations supplied by these axioms have in general been sufficient to determine all the unknown quantities in our statical problems. In all these problems therefore the magnitudes of the reactions and the positions of equilibrium of the bodies depended, not on the materials of the bodies, but on their geometrical forms and on the magnitudes of the impressed forces. It is evident, however, that these axioms must be insufficient to determine any unknown quantities which depend on the materials of the bodies. In such cases we must have recourse to some new experiments to discover another statical axiom. Thus, when we study the positions of equilibrium of rough bodies, another experimental result, depending on the degree of roughness of the special body considered, is found to be necessary. In the same way the mode of distribution of the pressure over the legs of the table is found to depend on the flexibility of the materials.

However slight the flexibility of the substance of the table may be, yet the weight  $W$  will produce some deformation however small. The magnitude of this will influence and be influenced by the reactions  $R_1, R_2$  &c. The amount of yielding produced by the acting forces in any body is usually considered in that part of mechanics called *the theory of elastic solids*. No complete solution of the special problem of the table has yet been found. But when any assumed law of elasticity is given, it is easy to show by some examples, how the problem becomes determinate. *Poisson's Éléments de Statique* and *Poisson's Traité de Mécanique*.

Ex. 1. A rectangular table has the legs at the four corners alike in all respects and slightly compressible. The amount of compression in each leg is supposed to be proportional to the pressure on that leg. Supposing the floor and the top of the table to be rigid, and the table loaded in any given manner, find the pressure on the four legs. Show that when the resultant weight lies in one of four straight lines on the surface of the table, the table is supported by three legs only. [Math. Tripos, 1860, Watson's problem, see also the Solutions for that year.]

Let the two sides  $AB, AD$  be the axes of  $x$  and  $y$ . Let the resultant weight  $W$  act at a point  $G$  whose coordinates are  $(xy)$ . Let  $AB=a, AD=b$ . Since the top of the table is rigid, the surface as altered by the compression of the legs is still plane. Also, since the compression is slight, we shall neglect small quantities of the second order, and suppose the pressures at  $A, B, C, D$  to remain vertical. We have the usual statical equations



$$\left. \begin{aligned} W &= R_1 + R_2 + R_3 + R_4, \\ Wx &= (R_2 + R_3) a, & Wy &= (R_3 + R_4) b \end{aligned} \right\} \dots\dots\dots (1).$$

Because a diagonal of the table remains straight, the middle point descends a space which is the arithmetic mean of the spaces descended by its two ends. It follows that the mean of the compressions of the legs  $A$  and  $C$  is equal to the mean of the compressions of the legs  $B$  and  $D$ . But it is given that the pressures are proportional to these compressions. Hence


$$R_1 + R_3 = R_2 + R_4 \dots\dots\dots (2).$$

These four equations determine the pressures.

If we put  $R_3=0$ , we easily find that  $2x/a + 2y/b = 1$ , i.e. the table is supported on the three legs  $A, B, D$  when the weight  $W$  lies on the straight line joining the middle points of  $AB, AD$ . Joining the middle points of the other sides in the same way, we obtain four straight lines represented by the dotted lines. When the weight  $W$  lies within this dotted figure all the four legs are compressed; when without this figure three legs only are compressed. The equations above written are then correct, only if we suppose that some of the reactions are negative. As this cannot in general be possible, we must amend the equations (1) by putting one reaction equal to zero. The equation (2) must then be omitted.

✓ Ex. 2.  $A$  and  $C$  are fixed points or pegs in the same vertical line, about which the straight beams  $ADB$  and  $CD$  are freely moveable.  $AB$  is supported in a horizontal position by  $CD$  and has a weight  $W$  suspended at  $B$ . Find the pressure at  $C$  (1) when there is a hinge joint at  $D$ , and (2) when  $CD$  forms one piece with  $AB$ , the weights of the beams being in each case neglected. [Math. Tripos, 1841.]

In the first part of the problem the action at  $D$  is a single force, in the second part it is a force and a couple, Art. 142. In both parts of the problem the action at  $C$  is a force.



In the first part, the actions at  $C$  and  $D$  are equal and act along  $CD$  by Art. 131. Taking moments about  $A$  for the rod  $AD$ , we easily find that this action is equal to  $W \cdot AB/AN$  where  $AN$  is a perpendicular on  $CD$ .

In the second part there is nothing to determine the direction of the action at  $C$ . We only know it balances an unknown force and a couple. If we write



down the three equations of equilibrium for the whole body, it will be seen that we cannot find the four components of the two pressures which act at  $A$  and  $C$ . The problem is therefore indeterminate.

Ex. 3. A rigid bar without weight is suspended in a horizontal position by means of three equal vertical and slightly elastic rods to the lower ends of which are attached small rings  $A$ ,  $B$ , and  $C$  through which the bar passes. A weight is then attached to the bar at any point  $G$ . Show that, on the assumption that the extension or compression of an elastic rod is proportional to the force applied to stretch or compress it, and provided the rods remain vertical, then the rod at  $B$  will be compressed if  $G$  lie in the direction of the longer of the two arms  $AB$ ,  $BC$ ,

and be at a greater distance from  $B$  than  $\frac{AB^2 + BC^2}{AB \cdot BC}$ . [Math. Tripos, 1883.]

*Resd.* Ex. 4.  $ABCD$  is a square; six rods  $AB$ ,  $BC$ ,  $CD$ ,  $DA$ ,  $AC$ ,  $BD$  are hinged together at the angular points, and equal and opposite forces,  $F$ , are applied at  $B$  and  $D$  in the directions  $DB$  and  $BD$  respectively. The rods are elastic, but the extensions or compressions which occur may be treated as infinitesimal.  $e_1$  is the ratio of the extension per unit length to the tension (or of the compression to the corresponding force) for the rod  $AB$ , and is a constant depending upon the material and the section of the rod.  $e_2, e_3 \dots e_6$  are similar constants for the other rods in the order written above. Prove that the tension of the rod  $BD$  is

$$\left(1 - \frac{2\sqrt{2}e_6}{e_1 + e_2 + e_3 + e_4 + 2\sqrt{2}(e_5 + e_6)}\right) F. \quad [\text{Coll. Exam. 1886.}]$$

The rods being only slightly elastic we form the ordinary equations of equilibrium on the supposition that the figure has its undisturbed form, i.e. that  $ABCD$  is a square. We then find that the thrust along every side is the same. If the thrust along any side be  $P$  and those along the diagonals  $BD$ ,  $AC$  be  $T$  and  $T'$ , we have also  $P\sqrt{2} + T' = 0$ ,  $P\sqrt{2} + T + F = 0$ .

We next seek for a geometrical relation between the six lengths of the figure after it has been disturbed by the action of the forces  $F$ ,  $F$ . If the lengths of the sides taken in the order mentioned in the question be  $a(1+x)$ ,  $a(1+y)$ ,  $a(1+z)$ ,  $a(1+u)$ ,  $a\sqrt{2}(1+\rho')$ ,  $a\sqrt{2}(1+\rho)$ , we find that  $2(\rho+\rho') = x+y+z+u$ , when the squares of the small quantities are neglected. Using the law of elasticity, this geometrical condition is equivalent to  $2(e_6T + e_5T') = (e_1 + e_2 + e_3 + e_4)P$ .

We have now three equations to find  $P$ ,  $T$  and  $T'$  in terms of  $F$ .

**150. Stiff Framework\*.** Let  $A_1, A_2$  &c. be  $n$  particles connected together by straight rods hinged to these particles. We shall suppose that all the forces which act on the system are applied to these particles, so that the reactions at the extremities of every rod are forces, both of which act along the rod. It is proposed to ascertain whether the ordinary statical equations are or are not sufficient in number to find all these reactions, i.e. to ascertain whether the problem of finding these pressures is determinate or indeterminate. In the latter contingency it is further proposed to ascertain whether the equations of elasticity are sufficiently numerous to enable us to complete the solution.

\* The reader may consult on the subject of frameworks two papers by Maxwell in the *Phil. Mag.*, 1864 and the *Edinburgh Transactions*, 1872, also the *Statique Graphique*, by Maurice Levy, 1887.

**151.** Let us *enquire* what number of connecting rods could make the framework stiff. Assuming  $n$  not to be less than 2, we start by stiffening two particles  $A_1$  and  $A_2$  by means of one connecting rod. The remaining  $n-2$  have to be jointed to these. In order that a third particle  $A_3$  should be rigidly connected to these two, it must be joined to both  $A_1$  and  $A_2$ , thus requiring two more connecting rods. If a fourth  $A_4$  is to be rigidly connected with these, it must be joined to any two out of the three particles already joined. Proceeding in this manner we see that for each particle joined to the system two additional rods are necessary. Thus to make a system of  $n$  particles rigid, a framework of  $2(n-2)+1$ , i.e.  $2n-3$ , connecting rods is sufficient.

When any particle, as  $A_3$ , is joined by two rods to two other particles as  $A_1, A_2$ , there must be some convention to settle on which side of the base  $A_1A_2$  the vertex of the triangle  $A_3A_1A_2$  is to be taken. If not, there may be more than one polygon having sides equal to the given lengths.

We must also notice that when the particle  $A_3$  is joined to the fixed particles  $A_1, A_2$  by two rods, if  $A_3$  should happen to be in the same straight line with  $A_1A_2$ , the connection is not made perfectly rigid. The particle  $A_3$  could make an *infinitely small displacement* perpendicular to the straight line  $A_1A_2A_3$  on either side of it. This is an imaginary displacement, to be taken account of when the circumstances of the problem require that we should neglect small quantities of the second order.

If the particles are not all in the same plane, and  $n$  is not less than 3, we start with three particles requiring three rods to stiffen them. Each additional particle of the remaining  $n-3$  must be attached to three of the particles already connected. Thus to make a system of  $n$  particles rigid, a framework of  $3(n-3)+3$ , i.e.  $3n-6$ , connecting rods is sufficient.

It is not necessary that the connections between the particles should be made in the precise way just described. All we have proved is that the system could be stiffened by  $2n-3$  or  $3n-6$  rods *properly placed*. These may be arranged in several different ways\* so as to stiffen the system. On the other hand if the rods are not properly placed the system may not be stiff; thus one part of the system may be stiffened by more than the necessary number of rods, and another part may not have a sufficient number.

A system of particles made rigid by just the necessary number of bars is said to be *simply stiff* or *just stiff*. When there are more bars than the necessary number, the system may be called *over stiff*. When the number of bars is less than the number necessary to stiffen the system, the framework is said to be *deformable*. The shape it will assume in equilibrium is then unknown and has to be deduced, along with the reactions, from the equations of equilibrium.

**152.** We may infer as a corollary from this that a polygon having  $n$  corners is in general given when we know the lengths of  $2n-3$  sides. If  $m$  be the number of sides and diagonals in the polygon, there must be  $m-(2n-3)$  relations between their lengths. It appears that  $2n-3$  of the  $m$  lengths are arbitrary except that

\* The argument may be summed up as follows. Taking any fixed axes, a figure is given *in position and form* when we know the  $2n$  or  $3n$  coordinates of its  $n$  corners. These are the arbitrary quantities of the framework. If only *its form* is to be determined we refer the figure to coordinate axes fixed relatively to itself, and the coordinates required to determine the *position* of a free rigid body are now no longer at our disposal. We therefore have  $2n-3$  or  $3n-6$  arbitrary quantities according as the body is in one plane or in space, Art. 206.

they must satisfy such conditions as will permit a figure to be formed; for instance if three of the arbitrary lengths form a triangle, any two of the lengths must together be greater than the third. The exceptional case referred to above occurs when some of these necessary conditions are only just satisfied.

If all the corners are joined, each to each, the number of lengths will be  $\frac{1}{2}n(n-1)$ . There will therefore be  $\frac{1}{2}(n-2)(n-3)$  relations between the sides and diagonals of a polygon of  $n$  corners. In the same way there will be  $\frac{1}{2}(n-3)(n-4)$  relations between the edges of a polyhedron.

**153.** Let us next enquire how many statical equations we have. Let us suppose the system to be acted on by any given forces whose points of application are at some or all of the particles. These we may call the external forces.

Since each particle separately is in equilibrium, we may, by resolving the forces on each parallel to the axes, obtain  $2n$  or  $3n$  equations of equilibrium according as the system is in one plane or in space.

However numerous the reactions along the rods may be, we can always eliminate them from these equations and obtain either three or six equations, according as the system is in one plane or in space. To prove this, we notice that, taking all the particles together as one system, the internal reactions balance each other. Resolving then the external forces in some two directions in the plane of the system and taking moments about some point, we obtain\* three equations of equilibrium free from all internal reactions (Art. 112). And it is clear that no resolutions in other directions and no moments about other points will give more independent equations than three (Art. 115). In the same way, if the system is in space, it will be shown that we can obtain six equations free from internal reactions by resolving in some three directions and taking moments about some three axes. On the whole then we have either  $2n-3$  or  $3n-6$  equations to find the reactions. In a simply stiff framework we have just this number of independent reactions. Thus in a framework, simply stiff, without any unknown external reactions, we have a sufficient number of equations to find all the  $2n-3$  or  $3n-6$  reactions.


If the framework is subject to external constraints, for example if some points are fixed in space, the number of bars necessary to stiffen the system is altered. Whether stiff or not let there be  $2n-3-k$  or  $3n-6-k$  bars. It follows easily that the equations of statics will supply  $k+3$  or  $k+6$  equations (after elimination of the internal reactions) to find the external reactions and the position of equilibrium. If these are sufficient the problem is determinate.

**154.** Although the equations in statics may be sufficient in number to determine the internal reactions, yet exceptional cases may arise. The equations thus obtained may not be independent, or they may be contradictory.

\* If it is not clear that these three equations must follow from the  $2n$  or  $3n$  equations of equilibrium of the separate particles, we may amplify the proof as follows. If any particle  $A_1$  is acted on by a reaction  $R_{12}$  tending to  $A_2$ , then the particle  $A_2$  is acted on by an equal and opposite reaction  $R_{21}$  tending to  $A_1$ . The resolved parts of  $R_{12}$  and  $R_{21}$  parallel to  $x$  will therefore also be equal and opposite. If then we add together all the equations obtained from all the particles separately by the resolution parallel to  $x$ , the sum will yield an equation free from all the  $R$ 's. In the same way the resolution parallel to  $y$  or  $z$  will each yield another equation free from all the internal reactions.

Next since the forces on each particle balance, the sum of their moments about any straight line is zero. But by the same reasoning as before the moment of the reaction  $R_{12}$  which acts on  $A_1$  must be equal and opposite to that of the reaction  $R_{21}$  which acts on  $A_2$ . Hence if we add all the equations obtained from all the particles by taking moments, the sum will yield an equation free from all the  $R$ 's.

As an example consider the case of three rods,  $A_1A_3$ ,  $A_3A_2$ ,  $A_1A_2$  jointed at  $A_1$ ,  $A_3$ ,  $A_2$ , and let the lengths be such that all three are in one straight line. Let the extremities  $A_1$ ,  $A_2$  be acted on by two opposite forces each equal to  $F$ . Let  $R_{13}$ ,  $R_{23}$ ,  $R_{12}$  be the reactions along  $A_1A_2$ ,  $A_2A_3$ ,  $A_1A_3$  respectively. Here we have a simply stiff framework and we should therefore find sufficient equations to determine the reactions. The equations of equilibrium for the three corners are however



$$R_{13} + R_{12} = F, \quad R_{13} = R_{23}, \quad R_{12} + R_{23} = F,$$

which are evidently insufficient to determine the three reactions.

The conditions under which these exceptional cases can arise are determined algebraically by the theory of linear equations. The  $2n - 3$  or  $3n - 6$  equations to find the reactions at the corners of the framework are all linear. If a certain determinant is zero, one equation at least can be derived from the others or is contradictory to them. In the latter case some of the reactions are infinite; this of course is impossible in nature. In the former case one reaction is arbitrary, and all the others can be found in terms of it and the given external forces. In a similar manner we can find the condition that two reactions are arbitrary. These conditions can be expressed in a more definite way, but as this part of the theory follows more easily from the principle of virtual work, we shall postpone its consideration until we come to the chapter on that subject.

**155.** Let us next suppose that the system of  $n$  particles has more than the number of bars necessary to stiffen it. In this case there are not enough equations to find the reactions unless something is known about them besides what is given by the equations of statics. The rods connecting the particles are in nature elastic, and the forces acting along them are due to their extensions or compressions. Supposing the law connecting the force and the extension to be known, we have to examine whether the additional equations thus supplied are sufficient to find the reactions. The framework, being acted on by external forces, will yield, and this yielding will continue to increase until the reactions thus called into play are of sufficient magnitude to keep the frame at rest. For the sake of brevity we shall suppose that the amount of the yielding is very slight. In this case we shall assume, in accordance with Hooke's law, that the reaction along any rod is some known multiple of the ratio of the extension to the original length. This multiple depends on the nature of the material of which the rod is made.

Let the framework have  $m$  rods, where  $m$  exceeds  $2n - 3$  or  $3n - 6$  by  $k$ . Taking the case in which the framework is not acted on by any external reactions, we shall require  $k$  additional equations (Art. 153). By Art. 152 there are  $k$  relations between the lengths of these rods. Let any one of these be

$$f(l_1, l_2, \&c.) = 0 \dots\dots\dots (1),$$

where  $l_1$ ,  $l_2$  &c. are the lengths of the rods. Differentiating this we have

$$M_1 dl_1 + M_2 dl_2 + \&c. = 0 \dots\dots\dots (2),$$

where  $M_1$ ,  $M_2$  &c. are partial differential coefficients, and  $dl_1$ ,  $dl_2$  &c. are the extensions of the sides. If  $R_1$ ,  $R_2$  &c. are the reactions along the sides we may, by Hooke's law, write this equation in the form

$$M_1 \lambda_1 l_1 R_1 + M_2 \lambda_2 l_2 R_2 + \&c. = 0,$$

where  $\lambda_1$ ,  $\lambda_2$  &c. are the reciprocals of the known multiples.

*It appears therefore that each equation such as (1) supplies one relation between the reactions. Thus the requisite number of additional equations can be deduced from the theory of elasticity.*

In the case of the three rods mentioned in Art. 154 we notice that the relation corresponding to (1) is  $l_{13} + l_{23} - l_{12} = 0$ , where  $l_{12} = A_1 A_2$ , &c. It follows by differentiation that the three reactions are equal in magnitude if all three rods are made of the same material and are of equal sectional areas.

### *Astatics*

**156.** *Let a rigid body be acted on at given points  $A_1, A_2$  &c. by forces  $P_1, P_2$  &c. whose magnitudes and directions in space are given. Let this body be displaced in any manner: it is required to find how the resultant force and couple are altered.*

Choosing any base of reference  $O$  and any rectangular axes  $Ox, Oy$  fixed in the body, we may imagine the displacement made by two steps. First, we may give the body a linear displacement by moving  $O$  to its displaced position  $O_1$ , the body moving parallel to itself; secondly, we may give the body an angular displacement, by turning the body round  $O_1$  as a fixed point until the axis  $Ox$  comes into its displaced position. Then every point of the body will be brought into its proper displaced position, for otherwise the several points of the body would not be at invariable distances from the base  $O$  and the axis  $Ox$ .

Since the forces  $P_1, P_2$  &c. retain unaltered their magnitudes and directions in space, it is clear that the linear displacement does not in any way affect the resolved parts of the forces, or the moment about  $O$ . We may therefore disregard the linear displacement and treat  $O$  and  $O_1$  as coincident points.

Consider next the angular displacement. It is clear that we are only concerned with the relative positions of the body and forces, for a rotation of both together will only turn the resultant force and couple through the same angle. Instead of turning the body round  $O$  through any given angle  $\theta$  keeping the forces unaltered, we may turn each force round its point of application through an equal angle in the opposite direction, keeping the body unaltered. See Art. 70.

**157.** We are now in a position to find the changes in the resultant force and couple. Let  $Ox, Oy$  be any axes fixed in the body. Let  $P$  be any one of the forces  $P_1, P_2$  &c. and let  $A$  be its

point of application. Let  $\alpha$  be the angle its direction makes with the axis of  $x$ . Let this force be turned round  $A$  through an angle  $\theta$  in the positive direction, so that it now acts in the direction indicated in the figure by  $AP'$ .

Let  $X, Y, G$  be the resolved parts of the forces, and the moment about  $O$  before displacement;  $X', Y', G'$  the same after displacement. Then, as in Art. 106,


$$X' = \Sigma P \cos(\alpha + \theta) = X \cos \theta - Y \sin \theta,$$

$$Y' = \Sigma P \sin(\alpha + \theta) = X \sin \theta + Y \cos \theta,$$

$$G' = \Sigma P \{x \sin(\alpha + \theta) - y \cos(\alpha + \theta)\}$$

$$= G \cos \theta + V \sin \theta,$$

$$\text{where } G = \Sigma (xP_y - yP_x), \quad V = \Sigma (xP_x + yP_y).$$



The symbol  $G$  represents the moment of the forces *before displacement* about the centre  $O$  of rotation. If the angle of rotation round  $O$  is a right angle,  $\theta = \frac{1}{2}\pi$  and  $G' = V$ . Thus the symbol  $V$  represents the moment of the forces about  $O$  after they have been rotated through a right angle\*. If it is permitted to alter slightly a name given by Clausius (see *Phil. Mag.*, August 1870),  $V$  might be called the *Virial of the forces*. After a rotation through an angle  $\theta$  let  $V'$  be the new value of the virial, then

$$V' = \Sigma P \{x \cos(\alpha + \theta) + y \sin(\alpha + \theta)\}$$

$$= V \cos \theta - G \sin \theta.$$

Thus it appears that the moment  $G$  is also what the virial becomes (with the sign changed) when the forces have been rotated through a right angle.

We may find another meaning for the virial  $V$ . Let us suppose the components  $P_x, P_y$  to act at  $O$ , and let their point of application be moved to  $N$ , where  $ON = x$ . The work of  $P_x$  is  $xP_x$ , that of  $P_y$  is zero. Let the point of application be further moved from  $N$  to  $A$ , where  $NA = y$ . The additional work of  $P_x$  is zero, that of  $P_y$  is  $yP_y$ . The sum of these two for all the forces is  $V$ . Thus  $V$  is the work of moving the forces from the base of reference  $O$  to their respective points of application, the forces being supposed unaltered in direction or magnitude.

**158.** If the body is in equilibrium before displacement, we have  $X = 0, Y = 0, G = 0$ . Hence after a rotational displacement through an angle  $\theta$  we have  $X' = 0, Y' = 0, G' = V \sin \theta$ . We therefore infer that the only other position in which the body can be in equilibrium is when  $\theta = \pi$ , i.e. when the position of the body has been reversed in space. If the body is in equilibrium in any two positions which are not reversals of each other, the body must be in equilibrium in all positions. Lastly, the analytical condition that there should be equilibrium in all positions is that  $V = 0$  in some one position of equilibrium.

\* Darboux, *Sur l'équilibre statique*, p. 8.

159. Ex. 1. A body is placed in any position not in equilibrium, and the forces are such that the components  $X$ ,  $Y$  are both zero. Find the angle through which the body must be rotated that it may come into a position of equilibrium.

Ex. 2. If a body be in a position of equilibrium under the action of forces whose magnitudes and directions in space are given, show that the equilibrium is stable or unstable according as  $V$  is positive or negative in the position of equilibrium.

160. **Centre of the forces.** It has been shown in Art. 118, that, provided the components of the forces (viz.  $X$  and  $Y$ ) are not both zero, the whole system can be reduced to a single resultant at a finite distance from the base of reference. In any position of the forces, the equation to this single resultant is

$$G' - \xi Y' + \eta X' = 0,$$

i.e.  $(G - \xi Y + \eta X) \cos \theta + (V - \xi X - \eta Y) \sin \theta = 0.$

Thus it appears that, as the forces are turned round their points of application, this single resultant always passes through a fixed point in the body, whose coordinates are given by

$$G - \xi Y + \eta X = 0,$$

$$V - \xi X - \eta Y = 0.$$

This point is called the *centre of the forces*. The first of these equations represents the line of action of the single resultant when  $\theta = 0$ , the second represents its line of action after a rotation through a right angle, i.e. when  $\theta = \frac{1}{2}\pi$ .

As every force in this theory has a point of application fixed in the body, it will be found convenient to regard the central point as the point of application of the single resultant. Thus the single resultant, like the other forces, has a fixed magnitude, a fixed direction in space, and a fixed point of application in the body. The centre of the forces may be defined in words similar to those already used in Art. 82 for parallel forces. *If the points of application of the given forces are fixed in the body, the point of application of their resultant is also fixed in the body, however the body is displaced, provided the given forces retain their magnitudes and directions in space unaltered. This fixed point is called the centre of the forces.*

Taking any one relative position of the body and forces, and any rectangular axes, the coordinates  $(\xi\eta)$  of the centre of the forces are given by

$$\xi R^2 = VX + GY, \quad \eta R^2 = VY - GX,$$

where  $X$ ,  $Y$ ,  $V$ ,  $G$  are referred to the origin as base, and  $R$  is the resultant of  $X$  and  $Y$ .

**161.** Ex. 1. If the forces of a system are reducible to a single resultant couple, show that the centre of the forces is at infinity.

Ex. 2. Show that, as the forces are rotated, the value of  $G/V$  at any assumed base  $O$  is always equal to the tangent of the angle which the straight line joining  $O$  to the centre  $C$  of the forces makes with the direction of the resultant force  $R$ , while the value of  $G^2 + V^2$  is invariable and equal to  $R^2 \cdot CO^2$ .

Since the system is equivalent to a single force  $R$  acting at  $C$ , it is evident that  $G = R \cdot ON$ , where  $ON$  is a perpendicular on the line of action of  $R$ . Turning  $R$  through a right angle, we have  $V = R \cdot CN$ . The results follow at once.

**162.** There is another method\* of finding the astatic resultant of a given system which is sometimes useful. The body having been placed in any position relative to the forces which may be convenient, let two axes  $Ox$ ,  $Oy$  be chosen so that the resolved parts of the forces in these directions, viz.  $X$  and  $Y$ , are neither of them zero. Consider first the resolved parts of all the forces parallel to  $x$ . By the theory of parallel forces these are equivalent to a single force, viz.  $X = \Sigma P_x$ , which acts at a point fixed in the body whose coordinates are  $(x_1, y_1)$ , where

$$x_1 X = \Sigma x P_x, \quad y_1 X = \Sigma y P_x.$$

Consider next the resolved parts parallel to  $y$ . These also form a system of parallel forces and are equivalent to a single force  $Y = \Sigma P_y$ , which acts at a point fixed in the body whose coordinates are  $(x_2, y_2)$ , where

$$x_2 Y = \Sigma x P_y, \quad y_2 Y = \Sigma y P_y.$$

Since the axes of coordinates are arbitrary and need not be at right angles, the forces have thus been reduced to two forces acting at two points fixed in the body in directions arbitrarily chosen but not parallel. The positions of these points depend on the directions chosen.

**163.** Let the fixed points thus found be called  $A$  and  $B$ . In any one relative position of the body and forces, let the two forces  $X$  and  $Y$  intersect in  $I$ , and let their resultant act along  $IF$ . Let  $IF$  intersect the circle described about the triangle  $ABI$  in  $C$ . Then, by the astatic triangle of forces,  $C$  is a point fixed in the body, and the resultant of  $X$  and  $Y$  may be supposed to act at  $C$ . The point  $C$  is therefore the centre of the forces.

Conversely, when the resultant force and the centre of the forces are known, that force may be resolved into two astatic forces by using the triangle of forces in the manner already explained in Art. 73.

\* The method explained in this Article has been used by Darboux, *Sur l'équilibre astatique*, and by Larmor, *Messenger of Mathematics*.




## CHAPTER V

### FRICTION

**164.** WHEN one body slides or rolls on another under pressure, it is found by experience that a force tending to resist motion is called into play. In order to discover the laws which govern the action of this force we begin with experiments on some simple cases of equilibrium, and then endeavour by a generalization to extend these so as to include the most complicated cases.

Let us consider the case of a box  $A$  resting on a rough table  $BC$ . A string  $DEH$  attached to the box at  $D$  passes over a small pulley  $E$  and supports a scale-pan  $H$  in which weights can be placed.

By putting weights into the box  $A$  and varying the weight at  $H$ , all cases can be tried. Supposing the



box loaded, we go on increasing the weight at  $H$  by adding sand (which can be afterwards weighed) until the box just begins to move. The result is that the box, whatever load it carries, does not move until the weight at  $H$  is a certain multiple of the weight of the box and load. Of course the experiment must be conducted with much greater attention to details than is here described. For example the friction at the pulley  $E$  must be allowed for.

**165. Laws of friction.** The results of this experiment suggest the following laws.

1. *The direction of the friction is opposite to the direction in which the body is urged to move.*
2. *The magnitude of the friction is just sufficient to prevent*

*motion.* Thus there is no friction between the box and the table until a weight applied at  $H$  begins to act on the box, and then the amount of the friction is equal to that weight.

3. *No more than a certain amount of friction can be called into play*, and when more is required to keep the body at rest, motion will ensue. This amount of friction is called *limiting friction*.

4. *The magnitude of limiting friction bears a constant ratio  $\mu$  to the normal pressure* between the body and the plane on which it rests. This constant ratio  $\mu$  depends on the nature of the materials in contact. It is usually called the *coefficient of friction*.

We do not here assert that the friction actually called into play is in every case equal to  $\mu$  times the normal pressure, but only that this is the greatest amount which can be called into play. For smooth bodies  $\mu = 0$ . For a great many of the bodies we have to discuss  $\mu$  lies between zero and unity.

5. *The amount of friction is independent of the area* of that part of the body which presses on the rough plane, provided that the normal pressure is unaltered.


6. *When the body is in motion, the friction called into play is found to be independent of the velocity and proportional to the normal pressure.* The ratio is not exactly the same as that found for limiting friction when the body is at rest.

It is found that the friction which must be overcome to *set the box in motion* along the table is greater than the friction between the same bodies *when in motion* under the same pressure. If the box has remained on the table for some time under pressure the friction which must be overcome is greater than if the bodies were merely placed in contact and immediately set in motion under the same pressure by the proper weight in the pan  $H$ . In some bodies this distinction between statical and dynamical friction is found to be very slight, in others the difference is considerable. The coefficient of friction  $\mu$  for bodies in motion is therefore slightly less than for bodies at rest.

It should be noticed that friction is one of those forces which are usually called *resistances*. This follows from the second of the laws enunciated above. When a body is pressed against a wall, a reaction or resistance is called into play and is of just the

magnitude necessary to balance the pressing force. If there is no pressure there is no reaction. In the same way friction acts on to prevent sliding, not to produce it.

**166.** There is another method of determining the laws of friction by which the use of the pulley and string is avoided and which therefore presents some advantages. Imagine the box  $A$  placed symmetrically on an inclined plane  $BC$ . Let the inclination of  $BC$  to the horizon be  $\theta$ . If  $W$  be the weight of the box we easily find that the normal reaction is  $R = W \cos \theta$ , and the limiting friction  $F = W \sin \theta$ . Hence  $\frac{F}{R} = \tan \theta$ . Let us now suppose the inclination




of the plane to the horizon to be gradually increased until the box  $A$  begins to slide. The friction  $F$  is then the limiting friction. It is found by experiment that this inclination is the same, whatever the weight of the box may be. It follows that the ratio of the limiting friction to the normal pressure is independent of that pressure.

This experiment supplies us with an easy method of approximating to the value of  $\mu$  for any two materials. Place a body constructed of one of these materials on an inclined plane constructed of the other material. Supposing  $A$  to be at rest, increase the inclination  $\theta$  until  $A$  just begins to slide, then  $\mu$  is slightly less than the value of  $\tan \theta$  thus found. Next suppose the inclination of the plane to be such that the body  $A$  slides, we might decrease it until the box is just stationary, then  $\mu$  is slightly greater than the value of  $\tan \theta$  thus found. In this way we have found two nearly equal numerical quantities between which the coefficient of friction, viz.  $\mu$ , must lie. *The value of which makes  $\tan \theta = \mu$  is often called the angle of friction.*

Ex. Assuming that limiting friction consists of two parts, one proportional to the pressure and the other to the surface in contact, show that if the least force which can support a rectangular parallelepiped whose edges are  $a$ ,  $b$ , and  $c$  on a given inclined plane be  $P$ ,  $Q$ , and  $R$  when the faces  $bc$ ,  $ca$ , and  $ab$  respectively rest on the plane, then  $(Q - R)bc + (R - P)ca + (P - Q)ab = 0$ . [Trin. Coll., 1862]

**167. The friction couple.** When a wheel rolls on a rough plane the experiment must be conducted in a different manner

Let a cylinder be placed on a rough horizontal plane and let its weight be  $W$ . Let two weights  $P$  and  $P + p$  be suspended by a string passing over the cylinder and hanging down through a slit in the horizontal plane. Let the plane of the paper represent a section of the cylinder through the string, let  $C$  be the centre,  $A$  the point of contact with the plane. Imagine  $p$  to be at first zero and to be gradually increased until the cylinder just moves. By resolving vertically the reaction at  $A$  is seen to be equal to  $W + 2P + p$ . By resolving horizontally we see that there can be no horizontal force at  $A$ . Thus the friction force is zero. Taking moments about  $A$  we see that there must be a friction couple at  $A$  whose magnitude is equal to  $pr$ .



168. The explanation of this couple is as follows. The cylinder not being perfectly rigid yields slightly at  $A$  and is therefore in contact with the plane over a small area. When the cylinder begins to roll, the elements of area which are behind the direction of motion are on the point of separating and tend to adhere to each other, the elements in front tend to resist compression. The resultant action across both sets of elements may be replaced by a couple and a single force acting at some convenient point of reference. The yielding of the cylinder at  $A$  also slightly alters the position of the centre of gravity of the whole mass, but this change is very insignificant and is usually neglected. The cylinder is treated as if the section were a perfect circle touching the plane at a geometrical point  $A$ . The whole action is represented by a force acting at  $A$  and a couple. The resolved parts of the force along the normal and tangent at  $A$  are often called respectively the *reaction* and the *friction force*. In our experiment the latter is zero. The couple is called the *friction couple*.

The results of experiment show that the magnitude of  $p$  when the cylinder just moves is proportional to the normal pressure directly and the radius of the cylinder inversely. We therefore state as another law of friction that the *moment of the friction couple is independent of the curvature and proportional to the normal pressure*. The ratio of the couple to the normal pressure is often called the *coefficient of the friction couple*. The

magnitude of the friction couple is usually very small and its effects are only perceptible when the circumstances of the case make the friction force evanescent.

The weight  $p$  is commonly spoken of as the *friction of cohesion*, which is then said to vary inversely as the radius of the cylinder. But we have preferred the mode of statement given above.

169. It should be noticed that the laws of friction are only approximations. It is not true that the ratio of the limiting friction to the pressure is absolutely constant for all pressures and under all circumstances. The law is to be regarded as representing in a compendious way the results of a great many experiments and is to be trusted only for weights within the limits of the experiments. These limits are so extended that the truth of the law is generally assumed in mathematical calculations. If we followed the proper order of the argument, we should now enquire how nearly the laws of friction approximate to the truth, so that we may be prepared to make the proper allowance when the necessity arises. We ought also to tabulate the approximate values of  $\mu$  for various substances. But these discussions would occupy too much space and lead us too far away from the theory of the subject.

170. The experimenters on friction are so numerous that only a few names can be mentioned. The earliest is perhaps Amontons in 1699. He was followed by Muschanbroek and Nollet. But the most famous are Coulomb (*Savants étrangers Acad. des Sc. de Paris* x. 1785); Ximénès (*Teoria e pratica delle resistenze de' solidi ne' loro attriti*. Pisa 1782); Vince (*Phil. Trans.* vol. 75, 1785) and Morin (*Savants étrangers Acad. des Sc. de Paris* iv. 1833). Besides these there are the experiments of Southern, Rennie, Jenkin and Ewing, Osborne Reynolds &c.

171. One of the laws of friction requires that the direction of the friction should be opposite to the direction in which the body under consideration is urged to move. When, therefore, the body can begin to move in only one way, the direction of the friction is known and only its magnitude is required. But when the body can move in any one of several ways, if properly urged, both the direction and the magnitude of the friction are unknown. It follows that problems on friction may be roughly divided into two classes. (1) We have those in which the bodies rest on one or more points of support, at all of which the lines of action of the frictions are known, but not the magnitudes. (2) There are those in which both the direction and magnitude of the friction have to be discovered.

consider now the directions of the friction forces are to be as covered when the system is bordering on motion.

**172.** *A particle is placed on a rough curve in two dimensions under the action of any forces. To find the positions of equilibrium.*

Let  $X$ ,  $Y$  be the resolved forces in any position  $P$  of the particle. Let  $R$  be the reaction measured inwards of the curve on the particle,  $F$  the friction called into play measured in the direction of the arc  $s$ . Let  $\psi$  be the angle the tangent makes with the axis of  $x$ . The particle is supposed to be on the proper side of the curve, so that it is pressed against the curve by the action of the impressed forces. Taking the figure of the next article, we have, by resolving and taking moments,

$$\begin{aligned} X \cos \psi + Y \sin \psi + F &= 0, \\ -X \sin \psi + Y \cos \psi + R &= 0. \end{aligned}$$

Now if  $\mu$  be the coefficient of friction  $F$  must be numerically less than  $\mu R$ . The required positions of equilibrium are therefore those positions at which the expression

$$\frac{X \cos \psi + Y \sin \psi}{-X \sin \psi + Y \cos \psi}$$

is numerically less than  $\mu$ . This expression is a function of the position of the particle on the curve. Let us represent it by  $f(x)$ .


The positions of equilibrium in which the particle borders on motion are found by solving the equations  $f(x) = \pm \mu$ . Since this equation may have several roots, we thus obtain several extreme positions of equilibrium. We must then examine whether equilibrium holds or fails for the intermediate positions, i.e. whether  $f(x)$  is  $<$  or  $> \mu$  numerically.

We may sometimes determine this last point in the following manner. Suppose an extreme position, say  $x = x_1$ , to be determined by solving the equation  $f(x) = \mu$ . If equilibrium exist in the positions determined by values of  $x$  slightly less than  $x_1$ ,  $f(x)$  must be increasing as  $x$  increases through the value  $x = x_1$ . On the contrary if equilibrium fail for these values of  $x$ ,  $f(x)$  must be decreasing. Thus equilibrium fails or holds for values of  $x$  slightly greater than  $x_1$  according as  $f'(x)$  is positive or negative when  $x = x_1$ . Let us next suppose that an extreme position, say  $x = x_2$ , is determined by solving the equation  $f(x) = -\mu$ . If equilibrium exist in the positions determined by values of  $x$  slightly less than  $x_2$ ,  $f(x)$  must be algebraically decreasing as  $x$  increases through the value  $x = x_2$ , and therefore  $f'(x_2)$  is negative.

If therefore any extreme position of equilibrium is determined by the value

$x = x_1$  of the independent variable, equilibrium fails or holds for values of  $x$  slightly greater than  $x_1$  according as  $f'(x_1)$  has the same sign as  $\mu$  or the opposite. It is clear that this rule may also be used in the case of a rigid body whose position in space is determined by only one independent variable.

**173. Cone of friction.** There is another method of finding the position of equilibrium which is more convenient when we wish to use geometry. Let  $\epsilon$  be the angle of friction, so that  $\mu = \tan \epsilon$ . At any point  $P$  draw two straight lines each making an angle  $\epsilon$  with the normal at  $P$ , viz. one on each side. Let these be  $PA, PB$ . Then the resultant reaction at  $P$  (i.e. the resultant of  $R$  and  $F$ ) must act between the two straight lines  $PA, PB$ . These lines may be called the extreme or bounding lines of friction. If the forces on  $P$  were not restricted to two dimensions, we should describe a right cone whose vertex is at  $P$ , whose axis is the line of action of the reaction  $R$ , and whose semi-angle is  $\tan^{-1} \mu$ . This cone is called the cone of limiting friction or more briefly the *cone of friction*.



Since the resultant reaction at  $P$  is equal and opposite to the resultant of the impressed forces on the particle we have the following rule. *The particle is in equilibrium at all points at which the impressed force acts within the cone of friction.* In the extreme positions of equilibrium the resultant of the impressed forces acts along the surface of the cone.

**174.** *A particle is placed on a rough curve in three dimensions under the action of any forces. To find the positions of equilibrium.*

Let  $X, Y, Z$  be the resolved parts of the impressed forces. Let  $R$  be their resultant,  $T$  their resolved part along the tangent to the curve at the point where the particle is placed. Since  $T$  must be less than  $\mu$  times the normal pressure in any position of equilibrium we have  $T^2 < \mu^2 (R^2 - T^2)$ . If  $ds$  be an element of the arc of the curve, this may be put into the form

$$\left( X \frac{dx}{ds} + Y \frac{dy}{ds} + Z \frac{dz}{ds} \right)^2 < \frac{\mu^2}{1 + \mu^2} (X^2 + Y^2 + Z^2).$$

Here  $X, Y, Z$  and  $s$  are functions of the coordinates  $x, y, z$ . The particle will be in equilibrium at all the points of the curve at

which this inequality holds. If we change the inequality into an equality, we have an equation to find the limiting positions of equilibrium.

**175.** A particle rests on a rough surface under the action of any forces. To find the positions of equilibrium.

Let  $f(x, y, z) = 0$  be the surface, let  $Q$  be the normal component of the impressed forces at the point where the particle is placed. In equilibrium we must have  $R^2 - Q^2 < \mu^2 Q^2$ . We have therefore

$$\frac{(Xf_x + Yf_y + Zf_z)^2}{f_x^2 + f_y^2 + f_z^2} > \frac{X^2 + Y^2 + Z^2}{1 + \mu^2}.$$

Here  $X, Y, Z$  and  $f$  are functions of the coordinates. If we change the inequality into an equality, we have a surface which cuts the given surface  $f=0$  in a curve. This curve is the boundary of the positions of equilibrium of the particle.

**176.** Ex. 1. A heavy bead of weight  $W$  can slide on a rough circular wire fixed in space with its plane vertical. A centre of repulsive force is situated at one extremity of the horizontal diameter, and the force on the bead when at a distance  $r$  is  $pr$ . Find the limiting positions of equilibrium.

If  $2\theta$  be the angle the radius at the bead makes with the horizon, the tangential and normal forces are  $(W \cos 2\theta - pr \sin \theta)$  and  $(W \sin 2\theta + pr \cos \theta)$ . Putting the ratio of the first to the second equal to  $\pm \tan \epsilon$ , we find  $\sin(\gamma \mp \epsilon - 2\theta) = \pm \cos \gamma \sin \epsilon$ , where  $W = pa \tan \gamma$  and  $a$  is the radius. Discuss these positions.

Ex. 2. A heavy particle rests in equilibrium on a rough cycloid placed with its axis vertical and vertex downwards. Show that the height of the particle above the vertex is less than  $2a \sin^2 \epsilon$ , where  $a$  is the radius of the generating circle.

Ex. 3. A rigid framework in the form of a rhombus of side  $a$  and acute angle  $\alpha$  rests on a rough peg whose coefficient of friction is  $\mu$ . Prove that the distance between the two extreme positions which the point of contact of the peg with any side can have is  $a\mu \sin \alpha$ . See Art. 173. [St John's Coll., 1890.]

Ex. 4. Two uniform rods  $AB, BC$  are rigidly joined at right angles at  $B$  and project over the edge of a table with  $AB$  in contact. Find the greatest length of  $AB$  that can project; and prove that if the coefficient of friction be greater than  $\frac{AB(AB+2BC)}{BC^2}$  the system can hang with only the end  $A$  resting on the edge. [Math. Tripos, 1874.]

Ex. 5. Three rough particles of masses  $m_1, m_2, m_3$ , are rigidly connected by light smooth wires meeting in a point  $O$ , such that the particles are at the vertices of an equilateral triangle whose centre is  $O$ . The system is placed on an inclined plane of slope  $\alpha$ , to which it is attached by a pivot through  $O$ ; prove that it will rest in any position if the coefficient of friction for any one of the particles be not less than

$$\frac{\tan \alpha}{m_1 + m_2 + m_3} (m_1^2 + m_2^2 + m_3^2 - m_2 m_3 - m_3 m_1 - m_1 m_2)^{\frac{1}{2}}. \quad [\text{Math. Tripos, 1877.}]$$

Ex. 6. A particle rests on the surface  $xyz = c^3$  under the action of a constant



force parallel to the axis of  $z$ : prove that the curve of intersection of the surface with the cone  $\frac{1}{x^2} + \frac{1}{y^2} = \frac{\mu^2}{z^2}$  will separate the part of the surface on which equilibrium is possible from that on which it is impossible;  $\mu$  being the coefficient of friction.

[Math. Tripos, 1870.]

Ex. 7. The ellipsoid  $\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1$  is placed with the axis of  $x$  vertical, its surface being rough. Show that a heavy particle will rest on it anywhere above its intersection with the cylinder  $\frac{y^2}{b^2} \left(1 + \frac{a^2}{\mu^2 b^2}\right) + \frac{z^2}{c^2} \left(1 + \frac{a^2}{\mu^2 c^2}\right) = 1$ ,  $\mu$  being the coefficient of friction.

[Trin. Coll., 1885.]

177. The following problem is regarded from more than one aspect to illustrate some different methods of proceeding.

Ex. 1. A ladder is placed with one end on a rough horizontal floor and the other against a rough vertical wall, the vertical plane containing the ladder being perpendicular to the wall. Find the positions of equilibrium.

Let  $AB$  be the ladder,  $2l$  its length,  $w$  its weight acting at its middle point  $C$ . Let  $\theta$  be its inclination to the horizon. See the figure of Ex. 2.

Let  $R, R'$  be the reactions at  $A$  and  $B$  acting along  $AD, BD$  respectively;  $\mu, \mu'$  the coefficients of friction at these points. The frictions at  $A$  and  $B$  are  $\xi R$  and  $\eta R'$ , where  $\xi, \eta$  are two quantities which are numerically less than  $\mu$  and  $\mu'$  respectively. In many problems  $\xi, \eta$  may be either positive or negative. In this case however, since friction is merely a resistance and not an active force, we may assume that the frictions act along  $AL$  and  $LB$ . We may therefore regard  $\xi, \eta$  as positive. This limitation will also follow from the equations of equilibrium.

By resolving and taking moments we have

$$\begin{aligned}\xi R &= R' & \eta R' + R &= w \\ 2\eta R' l \cos \theta + 2R' l \sin \theta &= w l \cos \theta.\end{aligned}$$


Eliminating  $R, R'$  we find  $\tan \theta = \frac{1 - \xi \eta}{2\xi}$ . Any positive value of  $\tan \theta$  given by this equation, where  $\xi, \eta$  are less than  $\mu, \mu'$ , will indicate a possible position of equilibrium. If the roughness is so slight that  $\mu\mu' < 1$ , the minimum value of  $\tan \theta$  is given by  $\tan \theta = \frac{1 - \mu\mu'}{2\mu}$ . If the roughness is so great that  $\mu\mu' > 1$ , the ladder will rest in equilibrium at all inclinations.

Ex. 2. The ladder being placed at any given inclination  $\theta$  to the horizon, find what weight can be placed on a given rung that the ladder may be in equilibrium.

Let  $M$  be the rung,  $W$  the weight on it,  $AM = m$ . Let  $\mu = \tan \epsilon, \mu' = \tan \epsilon'$ .

Geometrical Solution. If we make the angles  $DAE = \epsilon, DBE = \epsilon'$ , the resultant reactions at  $A$  and  $B$  must lie within these angles and must meet in some point which lies within the quadrilateral  $EFDH$ .

Let  $G$  be the centre of gravity of the weights  $W$  and  $w$ . If the vertical line through  $G$  pass to the left of  $E$ , the weight  $(W + w)$  may be supposed to act at some point  $P$  within the quadrilateral above mentioned. This weight may then be resolved obliquely into the two directions  $PA, PB$ . These may be balanced by two reactions at  $A$  and  $B$  each lying within its limiting lines.



The result is that there will be equilibrium if the vertical through  $G$  passes to the left of  $E$ .

It is evident that this reasoning is of general application. We may use it to find the conditions of equilibrium of a body which can slide with a point on each of two given curves whenever the impressed forces which act on the body can be conveniently reduced to a single force. We draw the limiting lines of friction at the points of contact, and thus form a quadrilateral. *The condition of equilibrium is that the resultant impressed force shall pass through the quadrilateral area.*

The abscissæ of the points  $E$  and  $G$  measured horizontally from  $A$  to the right are easily proved to be respectively

$$x = \frac{2l(\mu\mu' \cos \theta + \mu \sin \theta)}{\mu\mu' + 1}, \quad \bar{x} = \frac{(Wm + wl) \cos \theta}{W + w}.$$

If  $C$  lie to the right of the vertical through  $E$ , (i.e.  $l \cos \theta > x$ ) there cannot be equilibrium unless the given rung lie to the left of that vertical ( $m \cos \theta < x$ ). Also the weight  $W$  placed on the rung must be *sufficiently great* to bring the centre of gravity  $G$  to the left of that vertical ( $\bar{x} < x$ ).

If  $C$  lie to the left of the vertical through  $E$ , ( $l \cos \theta < x$ ) there is equilibrium whatever  $W$  may be if the given rung is also on the left of that vertical ( $m \cos \theta < x$ ). But if the given rung is on the right of the vertical ( $m \cos \theta > x$ ), the weight  $W$  placed on it must be *sufficiently small* not to bring the centre of gravity to the right of that vertical.

Lastly, if the vertical through  $E$  lie to the right of  $B$ , ( $\tan^{-1} \mu > \frac{1}{2}\pi - \theta$ ) there is equilibrium whatever  $W$  may be, and on whatever rung it may be placed.

Another problem is solved on a similar principle in Jellett's treatise on friction, 1872.

*Analytical solution.* Following the same notation as in Ex. 1 we have by resolving and taking moments


$$\begin{aligned} \xi R &= R', & \eta R' + R &= W + w, \\ 2\eta R'l \cos \theta + 2R'l \sin \theta &= (Wm + wl) \cos \theta. \end{aligned}$$

Eliminating  $R, R'$ , we find

$$\frac{2l(\xi\eta \cos \theta + \xi \sin \theta)}{\xi\eta + 1} = \frac{(Wm + wl) \cos \theta}{W + w} \dots\dots\dots (A).$$

The condition of equilibrium is that it is possible to satisfy this equation with values of  $\xi, \eta$  which are less than  $\mu, \mu'$  respectively. By seeking the maximum value of the left-hand side we may derive from this the geometrical condition that the centre of gravity of  $W$  and  $w$  must lie to the left of a certain vertical straight line. But our object is to discuss the equation otherwise.

Let us regard  $\xi, \eta$  as the coordinates of some point  $Q$  referred to any rectangular axes. Then (A) is the equation to a hyperbola, one branch of which is represented in the figure by the dotted line. If this hyperbola pass within the rectangle  $NN'$  formed by  $\xi = \pm\mu, \eta = \pm\mu'$ , the conditions of equilibrium can be satisfied by values of  $\xi, \eta$  less than their limiting values. If the curve does not cut the rectangle, there cannot be equilibrium without the assistance of more than the available friction. The right-hand side of (A) is the quantity already



called  $\bar{x}$ . Let it be transferred to the left-hand side and let the equation thus altered be written  $z=0$ . We notice that  $z$  is negative at the origin. In order that the hyperbola may cut the rectangle it is sufficient and necessary that  $z$  should be positive at the point  $N$ , i.e. when  $\xi=\mu$ ,  $\eta=\mu'$ . The required condition of equilibrium is therefore that  $\frac{2l(\mu\mu'\cos\theta + \mu\sin\theta)}{\mu\mu'+1} - \bar{x}$  should be a positive quantity.

This is virtually the same result as before and may be similarly interpreted.

Ex. 3. Let the ladder  $AB$  be placed in a given position leaning against the rough vertical face of a large box which stands on the same floor, as shown in the figure of Ex. 2. Determine the conditions of equilibrium.

We have now to take account of the equilibrium of the box  $BLL'$ . Let  $W'$  be its weight. Let  $R''$  be the reaction between it and the floor,  $\zeta R''$  the friction. We have then, in addition to the equations of Ex. 1,

$$R'' = W' + \eta R', \quad \zeta R'' = R'.$$

Eliminating  $R''$  we find  $(W' + w) \xi \eta \zeta + W' \zeta - w \xi = 0$ .

We have also by Ex. 1,  $\xi \eta + 2\xi \tan \theta - 1 = 0 \dots \dots \dots (A).$


Eliminating  $\eta$ , so as to express both  $\eta$  and  $\zeta$  in terms of one variable  $\xi$ , we find

$$2(W' + w) \tan \theta \xi \zeta + w \xi - (2W' + w) \zeta = 0 \dots \dots \dots (B).$$

The conditions of equilibrium are that the two equations A and B can be simultaneously satisfied by values of  $\xi$ ,  $\eta$ ,  $\zeta$  less than  $\mu$ ,  $\mu'$ ,  $\mu''$  respectively.

Regarding  $\xi$ ,  $\eta$ ,  $\zeta$  as the coordinates of a representative point  $Q$ , these equations represent two cylinders. These cylinders intersect in a curve. If any part of this curve lie within the rectangular solid bounded by  $\xi = \pm \mu$ ,  $\eta = \pm \mu'$ ,  $\zeta = \pm \mu''$  the conditions of equilibrium are satisfied.

But instead of using solid geometry we may represent (A) and (B) by two hyperbolas having different ordinates  $\eta$ ,  $\zeta$  but the same abscissa  $\xi$ . The frictions being resistances, we shall assume that they act so that  $\xi$ ,  $\eta$ ,  $\zeta$  are all positive. It will therefore be necessary only to draw that portion of the figure which lies in the positive quadrant. Take  $OM = \mu$ ,  $OM' = \mu'$ ,  $OM'' = \mu''$ . Let  $OB$  and  $AH$  represent the hyperbolas (B) and (A). Then we easily find



$$M'A = \frac{1}{\mu' + 2 \tan \theta}, \quad M''B = \frac{(2W' + w) \mu''}{2(W' + w) \mu'' \tan \theta + w}.$$

The condition of equilibrium is that an ordinate can be found intersecting the two hyperbolas in points  $Q$ ,  $Q'$  each of which lies within the limiting rectangles. The necessary conditions are therefore found by making an ordinate travel across the figure from  $OM'$  to  $N'N''$ . They may be summed up as follows.

(1) The hyperbola  $AH$  must intersect the area of the rectangle  $ON'$ ; the condition for this is that  $M'A < \mu$ .

(2) If the hyperbola  $OB$  intersect  $M''N''$  on the left-hand side of  $N''$ , i.e. if  $M''B < \mu$ , then  $M'A$  must be  $< M''B$ , for otherwise the ordinate  $QQ'$  would not cut both curves within the prescribed area. But this condition is included in (1) if  $M''B > \mu$ .

If the ladder is so placed that the inequality (2) becomes an equality while (1) is not broken, the frictions  $\eta$  and  $\zeta$  attain their limiting values while  $\xi$  is

not limiting, the ladder will therefore be on the point of slipping at its upper extremity, and the box will be just slipping along the plane.

If the ladder is so placed that the inequality (1) becomes an equality while (2) is not broken,  $\xi$  and  $\eta$  have their limiting values while  $\zeta$  is less than its limit. The box is therefore fixed and the ladder slips at both ends.

✓ **178. Ex. 1.** A ladder  $AB$  rests against a smooth wall at  $B$  and on a rough horizontal plane at  $A$ . A man whose weight is  $n$  times that of the ladder climbs up it. Prove that the frictions at  $A$  in the two extreme cases in which the man is at the two ends of the ladder are in the ratio of  $2n+1$  to 1.

✓ **Ex. 2.** A boy of weight  $w$  stands on a sheet of ice and pushes with his hands against the smooth vertical side of a heavy chair of weight  $nw$ . Show that he can incline his body to the horizon at any angle greater than  $\cot^{-1} 2\mu$  or  $\cot^{-1} 2\mu n$ , according as the chair or the boy is the heavier, the coefficient of friction between the ice and boy or the ice and chair being  $\mu$ . [Queens' Coll.]

**Ex. 3.** Two hemispheres, of radii  $a$  and  $b$ , have their bases fixed to a horizontal plane, and a plank rests symmetrically upon them. If  $\mu$  be the coefficient of friction between the plank and either hemisphere, the other being smooth, prove that, when the plank is on the point of slipping, the distance of its centre from its point of contact with the smooth hemisphere is equal to  $(a \sim b)/\mu$ . [St John's Coll., 1885.]

**Ex. 4.** A heavy rod rests with one end on a horizontal plane and the other against a vertical wall. To a point in the rod one end of a string is tied, the other end being fastened to a point in the line of intersection of the plane and wall. The string and rod are in a vertical plane perpendicular to the wall. Show that, if the rod make with the horizon an angle  $\alpha$  which is less than the complement of  $2\epsilon$ , then equilibrium is impossible unless the string make with the horizon an acute angle less than  $\alpha + \epsilon$ , where  $\epsilon$  is the angle of friction both with the wall and the plane. [Math. Tripos, 1890.]

**Ex. 5.** A parabolic lamina whose centre of gravity is at its focus rests in a vertical plane upon two rough rods of the same material at right angles and in the same vertical plane; if  $\phi$  be the inclination of the directrix to the horizon in one extreme position of equilibrium, prove that  $\tan^2(a - \phi) \tan(a + \epsilon - \phi) = \tan(a - \epsilon)$ ; where  $\epsilon$  is the angle of friction,  $a$  the inclination of one rod to the horizon.

[Trin. Coll., 1882.]

**Ex. 6.** Two rods  $AC, BC$  with a smooth hinge at  $C$  are placed in a given position with their extremities  $A$  and  $B$  resting on a rough horizontal plane. The plane of the rods being vertical, find the conditions of equilibrium.

Let  $\theta, \theta'$  be the inclinations of the rods to the horizon,  $W$  and  $W'$  their weights. Let  $(R, \xi R), (R', \eta R')$  be the reactions and frictions at  $A$  and  $B$ . Resolving and taking moments in the usual way, we find

$$\xi = \frac{W + W'}{W \tan \theta' + (2W + W') \tan \theta}, \quad \eta = \frac{W' + W}{W' \tan \theta + (2W' + W) \tan \theta'}.$$

If the value of  $\xi$  thus found is  $> \mu$  the system will slip at  $A$ ; if  $\eta > \mu$  it will slip at  $B$ . If the system slip at  $A$  only, then  $\xi > \eta$ ; this gives  $W \tan \theta < W' \tan \theta'$ .

**Ex. 7.** A groove is cut in the surface of a flat piece of board. Show that the form of the groove may be so chosen as to satisfy this condition, that if the board will just hang in equilibrium upon a rough peg placed at any one point of the groove, it will also just hang in equilibrium when the peg is placed at any other point. [Math. Tripos, 1859.]

Ex. 8. A lamina is suspended by three strings from a point  $O$ ; if the lamina be rough, and the coefficient of friction between it and a particle  $P$  placed upon it be constant, show that the boundary of possible positions of equilibrium of the particle on the lamina is a circle. [Math. Tripos, 1880.]

Let  $ON$  be a perpendicular on the lamina. Let  $D$  be the centre of gravity of the lamina,  $G$  that of the lamina and particle. Then in equilibrium  $OG$  is vertical and  $NG$  is the line of greatest slope. The angle  $NOG$  is equal to the inclination of the plane to the horizon and is constant because the equilibrium is limiting. The locus of  $G$  is a circle, centre  $N$ . Since  $DP : DG$  is constant the locus of  $P$  is also a circle.

Ex. 9. Spheres whose weights are  $W, W'$  rest on different and differently inclined planes. The highest points of the spheres are connected by a horizontal string perpendicular to the common horizontal edge of the two planes and above it. If  $\mu, \mu'$  be the coefficients of friction and be such that each sphere is on the point of slipping down, then  $\mu W = \mu' W'$ . [Math. Tripos.]

Consider one sphere: the resultant of  $T$  and  $\mu R$  balances that of  $W$  and  $R$ . By taking moments about the centre  $T = \mu R$ . Hence, by drawing a figure,  $R = W$ . Thus  $T = \mu W$  and the result follows.

Ex. 10. A uniform rod passes over one peg and under another, the coefficient of friction between each peg and the rod being  $\mu$ . The distance between the pegs is  $b$ , and the straight line joining them makes an angle  $\beta$  with the horizon. Show that equilibrium is not possible unless the length of the rod is  $> b \{1 + (\tan \beta)/\mu\}$ .

[Coll. Ex.]

✓ Ex. 11. A uniform rod  $ACB$ , length  $2a$ , is supported against a rough wall by a string attached to its middle point  $C$ : show that the rod can rest with  $C$  at any point of a circular arc, whose extremities are distant  $a$  and  $a \cos \epsilon$  from the wall, where  $\epsilon$  is the angle of friction. [Take moments about  $C$ .]

Ex. 12. Two uniform and equal rods of length  $2a$  have their extremities rigidly connected, and are inclined to each other at an angle  $2\alpha$ . These rods rest on a fixed rough cylinder with its axis horizontal, and whose radius is  $a \tan \alpha$ . Show that in the limiting position of equilibrium the inclination  $\theta$  to the vertical of the line through the point of intersection of the rods perpendicular to the axis of the cylinder is given by  $\sin^2 \alpha \sin \theta = \cos(\theta - \epsilon) \sin \epsilon$ , where  $\tan \epsilon$  is the coefficient of friction. [Coll. Ex.]

Ex. 13. Three equal uniform heavy rods  $AB, BC, CD$ , hinged at  $B$  and  $C$ , are suspended by a light string attached to  $D$  from a point  $E$ , and hang so that the end  $A$  is on the point of motion, towards the vertical through  $E$ , along a rough horizontal plane (coefficient of friction  $\mu = \tan \epsilon$ ): show that

$$\frac{\cos(\alpha - \epsilon)}{\cos \alpha} = \frac{\cos(\beta - \epsilon)}{3 \cos \beta} = \frac{\cos(\gamma - \epsilon)}{5 \cos \gamma} = \frac{\mu \cos(\theta - \epsilon)}{6 \cos \theta},$$

where  $\alpha, \beta, \gamma$  are the inclinations of the rods to the horizon beginning with the lowest, and  $\theta$  that of the string. [Coll. Ex., 1881.]

Take moments about  $B, C, D, E$  in succession for the rods  $AB, AB$  and  $BC$ , and so on. Subtracting each equation from the next in order, the results follow at once.

Ex. 14. A sphere rests on a rough horizontal plane, and its highest point is

joined to a peg fixed in the plane by a tight cord parallel to the plane. Show that, if the plane be gradually tilted about a line in it perpendicular to the direction of the cord, the sphere will not slip until the inclination becomes equal to  $\tan^{-1} 2\mu$ , where  $\mu$  is the coefficient of friction. [Math. Tripos, 1886.]

Ex. 15. A uniform hemisphere, placed with its base resting on a rough inclined plane, is just on the point of sliding down. A light string, attached to the point of the hemisphere farthest from the plane, is then pulled in a direction parallel to and directly up the plane. If the tension of the string be gradually increased until the sphere begins to move, it will slide or tilt according as  $13 \tan \phi$  is less or greater than 8, where  $\phi$  is the inclination of the plane to the horizon. The centre of gravity of the hemisphere is at a distance from the centre equal to three-eighths of the radius. [Coll. Ex., 1888.]

Ex. 16. A circular disc, of radius  $a$ , whose centre of gravity is distant  $c$  from its centre, is placed on two rough pegs in a horizontal line distant  $2a \sin \alpha$  apart. Show that all positions will be possible positions of equilibrium, provided

$$a \sin \alpha \sin (\lambda_1 + \lambda_2) > c \sin (2\alpha \mp \lambda_1 \pm \lambda_2),$$

where  $\lambda_1, \lambda_2$  are the angles of friction at the two pegs. [St John's Coll., 1880.]

Ex. 17. A number of equally rough particles are knotted at intervals on a string, one end of which is fixed to a point on an inclined plane. Show that, all the portions of the string being tight, the lowest particle is in its highest possible position, when they are all in a straight line making an angle  $\sin^{-1} (\tan \lambda / \tan \alpha)$  with the line of greatest slope,  $\lambda$  being the angle of friction and  $\alpha$  the inclination of the plane to the horizon. Show also that, if any portion of the string make this angle with the line of greatest slope, all the portions below it must do so too.

[Math. Tripos, 1886.]

Ex. 18. A rough paraboloid of revolution, of latus rectum  $4a$ , and of coefficient of friction  $\cot \beta$ , revolves with uniform angular velocity about its axis which is vertical: prove that for any given angular velocity greater than  $(g/2a)^{\frac{1}{2}} \cot \frac{1}{2}\beta$  or less than  $(g/2a)^{\frac{1}{2}} \tan \frac{1}{2}\beta$  a particle can rest anywhere on the surface except within a certain belt, but that for any intermediate angular velocity equilibrium is possible at every point of the surface. [Math. Tripos, 1871.]

Let  $mg$  be the weight of the particle. It is known by dynamics that we may treat the paraboloid as if it were fixed in space, provided we regard the particle as acted on by a force  $m\omega^2 r$  tending directly from the axis, where  $r$  is the distance of the particle from the axis, and  $\omega$  the angular velocity of the paraboloid.

We may prove that the ordinates in the limiting positions of equilibrium are given by  $\mu\omega^2 y^2 - (2a\omega^2 - g)y + 2a\mu g = 0$ . That a belt may exist, the roots of this quadratic must be real.

Ex. 19. A rod rests partly within and partly without a box in the shape of a rectangular parallelepiped, presses with one end against the rough vertical side of the box, and rests in contact with the opposite smooth edge. The weight of the box being four times that of the rod, show that, if the rod be about to slip and the box about to tumble at the same instant, the angle the rod makes with the vertical is  $\frac{1}{2}\lambda + \frac{1}{2} \cos^{-1} (\frac{1}{3} \cos \lambda)$ , where  $\lambda$  is the angle of friction. [Math. Tripos, 1880.]

Ex. 20. A glass rod is balanced partly in and partly out of a cylindrical tumbler with the lower end resting against the vertical side of the tumbler. If  $\alpha$  and  $\beta$  are

the greatest and least angles which the rod can make with the vertical, prove that the angle of friction is  $\frac{1}{2} \tan^{-1} \frac{\sin^2 \alpha - \sin^2 \beta}{\sin^2 \alpha \cos \alpha + \sin^2 \beta \cos \beta}$ . [Math. Tripos, 1875.]

Ex. 21. A heavy rod, of length  $2l$ , rests horizontally on the inside rough surface of a hollow circular cone, the axis of which is vertical and the vertex downwards. If  $2\alpha$  is the vertical angle of the cone, and if the coefficient of friction  $\mu$  is less than  $\cot \alpha$ , prove that the greatest height of the rod, when in equilibrium, above the vertex of the cone is  $l \cot \alpha \left\{ \frac{1 + \cos^2 \alpha + \sin \alpha \sqrt{(\sin^2 \alpha + 4\mu^2)}}{2(1 - \mu^2 \tan^2 \alpha)} \right\}^{\frac{1}{2}}$ . [Math. Tripos, 1885.]

Ex. 22. A heavy uniform rod  $AB$  is placed inside a rough curve in the form of a parabola whose focus is  $S$  and axis vertical. Prove that, when it is on the point of slipping downwards, the angle of friction is  $\frac{1}{2}(SAB - SBA)$ . [Coll. Ex., 1889.]

Ex. 23. A rod  $MN$  rests with its ends in two fixed straight rough grooves  $OA$ ,  $OB$ , in the same vertical plane, which makes angles  $\alpha$  and  $\beta$  with the horizon: prove that, when the end  $M$  is on the point of slipping down  $AO$ , the tangent of the inclination of  $MN$  to the horizon is  $\frac{\sin(\alpha - \beta - 2\epsilon)}{2 \sin(\beta + \epsilon) \sin(\alpha - \epsilon)}$ . [Math. Tripos, 1876.]

Ex. 24. A uniform rectangular board  $ABCD$  rests with the corner  $A$  against a rough vertical wall and its side  $BC$  on a smooth peg, the plane of the board being vertical and perpendicular to that of the wall. Show that, without disturbing the equilibrium, the peg may be moved through a space  $\mu \cos \alpha (a \cos \alpha + b \sin \alpha)$  along the side with which it is in contact, provided the coefficient of friction ( $\mu$ ) lie between certain limits;  $\alpha$  being the angle  $BC$  makes with the wall, and  $a$ ,  $b$  the lengths of  $AB$ ,  $BC$  respectively. Also find the limits of  $\mu$ . [Math. T., 1880.]

Ex. 25. An elliptical cylinder, placed in contact with a vertical wall and a horizontal plane, is just on the point of motion when its major axis is inclined at an angle  $\alpha$  to the horizon. Determine the relation between the coefficients of friction of the wall and plane; and show from your result that, if the wall be smooth, and  $\alpha$  be equal to  $45^\circ$ , the coefficient of friction between the plane and cylinder will be equal to  $\frac{1}{2}e^2$ , where  $e$  is the eccentricity of the transverse section of the cylinder. [Math. Tripos, 1883.]

Ex. 26. A rough elliptic cylinder rests, with its axis horizontal, upon the ground and against a vertical wall, the ground and the wall being equally rough; show that the cylinder will be on the point of slipping when its major axis plane is inclined at an angle of  $\pi/4$  to the vertical if the square of the eccentricity of its principal section be  $2 \sin \epsilon (\sin \epsilon + \cos \epsilon)$ , where  $\epsilon$  is the angle of friction. [Coll. Ex., 1885.]

Ex. 27. Three uniform rods of lengths  $a$ ,  $b$ ,  $c$  are rigidly connected to form a triangle  $ABC$ , which is hung over a rough peg so that the side  $BC$  may rest in contact with it; find the length of the portion of the rod over which the peg may range, showing that, if  $\mu > \frac{a(a+b+c)}{b(b+c)} \operatorname{cosec} C + \tan \frac{1}{2}(C-B)$ , where  $C > B$ , the triangle will rest in any position. [Math. Tripos, 1887.]

Ex. 28. A waggon, with four equal wheels on smooth axles whose plane contains the centre of gravity, rests on the rough surface of a fixed horizontal circular cylinder, the axles being parallel to the axis of the cylinder; investigate the pressures on the wheels, and prove that the inclination to the horizontal of the plane containing the axles is  $\tan^{-1} \{ \tan \alpha (w - w')/W \}$ , where  $w$ ,  $w'$  are the weights

on the two axles,  $W$  that of the whole waggon, and  $2\alpha$  is the angle between the tangent planes at the points of contact. [Math. Tripos, 1888.]

Ex. 29. Three circular cylinders  $A, B, C$ , alike in all respects, are placed with their axes horizontal and their centres of gravity in a vertical plane;  $A$  is fixed,  $B$  is at the same level, and  $C$  at a lower level touches them both, the common tangent planes being inclined at  $45^\circ$  to the vertical.  $B$  and  $C$  are supported by a perfectly rough endless strap of suitable length passing round the cylinders in the plane containing the centres of gravity. Show that equilibrium can be secured by making the strap tight enough, provided that the coefficient of friction between the cylinders is greater than  $1 - 1/\sqrt{2}$ ; and find how slipping will first occur if the strap is not quite tight enough. [Math. Tripos, 1888.]

Ex. 30. Two uniform rods  $AB, BC$ , of equal length, are jointed at  $B$ . They are at rest in a vertical plane, equally inclined to the horizon, with their lower ends in contact with a rough horizontal plane. Prove that, if they be on the point of slipping both at  $A$  and  $C$ , the frictional couple at the joint is  $W\alpha (\sin \alpha - 2\mu \cos \alpha)$ , where  $W$  is the weight of each rod,  $\alpha$  the inclination of each rod to the horizon,  $2a$  the length of each rod, and  $\mu$  the coefficient of friction. [St John's Coll., 1890.]

Ex. 31. Six uniform rods, each of length  $2a$ , are joined end to end by five smooth hinges, and they stand on a rough horizontal plane in equilibrium in the form of a symmetrical arch, three on each side; prove that the span cannot be greater than  $2a\sqrt{2}(1 + \sqrt{\frac{1}{6}} + \sqrt{\frac{1}{12}})$ , if the coefficient of friction of the rods and plane be  $\frac{1}{6}$ . [Coll. Ex., 1886.]

Consider only half the arch. The reaction at the highest point is horizontal, and equal to half the weight of one rod. Take moments (1) for the upper, (2) for the two upper, (3) for all three rods. We find that their inclinations to the vertical are  $\frac{1}{2}\pi, \tan^{-1}\frac{1}{3}, \tan^{-1}\frac{1}{6}$ . The result follows easily.

**179. Friction between wheel and axle.** Ex. 1. *A gig is so constructed that when the shafts are horizontal the centre of gravity of the gig and the shafts is over the axle of the wheels. The gig in this position rests on a perfectly rough ground. Find the direction and magnitude of the least force which, acting at the extremity of the shaft, will just move the gig.*


When an axle is made to fit the nave of a wheel, the relative sizes of the axle and hole are so arranged that the wheel can turn easily round the axle. The axle is therefore just a little smaller than the hole. Thus the two cylinders touch along some generating line and the pressures act at points in this line. Even if the axle were somewhat tightly clasped at first, yet by continued use it would be worn away so that it would become a little smaller than the hole.

It is possible that the axle may be so large that it has to be forced into the hole. When this is the case, besides the pressures produced by the weight of the gig, there will be pressures due to the compression of the axle. These last will act on every element of the surface of the axle and their magnitudes will depend on how much the axle has to be compressed to get it into the hole. If the axle and hole are not perfectly circular, these pressures may be unequally distributed over the surface of the axle. When these circumstances of the problem are not given, the pressures on the axle are indeterminate.

Let  $X, Y$  be the required horizontal and vertical components of the force applied at the extremity  $S$  of the shaft.



Consider the equilibrium of the wheel. Since it touches a perfectly rough ground at  $A$ , the friction at this point cannot be limiting. Let  $R$  and  $F$  be the reaction and friction. It is evident that the friction  $F$  must act to the left, if it is to balance the force  $X$  which is taken as acting to the right.



The axle will touch the circular hole in which it works at some one point  $B$ . At this point there will be a reaction  $R'$  and a friction  $F'$ , which is limiting when the gig is on the point of motion. Thus  $F' = \mu R'$ . The resultant of  $R'$  and  $\mu R'$  must balance the resultant of  $R$  and  $F$  and the weight of the wheel. It therefore follows that the point  $B$  is on the left of  $C$ , i.e. behind the axle. Let  $\theta$  be the angle  $ACB$ , let  $a$  and  $b$  be the radii of the wheel and axle. Taking moments about  $A$  we have

$$R'a \sin \theta = \mu R' (a \cos \theta - b).$$

Putting  $\mu = \tan \epsilon$ , this gives  $\sin (\epsilon - \theta) = \frac{b}{a} \sin \epsilon$ .

Since  $b$  is less than  $a$ , we see that  $\theta$  is positive and less than  $\epsilon$ .

Consider next the equilibrium of the gig. The forces  $R'$  and  $\mu R'$  act on the gig in directions opposite to those indicated in the figure. Let  $W$  be the weight of the gig, then resolving and taking moments about  $C$  we have

$$X = -R' \sin \theta + \mu R' \cos \theta,$$

$$Y = -R' \cos \theta - \mu R' \sin \theta + W,$$

$$Yl = \mu R' b,$$

where  $l$  is the length of the shaft. These equations give  $X$  and  $Y$ .


Ex. 2. A light string, supporting two weights  $W$  and  $W'$ , is placed over a wheel which can turn round a fixed rough axle. Supposing the string not to slip on the wheel, find the condition that the wheel may be on the point of turning round the axle. If  $a$ ,  $b$  be the radii of the wheel and axle, and  $\mu = \tan \epsilon$ , prove that

$$(W - W') a = (W + W') b \sin \epsilon.$$

Ex. 3. A solid body, pierced with a cylindrical cavity, is free to turn about a fixed axle which just fits the cavity, and the whole figure is symmetrical about a certain plane perpendicular to the axle. The axle being rough, and the body acted on by forces in the plane of symmetry, find the least coefficient of friction that the body may be in equilibrium.

The circular sections of the cavity and axle are drawn in the figure as if they were of different sizes. This has been done to show that the reaction and friction act at a definite point, but in the geometrical part of the investigation they should be regarded as equal.

Let the plane of symmetry be taken as the plane of  $xy$ , and let its intersection  $O$  with the axis be the origin. Let  $X, Y, G$  be the components of the forces, and let these urge the body to turn round the axis in a direction opposite to that of the hands of a watch.



The axle will touch the cavity along a generating line, let  $B$  be its point of intersection with the plane of  $xy$ . Let  $\theta$  be the angle  $BOx$ . Let  $R$  and  $F$  be the normal reaction and the friction at  $B$ ; when the body borders on motion we have  $F = \mu R$ .

By resolving and taking moments we find

$$R(\cos \theta + \mu \sin \theta) + X = 0,$$

$$R(\sin \theta - \mu \cos \theta) + Y = 0,$$

$$-\mu R a + G = 0,$$

where  $a$  is the radius of the cavity. Putting  $\mu = \tan \epsilon$ , we deduce from these equations


$$\tan(\theta - \epsilon) = Y/X, \quad R^2 = (X^2 + Y^2) \cos^2 \epsilon.$$

These determine the point  $B$  and the reaction  $R$ . The least value of the coefficient of friction is then given by

$$(X^2 + Y^2) a^2 \sin^2 \epsilon = G^2.$$

**180. Lemma.** *If a lamina be moved from any one position to any other in its own plane, there is one point rigidly connected to the lamina whose position in space is unchanged. The lamina may therefore be brought from its first to its last position by fixing this point and rotating the lamina about it through the proper angle.*

Let  $A, B$  be any two points in the lamina in its first position,  $A', B'$  their positions in the last position. Then if  $A, B$  can be brought into the positions  $A', B'$  by rotation about some point  $I$ , fixed in space, the whole lamina will be brought from its first to its last position. Bisect  $AA', BB'$  at right angles by the straight lines  $LI, MI$ . Then  $IA = IA'$ , and  $IB = IB'$ . Also, since  $AB$  is unaltered in length by its motion, the sides of the triangles  $AIB, A'IB'$  are equal, each to each. It follows that the angles  $AIB, A'IB'$  are equal, and therefore that the angles  $AIA'$  and  $BIB'$  are equal. If then we turn the lamina round  $I$ , as a point fixed in space, through an angle equal to  $AIA'$ ,  $A$  will take the position  $A'$ , and  $B$  will take the position  $B'$ . Thus the whole body has been transferred from the one position to the other.



If the body be simply translated, so that every point moves parallel to a given straight line, the bisecting lines  $LI, MI$  are parallel, and therefore the point  $I$  is infinitely distant.

If the angle  $AIA'$  is indefinitely small, the fixed point  $I$  of the lamina is called the *instantaneous centre of rotation*.

**181. Frictions in unknown directions.** We are now prepared to make a step towards the generalization of the laws of friction. Let us suppose a heavy body to rest on a rough horizontal table on  $n$  supports. Let these points be  $A_1, A_2, \dots, A_n$ , and let the pressures at these points be  $P_1, P_2, \dots, P_n$ . We shall also suppose the body to be acted on by a couple and a force applied at some convenient base of reference, the forces being all parallel to the table. To resist these forces a frictional force is called into play at each point of support. The directions and magnitudes of these frictional forces are unknown, except that the magnitude of each is less than the limiting friction, and the direction is opposed to the resultant of all the external and molecular forces which act on that point of support. If the pressures  $P_1, \dots, P_n$  are known, there are thus  $2n$  unknown quantities, and there are only three equations of equilibrium. The frictions at the points of support are therefore generally indeterminate.

By calling the frictions indeterminate we mean that there are different ways of arranging forces at the points of support which could balance the given forces and which *might* be frictional forces. Which of these is the true arrangement of the frictional forces depends on the manner in which the body, regarded as partially elastic, begins to yield to the forces. Suppose, for example, a force  $Q$  to act at a point  $B$  of the body, and to be gradually increased in magnitude. The frictions on the points of support nearest to  $B$  will at first be sufficient to balance the force, but, as  $Q$  gradually increases, the frictions at these points may attain their limiting values. As soon as they begin to yield, the frictions at the neighbouring points will be called into play, and so on throughout the body.

When the external forces are insufficient to move the body as a whole, the directions and magnitudes of the frictions at the points of support depend on the manner in which the body yields, however slight that yielding may be. Even if the external forces were absent, the body could be placed in a state of constraint and might be maintained in that state by the frictions. Thus the frictions depend on the *initial state of constraint* as well as on the external forces. It is also possible that the body, though apparently at rest, may be performing small oscillations about some position of stable equilibrium. This might cause other changes in the frictions.

By this we mean that the least diminution of roughness or the least increase of the forces will cause the body to move. We may enquire what is the condition that these forces may be just great enough to move the body, or just small enough not to move it.

When the body is just beginning to move, the arrangement of the frictional forces is somewhat simplified. We suppose the body to be so nearly rigid that the distances between the several particles do not sensibly change. Thus their motions are not independent, but are sensibly governed by the law proved in the lemma of Art. 180. The directions of the frictions, also, being opposite to the directions of the motions, are governed by the same law.

It will be seen from what follows that, when a rigid body turns round an instantaneous axis, the friction at every point of support acts in the direction which is most effective to prevent motion. If, therefore, the frictional forces thus arranged are insufficient to prevent motion, there is no other arrangement by which they can effect that result.

If the body move on a horizontal plane, no matter how slightly, it must be turning about some vertical axis; let this vertical axis intersect the plane in the point  $I$ . There are then two cases to be considered, (1) the point  $I$  may not coincide with any one of the points of support, and (2) it may coincide with some one of them.

Let us take these cases in order. The position of  $I$  is unknown; let its coordinates be  $\xi, \eta$  referred to any axes in the plane of the table. The points  $A_1, \dots, A_n$  are all beginning to move each perpendicular to the straight line which joins it to the point  $I$ . The frictions at these points will therefore be known when  $I$  is known. Their directions are perpendicular to  $IA_1, IA_2, \&c.$ , and they all act the same way round  $I$ . Their magnitudes are  $\mu_1 P_1, \mu_2 P_2, \&c.$ , if  $\mu_1, \mu_2, \&c.$  are the coefficients of friction. Since the impressed forces only just overbalance the frictions, we may regard the whole as in equilibrium. Forming then the three equations of equilibrium, we have sufficient equations to find both  $\xi, \eta$  and the condition that the body should be on the point of motion. It may be that these equations do not give any available values

of  $\xi$ ,  $\eta$ , and in such a case the point  $I$  cannot lie away from one of the points of support.

**183.** Let us consider next the case in which  $I$  coincides with one of the points of support, say  $A_1$ . The coordinates  $\xi$ ,  $\eta$  of  $I$  are now known. Just as before the frictions at  $A_2, \dots, A_n$  are all known, their directions are perpendicular to  $A_1A_2$ ,  $A_1A_3$ , &c. and their magnitudes are  $\mu_2P_2$ , &c. Since  $A_1$  does not move, the friction at  $A_1$  is not necessarily limiting friction. It may be only just sufficient to prevent  $A_1$  from moving. Let the components of this friction parallel to the axes  $x$  and  $y$  be  $F_1$  and  $F_1'$ . Forming as before the three equations of equilibrium, we have sufficient equations to find  $F_1$ ,  $F_1'$  and the required condition that the body may be on the point of motion. If, however, the values of  $F_1$ ,  $F_1'$  thus found are such that  $F_1^2 + F_1'^2$  is greater than  $\mu_1^2 P_1^2$ , the friction required to prevent  $A_1$  from moving is greater than the limiting friction. It is then impossible that the body could begin to turn round  $A_1$  as an instantaneous centre. We can determine by a similar process whether the body could begin to turn round  $A_2$ , and so on for all the points of support.


**184.** We shall now form the Cartesian equations from which the coordinates  $\xi$ ,  $\eta$  and the condition of limiting equilibrium are to be found. These however are rather complicated, and in most cases it will be found more convenient to find the position of  $I$  by some geometrical method of expressing the conditions of equilibrium.

Let the impressed forces be represented by a couple  $L$  together with the components  $X$  and  $Y$  acting at the origin. Let the coordinates of  $A_1$ ,  $A_2$  &c. be  $(x_1y_1)$ ,  $(x_2y_2)$ , &c. Let the coordinates of  $I$  be  $(\xi\eta)$ . Let the distances  $IA_1$ ,  $IA_2$  &c. be  $r_1$ ,  $r_2$  &c. Let the direction of rotation of the body be opposite to that of the hands of a watch. Then since the frictions tend to prevent motion, they act in the opposite direction round  $I$ .

The resolution of these frictions parallel to the axes will be facilitated if we turn each round its point of application through an angle equal to a right angle. We then have the frictions acting along the straight lines  $IA_1$ ,  $IA_2$  &c., all towards or all from the point  $I$ . Taking the latter supposition, their resolved parts are to be in equilibrium with  $X$  acting along the positive direction of the axis of  $y$  and  $Y$  along the negative direction of  $x$ .

We find by resolution

$$\left. \begin{aligned} \Sigma \mu P \frac{\xi - x}{r} + Y &= 0 \\ \Sigma \mu P \frac{\eta - y}{r} - X &= 0 \end{aligned} \right\} \dots\dots\dots (1).$$



The equation of moments must be formed without changing the directions of the frictions. Taking moments about  $I$ , we have

$$\Sigma \mu P r + Y \xi - X \eta - L = 0 \dots \dots \dots (2).$$

If the instantaneous centre  $I$  coincide with  $A_1$ , the equations are only slightly altered. We write  $(x_1 y_1)$  for  $(\xi \eta)$ ,  $P_1$  and  $-P_1'$  for  $\mu_1 P_1 \frac{y_1 - \eta}{r_1}$  and  $\mu_1 P_1 \frac{x_1 - \xi}{r_1}$ , and finally omit the term  $\mu_1 P_1 r_1$  in the moment.

**185. The Minimum Method.** There is another way of discussing these equations which will more clearly explain the connection between the two cases. If the body is just beginning to turn about some instantaneous axis, it would begin to turn about that axis if it were fixed in space. Let then  $I$  be any point on the plane of  $xy$  and let us enquire whether the body can begin to turn about the vertical through  $I$  as an axis fixed in space. Supposing all the friction to be called into play, the moment of the forces round  $I$ , measured in the direction in which the frictions act, is

$$u = \Sigma \mu P r + Y \xi - X \eta - L.$$

If, in any position of  $I$ ,  $u$  is negative, the moment of the forces is more powerful than that of the frictions; the body will therefore begin to move. If on the other hand  $u$  is positive, the moment of the frictions is more powerful than that of the forces, and the body could be kept at rest by less than the limiting frictions. Let us find the position of  $I$  which makes  $u$  a minimum. If in this position  $u$  is positive or zero, there is no point  $I$  about which the body can begin to turn.

To make  $u$  a minimum we equate to zero the differential coefficients of  $u$  with regard to  $\xi$ ,  $\eta$ . Since  $r^2 = (x - \xi)^2 + (y - \eta)^2$ , the equations thus formed are exactly the equations (1) already written down in Art. 184.

The statical meaning of these equations is that the pressures on the axis which has been fixed in space are zero when that axis has been so chosen that  $u$  is a minimum. If this is not evident, let  $R_x$  and  $R_y$  be the resolved pressures on the axis. The resolved parts parallel to the axes of the impressed forces and the frictions together with  $R_x$  and  $R_y$  must then be zero. But the equations (1) express the fact that these resolved parts without  $R_x$  and  $R_y$  are zero. It evidently follows that both  $R_x$  and  $R_y$  are zero.

That this position of  $I$  makes  $u$  a minimum and not a maximum may be shown analytically by finding the second differential coefficients of  $u$  with regard to  $\xi$  and  $\eta$ . The terms of the second order are then found to be

$$\Sigma \mu P \{ (\eta - y) d\xi - (\xi - x) d\eta \}^2 / 2r^3,$$

where the  $\Sigma$  implies summation for all the points  $A_1$ ,  $A_2$ , &c. Since each of these squares is positive,  $u$  must be a minimum.

It appears therefore that *the axis about which the body will begin to turn may be found by making the moment (viz.  $u$ ) of the forces about that axis a minimum; and the condition that the forces are only just sufficient to move the body is found by equating to zero the least value thus found.*

**186.** The quantities  $r_1$ ,  $r_2$ , &c. are necessarily positive, and therefore not capable of unlimited decrease. Besides the minima found by the rules of the differential calculus, other maxima or minima may be found by making some one of the quantities  $r_1$ ,  $r_2$ , &c. equal to zero.

Suppose  $u$  to be a minimum when  $r_1 = 0$ , i.e. when the point  $I$  coincides with  $A_1$ . Take  $A_1$  as the origin of coordinates. Let  $I$  receive a small displacement from

the position  $A_1$ , and let its coordinates become  $\xi=r_1 \cos \theta_1$ ,  $\eta=r_1 \sin \theta_1$ . Let the coordinates of  $A_2$ , &c. be  $(r_2 \theta_2)$ , &c. The value of  $u$ , when the first power only of the small quantity  $r_1$  is retained, becomes

$$u = \mu_1 P_1 r_1 + \mu_2 P_2 \{r_2 - r_1 \cos (\theta_1 - \theta_2)\} + \&c. + Y r_1 \cos \theta_1 - X r_1 \sin \theta_1 - L.$$

The condition that  $u$  should be a minimum is that the increment of  $u$  should be positive for all small displacements of  $L$ . This will be the case if the coefficient of  $r_1$ , viz.

$$\mu_1 P_1 - \mu_2 P_2 \cos (\theta_1 - \theta_2) - \&c. + Y \cos \theta_1 - X \sin \theta_1,$$

is positive for all values of  $\theta_1$ . We may write this in the form

$$\mu_1 P_1 + A \cos \theta_1 + B \sin \theta_1,$$

where  $A$  and  $B$  are quantities independent of  $\theta_1$ . It is clear that if this is positive for all values of  $\theta_1$ ,  $\mu_1 P_1$  must be numerically greater than  $(A^2 + B^2)^{\frac{1}{2}}$ .

$$\text{We notice that since } A = -\mu_2 P_2 \cos \theta_2 - \&c. + Y,$$

$$B = -\mu_2 P_2 \sin \theta_2 - \&c. - X,$$

the quantities  $A$  and  $-B$  are the resolved parts parallel to the axes of the external forces and of all the frictional forces except that at  $A_1$ . If  $F$  be the friction at the point  $A_1$ , the resultant pressure on the axis will be  $(A^2 + B^2)^{\frac{1}{2}} + F$ . This can be made to vanish by assigning to the friction  $F$  a value less than the limiting friction. See Art. 183.

It appears therefore that, if we include all the positions of  $I$  which make the moment  $u$  a minimum, viz. those which do, as well as those which do not coincide with a point of support, that position in which  $u$  is least is the position of the instantaneous axis.

**187.** It will be observed that, if the lamina is displaced round the axis through  $I$  through any small angle  $d\theta$ , the work done by the forces and the frictions is  $u d\theta$ , where  $d\theta$  is measured in the direction in which the frictions act. To make  $u$  a minimum is the same thing as to make this work a minimum for a given angle of displacement.

**188.** Ex. 1. A triangular table with a point of support at each corner  $A, B, C$  is placed on a rough horizontal floor. Find the least couple which will move the table.

It may be shown that the pressure on each point of support is equal to one third of the weight of the triangle. The limiting frictional forces at  $A, B, C$  are therefore each equal to  $\frac{1}{3}\mu W$ .

Let the triangle begin to turn about some point  $I$  not at a corner. Since the frictions balance a couple, these frictions when rotated through a right angle so as to act along  $AI, BI, CI$  must be in equilibrium. Hence  $I$  must lie within the triangle. Also, the frictions being equal, each of the angles  $AIB, BIC, CIA$  must be  $=120^\circ$ . If then no angle of the triangle is so great as  $120^\circ$ , the point  $I$  is the intersection of the arcs described on any two sides of the triangle to contain  $120^\circ$ . The least couple which will move the triangle is therefore  $\frac{1}{3}\mu W (AI + BI + CI)$ .

The triangle might also begin to turn about one of its corners. Suppose  $I$  to coincide with the corner  $C$ . Rotating the frictions as before, the magnitude of the friction at  $C$  must be just sufficient to balance two forces, each equal to  $\frac{1}{3}\mu W$ , acting along  $AC$  and  $BC$ . The resultant of these is clearly  $\frac{1}{3}\mu W \cdot 2 \cos \frac{C}{2}$ . Unless the angle  $C$  is  $> 120^\circ$  this resultant is  $> \frac{1}{3}\mu W$  and is therefore inadmissible. Thus





at  $R$ . Then if  $AR$  represent  $F$ ,  $RB$  must be less than  $F'$ , because there is no slipping at  $B$ . But, because  $R$  lies within the circle, the ratio  $AR : RB$  is less than the ratio  $AP : PB$ , i.e. is less than  $F : F'$ , and therefore  $RB$  is greater than  $F'$ . But this is contrary to supposition.

Thus the string being produced will always cut the arc of the circle and the part of the straight line in one point and one point only. The frictions always tend to that point when the rod is on the point of motion.


In order that the locus of  $P$  may be the dotted part of the circle it is necessary that the frictions should tend one from  $P$  and the other to  $P$  and the tension must therefore act in the angle between  $PA$  and  $PB$  produced. By the triangle of forces  $APB$  we see that the tension must act parallel to  $AB$ , and be proportional to it.

Ex. 4. A lamina rests on three small supports  $A, B, C$  placed on a horizontal table; one of these, viz.  $C$ , is smooth and the other two,  $A$  and  $B$ , are rough. A string attached to any point  $D$ , fixed in the lamina, is pulled horizontally so that the lamina is on the point of motion. If the position of the centre of gravity and the coefficients of friction are such that the limiting frictions  $F$  and  $F'$  at  $A$  and  $B$  are in the ratio  $BD : AD$ , prove that the locus of the intersection  $P$  of the string and the frictions  $F, F'$  is (1) a portion of the circle circumscribing  $ABD$ , (2) a portion of a rectangular hyperbola having its centre at the middle point of  $AB$  and also circumscribing  $ABD$ , (3) a portion of two straight lines.

Let  $AD = b$ ,  $BD = a$ , then  $Fb = F'a$ .

Draw  $LAL', HH'$  perpendiculars to  $AB$ . If the lamina slip at one point only of the supports  $A, B$ , the point  $P$  lies on these perpendiculars.

If the lamina slip at both  $A$  and  $B$ , we find, by taking moments about  $D$ , that  $\sin PAD = \sin PBD$ . The angles  $PAD$  and  $PBD$  are therefore either supplementary or equal. The locus of  $P$  is therefore the circle circumscribing the triangle  $ABD$ , and a rectangular hyperbola also circumscribing  $ABD$ . The first locus follows also from the triangle of astatic forces considered in Art. 71. The second locus may be found by taking  $AB$  as axis of  $x$  and equating the tangents of the angles  $PBA$  and  $PAB - \gamma$ , where  $\gamma$  is the difference of the angles  $DAB$  and  $DBA$ .



To determine the branches of these two curves which form the true locus of  $P$  we consider the relative positions of  $P$  and the instantaneous centre  $I$ . These two points lie at opposite ends of a diameter of a circle drawn round  $ABP$ . Hence, if  $P$  lie outside the perpendiculars  $LL', HH'$ ,  $I$  also must lie outside. The frictions cannot then balance the tension  $T$  unless the straight line  $PD$  passes *inside* the angle  $APB$ . Similarly, if  $P$  lie between the perpendiculars,  $PD$  must be *outside* the angle  $APB$ .


The straight lines  $LL', HH', DA, DB$  divide space into ten compartments. Several of these compartments are excluded from the locus of  $P$  by the rules just given. It will be convenient to mark (by shading or otherwise) the compartments in which  $P$  can lie. We then sketch the circle and the hyperbola and take only those

branches which lie on a marked compartment. The figures are different according as  $D$  lies between or outside the lines  $II'$ ,  $III'$ .

Ex. 5. If in the last example the limiting frictions are in any ratio, the locus of the intersection of the string and frictions is a portion of a curve of the fourth degree and of two straight lines. The proper portions, as before, are those branches which lie in the marked compartments.

**189.** Ex. 1. A uniform straight rod  $AB$  is placed on a rough table, and all its elements are equally supported by the table. Find the least force which, acting at one extremity  $A$  perpendicular to the rod, will move it.

Let  $l$  be the length of the rod,  $w$  its weight per unit of length. Each element  $dx$  of the rod presses on the table with a weight  $w dx$ . The limiting friction at this element is therefore  $\mu w dx$ . If  $I$  be the centre of instantaneous rotation, the friction at each element acts perpendicular to the straight line joining it to  $I$ , and all these are in equilibrium with the impressed force  $P$  at  $A$ .



The point  $I$  must lie in the length of the rod. For suppose it were on one side of the rod, then, rotating (as already explained) the frictions through a right angle so that they all act towards  $I$ , these should be in equilibrium with a force  $P$  acting parallel to the rod. But this is impossible unless  $I$  lie in the length of the rod.

Next, let  $I$  be on the rod, and let  $AI = z$ . The friction at any element  $H$  or  $H'$  acts perpendicular to the rod in the direction shown in the figure. The resultant frictions on  $AI$  and  $BI$  are therefore  $\mu w z$  and  $\mu w (l - z)$ . These act at the centres of gravity of  $AI$  and  $BI$ . Resolving and taking moments about  $A$ , we have

$$\mu w z - \mu w (l - z) = P, \quad \mu w z^2 = \mu w (l^2 - z^2).$$

The last equation gives  $z\sqrt{2} = l$ , and the first shows that  $P = \mu W(\sqrt{2} - 1)$ , where  $W$  is the weight of the rod.

Ex. 2. Show that the rod could not begin to turn about a point  $I$  on the left of  $A$  or on the right of  $B$ .

Ex. 3. If the pressure of an element on the table vary as its distance from the extremity  $A$  of the rod; and  $P, Q$  be the forces applied at  $A, B$  respectively which will just move the rod, prove that the ratio of  $P$  to  $Q$  is  $2(\sqrt{2} - 1)$ .

Ex. 4. Two uniform equally rough rods  $AB, BC$ , smoothly hinged together at  $B$ , are placed in the same straight line on a rough horizontal table, and the extremity  $A$  is acted on by a force  $P$  in a direction perpendicular to the rods. If  $P$  is gradually increased until motion begins, show that the rod  $AB$  begins to move before  $BC$  or both begin to move together according as  $2(\sqrt{2} - 1)W'$  is greater or less than  $W$ , where  $W, W'$  are the weights of the rods  $AB, BC$  respectively. If both rods begin to move together, prove that the instantaneous centre of rotation of  $AB$  is at a distance  $z$  from  $A$  where  $\frac{2z^2}{l^2} = 1 + 2(\sqrt{2} - 1)\frac{W'}{W}$  and  $l$  is the length of  $AB$ .

Ex. 5. A heavy rod  $AB$  placed on a rough horizontal table is acted on at some point  $C$  in its length by a force  $P$ , in a direction making an angle  $\alpha$  with the rod, and the force is just sufficient to produce motion. If the instantaneous centre lie in a straight line drawn through  $B$  perpendicular to the rod and be a distance

from  $A$  equal to twice the length  $AB$ , prove that  $\tan \alpha = 2(2 - \sqrt{3})/\sqrt{3} \log 3$ . Find the position of  $C$ .

Ex. 6. A hoop is laid upon a rough horizontal plane, and a string fastened to it at any point is pulled in the direction of the tangent line at the point. Prove that the hoop will begin to move about the other end of the diameter through the point. [Math. Tripos, 1873.]

Let  $A$  be the point,  $AB$  the diameter through  $A$ . If we rotate each force round its point of application through a right angle the frictional forces will act towards the centre  $I$  of rotation Art. 184. The point  $I$  is therefore so situated that the resultant of the frictional forces (regarded as acting towards  $I$  from the elements of the hoop) is parallel to the diameter  $AB$ . It easily follows that  $I$  must lie on the diameter  $AB$ .

Let us next consider the equation of moments. The point  $I$  must be so situated in the diameter  $AB$  that the moment about  $A$  of the frictions at all the elements of the hoop is zero. This condition is satisfied if  $I$  is at the end  $B$  of the diameter  $AB$ , for then the line of action of the friction at every element passes through  $A$ .

It is, perhaps, unnecessary to prove that no point, other than  $B$ , will satisfy this condition. It may however be shown in the following manner. If possible let  $I$  lie on  $AB$  within the circle. Whatever point  $P$  is taken on the hoop the angle  $IPA$  is less than a right angle. Since the friction at  $P$  acts in a direction at right angles to  $IP$ , it will become evident by drawing a figure that the friction at every element tends to produce rotation round  $A$  in the same direction. The moment therefore of the frictions about  $A$  could not be zero. In the same way we can prove that  $I$  cannot lie outside the circle.

Ex. 7. A uniform semicircular wire, of weight  $W$ , rests with its plane horizontal on a rough table,  $AB$  is the diameter joining its ends, and  $C$  is the middle point of the arc; a string tied to  $C$  is pulled gently in the direction  $CA$ , and the tension increased until the wire begins to move. Show that the tension at this instant is equal to  $2\sqrt{2}\mu W/\pi$ . [The instantaneous axis is at  $B$ .] [St John's Coll., 1886.]

Ex. 8. A uniform piece of wire, in the form of a portion of an equiangular spiral, rests on a rough horizontal plane; show that the single force which, applied to a point rigidly connected with it, will cause it to be on the point of moving about the pole as instantaneous centre, is equal to the weight of a straight wire of length equal to the distance between the ends of the spiral, multiplied by the coefficient of friction. Show how to find the point. [Math. Tripos, 1888.]

Ex. 9. Three equal weights, occupying the angles  $A, B, C$  of an equilateral triangle, are rigidly connected and placed upon a rough inclined plane with the base  $AB$  of the triangle along the line of greatest slope, and the highest weight  $A$  is attached by a string to a point  $O$  in the line of the base produced upwards; if the system be on the point of moving, prove that the tangent of the inclination of the plane is  $(2 + \sqrt{3})\mu/\sqrt{3}$ , where  $\mu$  is the coefficient of friction. [Math. Tripos, 1870.]

Suppose  $I$  not at a corner, the three frictions are then equal. Since  $A$  can only move perpendicular to  $OA$ ,  $I$  must lie in  $OAB$ . Unless  $I$  lie between  $A$  and  $B$  and at the foot of the perpendicular from  $C$  on  $AB$ , the three frictions will have a component perpendicular to  $AB$ . Taking moments about  $I$ , we find the result given in the question. Next suppose  $I$  to be at the corner  $A$ . The frictions at  $B$  and  $C$  when resolved perpendicular to  $AB$  are then too great for the limiting friction at  $A$ . This supposition is therefore impossible.

Ex. 10. A three-legged stool stands on a horizontal plane, the coefficient of friction being the same for the three feet; a small horizontal force is applied to one of the feet in a given direction, and is gradually increased until the stool begins to move; show that this force will be greatest when its direction intersects the vertical through the centre of gravity of the stool.

Show also that if the force when equal to twice the whole friction of the foot on which it acts, applied in a direction whose normal at the foot passes between the two other feet, causes the foot to begin to move in its own direction, the centre of gravity of the stool is vertically above the centre of the circle inscribed in the triangle formed by the feet. [Math. Tripos.]

Ex. 11. A flat circular heavy disc lies on a rough inclined plane and can turn about a pin in its circumference; show that it will rest in any position if  $32\mu > 9\pi \tan i$ , where  $i$  is the inclination of the plane to the horizon. The weight is supposed to be equally distributed over its area. [Pet. Coll., 1857.]

Let  $W$  be the weight of the disc. The origin being at the pin the friction at any element  $r d\theta dr$  is  $\mu W \cos i \cdot r d\theta dr / \pi a^2$ . Taking moments about the pin the result follows by integration.

Ex. 12. A right cone, of weight  $W$  and angle  $2\alpha$ , is placed in a circular hole cut in a horizontal table with its vertex downwards. Show that the least couple which will move it is  $\mu W r \operatorname{cosec} \alpha$ , where  $r$  is the radius of the hole.

The pressure  $R ds$  on each element  $ds$  of the hole acts normally to the surface of the cone, hence, resolving vertically,  $\int R ds \sin \alpha = W$ . The limiting friction on each element is  $\mu R ds$ , hence, taking moments about the axis of the cone, the result follows.

Ex. 13. A heavy particle is placed on a rough inclined plane, whose inclination is equal to the limiting angle of friction; a thread is attached to the particle and passed through a hole in the plane, which is lower than the particle but not in the line of greatest slope; show that, if the thread be *very slowly* drawn through the hole, the particle will describe a straight line and a semicircle in succession.

[Maxwell's problem, Math. Tripos, 1866.]


Let  $W$  be the weight resolved along the line of greatest slope,  $F$  the friction, then  $F = W$ . As the particle moves very slowly, the forces  $F$ ,  $W$  and the tension  $T$  are always in equilibrium. As long as the hole  $O$  is lower than the particle,  $T$  is infinitely small and just disturbs the equilibrium. The particle therefore descends along the line of greatest slope. When the particle  $P$  passes the horizontal line through  $O$ ,  $T$  becomes finite. Hence  $T$  bisects the angle between  $F$  and  $W$ . The path is therefore such that the radius vector  $OP$  makes the same angle with the tangent (i.e.  $F$ ) that it makes with the line of greatest slope. This, by a differential equation, obviously gives a semicircle having  $O$  for one extremity of its horizontal diameter.

Ex. 14. If, on a table on which the friction varies inversely as the distance from a straight line on it, a particle is moved from one given point to another, so that the work done is a minimum, the path described is a circle. [Trin. Coll.]

This result follows at once from Lagrange's rule in the Calculus of Variations.

190. Ex. 1. Two heavy particles  $A$ ,  $A'$ , placed on a rough table, are connected by a string without tension and very slightly elastic. The particle  $A$  is acted on by a force  $P$  in a given direction  $AC$  making with  $A'A$  produced an angle  $\beta$  less than a right angle. As  $P$  is gradually increased from zero, will  $A$  move first or will both move together?

Let  $F$ ,  $F'$  be the limiting frictions at  $A$ ,  $A'$ . Suppose  $P$  to increase from zero: while  $P$  is less than  $F'$  it is entirely balanced by the friction at  $A$ . The string, however nearly inelastic it may be, has no tension until  $A$  has moved. Let  $P$  be a little greater than  $F'$ ; take  $AL$  to represent  $P$  and draw  $LM M'$  parallel to  $AA'$ ; with centre  $A$  and radius  $F$  describe a circle cutting  $LM M'$  in  $M$  and  $M'$ , then  $LM$  represents the tension of the string. Of the two intersections  $M$ ,  $M'$ , the nearest to  $L$  is chosen, for this makes the friction at  $A$  act opposite to  $P$  when  $P = F$ .



As  $P$  gradually increases  $M$  travels along the arc  $CH$ . The equilibrium of the particle  $A$  becomes impossible when  $LM M'$  does not cut the circle, i.e. when  $M$  reaches  $H$ . The particle  $A'$  borders on motion when the tension  $LM$  becomes equal to  $F'$ . Now  $HK = F \cot \beta$ . Hence the particle  $A$  moves alone if  $F \cot \beta < F'$  but both move together if  $F \cot \beta > F'$ .

When the limiting frictions  $F$ ,  $F'$  are equal, and  $\beta$  is less than half a right angle, both particles move together. One friction acts along  $AA'$  and the other makes an angle  $\beta$  with the force  $P$ . Also  $P = 2F \cos \beta$ .

In this solution the point  $M'$  has been excluded by the principle of continuity, though statically  $A$  would be in equilibrium under the forces represented by  $AL$ ,  $LM'$ ,  $M'A$ . If the string  $AA'$  had a proper initial tension, but balanced by frictions at  $A$  and  $A'$  together with an initial force  $P$  along  $AC$ , then  $M'$  would be the proper intersection to take.

Ex. 2. Two weights  $A$  and  $B$  are connected by a string and placed on a horizontal table whose coefficient of friction is  $\mu$ . A force  $P$ , which is less than  $\mu A + \mu B$ , is applied to  $A$  in the direction  $BA$ , and its direction is gradually turned round an angle  $\theta$  in the horizontal plane. Show that if  $P$  be greater than  $\mu \sqrt{A^2 + B^2}$ , then both  $A$  and  $B$  will slip when  $\cos \theta = \{\mu^2 (B^2 - A^2) + P^2\} / 2\mu BP$ , but if  $P$  be less than  $\mu \sqrt{A^2 + B^2}$  and greater than  $\mu A$ , then  $A$  alone will slip when  $\sin \theta = \mu A / P$ . [Math. Tripos.]

Ex. 3. The  $n$  particles  $A_0, A_1, \dots, A_{n-1}$ , of equal weights, are connected together, each to the next in order, by  $n-1$  strings of equal length and very slightly elastic. These are placed on a rough horizontal plane with the strings just stretched but without tension, and are arranged along an arc of a circle less than a quadrant. The particle  $A_{n-1}$  is now acted on by a force  $P$  in the direction  $A_{n-1}A_n$ , where  $A_n$  is an imaginary  $(n+1)$ th particle. Supposing  $P$  to be gradually increased from zero, find its magnitude when the system begins to move.

Let us suppose that any two consecutive particles  $A_m$  and  $A_{m+1}$  both border on motion. Let  $\phi_m$  be the angle the friction at  $A_m$  makes with the chord  $A_{m+1}A_m$ . Let  $T_m$  be the tension of the string  $A_m A_{m+1}$ . Let  $\beta$  be the angle between any string and the next in order. Let  $F$  be the limiting friction at any particle.

Resolving the forces on the particles  $A_m$  and  $A_{m+1}$  perpendicularly to  $A_{m-1}A_m$  and  $A_{m+1}A_{m+2}$  respectively, we find

$$T_m \sin \beta = F \sin (\phi_m + \beta), \quad T_m \sin \beta = F \sin \phi_{m+1}.$$

Resolving the same forces perpendicularly to the frictions on the two particles, we have  $T_m \sin \phi_m = T_{m-1} \sin (\phi_m + \beta)$ ,  $T_{m+1} \sin \phi_{m+1} = T_m \sin (\phi_{m+1} + \beta)$ .

Comparing the first two equations, we see that  $\phi_m + \beta$  and  $\phi_{m+1}$  are either equal or supplementary. The other two equations show that the second alternative makes  $T_{m+1} = T_{m-1}$ . Both these alternatives are statically possible, and thus forces which might be friction forces could be arranged at the several particles in many ways so that equilibrium would be preserved.

We shall take the alternative which agrees with the supposition that the strings are initially without tension. When  $P$  is less than  $F$  the friction at  $A_{n-1}$  acts in the direction opposite to  $P$ , and all the tensions are zero. When  $P$  has become greater than  $F$ , the string  $A_{n-2}A_{n-1}$  is slightly stretched and the tension  $A_{n-2}A_{n-1}$  is called into play. The friction at  $A_{n-2}$  acts opposite to this tension, and all the other tensions are zero. Thus, as  $P$  continually increases, the tensions and frictions are one by one called into play. Supposing the tensions to be initially zero, we shall assume that the tensions produced by  $P$  are such that their magnitudes continually increase from the string with zero tension up to the string  $A_{n-1}A_n$ . Any other supposition would lead to the result that by pulling a string at one end we could produce, after overcoming the resistances, a greater tension at the other end. Since then  $T_{m+1}$  must be greater than  $T_{m-1}$ , we have  $\phi_{m+1} = \phi_m + \beta$ .

Suppose that all the particles from  $A_p$  to  $A_{n-1}$  border on motion and that  $T_{p-1} = 0$ ; we have then  $\phi_p = 0$ ,  $\phi_{p+1} = \beta$ , and in general

$$\phi_{p+\kappa} = \kappa\beta, \quad T_{p+\kappa} \sin \beta = F \sin (\kappa + 1) \beta.$$

Since  $T_{n-1} = P$ , we see that the force  $P$  required to make all the particles from  $A_p$  to  $A_{n-1}$  border on motion is

$$P = F \sin (n - p) \beta \cdot \operatorname{cosec} \beta.$$

When  $P$  becomes greater than the value given by this equation, a tension in the string  $A_{p-1}A_p$  will be called into play. The tension of  $A_pA_{p+1}$  required to move  $A_p$  without  $A_{p-1}$  is  $F \operatorname{cosec} \beta$ , while that required to move both is  $F \sin 2\beta \cdot \operatorname{cosec} \beta$ . Since the latter is less than the former tension, the friction at  $A_{p-1}$  will become limiting before  $A_p$  begins to move. Thus we see that, as  $P$  continues to increase, the successive particles border on motion, but no one begins to move without the others.

If  $n\beta$  be less than a right angle, we conclude that all the particles begin to move together, and that the force required to move them is  $P = F \sin n\beta \operatorname{cosec} \beta$ .

If  $n\beta$  be greater than a right angle, we have shown that, without destroying the equilibrium,  $P$  can increase up to  $F \sin p\beta \cdot \operatorname{cosec} \beta$ , where  $p\beta$  is less and  $(p+1)\beta$  greater than a right angle. We have then  $T_{n-p-1} = 0$ . When  $P$  becomes greater than this value, the particle  $A_{n-1}$  will begin to move alone. For the tension required to move  $A_{n-1}$  is  $F \operatorname{cosec} \beta$ , and the tension  $T_{n-2}$  is then  $F \cot \beta$ . Since this is less than  $F \sin p\beta \operatorname{cosec} \beta$ , the system  $A_{n-2}, A_{n-3}, \&c.$  is not bordering on motion.

## CHAPTER VI

### THE PRINCIPLE OF VIRTUAL WORK

191. <sup>134.</sup> IN a former chapter the principle of virtual work has been established for forces which act on a particle. It is now proposed to consider this principle more fully, and to apply it to a system of bodies in two and three dimensions.

The principle itself may be enunciated as follows. *Let any number of forces  $P_1, P_2$  &c. act at the points  $A_1, A_2$  &c. of a system of bodies. These bodies are connected together in any manner so as either to allow or exclude relative motion, and they therefore exert mutual actions and reactions on each other. Let the system be slightly displaced so that the points  $A_1, A_2$  &c. assume the neighbouring positions  $A'_1, A'_2$  &c. Let  $dp_1, dp_2$  &c. be the projections of the displacements  $A_1A'_1, A_2A'_2$  &c. on the directions of the forces  $P_1, P_2$  &c. respectively, and let  $dW = P_1dp_1 + P_2dp_2 + \text{&c.}$  Then the system is in equilibrium if  $dW = 0$  for all displacements consistent with the geometrical connexions between the bodies of the system.*

*Also the system is not in equilibrium if one or more displacements can be found for which  $dW$  is not equal to zero.*

Strictly speaking we should say, not that  $dW$  is zero, but that  $dW$ , in the language of the differential calculus, is a small quantity of the second order. This will be understood in what follows.

192. These displacements are to be regarded as imaginary motions which the system might, but does not necessarily, take. The principle of virtual work supplies a test, whether a given position of the system is one of equilibrium or not. We first consider what are the possible ways in which the system could begin to move out of the given position. If for any one of these

the sum  $\Sigma Pdp$  is zero, then the system will not begin to move in that mode of displacement. In this way all the possible displacements are examined, and if  $\Sigma Pdp$  is zero for each and every one, the given position is one of equilibrium.

These small tentative displacements of the system are called *virtual displacements*. The product  $Pdp$  is called, sometimes the *virtual moment*, and sometimes the *virtual work* of the force  $P$ . The sum  $\Sigma Pdp$  is called the virtual moment or virtual work of all the forces.

**193.** A proof of the principle of virtual work for forces acting on a single particle has been already given in Chap. II. No satisfactory method has yet been found by which the principle for a system of bodies can be deduced directly from the elementary axioms of statics. Lagrange has made a brilliant attempt which will be discussed a little further on.

There is another line of argument which may be adopted. The system is regarded as composed of simpler bodies, each acted on by some of the forces, and connected together by mutual actions and reactions. Thus Poisson regards the system as a collection of points in equilibrium connected together as if by flexible strings or inflexible rods without weight. To avoid making any assumptions concerning the molecular structure of bodies, we shall regard the system as made up of rigid bodies of such size that the elementary laws of statics may be applied to them.

The principle will first be proved for the simpler body, assuming the composition and resolution of forces. The principle will therefore be true for the general system, provided we include amongst the forces  $P_1, P_2$  &c. all the mutual actions and reactions of the bodies of the system.

Lastly, these actions and reactions are examined, and it will be proved that they do not put in an appearance in the general equation of virtual work. It follows that the principle may be used as if  $P_1, P_2$  &c. were the only forces acting on the system.

The chief objection to this mode of proof is that the mutual actions and reactions must be sufficiently known to enable us to prove that their separate virtual works are either zero or cancel each other.



In this mode of proof we have in part followed the lead of Fourier. See *Journal Polytechnique*, Tome II.


To prove the converse theorem we shall examine how a system could begin to move from a position of rest. We shall show that every such displacement is barred if for that displacement the virtual work of the forces is zero.

**194. Proof of the principle for a free rigid body.** We begin by proving that *the virtual work of any system of finite forces  $P_1, P_2$  &c. is equal to that of their resultants provided the points of application of all the forces are connected by invariable relations.* See Art. 19.

The general process by which these resultants are found may be separated into three steps; (1) we may combine or resolve forces acting at a point by the parallelogram of forces; (2) we may transfer a force from one point  $A$  of its line of action to another  $B$ ; (3) we may remove from or add to the system, equal and opposite forces. By the repeated action of these steps we have been able in the preceding chapters to change one set of forces into another simpler set, which we called their resultant. See Art. 117.

It has been proved in Art. 66 that the virtual work is not altered by the first of these processes. We shall now show that the virtual work of a force is not altered by the second process. It follows that the sum of the virtual works of two equal and opposite forces introduced by the third process is zero, and cannot affect the general virtual work of all the forces.

Let  $A'B'$  be the displaced position of  $AB$ . Draw  $A'M, B'N$  perpendiculars on  $AB$ . Let  $F$  be the force whose point of application is to be transferred from  $A$  to  $B$ . Before and after the



transference its virtual works are  $F \cdot AM$  and  $F \cdot BN$  respectively. Since  $A'B'$  makes with  $AB$  an infinitely small angle whose cosine may be regarded as unity, we have  $MN$  equal to  $A'B'$ . Hence, if the distance between the two points of application remain unaltered, i.e.  $AB = A'B'$ , we have  $BN = AM$ . It immediately follows that  $F \cdot AM = F \cdot BN$ .

Thus in all changes of forces into other forces consistent with the principles of statics, the work of the forces due to any given small displacement is unaltered.

**195.** We may now apply this result to a system of forces  $P_1, P_2$  &c. acting on a free rigid body.

All these forces can be reduced to a force  $R$  acting at an arbitrary point  $O$ , and a couple  $G$ , Art. 105. By what precedes the virtual work of the forces  $P_1, P_2$  &c. due to any displacement is equal to the virtual work of  $R$  and  $G$ .

If the forces  $P_1, P_2$  &c. are in equilibrium, both  $R$  and  $G$  are zero, Art. 109. Hence the virtual work of  $P_1, P_2$  &c. for any displacement is zero.

Conversely, if the virtual work of  $P_1, P_2$  &c. is zero for all displacements, then the virtual work of  $R$  and  $G$  is zero. We shall now show that this requires that  $R$  and  $G$  should each be zero. First let the body be moved parallel to itself through any small space  $\delta r$  in the direction in which  $R$  acts. The virtual work of the force  $R$  is  $R\delta r$ . Let  $AB$  be the arm of the couple and let the forces act at  $A$  and  $B$ . Since equal and parallel displacements  $AA', BB'$  are given to  $A$  and  $B$ , while the forces acting at  $A$  and  $B$  are equal and opposite, it is evident that the works due to the two forces cancel each other. The work of the couple  $G$  is therefore zero. Hence the sum of the works of  $R$  and  $G$  cannot vanish unless  $R=0$ .

Next let the body be turned through a small angle  $\delta\omega$  round a perpendicular drawn through  $O$  to the plane of the couple, and let this rotation be in the direction in which the couple urges the body. Let  $O$  bisect the arm  $AB$  and let the forces of the couple be  $\pm Q$ . Each of the points  $A$  and  $B$  receives a displacement equal to  $\frac{1}{2}AB\delta\omega$  in the direction of the force acting at that point. The sum of the works due to these two forces is therefore  $AB \cdot Q\delta\omega$ , i.e.  $G\delta\omega$ . Since the point of application of  $R$  is not displaced, the virtual work of  $R$  (even if  $R$  were not zero) is zero. Hence the sum of the virtual works of  $R$  and  $G$  cannot vanish unless  $G=0$ . It immediately follows that the body is in equilibrium.

**196. On the forces which do not put in an appearance in the equation of virtual work.** When the body is not free but can move either under the guidance of fixed constraints or

under the action of other rigid bodies it becomes necessary (as explained in Art. 193) to determine what actions and reactions do not appear in the general equation of virtual work. We cannot make an exhaustive list, but we may make one which will include those cases which commonly occur.

I. *Let two particles  $A, B$  of the system act on each other by means of forces along  $AB$ , then if the distance  $AB$  remain invariable for any displacement, the virtual works of the action and the reaction destroy each other.* For example, if the points  $A, B$  are connected by an inelastic string, the tension does not appear in the equation of virtual work.

This follows at once from Art. 194, for the force at  $A$  may be transferred to  $B$ . The two equal and opposite forces acting at  $B$  have then the same displacement. Hence their virtual works are equal and opposite.

II. *If any body of the system is constrained to turn round a point or an axis fixed in space, the virtual work of the reaction at this point or axis is zero.* This is evidently true, for the displacement of the point of application of the force is zero.


III. *Let any point  $A$  of a body be constrained to slide on a surface fixed in space.*

If the surface is smooth, the action  $R$  on the point  $A$  of the body is normal to the surface. Let  $A$  move to a neighbouring point  $A'$ , then  $AA'$  is at right angles to the force. The work by Art. 68 is therefore zero.

If the surface is rough, let  $F$  be the friction. This force acts along  $A'A$ , and its work is  $-F \cdot AA'$ . This is not generally zero.

IV. *If any body of the system roll without sliding on a fixed surface, the work of the reaction is zero.*

If this is not evident, it may be proved as follows. In the figure the body  $DAE$  rolls on the fixed surface  $MABN$  and takes a neighbouring position  $D'BE'$ . The plane of the paper represents a section of the surfaces drawn through their common normal at  $A$ , and contains the elementary arc  $AB$  of rolling. In this displacement the point  $A$  of the body begins to move along the common normal and arrives at  $A'$ . If we replace the curves  $DAE, MAB$  by their circles of curvature, we know (since the arcs  $AB, A'B$  are equal) that  $AA' : AB^2$  is half the sum of the opposite curvatures. Assuming



these curvatures to be finite, it follows that  $AA'$  is of the same order of small quantities as  $AB^2$ , i.e.  $AA'$  is of the second order of small quantities. Hence, when we retain only terms of the first order, as in the principle of virtual work, we may treat the rolling body as if it were turning round a point  $A$  fixed (for the instant) in space. It follows therefore from the result of the last article that, when a body rolls on a fixed surface, which may be either rough or smooth, the virtual work of the reaction is zero.

V. If the surface on which the body rolls is another body of the system, the surface is moveable. But we may show that, *if both bodies are included in the same equation of virtual work, the mutual action does not appear in that equation.*

To prove this we notice that we may construct any such displacement of the two bodies (1) by moving the two bodies together until the body  $MABN$  assumes its position in the given displacement, and then (2) rolling the body  $DAE$  on the body  $MABN$ , now considered as fixed, until  $DAE$  also reaches its final position. During the first of these displacements the action and reaction at  $A$  are equal and opposite, while their common point of application  $A$  has the same displacement for each body. Their virtual works are therefore equal and opposite, and their sum is zero. During the second displacement the body  $DAE$  rolls on a fixed surface, and the virtual work of its reaction is zero. See Art. 65.

**197. Work of a bent elastic string.** If the points  $A, B$ , are connected by an elastic string, it may be necessary to know what the work of the tension is when the length is increased from  $l$  to  $l+dl$ . We shall show that, whether the string connecting  $A$  and  $B$  is straight, or bent by passing through smooth rings fixed or moveable or over a smooth surface, the work is  $-Tdl$ .

For the sake of greater clearness we shall consider the cases separately.

(1) Let the string be straight. Referring to the figure of Art. 194, the virtual work of the tension at  $A$  is  $+T \cdot AM$ . The positive sign is given because the tension acts at  $A$  in the direction  $AB$  and the displacement  $AM$  is in the same direction, Art. 62. The work of the tension at  $B$  is  $-T \cdot BN$ . The sum of these two is  $-T(A'M' - AB)$  i.e.  $-Tdl$ .


If the action between  $A$  and  $B$  is a push  $R$  instead of a pull  $T$ , the same argument will apply but we must write  $-R$  for  $T$ , so that the virtual work is  $Rdl$ .

If the action between  $A$  and  $B$  is due to an attractive or repulsive force  $F$  the result is still the same; the virtual works are  $-Fdl$  or  $+Fdl$  according as the force  $F$  is an attraction or a repulsion.

(2) Suppose the string joining  $A$  and  $B$  is bent by passing through any number of small smooth rings  $C, D$  &c. fixed in space.

Taking two rings only as sufficient for our argument, let these be  $C$  and  $D$ . Let  $A, B$  be displaced to  $A', B'$ , and let  $A'M, B'N$  be perpendiculars on  $AC$  and  $DB$ . The

whole length  $l$  of the string is lengthened by  $BN$  and shortened by  $AM$ , hence  $dl = BN - AM$ . The tension  $T$  being the same throughout the string, the work at  $A$



is  $T \cdot AM$ , that at  $B$  is  $-T \cdot BN$ . Exactly as before, the whole work is the sum of these two, i.e.  $-Tdl$ .

(3) Suppose the rings  $C, D$  &c., through which the string passes, are attached to other bodies of the system. The rings themselves will now be also moveable.

Supposing all these bodies to be included in the same equation of virtual work, the system is acted on by the following forces, viz.  $T$  at  $A$  along  $AC$ ,  $T$  at  $C$  along  $CA$ ,  $T$  at  $C$  along  $CD$ ,  $T$  at  $D$  along  $DC$  and so on. By what has just been proved, the work of the first and second of these taken together is  $-Td(AC)$ , the work of the third and fourth is  $-Td(CD)$  and so on. Hence, if  $l$  be the whole length of the string, viz.  $AC + CD + \&c.$ , the whole work is  $-Tdl$ .

In all these cases we see that, if the length of the string is unaltered by the displacement, the tension does not appear in the equation of virtual work.

(4) Let the string joining  $A$  and  $B$  pass over any smooth surface, which either is fixed in space, or is one of the bodies to be included in the equation of virtual work. Each elementary arc of the string may be treated in the manner just explained. The work done by the tension is therefore as before equal to  $-Tdl$ .

In order not to interrupt the argument, we have assumed that *the tension of a string is unaltered by passing over a smooth pulley or surface*. To prove this, let us suppose the string to pass over any arc  $BC$  of a smooth surface. Any element  $PP'$  of the string is in equilibrium under the action of the tensions at  $P, P'$  and the normal reaction of the smooth surface. The resolved part of these forces along the tangent at  $P$  must therefore be zero. Let  $T, T'$  be the tensions at  $P, P'$ ,  $d\psi$  the angle between the tangents at these points, and let  $ds$  be the length of  $PP'$ . Supposing the pressure per unit of length of the string on the surface to be finite and equal to  $R$ , the pressure on the arc  $PP'$  is  $Rds$ . The resolved part of this along the tangent at  $P$  is less than  $Rds \sin d\psi$ , and is therefore of the second order of small quantities. The difference of the resolved parts of the tensions is  $T - T' \cos d\psi$ , which, when small quantities of the second order are neglected, reduces to  $T - T'$ . Since this must be zero, we have  $T = T'$ . Taking a series of elements of the string, viz.  $PP', P'P''$  &c., it immediately follows that the tensions at  $P, P', P''$  &c. are all equal, i.e. the tension of the string is the same throughout its length. If the surface were rough, this result would not follow, for the frictions must then be included in the equation of equilibrium formed by resolving along the tangent. We may also prove the equality of the tensions by applying the principle of virtual work to the string  $BC$ . Sliding the string without change of length along the surface, we have  $T \cdot BB' = T' \cdot CC'$ . Hence  $T = T'$ .

When the surface is a rough circular pulley which can turn freely about a smooth axis, and the string lies in a plane perpendicular to the axis, we can prove the equality of the tensions by taking moments about the axis. Let the string be  $ABCD$  and let it touch the cylinder along the arc  $BC$ . Let  $T, T'$  be the tensions

of  $AB$ ,  $CD$ ,  $r$  the radius of the cylinder. Taking moments about the axis, we have  $T'r = T''r$ . This gives  $T' = T''$ .

**198.** In the preceding arguments we have tacitly assumed that the pressures which replace the constraints are finite in magnitude. If this were not true it is not clear that the virtual work would be zero. It is not enough to make a product  $P \cdot dp$  vanish that one factor viz.  $dp$  should be zero, if the other factor  $P$  is infinite. Such cases sometimes occur in our examples when we treat the body under consideration as an unyielding rigid mass. But in nature the changes of structure of the body cannot be neglected when the forces acting on it become very great. The displacements are therefore different from those of a rigid body.

**199. Converse of the principle of virtual work.** We shall now prove the converse principle of virtual work for a system of bodies. *The system being placed at rest in some position, it is given that the work of the external forces is zero for all small displacements which do not infringe on the constraints. It is required to prove that the system is in equilibrium.*

If the system is not in equilibrium it will begin to move. Let us then examine all the ways in which the system could begin to move from its position of rest. Some one way having been selected, it is clear that by introducing a sufficient number of smooth constraining curves we can so restrain the system that it cannot move in any other way. Thus if any point of one of the bodies would freely describe a curve in space, we can imagine that point attached to a small ring which can slide along a rigid smooth wire, whose form is the curve which the point would freely describe. The point is thus prevented from moving in any other way. The reaction of this smooth curve has been proved to have no virtual work. It is also clear that these constraining curves in no way alter the work of the external forces during the displacement of the body.

In order to prevent the system from moving from its initial position it will now only be necessary to apply some force  $F$  to some one point  $A$  in a direction opposite to that in which  $A$  would move if  $F$  did not act. The forces of the system are now in equilibrium with  $F$ . Let the system receive an arbitrary virtual displacement along the only path open to it. In this displacement let the point  $A$  come to  $A'$ . Then the work of the forces plus the

work of  $F$  is zero. But it is given that the work of the forces is zero for every such displacement, hence the work of  $F$  is zero. But this work is  $-F.AA'$ , and since  $AA'$  is arbitrary it immediately follows that  $F$  must be zero. Thus no force is required to prevent the system from moving from its place of rest along any selected path. The system is therefore in equilibrium. *Treatise on Natural Philosophy*, Thomson and Tait, 1879, Art. 290.

**200. Initial motion.** Let us imagine a system to be placed at rest, and yet not to be in equilibrium under the action of the given external forces. We shall show that *the system will so begin to move \* that the work of the forces in the initial displacement is positive.*

The proof of this is really a repetition of the argument already given in Art. 199. If the system begin to move from the position of rest in any given way, we constrain it to move only in that way. If  $F$  be the force acting at  $A$  which will prevent motion, we find as before that the work of the forces plus that of  $F$  is zero. But  $F$  must act opposite to the direction in which  $A$  would move if  $F$  were not applied, hence its work is negative; and the work of the impressed forces in this displacement is therefore positive.

**201.** It follows from this result, that *it is sufficient to ensure equilibrium that the work of the forces should be negative instead of zero for all displacements*, for then there is no displacement which the system could take from its state of rest. If however the work of the forces is negative for any one displacement, it must be positive for an equal and opposite displacement, i.e. one in which the direction of motion of every particle is reversed. To exclude therefore all displacements which make the work positive, it is in general necessary that the work should be zero for all displacements.

In some special cases of constraint it may happen that one displacement is possible while the opposite is impossible. *It is then not necessary that the work should be zero for this displacement.* For example, a heavy particle placed inside a cone with the axis vertical is clearly in equilibrium, yet the work done in any displacement is negative and not zero.

**202. Method of using the principle.** Let us suppose that points  $A_1, A_2$ , &c. of a system are constrained to move on fixed surfaces. We have then two objects, (1) to form those equations of equilibrium which do not contain the reactions, (2) to find the reactions. To effect the former purpose we give the system all necessary displacements which do not separate  $A_1, A_2$ , &c. from the constraining surfaces, and equate the sum of the

\* *Dynamical proof.* When a system starts from a position of rest, it is proved in dynamics that the semi vis viva after a displacement is equal to the work done by the external forces. Now the vis viva cannot be negative, because it is the sum of the masses of the several particles multiplied by the squares of their velocities. It is therefore clear that the system cannot begin to move in any way which makes the virtual work of the forces negative.

surface on which it rests. Assuming the work of the corresponding reaction and still equating the sum of the virtual work to zero we have an equation to find that reaction.

**203.** *To deduce the equations of equilibrium from the principle of work.*

The equations of equilibrium of a system are really equivalent to two statements, (1) the sum of the resolved parts of the forces in any direction for each body or collection of bodies in the system is zero, (2) the sum of the moments about any or every straight line is zero.

The equations of equilibrium of a system in one plane have been obtained in Chap. iv., Arts. 109—111. The corresponding equations of a system in three dimensions will be given at length in a later chapter. But to avoid repetition they are included in the following reasoning. See also Arts. 105 and 113.

We have now to deduce these two results from the principle of work. As before, let  $P_1, P_2$  &c. be the forces,  $A_1, A_2$  &c. the points of application,  $(\alpha_1, \beta_1, \gamma_1), (\alpha_2, \beta_2, \gamma_2)$  &c. their directions. Let the body or collection of bodies receive a small displacement parallel to the axis of  $x$  through a small space




Fig. 1.




Fig. 2.

Then if  $A$  be moved to  $A'$ ,  $AA' = dx$ , (Fig. 1), and the projection of  $AN$  on the line of action of  $P$  is  $dx \cos \alpha$ . Hence, by the principle of work,

$$P_1 \cos \alpha_1 dx + P_2 \cos \alpha_2 dx + \dots = 0.$$

Dividing by  $dx$ , this gives the equation of resolution, viz.

$$P_1 \cos \alpha_1 + P_2 \cos \alpha_2 + \dots = 0.$$

In this equation all the reactions on the special body considered due to the other bodies are to be included.

To find the sum of the moments of the forces about any straight



line, say the axis of  $z$ , let us displace the special body considered round that axis through an angle  $d\omega$ .

First let the forces act in the plane of  $xy$ , and let  $p_1, p_2$  &c. be the perpendiculars from the origin on their respective lines of actions. Thus in Fig. 2,  $OM = p$ . The displacement  $AA'$  of  $A$  due to the rotation is  $OA \cdot d\omega$ . The projection of this on the line of action of  $P$  is  $OA \, d\omega \sin OAM$ , i.e.  $p d\omega$ . Hence by the principle of work

$$P_1 p_1 d\omega + P_2 p_2 d\omega + \dots = 0.$$

Dividing by  $d\omega$ , we have the equation of moments, viz.

$$P_1 p_1 + P_2 p_2 + \dots = 0.$$

Next, let the forces act in space. We first resolve each force parallel and perpendicular to the axis about which we take moments. The resolved parts of  $P$  are respectively  $P \cos \gamma$  and  $P \sin \gamma$ . The displacement  $AA'$  of its point of application due to a rotation round  $z$  is perpendicular to the axis of  $z$ . The work of the first of these components is therefore zero. The second component is parallel to the plane of  $xy$ , and its work is found in exactly the same way as if it acted in the plane of  $xy$ . If  $p$  be the length of the perpendicular from  $O$  on the projection on  $xy$  of its line of action, the work is  $P \sin \gamma p d\omega$ . We therefore find as before

$$P_1 \sin \gamma_1 p_1 + P_2 \sin \gamma_2 p_2 + \dots = 0,$$

which is the usual equation of moments.

**204. Combination of equations.** The equations of equilibrium of each of the bodies forming a system, having been found by resolving and taking moments, we can combine these equations at pleasure in any linear manner. For example we might multiply by  $\lambda$  an equation obtained by resolving parallel to some straight line  $x$ , and multiply by  $\mu$  another equation obtained by taking moments about some straight line  $z$ . Adding the results, we get a new equation which may be more suited to our purpose than either of the original ones.

We shall now show that this derived equation might be obtained directly from the principle of work by a suitable displacement. Suppose both the equations combined as above to be equations of equilibrium of the same body. Let these be written in the form

$$\Sigma P \cos a = 0, \quad \Sigma P p = 0.$$

If we displace the body parallel to  $x$  through a small space  $dx$  and rotate it round  $z$  through an angle  $d\omega$ , the work of any force  $P$  due to the whole displacement is, by Art. 65, equal to the sum of the works of  $P$  due to each displacement. The equation of work obtained by this displacement is therefore

$$(\Sigma P \cos a) dx + (\Sigma P p) d\omega = 0.$$

If then we take  $dx : d\omega$  in the ratio  $\lambda : \mu$ , the derived equation follows at once.

If the equations to be combined are equations of equilibrium of different bodies, these different bodies are to be displaced, a linear displacement corresponding

As in forming the equations of equilibrium by resolving and taking moments we suppose the constraints removed and replaced by corresponding reactions, so in forming these work equations the same supposition must be made.

It further appears that, if we can eliminate any unknown reactions from the equations of equilibrium by choosing the multipliers  $\lambda$ ,  $\mu$  &c. properly and adding the equations, then the same resulting equation can always be obtained (equally free from the same reactions) from the principle of work by giving the system a suitable displacement or series of displacements.

✓ **205. Examples on Virtual Work.** Ex. 1. *A flat semicircular board with its plane vertical and curved edge upwards rests on a smooth horizontal plane, and is pressed at two given points of its circumference by two beams which slide in smooth vertical tubes. Find the ratio of the weights of the beams that the board may be in equilibrium.* [Math. Tripos, 1853.]

Let  $W$ ,  $W'$  be the weights of the beams  $AB$ ,  $A'B'$ ;  $\phi$ ,  $\phi'$  the angles which the radii  $CA$ ,  $CA'$  make with the horizontal diameter  $Cx$ . Let  $a$  be the radius of the sphere,  $b$  the distance between the tubes. If  $y$ ,  $y'$  be the altitudes above  $Cx$  of the centres of gravity of the rods, we have by the principle of work,

$$-Wdy - W'dy' = 0.$$

The negative sign is used because the  $y$ 's are measured upwards *opposite* to the direction in which the weights are measured. Since  $y$  and  $y'$  differ from  $a \sin \phi$  and  $a \sin \phi'$  by constants, viz. half the lengths of the rods, we find

$$W \cos \phi d\phi + W' \cos \phi' d\phi' = 0.$$


But by geometry

$$a \cos \phi + a \cos \phi' = b.$$

Differentiating the latter equation, and eliminating  $d\phi : d\phi'$ , we find

$$W \cot \phi = W' \cot \phi',$$


which gives the required ratio.



✓ Ex. 2. Three heavy rods, which can slide freely through three vertical tubes fixed in space, rest with one extremity of each on a smooth hemisphere. The hemisphere rests with its plane face on a smooth horizontal plane. If  $Cx$  be any horizontal line through the centre  $C$ ,  $\theta_1$ ,  $\theta_2$ ,  $\theta_3$  the angles which the planes through  $Cx$  and the lower extremities of the rods make with a horizontal plane, and  $W_1$ ,  $W_2$ ,  $W_3$  the weights of the rods, prove that in equilibrium  $\sum W \cot \theta = 0$ .

✓ Ex. 3. Eight rods perfectly similar and uniform are jointed together in the form of an octahedron, and being suspended from one of the angles are supported by a string fastened to the opposite angle, the string being elastic and such that the weight of all the rods together would stretch it to double its natural length, viz. that of one of the rods. Prove that in the position of equilibrium the rods will be inclined to the vertical at an angle  $\cos^{-1} \frac{3}{4}$ . [Coll. Ex., 1889.]

Let the eight rods be  $AE, BE, CE, DE$ ;  $AF, BF, CF, DF$  and let  $EF$  be the elastic string. Let  $W$  be the weight of any rod,  $2a$  its length, and  $\theta$  the inclination to the vertical. The octahedron being in its position of equilibrium, let the system receive a symmetrical displacement so that the angle  $\theta$  is increased by  $d\theta$ . Taking  $E$  for origin, the depth of the centre of gravity of any one of the four upper rods is  $a \cos \theta$ , the virtual work of the weights of these rods is therefore  $4Wd(a \cos \theta)$ . The depth of the centre of gravity of any one of the four lower rods is  $3a \cos \theta$ , the virtual work of their weights is  $4Wd(3a \cos \theta)$ .



Since the unstretched length of the string is  $2a$  and its stretched length is  $EF = 4a \cos \theta$ , the tension is, by Hooke's law,  $T = E(4a \cos \theta - 2a)/2a$ , where  $E$  is the weight which would stretch the string to twice its natural length, i.e.  $E = 8W$ . The virtual work is  $-Td(4a \cos \theta)$ , Art. 197. Adding all these several virtual works together we have  $16Wd(a \cos \theta) - Td(4a \cos \theta) = 0$ . Substituting for  $T$  we easily find that  $\cos \theta = \frac{1}{2}$ .

Ex. 4. Show that the force necessary to move a cylinder of radius  $r$  and weight  $W$  up a plane inclined at angle  $\alpha$  to the horizon by a crowbar of length  $l$ , inclined at  $\beta$  to the horizon, is  $\frac{Wr}{l} \cdot \frac{\sin \alpha}{1 + \cos(\alpha + \beta)}$ . [Math. Tripos, 1874.]

Ex. 5. A smooth rod passes through a smooth ring at the focus of an ellipse whose major axis is horizontal, and rests with its lower end on the quadrant of the curve which is furthest removed from the focus. Show that its length must be at least  $\frac{3}{2}a + \frac{1}{2}a\sqrt{(1 + 8e^2)}$ , where  $a$  is the semi-major axis and  $e$  the eccentricity. [Math. Tripos, 1883.]

Ex. 6. An isosceles triangular lamina with its plane vertical rests vertex downwards between two smooth pegs in the same horizontal line; show that there will be equilibrium if the base make an angle  $\sin^{-1}(\cos^2 \alpha)$  with the vertical;  $2a$  being the vertical angle of the lamina, and the length of the base being three times the distance between the pegs. [Math. Tripos, 1881.]

Ex. 7. Three rigid rods  $AB, BC, CD$ , each of length  $2a$ , are smoothly jointed at  $B, C$ . The system is placed so that the rods  $AB, CD$  are in contact with two smooth pegs distant  $2c$  apart in the same horizontal line, and the rods  $AB, CD$  make equal angles  $\alpha$  with the horizon. Prove that the tension of a string in  $AD$  which will maintain this configuration is  $\frac{1}{2}W \operatorname{cosec} \alpha \sec^2 \alpha \{3c/a - (3 + 2 \cos^3 \alpha)\}$ , where  $W$  is the weight of either rod. [St John's Coll., 1890.]

Ex. 8. Four rods, equal and uniform, rest in a vertical plane in the form of a square with a diagonal vertical and the two upper rods resting on two smooth pegs in a horizontal line. Show that the pegs must be at the middle points of the rods, and find the actions at the hinges. [Coll. Ex., 1884.]

Ex. 9. Three equal and similar uniform heavy rods  $AB, BC, CD$ , freely jointed at  $B$  and  $C$ , have small smooth weightless rings attached to them at  $A$  and  $D$ : the rings slide on a smooth parabolic wire, whose axis is vertical and vertex upwards, and whose latus rectum is half the sum of the lengths of the three rods: prove that in the position of equilibrium the inclination  $\theta$  of  $AB$  or  $CD$  to the vertical is given by the equation  $\cos \theta - \sin \theta + \sin 2\theta = 0$ . [Coll. Ex., 1881.]

Ex. 10. A smooth hemispherical bowl of radius  $r$  is fixed with its rim horizontal. A uniform heavy rectangle  $ABCD$  rests with two points  $A, B$  on the internal surface of the bowl, and its sides  $AD, BC$  resting on, and reaching beyond, the edge of the bowl. If  $\theta$  be its inclination to the horizontal, show that

$$4(r^2 - b^2) \cos^2 2\theta - a^2 \cos^2 \theta = 0,$$

where  $AB = 2b, BC = 2a$ .

[Coll. Ex., 1891.]

Ex. 11.  $n$  equal uniform rods, each of weight  $W'$  and length  $l$ , are jointed so as to form symmetrical generators of a cone whose semi-vertical angle is  $\alpha$ , the joint being at the vertex of the cone. The rods are placed with their other ends in contact with the interior of a sphere whose radius is  $r$ , so that the axis of the cone is vertical, and a weight  $W$  is hung on at the joint. Show that

$$l^2 (3n^2 W'^2 + 4n W' W) \cos^2 \alpha = (r^2 - l^2) (n W' + 2W)^2,$$

and find the action at the joint on each rod.

[Coll. Ex., 1884.]

Ex. 12. A conical tent resting on a smooth floor is made of an indefinitely great number of equal isosceles triangular elements hinged at the vertex, and kept in shape by a heavy circular ring placed on it as a necklace. Show that in equilibrium the semi-vertical angle of the cone is  $\sin^{-1} \left\{ \frac{r}{h} \left( \frac{3W'}{W + 3W'} \right) \right\}^{\frac{1}{3}}$ , where  $W, W'$  are respectively the weights of the cone and the ring and  $r, h$  are in like manner the radius of the ring and the slant side of the cone.

[St John's Coll., 1885.]

Ex. 13. A smooth fixed sphere supports a zone of very small equal smooth spherical particles, and the whole is prevented from slipping off the sphere by an elastic ring occupying a horizontal circle of angular radius  $\alpha$ . Show that in the position of equilibrium the tension of the band is  $T$ , where  $2\pi T = W \tan \alpha$ , and  $W$  is the whole weight of the ring and particles together.

[St John's Coll., 1885.]

It may be assumed that the centre of gravity of such a zone is half way between the bounding planes.

### *The work function.*

**206. Coordinates of a system.** Our general object in statics is to find the positions of equilibrium of a system. To solve this problem we require some quantities which when given will determine the position of the system in space. Thus the position of a particle in geometry of two dimensions is defined when we know its coordinates  $x, y$ . In the same way if a body is free to move in the plane of  $xy$ , its position is fixed when we know the coordinates  $x, y$  of some point in it and also the angle  $\theta$  some straight line fixed in the body makes with the axis of  $x$ . These three quantities, viz.  $x, y$  and  $\theta$ , are called the coordinates of the body.

If the body is in space we define its position by giving (1) the coordinates  $x, y, z$  of some point  $A$  fixed in the body, (2) the two angles some straight line  $AB$  fixed in the body makes with the axes of  $x$  and  $y$ . If no more than this is given, the position of the body is not fixed, for it could be turned round  $AB$  as an axis. We

therefore require (3) the angle some plane drawn through  $AB$  and fixed in the body makes with some plane fixed in space. These six quantities, or any other six which fix the place of the body, are called its coordinates.

If the body be under constraint the case is a little altered. Thus suppose the extremities of a rod of given length are constrained to rest on two given curves in a vertical plane; its position is defined simply by its inclination to the horizon or by the abscissa of one extremity. Either of these, or any other quantity which defines the position of the rod, is called its coordinate.

207. In the general case of a system of bodies, *any quantities which, when given, determine the positions of all the members of the system are called the coordinates of that system*. Just as the Cartesian coordinates of a point are connected by one or more equations when the point is constrained to lie on a given surface or curve, so the coordinates of a system are connected by equations when the system is subject to constraints. By help of these equations we can eliminate as many coordinates as there are equations, and thus make the position of the system depend on a smaller number of coordinates. There being now no equations of constraint, these remaining coordinates are independent of each other.

Let us suppose that the system is referred to independent coordinates. Since each may be varied without altering the others, there are as many ways of moving the system as there are coordinates. Any *small* displacement, indicated by varying simultaneously several coordinates, may be *constructed* by varying first one of the coordinates and then another, and so on. *The number of independent coordinates is therefore called the number of degrees of freedom of the system*.

208. **The work function.** Let a system of bodies be placed in any position, and let it receive any indefinitely small displacement which the constraints imposed on the system permit it to take. Let  $X, Y, Z$  be the components of any force  $P$ , and let  $(xyz)$  be the rectangular Cartesian coordinates of its point of application. The work of  $P$  is the same as that of its components, so that the general expression for the work is

$$\Sigma P dp = \Sigma (X dx + Y dy + Z dz) \dots \dots \dots (1),$$

where the  $\Sigma$  implies summation for all the forces of the system.

Let the independent coordinates of the system be  $\theta, \phi, \psi$  &c.

Then since these determine its position, the coordinates  $x, y, z$  of every point of each body can be expressed in terms of  $\theta, \phi$  &c. Thus  $x, y, z$  and  $X, Y, Z$  are all known functions of  $\theta, \phi$  &c. Substituting, the equation (1) takes the form

$$\Sigma P dp = \Theta d\theta + \Phi d\phi + \&c. \dots\dots\dots(2),$$

where  $\Theta, \Phi$  &c. are all known functions of the coordinates  $\theta, \phi$  &c.

**209.** *The coefficients  $\Theta, \Phi$ , &c. have sometimes an elementary statical meaning.*

Suppose for example that the change in the coordinate  $\theta$  (the others remaining constant) had the effect of turning the body about some straight line through the angle  $d\theta$ . Then  $\Theta d\theta$  is the work of the forces when this displacement is given to the body. But, by Art. 203, this work is  $Md\theta$ , where  $M$  is the moment. It follows that  $\Theta$  is the moment of the forces about the straight line.

Again, suppose that the change of some abscissa  $\phi$  had the effect of moving the body parallel to the axis of  $x$ , then by the same article,  $\phi$  is the resolved part of the forces parallel to that axis.

**210.** In most cases *the expression for the work is found to be a perfect differential of some quantity which we may call  $W$ .* For example, suppose the force  $P$  which acts on the point  $(xyz)$  to be due to the repulsion of some centre of force  $C$ , i.e. let  $P$  be a force whose line of action always passes through a point  $C$  fixed in space. If  $r$  be the distance from  $C$  to the point of application, the work of such a force for any small displacement is  $Pdr$ . If then the magnitude of  $P$  is some function of the distance  $r$ , the part contributed by such a central force to the expression  $\Sigma P dp$  is a perfect differential.

To take another case, let a force  $T$  acting between two points  $A, A'$  which move with the system be caused by such an elastic string as that described in Art. 197 or in any other way, so only that the force is some function of the distance between  $A$  and  $A'$ . The work of such a force is  $\pm Tdr$ , and as  $T$  is a function of  $r$ , this again is a perfect differential.

The system may be under the action of a variety of central forces, attracting many points of the system; or again there may be any number of actions between different sets of points, yet in all these cases *the share contributed by each force to the virtual work is a perfect differential.*

These two typical cases represent the forces which in most cases act on the system. The external forces are generally central forces, and the internal forces either do not appear in the equation

of virtual work or appear as forces between one point and another such as those just described.

211. Since the expression (2) in Art. 208 represents the work of the forces due to any general small displacement, the integral of that expression when taken between any limits is the work of the forces as the system makes a finite displacement, i.e. as the system moves from any position I. to another II. The lower limit of the integral is found by giving the coordinates  $\theta$ ,  $\phi$  &c. their values in the position I., and the upper limit by giving the same coordinates their values in the position II.

When the expression (2) is a perfect differential, this integration can be effected without knowing the route by which the system travels from the one position to the other. The integral  $W$  is a function of the upper and lower limits, and will thus depend on the initial and final position of the system and not on any intermediate position. It follows that *the work due to a displacement from one given position to another is the same, whatever route is taken by the system, provided always none of the geometrical constraints are violated.*

*When the forces are such that the expression  $\Sigma Pdp$  is a perfect differential, they are said to form a conservative system.*

Suppose we select any one position of the system of bodies as a standard, and let this position be defined by the values of the coordinates  $\theta = \theta_1$ ,  $\phi = \phi_1$ , &c. Then *taking this standard position as the lower limit of the integral* and any general position as the upper limit, we have

$$W = \int \Sigma Pdp = F(\theta, \phi, \&c.) - F(\theta_1, \phi_1, \&c.);$$

when it is not necessary to make an immediate choice of a standard position we write the integral in its indefinite form, viz.

$$W = F(\theta, \phi, \&c.) + C.$$

The function  $W$ , particularly when used in the indefinite form, is often called the *force function*, or *work function*.

Sometimes *the upper limit is made the standard position* and the general position the lower limit. If this standard is determined by the values  $\theta = \theta_2$ ,  $\phi = \phi_2$ , &c.; the integral becomes

$$V = F(\theta_2, \phi_2, \&c.) - F(\theta, \phi, \&c.).$$

This is usually called *the potential energy of the forces with reference to the position defined by  $\theta = \theta_2$ ,  $\phi = \phi_2$ , &c.*

If the two standards of reference were identical, we should have  $W = -V$ . But both these standards are seldom used in the same problem. In every case that standard of reference is generally chosen which is most suitable to the particular problem under discussion. We notice that  $W + V$  is the work of the forces as the system moves along any route from the position  $(\theta_1, \phi_1, \&c.)$  to the position  $(\theta_2, \phi_2, \&c.)$ , and these being fixed, the sum is constant for all positions of the system of bodies.

**212. Maximum and Minimum.** Suppose the system to be in a position of equilibrium. We then have  $dW = 0$  for every virtual displacement, so that  $W$  is a maximum, a minimum, or stationary. The last alternative represents the case in which the evanescence of the first differential coefficients does not indicate a true maximum or minimum.

We have therefore another method of finding the positions of equilibrium of a system. We regard the work function as a known function of the coordinates,  $\theta, \phi, \&c.$  of the system, say

$$W = F(\theta, \phi, \dots) + C.$$

To find the positions of equilibrium we use any of the rules given in the differential calculus to find the values of  $\theta, \phi, \&c.$  which make  $W$  a maximum or minimum.

**213.** If the coordinates  $\theta, \phi, \&c.$  are all independent, we make the differential coefficient of  $W$  with regard to each of the variables equal to zero. This is equivalent to giving the system the geometrical displacements indicated by varying  $\theta, \phi, \&c.$  in turn, and equating the virtual work in each case to zero. *But the process is analytical instead of geometrical, and this has sometimes great advantages.*

When we cannot express the position of the system by independent coordinates, we may yet reduce the problem to the solution of equations by using Lagrange's method of indeterminate multipliers. Let the  $n$  coordinates  $\theta_1, \theta_2, \&c.$  be connected by the  $m$  geometrical relations

$$f_1(\theta_1, \theta_2, \&c.) = 0, \quad f_2(\theta_1, \theta_2, \&c.) = 0, \quad \&c. = 0,$$

so that  $n - m$  of the coordinates are independent. Differentiating and using the  $m$  multipliers  $\lambda_1, \lambda_2, \&c.$  we have

$$\Sigma \left( \frac{dW}{d\theta} + \lambda_1 \frac{df_1}{d\theta} + \lambda_2 \frac{df_2}{d\theta} + \dots \right) d\theta = 0,$$

where  $\Sigma$  implies summation for  $\theta_1, \theta_2, \&c.$  Since there are  $m$  multipliers at our disposal we choose these so that the coefficients of the differentials of the dependent coordinates are zero. The remaining  $\theta$ 's being independent we can make each vary separately and it then follows from the equation that the corresponding coefficient is zero. The coefficient of every  $d\theta$  being zero, we obtain  $n$  equations of the form

$$\frac{dW}{d\theta} + \lambda_1 \frac{df_1}{d\theta} + \lambda_2 \frac{df_2}{d\theta} + \dots = 0.$$

Joining these to the  $m$  given geometrical relations we have  $m + n$  equations to find the  $n$  coordinates and the  $m$  multipliers.



**214. Stable and Unstable equilibrium.** It should be noticed that it is necessary and sufficient for equilibrium that the work function  $W$  is a maximum, a minimum, or stationary. There is however an important distinction between these cases.

*Suppose the system is in equilibrium in such a position that  $W$  is a true maximum, i.e.  $W$  is decreased if the system is moved into any neighbouring position which is consistent with the constraints. Let the system be actually placed at rest in any one of these neighbouring positions. Not being in equilibrium in this new position it will begin to move. By Art. 200 it must so move that the initial work of the forces is positive, i.e. it must so move that  $W$  increases. The system therefore tends to approach closer to its original position of equilibrium. The original position is therefore said to be stable.*

*Suppose next the system is in equilibrium in such a position that  $W$  is a true minimum, i.e.  $W$  is increased if the system is moved into any neighbouring position. Let the system be placed at rest in one of these neighbouring positions, then, by the same reasoning as before, it will begin to move on some path which will take it further off from its original position of equilibrium. The equilibrium is then said to be unstable.*

*Lastly, suppose the system is in equilibrium in such a position that  $W$  is neither a true maximum nor a true minimum, i.e.  $W$  is decreased when the system is moved into some neighbouring positions and increased when the system is moved into some others. By the same reasoning as in the two preceding cases the equilibrium is stable for some displacements and unstable for others. According to the definition given in Art. 75 this state of equilibrium is to be regarded as on the whole unstable.*

**215.** We have only considered how the system *begins to move*, and not whether it may afterwards approach or recede from the position of equilibrium. As explained in Art. 75, this is a dynamical problem. The general result however agrees with what has been proved above.

**216.** Instead of using the work function we may use the potential energy. Since their sum  $W + V$  is constant, the general results are just reversed. When the system is placed at rest in any position other than one of equilibrium, it *begins to move so*

that the potential energy decreases. In a position of equilibrium the potential energy is a maximum, a minimum, or stationary. The equilibrium is *stable or unstable according as the potential energy is a true minimum or maximum.*

217. We have supposed in what precedes that none of the neighbouring positions are also positions of equilibrium. It is of course possible that  $W$  should be constant for two consecutive positions of the system of bodies, and yet (say) greater than when the system is moved into any other neighbouring position. In such a case the equilibrium is *neutral* for the displacement from one of the consecutive positions to the other and stable for all other displacements. Various cases may occur. For example, the equilibrium may be neutral for more than one or for all displacements from a given position of equilibrium; or again  $W$  may be constant for all positions defined by some relations between the coordinates, and yet (say) a maximum for all displacements from this locus. We then have a locus of positions of equilibrium, each of which is stable for all displacements which do not move the system along the locus.

In a system with two coordinates  $\theta, \phi$ , we could regard  $W$  as the ordinate of a surface whose  $x$  and  $y$  coordinates are  $\theta$  and  $\phi$ . Every geometrical peculiarity connected with the maximum and minimum ordinates of such a surface has a corresponding statical peculiarity in the positions of equilibrium of the system.

218. **Altitude of the centre of gravity a maximum or minimum.** There is one important application of the theorem on virtual work of which much use is made. Let gravity be the only external force acting on the system. Let  $z_1, z_2$  &c. be the altitudes above any fixed horizontal plane of the several heavy particles, and  $\bar{z}$  the altitude of their centre of gravity. If  $m_1, m_2$  &c. be the masses of these particles, we have  $\bar{z}\Sigma m = \Sigma mz$ . If  $g$  be a constant, so that  $mg$  represents the weight of the mass  $m$ , the virtual work of the weights is

$$dW = -\Sigma mgdz = -g\Sigma md\bar{z}.$$

The work function is therefore  $W = -\bar{z}g\Sigma m + C$ .

This is a true maximum or a true minimum, according as  $\bar{z}$  is at the least or greatest height.

We deduce the following theorem. *Let a system of bodies be under the influence of no forces but their weights, together with such*

mutual reactions as do not appear in the equation of virtual work, and let it be supported by frictionless reactions with other fixed surfaces, or in some other way by forces which do not appear in the equation of virtual work; the possible positions of equilibrium may be found by making the altitude of the centre of gravity of the system above any fixed horizontal plane a maximum, a minimum, or stationary. The equilibrium will be stable or unstable according as the altitude of the centre of gravity is or is not a true minimum.

**219. Alternation of stable and unstable positions.** Suppose the constraints are such that the system moves with one degree of freedom. Then as the system moves through space the centre of gravity will describe some definite curve. The positions in which the ordinate is a true maximum and a true minimum must evidently occur alternately. It follows that the truly stable and truly unstable positions of equilibrium occur alternately.

**220. Analytical method of determining the stability of a system.** To show how this theorem may be used to find positions of equilibrium in an analytical manner, let us suppose, as an example, that the system has one degree of freedom. We first choose some convenient quantity by which the position of the system is fixed, and which is therefore called its coordinate. Let this be called  $\theta$ . Then the value of  $\theta$  when the system is in equilibrium is the quantity to be found. Let  $\bar{z}$  be the altitude of the centre of gravity of the system above some fixed horizontal plane. From the geometry of the question we now express  $\bar{z}$  in terms of  $\theta$ . The required value of  $\theta$  is then found by making  $d\bar{z}/d\theta = 0$ . To determine whether the equilibrium is stable or unstable, we differentiate again and find  $d^2\bar{z}/d\theta^2$ . If this second differential coefficient is positive, when  $\theta$  has the value just found, the equilibrium is stable. If negative, the equilibrium is unstable. If zero we must examine the third and higher differential coefficients of  $\bar{z}$ , following the rules given in the differential calculus to discriminate whether a function of one independent variable is a maximum or minimum.


If the coordinate  $\theta$  cannot vary from  $\theta = -\infty$  to  $\theta = +\infty$ , it may itself have maxima and minima. It must be remembered that these values of  $\theta$  may lead to maxima and minima values of  $\bar{z}$  other than those given by the ordinary theory in the differential calculus.

**221. Examples.** Ex. 1. A uniform heavy rod  $AB$  rests against a smooth vertical wall and over a smooth peg  $C$ . Find the position of equilibrium, and determine whether it is stable or unstable.

Let the length of the rod be  $2a$  and let the distance of  $C$  from the wall be  $b$ . Let the inclination of the rod to the wall be  $\theta$ . Taking the horizontal through  $C$  for the axis of  $x$ , we find for the altitude  $z$  of the centre of gravity

$$\begin{aligned} z &= a \cos \theta - b \cot \theta, \\ dz/d\theta &= -a \sin \theta + b (\sin \theta)^{-2}, \\ d^2z/d\theta^2 &= -a \cos \theta - 2b (\sin \theta)^{-3} \cos \theta. \end{aligned}$$

Putting  $dz/d\theta = 0$ , we find that in the position of equilibrium  $\sin^3 \theta = b/a$ . Since  $d^2z/d\theta^2$  is negative the equilibrium is unstable.




Ex. 2. A frustum of a right cone is suspended from a smooth vertical wall by a string, having one extremity attached to a point in its base, and the frustum is in equilibrium with one point of the base in contact with the wall. If the length  $l$  of the string is equal to the diameter of the base and the centre of gravity is at a distance  $kl$  from the base, show that the tangent of the inclination of the string to the vertical is  $\frac{3}{2}k$ . Is the equilibrium stable?

Ex. 3. A body is kept in equilibrium by three forces  $P, Q, R$  acting at certain points  $A, B, C$  in it. When the body is disturbed the forces continue to act at these points parallel to directions fixed in space and their magnitudes are unaltered. If  $a, b, c$  be the distances of  $A, B, C$  from  $O$ , the point of intersection of the three lines of action when the body is in equilibrium, show that the equilibrium is stable, neutral, or unstable, for displacements in the plane of the forces, according as  $Pa + Qb + Rc$  is positive, zero, or negative;  $a, b, c$  being counted positive if drawn from  $O$  in the directions of the forces. [Coll. Ex., 1892.]

An elementary solution of this problem has been given in Art. 77. To use the test given by the principle of work we turn the body round  $O$  through an angle  $\theta$  and place it at rest in this new position. The work done in returning to its old position is  $X \text{ versin } \theta$  where  $X = Pa + Qb + Rc$ . If  $X$  is positive, the equilibrium is stable by Art. 200 or 214.

**222. Ex.** A heavy body can move in a vertical plane in such a manner that two of its points, viz.  $A$  and  $B$ , are constrained to slide, one on each of two equal and similar smooth curves whose equations are respectively  $x = f(y)$  and  $x = -f(y)$ ,  $y$  being vertical. The perpendicular on the chord  $AB$  drawn from the centre of gravity  $G$  bisects  $AB$  in  $E$ . Show how to find the positions of equilibrium, and determine whether the position in which  $AB$  is horizontal is stable or not.



Let  $AB = 2a$ ,  $GE = h$ . Let  $\theta$  be the inclination of  $AB$  to the horizon and  $(xy)$  the coordinates of  $G$ . Then since the points  $A, B$  lie on the given curves we find

$$\left. \begin{aligned} x + h \sin \theta + a \cos \theta &= f(y - h \cos \theta + a \sin \theta) \\ x + h \sin \theta - a \cos \theta &= -f(y - h \cos \theta - a \sin \theta) \end{aligned} \right\} \dots \dots \dots (1).$$

Eliminating  $x$ , we have

$$2a \cos \theta = f(y - h \cos \theta + a \sin \theta) + f(y - h \cos \theta - a \sin \theta) \dots \dots \dots (2).$$

Differentiating this and putting  $dy/d\theta=0$ , we find

$$\left. \begin{aligned} -2a \sin \theta &= f' (y - h \cos \theta + a \sin \theta) (h \sin \theta + a \cos \theta) \\ &+ f'' (y - h \cos \theta - a \sin \theta) (h \sin \theta - a \cos \theta) \end{aligned} \right\} \dots\dots\dots(3).$$

Joining this equation to (1) and (2) we have three equations to find  $x, y, \theta$ . It is clear that (3) is satisfied by  $\theta=0$ , this therefore is one position of equilibrium.

To determine if this horizontal position is stable, we differentiate (2) *twice* to find  $d^2y/d\theta^2$ . We easily find after reduction

$$-\frac{d^2y}{d\theta^2} = \frac{a + a^2 f'' (y - h)}{f' (y - h)} + h \dots\dots\dots(4).$$

The position of equilibrium is stable or unstable according as the right-hand side is negative or positive.

We may obtain a geometrical interpretation for the equation (4) in the following manner. The straight line  $AB$  being in its horizontal position, let  $n$  be the length of the normal to the curve at either  $A$  or  $B$  intercepted between the curve and the axis of  $y$ . Let  $\rho$  be the radius of curvature at  $A$  or  $B$ , estimated positive when measured from the curve in the direction of  $n$ , and let  $\psi$  be the inclination of the tangent at  $A$  or  $B$  to the axis of  $y$ . We know by the differential calculus that if  $x=f(y)$  be the equation to a curve,  $\tan \psi=f'(y)$ , while  $n$  and  $\rho$  are given by

$$n = x \{1 + (f'(y))^2\}^{\frac{1}{2}}, \quad \rho = \frac{\{1 + (f'(y))^2\}^{\frac{3}{2}}}{-f''(y)};$$

remembering that  $a$  and  $y-h$  are the equilibrium coordinates of  $A$  we find

$$\frac{d^2y}{d\theta^2} = \frac{n^3 - a^2 \rho}{a \rho \tan \psi} - h \dots\dots\dots(5).$$

The horizontal position of equilibrium is therefore stable or unstable according as the right-hand side of this equation is positive or negative.

If in the position of equilibrium  $d^2y/d\theta^2$  should be zero, the equilibrium is said to be neutral to a first approximation. We must then continue our differentiations of (2) to ascertain if  $y$  is a true maximum or minimum, or neither. We find that  $d^3y/d\theta^3=0$ , and

$$-\frac{d^4y}{d\theta^4} = \frac{-a + (3h^2 - 4a^2) f'' (y - h) + 6a^2 h f''' (y - h) + a^4 f'''' (y - h)}{f' (y - h)} - h.$$

The equilibrium is therefore stable or unstable according as the right-hand side is negative or positive. If this again vanish we proceed to higher differential coefficients.

**223.** Ex. 1. A prism whose cross section is an equilateral triangle rests with two edges on smooth planes inclined at angles  $\alpha, \beta$  to the horizon. If  $\theta$  be the angle which the plane containing these edges makes with the vertical, show that

$$\tan \theta = \frac{2\sqrt{3} \sin \alpha \sin \beta + \sin (\alpha + \beta)}{\sqrt{3} \sin (\alpha - \beta)}. \quad [\text{Coll. Ex., 1889.}]$$

Ex. 2. The form of a bowl of revolution is such that every rod resting horizontally in it is in neutral equilibrium to a first approximation. Show that the differential equation to the generating curve is  $(dx/dy)^2 = 2 \log a/x$  where  $y$  is vertical. Show also that the equilibrium is stable or unstable according as the length of the rod is less or greater than  $2a/e^{\frac{1}{2}}$ , where  $e$  is the base of Napier's logarithms.

Ex. 3. A uniform square board is capable of motion in a vertical plane about a hinge at one of its angular points; a string attached to one of the nearest angular

points, and passing over a pulley vertically above the hinge at a distance from it equal to a side of the square supports a weight whose ratio to the weight of the board is  $1 : \sqrt{2}$ . Find the positions of equilibrium, and determine whether they are respectively stable or unstable. [Math. Tripos, 1855.]

Ex. 4. The extremities of a rod without weight are capable of sliding on a smooth fixed vertical wire bent into the form of a circle. A weight is suspended from the extremities of the rod by two strings, which pass through a small smooth fixed ring, vertically below the centre of the circle. Show that the weight will be in stable equilibrium when the rod passes through the middle point of the polar of the ring with respect to the circle. [Math. Tripos, 1859.]

Ex. 5. A uniform regular tetrahedron has three corners in contact with the interior of a fixed hemispherical bowl of such magnitude that the completed sphere would circumscribe the tetrahedron; prove that every position is one of equilibrium. If  $P, Q, R$  be the pressures on the bowl, and  $W$  the weight of the tetrahedron, prove that  $3(P^2 + Q^2 + R^2) - 2(QR + RP + PQ) = 3W^2$ . [Math. Tripos, 1869.]

Ex. 6. A right cone rests with its curved surface in contact with two smooth equal cylinders whose axes are parallel, in the same horizontal plane, and distant  $d$  apart, and whose cross sections are circles of radii  $a$ . Show that the cone can rest in equilibrium with its axis in a plane perpendicular to the axes of the cylinders and inclined at an angle  $\theta$  to the vertical given by  $4d \cos \theta = 3r \cos^2 \alpha + 4a \cos \alpha$ , where  $2\alpha$  is the vertical angle of the cone and  $r$  is the radius of its base; and determine whether the position is one of stable equilibrium. [Math. Tripos, 1890.]

Ex. 7. A conical plug of height  $h$  and semi-vertical angle  $\alpha$  is at rest in a circular hole of radius  $a$ . Show that the vertical position of equilibrium is one of stability or of instability according as  $16a$  is greater or less than  $3h \sin 2\alpha$ .

[St John's Coll., 1887.]

**224.** Ex. One end  $A$  of a straight beam  $AB$  rests against a smooth vertical wall, and the other  $B$  rests on an unknown curve. If  $l$  be the length of the beam,  $h$  the altitude of the centre of gravity, find the form of the curve that the relation  $4ch - l^2 = c^2$  may hold in the position of equilibrium whatever values  $l$  and  $h$  may have. [Boole's problem.]

Let  $(0, y')$   $(x, y)$  be the coordinates of  $A$  and  $B$ . Then

$$2h = y + y' \dots (1), \quad x^2 + 4(y - h)^2 = l^2 \dots (2).$$

We notice that a curve could be found such that a rod of given length  $l$  could rest on it in equilibrium in the manner described in the question. Such a curve is found by making the altitude  $h$  constant.

The curve is therefore the ellipse (2) where  $h$  and  $l$  have any constant values which satisfy the given relation. The envelope of all these ellipses must also satisfy the mechanical problem, because the envelope touches every ellipse and the reaction will suit either curve. The envelope found in the usual way is the parabola  $x^2 = 4cy$ .

We might find this parabola without using the theory of envelopes. Since in equilibrium  $dh = 0$  when  $l$  is constant, we have by differentiating (2)


$$x dx + 4(y - h) dy = 0.$$

But (2) is satisfied when  $h$  and  $l$  both vary;  $\therefore x dx + 4(y - h)(dy - dh) = l dl$ , also since  $4ch - l^2 = c^2$ ,  $2cdh = l dl$ .

Eliminating the differentials we find  $2(h - y) = c$ . Joining this to the given relation we can express  $h$  and  $l$  in terms of  $y$ . Substituting these in (2) the required relation between  $x$  and  $y$  is found. It reduces to the parabola already found.

**225. Ex.** A heavy body can move in a vertical plane in such a manner that

two straight lines  $CA$ ,  $CB$  fixed in it are constrained to slide on two equal and similar curves fixed in space. The equations to the curve are  $p=f(\omega)$  and  $q=f(\omega')$ , where  $p$ ,  $q$  are the perpendiculars drawn from the origin on the tangents, and  $\omega$ ,  $\omega'$  are the angles which these perpendiculars make with opposite sides of the axis of  $x$ ,  $y$  being vertical as before. The centre of gravity  $G$  lies in the bisector of the angle  $C$  at a distance  $h$  from either of the straight lines  $CA$ ,  $CB$ . Show how to find the inclination of  $CG$  to the vertical when the body is in equilibrium, and determine whether the position in which  $CG$  is vertical is stable or unstable.



Let  $\alpha$  be the angle  $CG$  makes with either  $CA$  or  $CB$ , and  $\theta$  the inclination of  $CG$  to the vertical. Let  $y$  be the altitude of  $G$ . We first show by geometrical considerations that  $y \sin 2\alpha = (p-h) \cos(\theta-\alpha) + (q-h) \cos(\theta+\alpha)$ .

Remembering that  $p=f(\theta+\alpha)$  and  $q=f(\alpha-\theta)$  we have, by equating  $dy/d\theta$  to zero, an equation to find  $\theta$ .

In the position in which  $CG$  is vertical  $\theta=0$ , hence  $p=q$ . Differentiating a second time, we have

$$\frac{\sin 2\alpha}{2} \frac{d^2y}{d\theta^2} = \left( h - p + \frac{d^2p}{d\theta^2} \right) \cos \alpha + 2 \frac{dp}{d\theta} \sin \alpha.$$

We may obtain a geometrical interpretation of this value of  $d^2y/d\theta^2$ . The body being in the position in which  $CG$  is vertical, the straight line  $CA$  will touch one of the curves in some point  $P$ . Let  $\rho$  be the radius of curvature of the curve at  $P$ ,  $\xi$  the horizontal abscissa of  $P$ . We may then show that

$$\sin \alpha \frac{d^2y}{d\theta^2} = h + \rho - 2\xi \sec \alpha.$$

The equilibrium is stable or unstable according as the value of  $d^2y/d\theta^2$  is positive or negative. If the value is zero, we must differentiate a second time.

**226. Examples of atoms.** Some good examples of the method of using the work function to determine questions of stability are supplied by Boscovich's theory of atoms. Almost all the following results are enunciated by Sir W. Thomson in an interesting paper contributed to *Nature*, October 1889.

It is enough for our present purpose to say that Boscovich supposed matter to consist of atoms or points between which there is repulsion at the smallest distance, attraction at greater distances, repulsion at still greater distances, and so on, ending with attraction according to the Newtonian law for all distances for which this law has been proved. Boscovich suggested numerous transitions from attraction to repulsion and vice versa, but for the sake of simplicity, we shall here consider problems which involve only one change from repulsion to attraction.

Suppose then that the mutual force between two atoms is repulsive when the distance between them is less than  $p$ , zero when it is equal to  $p$ , and attractive when greater than  $p$ . With this supposition we shall consider the stability of the equilibrium of some groups of atoms.

**227. Ex. 1.** Three particles, whose masses are  $m, m', m''$  repel each other so that the force between  $m$  and  $m'$  is  $F = -mm'(r-p)^{n-1}$  where  $n$  is an even integer. The particles are in equilibrium when placed at the corners of an equilateral triangle each of whose sides is equal to  $p$ . Show that the equilibrium is stable.

The term of the work function  $W$  corresponding to  $F$  is  $\int F dr = -\frac{mm'}{n}(r-p)^n$ .

When the atoms are displaced, let the three sides of the triangle be  $p+x, p+y, p+z$ . We have by Art. 211,  $n(C-W) = m'm''x^n + m''m'y^n + mn'z^n$ .

The equilibrium is stable or unstable according as  $W$  is a maximum or a minimum, i.e. according as the right-hand side is a minimum or a maximum. But, since  $n$  is even, the right-hand side is a minimum when  $x, y, z$  are each zero; for these values make the right-hand side zero and all others make it greater than zero. The equilibrium is therefore stable.

We have taken the law of force to be a single power of  $r-p$ , but it is clear that the same reasoning will apply if the law of force is expressed by several terms with different odd powers. Even greater generality may be given to the law, for it is sufficient that the lowest power should be odd.

In just the same way we may prove that a group of four particles placed at the corners of a regular tetrahedron, each of whose edges is equal to  $p$ , is a stable arrangement.

**Ex. 2.** Three equal atoms  $A, B, C$  are placed in equilibrium in a straight line. Supposing the force of repulsion to be  $F = -\mu(r-p)^{n-1}$ , where  $n$  is even, determine if the configuration is stable or unstable.

It is clear that in the position of equilibrium the distances  $AB, BC$  are each less than the critical distance  $p$ , while  $AC$  is greater than  $p$ . Let  $AB$  and  $BC$  be each equal to  $a$ . As we are only concerned with relative displacements, let  $A$  be fixed. Let  $B', C'$  be the displaced positions of  $B, C$ ; let  $(xy)$  be the coordinates of  $B'$  referred to  $B$ , and  $(x'y')$  those of  $C'$  referred to  $C$ . If  $r = AB'$ , we have

$$r = \{(a+x)^2 + y^2\}^{\frac{1}{2}} = a + x + \frac{y^2}{2a} + \&c.$$

$$\therefore (r-p)^n = (a-p)^n + n(a-p)^{n-1} \left( x + \frac{y^2}{2a} \right) + n \frac{n-1}{2} (a-p)^{n-2} x^2 + \&c.$$

If we replace  $(xy)$  by  $(x'-x, y'-y)$ , this expression gives the value of  $(r''-p)^n$  where  $r'' = B'C'$ . If instead we replace  $(xy)$  by  $(x'y')$  and write  $2a$  for  $a$ , the expression gives the value of  $(r'-p)^n$ , where  $r' = AC'$ .

Taking all these expressions, we have as before

$$\begin{aligned} \frac{n}{\mu}(C-W) &= (r-p)^n + (r'-p)^n + (r''-p)^n \\ &= n(a-p)^{n-1} \left\{ x' + \frac{(y-y')^2 + y'^2}{2a} \right\} + n \frac{n-1}{2} (a-p)^{n-2} \{ x^2 + (x'-x)^2 \} \\ &\quad + n(2a-p)^{n-1} \left\{ x' + \frac{y'^2}{4a} \right\} + n \frac{n-1}{2} (2a-p)^{n-2} x'^2 + \&c., \end{aligned}$$

where all the constant terms have been absorbed into one constant, viz.  $C$ .

To find the position of equilibrium, we make  $W$  a maximum or a minimum, i.e.

we put  $\frac{dW}{dx} = 0, \quad \frac{dW}{dx'} = 0, \quad \frac{dW}{dy} = 0, \quad \frac{dW}{dy'} = 0$ . These give  $(a-p)^{n-1} + (2a-p)^{n-1} = 0$ .



Hence, since  $n-1$  is odd and  $p$  lies between  $a$  and  $2a$ , we find  $-(a-p)=2a-p$  and therefore  $a=\frac{2}{3}p$ . This result might have been more simply obtained by equating the forces on the particle  $A$  due to the repulsion of  $B$  and the attraction of  $C$ .

To distinguish whether  $W$  is a maximum or a minimum, we examine the terms of the second order. We find that those on the right-hand side are

$$-n(p-a)^{n-1} \frac{(2y-y')^2}{4a} + n \frac{n-1}{2} (p-a)^{n-2} \{x^2 + x'^2 + (x'-x)^2\}.$$

It is clear that this expression cannot keep one sign for all values of  $x, y, x', y'$  for the terms with  $(y, y')$  are negative and those with  $(x, x')$  positive. We therefore infer that  $W$  is neither a maximum nor a minimum. The equilibrium is stable for all displacements in which the particles remain in the original straight line. It is unstable for all displacements in which they are moved perpendicular to that straight line. On the whole the equilibrium is unstable.

This method of solution has been adopted in order to show how the rules of the differential calculus may be used in making  $W$  a maximum or minimum. The result may be more simply obtained by displacing one particle perpendicularly to the straight line  $ABC$  and calculating the normal force of repulsion on it. The equilibrium is then seen to be unstable for this displacement.

Ex. 3. Show that the following configurations of four equal atoms are unstable.

- (1) Three atoms at the corners of an equilateral triangle and one at the centre.
- (2) The four atoms at the corners of a square.
- (3) The four atoms in one straight line.

Ex. 4. Three equal particles repelling each other according to the  $n$ th power of the distance are connected together by three equal elastic strings. Find the position of equilibrium and show that it is stable if  $n < p/(p-a)$ , where  $a$  is the unstretched, and  $p$  the stretched length of any string.

**228.** Ex. Three fine rigid bars, coinciding with the diagonals of a regular hexagon, are each freely moveable about their common centre in the plane of the hexagon; six equal particles at the extremities of the bars repel one another with a force varying inversely as any power of the distance. Show that the equilibrium of the system is stable. [Math. Tripos, 1859.]

**229. On Frameworks.** The determination of the forces which act along the rods of a framework supply some good examples of the use of the theory of work. The general method of proceeding may be described as follows. If we remove such of the connecting rods as we may choose, and replace these by forces acting at their extremities, we so loosen the constraints that the framework admits of displacement. The principle of work then gives equations connecting the forces which act on the system but omitting all those reactions which act between the rods not removed. We thus form equations to find the reactions on any one or more rods we choose to select.

**230.** Ex. A framework, consisting of any number of rods, not necessarily in one plane, is acted on by forces at the corners. If  $R$  be the reaction along any rod regarded as positive when in a state of thrust,  $r$  the length of that rod, and if

$X, Y, Z$  be the components of the forces at that corner whose coordinates are  $x, y, z$ , prove that

$$\Sigma Rr + \Sigma (Xx + Yy + Zz) = 0,$$

where the  $\Sigma$  implies summation over the whole framework. Maxwell, *Edinburgh Transactions*, 1872, Vol. 26, p. 14.

Let us remove all the rods and apply the corresponding reactions at particles placed at the corners. We now displace the system by giving it a slight enlargement, so that the displaced figure is similar to the original one. The principle of work gives  $\Sigma Rdr + \Sigma (Xdx + Ydy + Zdz) = 0$ . But, since the figures are similar,  $dr/r = dx/x = \&c$ . Substituting, the result follows at once. As an example of this theorem see Art. 130, Ex. 5.

**231.** When we apply the principle of work to a frame, we have to displace the corners. It will be found convenient to distinguish these displacements by different names.

If the frame is not stiffened by the proper number of rods (Art. 151) the angles may receive finite changes of magnitude without altering the length of any side. When this is the case any change is called a *normal or ordinary deformation*. The actual displacement given may be infinitely small, but in a normal deformation the change of angle may be increased until it becomes finite.

If the framework is stiffened by the proper number of rods, the connecting rods may possibly be so arranged that the angles can receive infinitely small changes in magnitude, but not finite changes, without altering the length of any side (Art. 151). Such a displacement is called an *abnormal or singular deformation*. This is an imaginary displacement, which could be a real one only when small quantities of the second order are neglected.

If the frame is stiffened by only just the proper number of rods so that there are no relations between the lengths of the rods, any side of the frame can be increased in length without breaking its connection with the others. Such a frame is said to be *simply stiff or freely dilatable*.

If there are more rods than are necessary to stiffen the frame, so that there are relations between the lengths of the sides, one rod cannot be altered in length without altering some of the others. Such a frame is said to be *indilatable or dilatable under one or more conditions*.

These names are due partly to Maxwell, *Phil. Mag.* 1864, and partly to M. Lévy, *Statique Graphique*.

**232.** A simply stiff frame of rods connected by smooth hinges at the corners  $A_1, A_2$  &c. is in equilibrium under the action of any forces.

*It is required to find the stress along any side  $A_1A_2$  which is not acted on by the external forces.*

Let  $R_{12}$  be the reaction along this rod, and let it be regarded as positive when the rod is in a state of thrust. Let  $l_{12}$  be the length of the side.

Since the external forces are in equilibrium the work due to any virtual displacement of the frame which does not alter the length of any side is zero. Let us remove the rod  $A_1A_2$  from the frame and replace its effects by applying to the particles at its extremities forces each equal to  $R_{12}$ . If we now fix in space any other side, say the adjoining side  $A_1A_n$ , the polygon will have one degree of freedom. It may be deformed, and each corner will describe a curve fixed in space. Supposing a small deformation given, let the length  $l_{12}$  be increased by  $dl_{12}$ , and let  $dW$  be the work of the external forces. Then, since the other reactions do not put in any appearance in the equation of work, we have

$$R_{12}dl_{12} + dW = 0 \dots\dots\dots(1).$$

If in addition to this deformation we give the side  $A_1A_n$  any virtual displacement, the frame moving with it as a whole, the work  $dW$  is not altered. We see therefore that the mode of displacement is immaterial. It is not even necessary to remove the side  $l_{12}$ , we simply let its length increase by  $dl_{12}$ . If  $dW$  be the resulting work of the forces, the reaction  $R_{12}$  is given by

$$R_{12} = - \frac{dW}{dl_{12}} \dots\dots\dots(2).$$

It appears that, *if the length of any rod, not acted on by the external forces, can be increased without undoing the frame the reaction along that rod is determinate.* For example, if there are no external forces acting on the frame, the reaction along any such side is zero.

**233.** If the rod  $A_1A_2$  is acted on by some of the external forces the reactions at the corners  $A_1, A_2$  do not necessarily act along the length of the rod. We may reduce this case to the one already considered in the last article by replacing each of these forces by two parallel forces, one acting at each extremity of the rod. This method has been explained in Art. 134. We may also find the reactions by a more direct process.

Let  $R_{12}, S_{12}$  be the components of the action at the corner  $A_1$  of the rod  $A_1A_2$ , resolved along and perpendicular to the length of the rod. In the same way  $R_{21}, S_{21}$  are the components at the

as positive when the rod is in the state of thrust.

Let the system be so deformed that the length of the side  $A_1A_2$  is increased by  $dL_{12}$ , while the corner  $A_2$  and the direction in space of that side are unaltered. The virtual work of the reactions  $R_{21}$ ,  $S_{21}$  and  $S_{12}$  in this displacement is evidently zero. Let  $dW$  be the virtual work of the external forces which act on the system, excluding the rod  $A_1A_2$ , then

$$R_{12}dL_{12} + dW = 0.$$

To find the reaction  $S_{12}$  a different displacement must be given to the system. The external forces which act on the rod  $A_1A_2$  having been removed, the remaining external forces are not in equilibrium. The virtual work for a displacement of the frame as a whole is not necessarily zero. Keeping  $A_2$  as before fixed in space and not altering the length  $l_{12}$ , let us turn the frame round an axis perpendicular to the plane containing  $A_2$  and the force  $S_{12}$ . If  $d\theta$  be the angle of displacement and  $dW$  the work of the forces, we have

$$S_{12}d\theta + dW = 0.$$

By giving the frame these two deformations the reactions  $R_{12}$  and  $S_{12}$  at the corner  $A_1$  can be found. If the frame be perfectly free, the deformation necessary to find  $S_{12}$  can always be given. The deformation necessary to find  $R_{12}$  requires that the length of the rod can be altered. It follows that *both these reactions are determinate if the length of the rod  $A_1A_2$  can be altered without destroying the connections of the frame.*

If the frame is subject to any external constraints, these may be replaced by pressures at the points of constraint. When the magnitudes of these pressures have been deduced from the general equations of equilibrium, we may regard the frame as perfectly free and acted on by known forces. The reactions at any corner may then be found as if the frame were free.

It is not meant that in every case exactly these displacements must be given to the system, for these may not suit the geometrical conditions of the problem. Other displacements may recommend themselves by their symmetry or by the ease with which the virtual work due to those displacements can be found. Any two

If the system be in three dimensions, the direction of  $S_{12}$  may be unknown as well as its magnitude. In this case the components of  $S_{12}$  in two convenient directions may be used instead of  $S_{12}$ . Three displacements to supply three equations of virtual work will then be necessary.

**234. Examples.** Ex. 1. Six equal heavy rods, freely hinged at the ends, form a regular hexagon  $ABCDEF$ , which when hung up by the point  $A$  is kept from altering its shape by two light rods  $BF, CE$ . Prove that the thrusts of the rods  $BF, CE$  are as 5 to 1, and find their magnitudes. [Math. T., 1874.]

Let the length of any side be  $2a$ , and let  $\theta$  be the angle which either of the upper sides makes with the vertical.

To find the thrust  $T$  of  $BF$ , we suppose the length of  $BF$  to be slightly increased. The inclinations of  $AB$  and  $AF$  to the vertical are therefore increased by  $d\theta$ . The work of the thrust  $T$  is  $Td(4a \sin \theta)$ . The work of the weights of the two upper rods is  $2Wd(a \cos \theta)$ .

The centre of gravity of each of the four other rods is slightly raised, and the work of their weights is  $4Wd(2a \cos \theta)$ . We have therefore

$$Td(4a \sin \theta) + 2Wd(a \cos \theta) + 4Wd(2a \cos \theta) = 0, \quad \therefore 2T = 5W \tan \theta.$$

To find the thrust  $T'$  of the rod  $CE$ , we suppose the length of  $CE$  to be slightly altered. No work is done by the weights of the four upper rods. The centres of gravity of the two lower rods are however slightly raised. If  $\theta$  be the angle either of the lower rods makes with the vertical, we easily find



$$T'd(4a \sin \theta) + 2Wd(a \cos \theta) = 0, \quad \therefore 2T' = W \tan \theta.$$

The result given in the question follows at once.

Ex. 2. A tetrahedron, formed of six equal uniform heavy rods, freely jointed at their extremities, is suspended from a fixed point by a string attached to the middle point of one of its edges. It is required to find the reactions at the corners.

The tetrahedron is regular, hence the upper and lower rods, viz.  $AB$  and  $CD$ , are horizontal. Let  $L$  and  $M$  be their middle points, then  $LM$  is vertical; let  $LM = z$ . Let  $P, P'$  be the thrusts along these rods and  $w$  the weight of any rod.

Without altering the direction in space of the upper rod, or the position of its middle point, let us increase its length by  $dr$ . Since the transverse reactions at its extremities will do no work in this displacement, the equation of virtual work is



$$Pdr + 4wz + 12zdz = 0 \quad (1)$$

In the same way, if we increase the length of the lower bar by  $dr$  without altering its direction in space or the position of its middle point, the equation of virtual work is

$$P'dr - 4w \cdot \frac{1}{2}dz - wdz + Tdz = 0 \dots\dots\dots$$

where  $T$  is the tension of the string. Since  $T = 6w$ , and the ratio  $dr : dz$  is the same for each rod, these two equations give at once  $P = P'$ .

To find the relation between  $dr$  and  $dz$  we require some geometrical considerations. From the right-angled triangles  $BLC$ ,  $LCM$  we have

$$BC^2 - BL^2 = CL^2 = CM^2 + z^2 \dots\dots\dots$$

In obtaining equation (1), the half side  $BL$  is altered by  $\frac{1}{2}dr$ , the other lengths and  $BC$  being unaltered; we therefore have

$$-BL \cdot dBL = z dz, \quad \therefore dr = -2\sqrt{2}dz.$$

In obtaining (2) the opposite half side is altered by  $\frac{1}{2}dr$ , we therefore have as before  $dr = -2\sqrt{2}dz$ . Substituting these values of  $dr$  in (1) and (2) we find that each of the thrusts  $P$  and  $P'$  is equal to  $\frac{3}{4}\sqrt{2}w$ .

We have now to find the other reactions. Since three rods meet at each corner it is necessary to specify the arrangement of the hinges. We assume that each of the rods which meet at any corner is freely hinged to a weightless particle situated at that corner. Since this particle may afterwards be considered as joined to the extremity of any one of the three rods, we thus include the case in which two rods at any corner are hinged to the third.

The reaction between a particle and any one of the rods which meet it will be a single force. By taking moments for the rod about a vertical drawn through one end, we may show that the reaction at the other end lies in the vertical plane through the rod. The reaction may therefore be obliquely resolved into a component acting along that rod and a vertical force. Let  $Q$  and  $Z$  be the components of the reaction on either of the rods  $AC$ ,  $AD$ ,  $Q$  being positive when it compresses the rod and  $Z$  when acting upwards. In the same way  $Q'$  and  $Z'$  will represent the components of the reaction on either of these rods at their lower extremities.

Let us now lengthen each of the four inclined rods by  $d\rho$ , keeping the upper ends fixed. The equation of virtual work for the lower bar together with the two particles at each end is then

$$4Q'd\rho + 4Z'dz + wdz = 0 \dots\dots\dots$$

Since the rod  $CD$  has here received simply a vertical displacement, this equation might have been obtained by resolving vertically the forces on the rod and equating the sum to zero, Art. 204.

To find the relation between  $d\rho$  and  $dz$  we recur to (3). In obtaining equation (4),  $BC$  is altered by  $d\rho$  while  $BL$  and  $CM$  are unaltered, hence

$$BC \cdot dBC = z dz, \quad \therefore dz = \sqrt{2}d\rho.$$

We therefore have

$$2\sqrt{2}Q' + 4Z' + w = 0 \dots\dots\dots$$

Resolving the forces on the particle at  $C$  in the direction  $CD$ , we find

$$-P' = 2Q' \cos 60^\circ \dots\dots\dots$$

$$T \cdot AB \cdot \left( \frac{1}{BP} + \frac{1}{AQ} + \frac{1}{AB} \right) = W \cos A \cos B \operatorname{cosec} C,$$

$W$  is the weight of the two rods.

[Coll. Exam., 1890.]

4. A frame  $ABCD$  is formed of four light rods, each of length  $a$ , freely joined together; it rests with  $AC$  vertical and the rods  $BC$ ,  $CD$  in contact with frictionless supports  $E$ ,  $F$  in the same horizontal line at a distance  $c$  apart, the rods  $AB$ ,  $AD$  being kept apart by a light rod of length  $b$ . Show that, when a weight  $W$  is placed on the highest joint  $A$ , it produces in  $BD$  a thrust of magnitude  $R$ , where  $R^2 = W^2(2a^2c - b^2)$ . Examine the case when  $b = (2a^2c)^{\frac{1}{2}}$ . [Math. T., 1886.]

5. Four equal rods  $ARB$ ,  $CRD$ ,  $ESB$ ,  $FSD$  form with each other a rhombus  $ABCD$ ;  $A$  and  $C$  are fixed hinges at a distance  $a$  from  $R$ ;  $R$ ,  $B$ ,  $S$  and  $D$  are free joints, and at  $E$  and  $F$  forces, each equal to  $P$ , are applied perpendicular to the rods  $ES$  and  $FD$ . If  $\alpha$  be the angle which the reactions at  $A$  and  $C$  make with  $AC$ ,  $2\theta$  the angle  $ARC$ , and  $b$  a side of the rhombus, show that  $a \cot \alpha = 2(a+b) \tan \theta + a \cot \theta$ .

[Coll. Exam., 1889.]

6. Take  $AC$  as axis of  $x$ , its middle point as origin. Let  $X$ ,  $Y$  be the reactions at  $A$  and  $C$ ;  $x = a \sin \theta$ ,  $y = 2(a+b) \cos \theta$  the coordinates of  $E$ . Increasing the length of  $AC$  without altering its direction in space, or the position of its middle point, we have, by the principle of virtual work,  $Xa \sin \theta + P \sin \theta dy - P \cos \theta dx = 0$ . Also by the condition  $Y + P \sin \theta = 0$ . The result follows at once.

7. Four equal rods  $AB$ ,  $BC$ ,  $CD$ ,  $DA$  are freely jointed at the ends so as to form a square and are suspended by the corner  $A$ . The rods are kept apart by a string without weight joining the middle points of  $AB$ ,  $BC$ . Show that the tension of the string and the reaction at the lowest point  $C$  are respectively  $4W$  and  $5W$ , where  $W$  is the weight of any rod.

8. A succession of  $n$  rhombus figures of equal sides, each being  $b$ , are placed so that they have equal diagonals in a straight line and one angular point common to successive figures, and the extreme sides of the first and last rhombus are produced to meet at points  $A$ ,  $B$ ,  $C$ ,  $D$  respectively. Show that the equal lengths  $a$  in opposite directions to points  $A$ ,  $B$ ,  $C$ ,  $D$  respectively. Consider now all the straight lines in the figure to be rods hinged freely where they meet and having fixed hinges at  $C$  and  $D$ . At  $A$  and  $B$ , the free ends, are applied equal forces perpendicular to the rods; show that the reactions at  $C$  and  $D$  are  $2a \cot \phi$  and  $2(a+nb) \tan \theta + a \cot \theta$ ,  $\theta$  being the angle which the common diagonal makes with any side.

[Coll. Exam., 1889.]

9. A tripod stand is constructed of three equal uniform rods connected by a universal joint at one extremity of each; the whole rests on a smooth horizontal plane and is prevented from collapsing through having the lower extremities connected by strings equal in length to the rods. Find the tensions of the strings. In particular, if a weight  $W$  equal to that of each rod be suspended from this joint, then the tension is  $\frac{5}{3} \sqrt{6}W$ .

[St John's Coll., 1882.]

10. Six uniform rods, each of weight  $W$ , are jointed together to form a regular hexagon, which is hung up from a corner. The two middle rods are connected by a light horizontal rod. Show that, if they rest vertically, the horizontal distance between the points of support is independent of its length. If the horizontal

rod be heavy, and uniform in length and material with the others, show that the ratio is 6 : 1, and that the stress in the horizontal rod is  $\frac{7}{2}W\sqrt{3}$ . Find also the stresses at the joints. [Coll. Exam., 1900.]

**235. Abnormal deformations.** Referring to the general theorem considered in Art. 232 we notice that there is a peculiar case of exception. Let us suppose that the forces which act on the frame are applied at the corners so that the reactions act along the sides of the polygon.

The side  $A_1A_2$  being removed, the polygon may be deformed. The principle of virtual work then gives

$$R_{12}dl_{12} + dW = 0 \dots\dots\dots (1)$$

Supposing the side  $A_nA_1$  to be fixed in space, it is possible when the frame is deformed, that the corner  $A_2$  may begin to move perpendicularly to the side  $A_1A_2$ . In this case  $dl_{12} = 0$ . If the side  $A_nA_1$  is also displaced in any manner, by the frame moving as a whole, the quantity  $dl_{12}$  is unaltered and is therefore still zero. When the rod  $A_1A_2$  is replaced, it is now possible to give the frame a small deformation without altering the length of any side, provided we neglect small quantities of the second order. Since the frame is now stiff, this deformation is of the kind called *abnormal*. Art. 231.

The external forces acting on the frame are in equilibrium, hence their virtual work for every displacement of the frame as a whole is zero. If it be not zero for this abnormal deformation, the reaction  $R_{12}$  must be infinite. But if it be zero the equation (1) becomes nugatory, since both  $dl_{12}$  and  $dW$  are zero. The reaction  $R_{12}$  may now be finite.

In order, then, to deform the frame so that the reaction  $R_{12}$  may do work, we must remove, or lengthen, *two or more sides*. Let these be the given side  $l_{12}$  and any other say  $l_{23}$ . We now have

$$R_{12}dl_{12} + R_{23}dl_{23} + dW = 0 \dots\dots\dots (2)$$

To use this equation we must know the ratio between the corresponding increments of any two sides. The equation (2) may then give the relation between the corresponding reactions. The



Regarding the stiff framework as a general polygon with undetermined angles, we can find as many angles as may be convenient in terms of the sides. We suppose, as an example, that two equations have been found connecting two angles  $\theta_1, \theta_2$  with the sides. Let these be

$$\begin{aligned} f_1(\cos \theta_1, \cos \theta_2, l_{12}, l_{23}, \&c.) &= 0 \\ f_2(\cos \theta_1, \cos \theta_2, l_{12}, l_{23}, \&c.) &= 0 \end{aligned} \quad \dots\dots\dots$$

Since this particular polygon can have a slight deformation without changing the lengths of its sides we must have

$$\frac{df_1}{d\theta_1} d\theta_1 + \frac{df_1}{d\theta_2} d\theta_2 = 0, \quad \frac{df_2}{d\theta_1} d\theta_1 + \frac{df_2}{d\theta_2} d\theta_2 = 0 \dots\dots\dots$$

These give  $d\theta_1 = 0$  and  $d\theta_2 = 0$ , unless the special polygon under consideration is such that the determinant

$$J = \begin{vmatrix} df_1/d\theta_1 & df_1/d\theta_2 \\ df_2/d\theta_1 & df_2/d\theta_2 \end{vmatrix} = 0 \dots\dots\dots$$

If we vary the lengths of the rods, the corresponding changes of the angles are given by

$$\left. \begin{aligned} \frac{df_1}{d\theta_1} d\theta_1 + \frac{df_1}{d\theta_2} d\theta_2 &= - \sum \frac{df_1}{dl} dl \\ \frac{df_2}{d\theta_1} d\theta_1 + \frac{df_2}{d\theta_2} d\theta_2 &= - \sum \frac{df_2}{dl} dl \end{aligned} \right\} \dots\dots\dots$$

Multiplying these equations by the minors of the first row of the determinant  $J$  and adding the results, the left-hand side will vanish. We thus obtain a relation between the increments of length of the rods of the form

$$P_{12}dl_{12} + P_{23}dl_{23} + \dots = 0.$$

This relation must be satisfied by any assumed changes of length of the rods.

**237. Indeterminate tensions.** It is generally convenient to consider these indeterminate reactions apart from the action of external forces. To make this point clear, let us suppose that a set of external forces in all respects the same can produce different sets of internal stress when they act separately on a stiff frame. Then, reversing one set of the external forces and letting them act simultaneously, we have the frame in a self-strained condition with no external forces. If then we can find all the internal stresses when no forces act, we can superimpose them on any set of stresses produced by a given set of forces, to find all the internal stresses of stress consistent with those forces.




body round  $I$ . Let the arc  $II' = ds$ .

Since the angle between the tangents  $II', IJ'$  to the two curves is infinitely small, these curves touch each other at the point  $I$ . *The motion of the body may therefore be constructed by making the second curve roll without sliding on the first, carrying the body with it.* It is also clear that  $ds:d\theta$  is the ratio of the velocity with which the instantaneous centre describes either curve to the angular velocity of the body.

At the beginning of the first element of time let  $P$  be the position of any point of the body, then since  $P$  begins to move in a direction perpendicular to  $PI$ ,  $PI$  is a normal to the path of  $P$ . Let  $P'$  be the position in space of  $P$  at the end of the time  $dt$ ; then the angle  $PIP' = d\theta$ . Since the body now begins to turn round  $I'$ ,  $P'I'$  is a consecutive normal to the path of  $P$ .

If then  $P$  be so placed that the angle  $IP'I'$  is also equal to  $d\theta$ , two consecutive normals to the path of  $P$  will be parallel, and hence the radius of curvature of the path of  $P$  will be infinite. If therefore we describe a circle passing through  $I$  and  $I'$ , so that it contain an angle equal to  $d\theta$ , then *every point of the circumference of this circle is at a point of its path at which the radius of curvature is infinite.* For statical purposes we shall refer to this circle as the *circle of stability*. To construct this circle, we draw



a normal at the instantaneous centre of rotation  $I$  to the path of the point  $P$  in space and measure along this normal a length  $IS = ds/d\theta$ . The circle described on  $IS$  as diameter is the circle of stability.

Let  $G$  be any point of the body not on the circle of stability, and let  $P$  be that point in the straight line  $IG$ , at which the radius of curvature is infinite. As before  $GPI$  is a normal both to the locus of  $G$  and to that of  $P$ . See the figure of the last article. If we now turn the body round  $I$  through an angle  $d\theta$ , the points  $G$  and  $P$  will assume the positions  $G'$  and  $P'$  where the angles  $GIG'$  and  $PIP'$  are each equal to  $d\theta$ , and  $I'P'$  is parallel to  $IPG$ . Also  $G'I'$  is the consecutive normal to the locus of  $G$ ; and if  $G'I'$  intersect  $GI$  in  $O$ ,  $O$  will be the required centre of curvature. We have by similar triangles

$$GP : GI = G'P' : G'I = G'I' : G'O.$$

In the limit the three points,  $P$ ,  $P'$ , and the intersection  $P_1$  of the circle with  $GO$ , coincide. We then have  $R \cdot GP_1 = GI^2$ .

We have therefore the following rule\*; *to find the radius of curvature  $R$  of the path of  $G$ , let  $GI$  intersect the circle of stability in  $P_1$ ; then  $R \cdot GP_1 = GI^2$ .*

In the standard figure, lines drawn from  $G$  towards  $I$  have been taken as positive; it follows that  $R$  is positive or negative according as  $GP$  is positive or negative. We therefore infer that *the path of every point  $G$  is concave or convex towards  $I$  according as  $G$  lies without or within the circle of stability.*

**241. Statical rule.** In a position of equilibrium the tangent to the path of the centre of gravity  $G$  is horizontal, hence the position of equilibrium is such that  $IG$  is vertical. The equilibrium is stable or unstable according as the altitude of the centre of gravity is a minimum or a maximum, i.e. according as the concavity of the path is upwards or downwards. But this point is settled at once by the rule that the path of  $G$  is concave towards  $I$  except when  $G$  lies within the circle of stability.


**242. Ex. 1.** Two points  $A, B$  of a moving body describe known curves. Show how to find (1) the position of the instantaneous centre  $I$ , (2) the circle of stability.

\* This formula for  $R$  is practically equivalent to that given by Abel Transon in *Liouville's Journal*, 1845, x. p. 148, though he uses the diameter  $IS$  of the circle instead of the circle itself. His object is to find the radius of curvature of a roulette. See also a paper by Chasles on the radius of curvature of the envelope of a roulette.

Ex. 2. A body moves in one plane and the instantaneous centre of rotation is known. Show that a straight line attached to the moving body touches its envelope in a point  $G$  which is found by drawing a perpendicular  $IG$  on the straight line.

Since  $GI$  is normal to the locus of  $G$ , an element  $GG'$  of the path of  $G$  lies on the straight line. Thus the straight line intersects its consecutive position in  $G'$ , i.e.  $G'$  or  $G$  is a point on the envelope. [Roberval's rule.]

Ex. 3. A body moves in one plane and the instantaneous position of the circle of stability is known. Prove the following construction to find the radius of



curvature of the envelope of a straight line attached to the moving body: draw a perpendicular  $IQ$  on the straight line from the instantaneous centre  $I$  and let it cut the circle of stability in  $P_1$ . Take  $IO = IP_1$  on  $QP_1I$  produced if necessary, then  $O$  is the required centre of curvature.

By the last example,  $IO$  is a normal at  $Q$  to the envelope. If we now turn the body and the attached straight line round  $I$  through an angle  $d\theta$ , and draw from  $I'$  a perpendicular  $I'Q'$  on the straight line thus displaced, it is clear that  $Q'I'$  is the consecutive normal to the envelope. Let  $Q'I'$  intersect  $QI$  in  $O$ , then  $O$  is the required centre of curvature.


Since  $IO$  and  $I'O$  are perpendiculars to two consecutive positions of the same straight line, the angle  $IOI'$  is equal to  $d\theta$ . Draw  $I'P'$  parallel to  $IP_1$  to intersect the circle of stability in  $P'$ , then as in Art. 239 the angle  $P'IP_1$  is also equal to  $d\theta$ . Thus  $I'O$  is parallel to  $P'I$  and  $P'O$  is a parallelogram. Therefore  $IO$  is equal to  $I'P'$ , and in the limit  $IO$  and  $IP_1$  are equal.

Ex. 4. The corners of a triangle  $ABC$  move along three curves, the normals at  $A$ ,  $B$ ,  $C$  meet in  $I$  and  $\alpha, \beta, \gamma$  are the angles at  $I$  subtended by the sides. If  $\rho_1, \rho_2, \rho_3$  be the radii of curvature of the curves, prove that

$$\frac{AI^2 \sin \alpha}{\rho_1} + \frac{BI^2 \sin \beta}{\rho_2} + \frac{CI^2 \sin \gamma}{\rho_3} = AI \sin \alpha + BI \sin \beta + CI \sin \gamma.$$

**243.** Ex. 1. A homogeneous rod  $AB$ , of length  $2l$ , rests in a horizontal position inside a bowl formed by a surface of revolution with its axis vertical. Show that the equilibrium is stable or unstable according as  $l^2\rho$  is less or greater than  $n^3$ , where  $\rho$  is the radius of curvature at  $A$  or  $B$  and  $n$  is the length of the normal. [See Art. 222.]

The normals at  $A$  and  $B$  meet in a point  $I$  on the axis of revolution. and  $BM$  so that each is equal to  $AI^2/\rho$ . The circle described about  $ILM$  is the circle of stability. Let the circle drawn through  $I$  touching the rod at  $G$  cut  $AI$  in a point  $H$ , then  $AH \cdot AI = AG^2$ . The equilibrium is unstable if  $G$  is within the circle  $ILM$ , i.e. if  $AL$  is less than  $AH$ , i.e. if  $n^2/\rho$  is less than  $l^2/n$ .



If the extremities of the rod terminate in small smooth rings which slide on a curve symmetrical about the vertical axis, the position  $A'B'$ , in which the normals at  $A'B'$  meet in a point  $I$  below the rod, is also a position of equilibrium. Following the same reasoning the concavity of the path of  $G$  is turned towards  $I$  when  $I$  is below the rod. The conditions of stability are therefore reversed, the equilibrium is therefore stable or unstable according as  $l^2\rho$  is  $>$  or  $<$   $n^3$ .

Ex. 2. The extremities of a rod are constrained by small rings to be in contact with a smooth elliptic wire. If the major axis is vertical prove that the horizontal position is unstable and the upper stable if the length of the rod is greater than the latus rectum. These conditions are reversed if the length of the rod is less than the latus rectum. If the minor axis is vertical the lower horizontal position is stable and the upper unstable.

In an ellipse  $\rho (b^2/a^2) = n^3$ , where  $2a$  and  $2b$  are respectively the vertical and horizontal axes. Using this property, the results follow from those of Ex. 1.

It has been shown in Art. 126, that when the major axis of the ellipse is vertical the rod is in equilibrium only when it is horizontal or passes through the focus. The condition of stability in the latter case follows easily from the fact that the altitude of the centre of gravity must be a minimum. Let the rod be in equilibrium at the lower focus and let  $S$  be the lower focus. Let  $AM$ ,  $BN$  be perpendiculars from  $A$  and  $B$  to the lower directrix. The altitude of the centre of gravity above the lower directrix is  $\frac{1}{2}(AM + BN) = \frac{1}{2e}(SA + SB)$ . Since  $SA$  and  $SB$  are two sides of the triangle  $SAB$ , this altitude is a minimum when  $S$  lies on the rod  $AB$ . In the same way, when the rod is in equilibrium at the upper focus, the depth of the centre of gravity below the upper directrix is represented by the same expression. When therefore the rod passes through the lower focus the equilibrium is stable, when it passes through the upper focus the equilibrium is unstable.

Ex. 3. The extremities  $A$ ,  $B$  of a rod are constrained by two fine rings to slide on one on each of two equal and opposite catenaries having a common vertical axis and a common horizontal axis. Prove that the lower horizontal position of the rod is stable, see Art. 126, Ex. 5.

body to be displaced in a plane of symmetry so that the problem be considered to be one in two dimensions.

The geometrical method explained in Art. 241 supplies cases an easy solution. Let  $I$  be the point of contact of bodies, then  $I$  is the centre of instantaneous rotation. Let  $C'IC$  be the common normal in the position of equilibrium,  $C, C'$  the centres of curvature. We shall suppose these curvatures positive when measured in opposite directions. If the upper body is slightly displaced so that  $I'$  becomes the new point of contact, the angle viz.  $d\theta$  turned round by the body is equal to the angle between the normals  $CJ'$  and  $C'I'$ , and this is evidently equal to the sum of the angles  $J'CI, I'C'I$ . We therefore have

$$\frac{ds}{\rho} + \frac{ds}{\rho'} = d\theta,$$


where  $II' = IJ' = ds$  as before. See also Salmon's *Higher Curves*, Art. 312, or Besant's *Roulettes and Glissettes*, Art. 10.

To construct the circle of stability we measure along the normal  $IC$  in the position of equilibrium a length  $IS$ .

Writing  $z$  for this length, we see that  $\frac{1}{z} = \frac{1}{\rho} + \frac{1}{\rho'}$ . The circle described on  $IS$  as *diameter* is the circle of stability. Let  $IG$  be the line of gravity,  $P$  the point of intersection of  $IG$  with the circle in  $P$ .

If the centre of gravity  $G$  lie without this circle, the direction of its path is turned towards  $I$ . Hence the equilibrium is unstable according as  $G$  is below or above the point  $P$ . If  $G$  lies on the circle with  $P$  the equilibrium is neutral to a first approximation.

The critical altitude  $IP$  which separates stability and instability is clearly  $IP = z \cos \alpha = \frac{\rho\rho' \cos \alpha}{\rho + \rho'}$ , where  $\alpha$  is the inclination of the common normal in the position of equilibrium to the vertical.




**245. Ex. 1.** A solid hemisphere (radius  $\rho$ ) rests on the summit of a fixed sphere (radius  $\rho'$ ) with the curved surfaces in contact. If the centre of gravity of the hemisphere be at a distance  $h$  from its base, show that the equilibrium is stable if  $h < \rho \cos \alpha$ , where  $\alpha$  is the inclination of the common normal to the vertical.

Ex. 2. A solid hemisphere rests on a rough plane inclined to the horizon at angle  $\beta$ . Find the inclination of the plane base to the horizon and show that the equilibrium is stable.

The centre of gravity must lie in the vertical through  $I$ , and  $CG$  is also perpendicular to the base. Hence the required inclination of the base is the supplement of the angle  $CGI$ . The vertical through  $I$  cannot pass through  $G$  if  $CI \sin \beta$  is greater than  $CG$ . Since  $CG = \frac{3}{8}\rho$ , it is necessary for equilibrium that  $\sin \beta < \frac{8}{9}$ .

To find the circle of stability we notice that  $\rho' = \infty$ , and therefore  $z = \rho$ . The circle described on  $IC$  is therefore the circle of stability. Since the angle  $CGI$  is greater than a right angle, it is obvious that  $G$  lies inside the circle. The concavity of the path of  $G$  is therefore upwards, and the equilibrium is stable.



Ex. 3. A solid homogeneous hemisphere, of radius  $a$  and weight  $W$ , rests in apparently neutral equilibrium on the top of a fixed sphere of radius  $b$ . Prove that  $5a = 3b$ . A weight  $P$  is now fastened to a point in the rim of the hemisphere. Prove that, if  $55P = 18W$ , it still can rest in apparently neutral equilibrium on the top of the sphere. [Math. Tripos, 1894.]

Ex. 4. A heavy hemispherical bowl, of radius  $a$ , containing water, rests on a rough inclined plane of angle  $\alpha$ ; prove that the ratio of the weight of the bowl to that of the water cannot be less than  $\frac{2 \sin \alpha}{\sin \phi - 2 \sin \alpha}$ , where  $\pi a^2 \cos^2 \phi$  is the area of the surface of the water. [Math. Tripos, 1895.]

When the bowl is displaced the water is supposed to move in the bowl so as to be always in a position of equilibrium. Its statical effect is therefore the same as if it were collected into a particle and placed at the centre of the bowl. The weight of the bowl may be collected at its centre of gravity, i.e. at the middle point of the middle radius.


Ex. 5. A parabolical cup, the weight of which is  $W$ , standing on a horizontal table, contains a quantity of water, the weight of which is  $nW$ : if  $h$  be the height of the centre of gravity of the cup and the contained water, the equilibrium will be stable provided the latus rectum of the parabola be  $> 2(n+1)h$ . [Math. Tripos, 1896.]

Let  $H$  be the centre of gravity of the water when the axis of the cup is vertical. Let the cup and the contained water be placed at rest in a neighbouring position with the surface of the water horizontal; Art. 215. It may be shown that the vertical through the centre of gravity  $H'$  of the displaced water intersects the axis of the paraboloid in a point  $M$ , where  $HM$  is half the latus rectum. The point  $M$  is called the *metacentre*. As in the last example the weight of the fluid may be collected into a particle and placed at the metacentre. The weight of the cup may be collected at the centre of gravity  $G$  of the cup. The equilibrium is stable if



of gravity of the body is below or above the centre of curvature at the point of con


There is one case however which requires a little further consideration. Let us suppose that the evolute has a cusp  $O$  which points vertically downwards when the point of contact is at some point  $A$ . Let us also suppose that the centre of gravity  $G$  of the body is at a very little distance above  $O$ . The position of the body is unstable, but a stable position exists in immediate proximity on each side in which the tangent from  $G$  to the evolute is vertical. That these positions are stable is clear, for since the cusp points downwards either tangent from  $G$  will touch the evolute at a point  $L$  or  $M$  which is above  $G$  when that tangent is vertical. When  $G$  moves down to  $O$  these two flanking stable positions come nearer to the unstable position and finally come up to it. When therefore the centre of gravity is at the cusp of the evolute, the equilibrium is stable.



In the same way, if the cusp  $O$  point upwards and  $G$  be situated at a short distance below  $O$ , the equilibrium is stable with a near position of instability on each side. In the limit when  $G$  coincides with  $O$ , the equilibrium becomes unstable. The reader may consult a paper by J. Larmor on *Critical Equilibrium* in the fourth volume of the *Proceedings of the Cambridge Philosophical Society*, 1900.

**247. Spherical bodies, second approximation.** When the equilibrium is neutral it is necessary to examine the higher differential coefficients to settle the stability or instability of the equilibrium. The geometrical method is not very convenient for this purpose. When both surfaces are spherical we can investigate all the conditions of equilibrium by the method of Art. 224.

Let the body, as represented in the figure of Art. 244, be placed so that  $J'$  comes into the position  $I'$ . The position of the body is then represented in the adjoining figure, where  $J$  represents that point of the upper body which in equilibrium coincided with  $I$ . Let  $JG=r$ . Let  $\psi'=IC'I'$ ,  $\psi=JCI'$ , then  $\rho'\psi'=\rho\psi$ . Let  $y$  be the altitude of  $G$  above  $C'$ . The inclinations to the vertical of  $C'C$ ,  $CJ$  and  $JG$  are respectively  $\alpha+\psi'$ ,  $\alpha+\psi+\psi'$  and  $\psi+\psi'$ . Projecting these three lines on the vertical, we have



$$y = (\rho + \rho') \cos(\alpha + \psi') - \rho \cos(\alpha + \psi + \psi') + r \cos(\psi + \psi')$$

mined to any degree of approximation by the rule of Art. 220.

The coefficient of  $\psi'$  is zero, that of  $\frac{1}{2}\psi'^2$  is  $(z \cos \alpha - r) \rho'^2/z^2$ , where  $z$  has the same meaning as before. The equilibrium is stable or unstable according as this coefficient is positive or negative, i.e. according as  $r$  is less or greater than  $z \cos \alpha$ .

If this coefficient also vanish the equilibrium is neutral to a first approximation. We then examine the coefficient of  $\psi'^3$ . Unless this also vanishes the equilibrium is stable for displacements on one side of the position of equilibrium and unstable for displacements on the other. Supposing however that the coefficient of  $\psi'^3$  does vanish, we examine the terms of the fourth order. The equilibrium is then stable or unstable according as the coefficient of  $\psi'^4$  is positive or negative.

**248.** Ex. 1. A spherical surface rests on the summit of a fixed spherical surface, the centre of gravity being at such a height above the point of contact that the equilibrium is neutral to a first approximation. If the lower surface is convex upwards as in the diagram, prove that, whether the upper body has its convexity upwards or downwards, the equilibrium is unstable. If the lower surface has its concavity upwards, the equilibrium is stable or unstable according as the radius of curvature of the lower body is greater or less than twice that of the upper body.


The coefficient of  $\psi'^2$  is here zero. The coefficient of  $\psi'^4$  after elimination of  $r$  reduces to  $-\rho'(\rho' + 2\rho)(\rho' + \rho)/24\rho^2$ . Since the equilibrium is therefore stable or unstable according as this coefficient is positive or negative, the results follow at once.

Ex. 2. A body, whose lower portion is bounded by a spherical surface, rests in apparently neutral equilibrium within a fixed spherical bowl with the point of contact at the lowest point. If the radius of one surface is twice that of the other, show that the equilibrium is really neutral.

**249. Non-spherical bodies, second approximation.** If the boundaries of the bodies in contact are not spherical we may adopt the following method.

Suppose the upper body has rolled away from its position of equilibrium into that represented in the figure of Art. 247. Then it is clear that, if  $G$  in that figure is to the right of the vertical through  $I'$ , the body will roll further away from the position of equilibrium, but if  $G$  is on the left of the vertical, the body will roll back. Let  $i$  be the angle  $GI'$  makes with the vertical; our object will be to find  $i$ .

Let  $\phi$  be the angle  $GI'$  makes with the common normal at  $I'$ , viz.  $I'C$ , and let  $GI' = r$ . Let  $I'J''$  be any further arc  $\delta s$  over which the body may be made to roll. Let  $\rho, \rho'$  be the radii of curvature of the upper and lower



bodies at  $I'$ . Then we have  $\frac{dr}{ds} = \sin \phi$  (1)

Lastly, let  $\psi'$  be the inclination of the normal  $CC'$  to the vertical, then  $i = \psi' - \phi$  and  $d\psi'/ds = 1/\rho'$ . Hence by (2) 
$$\frac{di}{ds} = \frac{1}{\rho} + \frac{1}{\rho'} - \frac{\cos \phi}{r} \dots\dots\dots(3).$$

These three equations supply all the conditions of stability. In the position of equilibrium the centre of gravity is vertically over the point of support. Hence  $i=0$ . In any other position the value of  $i$  is given by Taylor's series, viz.

$$i = \frac{di}{ds} \delta s + \frac{d^2i}{ds^2} \frac{\delta s^2}{1 \cdot 2} + \&c.$$

If in this series the first differential coefficient which does not vanish is positive and of an odd order, it is clear that the straight line  $IG$  will move to the same side of the vertical as that to which the body is moved. The equilibrium will therefore be unstable for displacements on either side of the position of equilibrium. If the coefficient is negative the equilibrium will be stable. If the term is of an even order, it will not change sign with  $\delta s$ , the equilibrium will therefore be stable for a displacement on one side and unstable for a displacement on the other side.

The first differential coefficient is given by (3). The second may be found by differentiating (3) and substituting for  $d\phi/ds$  and  $dr/ds$  from (2) and (1). The third differential coefficient may be found by repeating this process. In this way we may find any differential coefficient which may be required.

*Firstly.* Suppose the body such that  $di/ds$  is not zero in the position of equilibrium. The condition of stability is therefore that  $\frac{1}{\rho} + \frac{1}{\rho'} - \frac{\cos \phi}{r}$  is negative. This leads to the rule already considered in Art. 244.

*Secondly.* Suppose the body such that in the position of equilibrium the centre of gravity lies on the circle of stability. We then have  $di/ds=0$ . Differentiating (3) and substituting for  $(\cos \phi)/r$  its value  $1/\rho + 1/\rho'$  we find

$$\frac{d^2i}{ds^2} = \frac{d}{ds} \left( \frac{1}{\rho} + \frac{1}{\rho'} \right) + \tan \phi \left( \frac{1}{\rho} + \frac{1}{\rho'} \right) \left( \frac{1}{\rho} + \frac{2}{\rho'} \right) \dots\dots\dots(4).$$

Unless this vanishes the equilibrium will be stable for displacements on one side and unstable for displacements on the other side of the position of equilibrium.

*Thirdly.* Suppose the second differential coefficient given by (4) is also zero in the position of equilibrium. We find by differentiating (3) twice and substituting for  $r$  as before

$$\frac{d^3i}{ds^3} = \frac{d^2}{ds^2} \left( \frac{1}{\rho} + \frac{1}{\rho'} \right) + \left( \frac{1}{\rho} + \frac{1}{\rho'} \right) \left\{ \left( \frac{1}{\rho} + \frac{2}{\rho'} \right) \frac{1}{\rho'} - \tan \phi \frac{d}{ds} \frac{1}{\rho} - 3 \tan^2 \phi \left( \frac{1}{\rho} + \frac{1}{\rho'} \right) \left( \frac{1}{\rho} + \frac{2}{\rho'} \right) \right\}.$$

\* The equation (2) is useful for other purposes besides that of finding the conditions of stability. For example it may be very conveniently used in the differential calculus to find the conic of closest contact at any point  $I$  of a curve. If  $\phi$  be the angle between the central radius and the radius of curvature  $\rho$  at any point  $P$  of a conic, it may be shown that  $\tan \phi = -\frac{1}{3} \frac{d\rho}{ds}$ , where  $\phi$  is positive when measured behind the normal as  $P$  travels along the conic in the direction in which the arc  $s$  is measured. Suppose  $G$  to be the centre of the conic, then assuming this value of  $\phi$ , the distance  $r$  of the centre of the conic from  $I$  is given by the equation (2) in the text.

Generally the equation (2) is useful to find the point of contact with its envelope of a straight line  $IG$  drawn through each point of a curve making with the normal

The equilibrium is stable or unstable according as this expression is negative or positive.

**250.** Ex. 1. A body rests in neutral equilibrium to a first approximation on the surface of another, and both are symmetrical about the common normal. Show that the equilibrium cannot be stable unless either the point of contact is the summit of the fixed surface or  $\rho' = -2\rho$ .

Ex. 2. A body rests in neutral equilibrium to a second approximation on an inclined plane. Show that the equilibrium is stable or unstable according as  $\rho'$  is positive or negative.



Ex. 3. A body rests in equilibrium on the surface of another body fixed in space and the centre of gravity  $G$  of the first body is acted on by a central force towards some point  $O$  in  $GI$  produced and varying as the distance therefrom. If  $G'$  is taken on  $IG$  so that  $\frac{1}{IG'} = \frac{1}{IG} + \frac{1}{IO}$ , the equilibrium is stable or unstable according as  $G'$  lies within or without the circle of stability.

**251. Rocking Stones in three dimensions.** The upper body being in a position of equilibrium, let the common tangent plane at the point of contact be taken as the plane of  $xy$ . Let the equations to the upper and lower bodies respectively

$$\left. \begin{aligned} 2z &= ax^2 + 2bxy + cy^2 + \&c. \\ -2z' &= a'x^2 + 2b'xy + c'y^2 + \&c. \end{aligned} \right\} \dots\dots\dots$$

In the standard case, therefore, the two bodies have their convexities turned towards each other. We shall now suppose the upper body to be displaced from its position of equilibrium by rolling over the lower along the axis of  $x$  through an arc  $ds$ . Take  $OP = OP' = ds$ .

We have first to determine how the upper body must be rotated to bring its tangent plane at  $P$  into coincidence with that at  $P'$ . Referring to equations (1)



see that the tangents at  $P$  and  $P'$  to  $OP$  and  $OP'$  make angles with the plane of  $xy$  which are  $dz/dx = ads$  and  $dz'/dx = -a'ds$ . To make these tangents coincide, the upper body must be rotated through an angle  $\theta$  such that  $\theta = \frac{a'ds}{a}$ .

**252.** The body being placed at rest in its new position, the centre of gravity is no longer in the vertical through the point of contact. The weight will therefore make the body begin to move. *Let us suppose that the body is constrained either to go back to its position of equilibrium by the way it came or to recede further along that course.* The equilibrium will then be stable or unstable according as the moment of the weight about a parallel to  $Oy'$  through the new point of contact tends to bring the body back to or further from the position of equilibrium.

It will be found more convenient to refer the displacement of  $G$  to the rectangular axes  $Ox'$ ,  $Oy'$ ,  $Oz$  instead of the original axes. Let  $x'$ ,  $y'$ ,  $z$  be the coordinates of  $G$  in the position of equilibrium, let  $r = OG$  and let  $\alpha'$ ,  $\beta'$ ,  $\gamma$  be the direction angles of  $OG$ . Then  $x' = r \cos \alpha'$ ,  $y' = r \cos \beta'$ ,  $z = r \cos \gamma$ .

If we draw  $GN$  a perpendicular on  $Oy'$ , the point  $G$  will be displaced by rotation  $\Omega$  along a small arc  $GG'$  of a circle whose plane is parallel to  $x'z$ , whose centre is  $N$  and radius  $NG$ . The displacements of  $G$  parallel to  $x'$  and  $z$  are therefore  $\Omega z$  and  $-\Omega x'$ . The resolved forces on  $G$  parallel to the axes  $x'$ ,  $y'$ ,  $z$  are

$$X = -W \cos \alpha', \quad Y = -W \cos \beta', \quad Z = -W \cos \gamma,$$

where  $W$  is the weight of the body. The moment of these about a parallel to  $Oy'$  drawn through the new point of contact  $P$  is

$$M = (z - \Omega x') X - (x' + \Omega z - ds \sin i) Z \\ = \{r\Omega (\cos^2 \alpha' + \cos^2 \gamma) - ds \sin i \cos \gamma\} W.$$

The equilibrium is therefore stable or unstable according as the sign of  $M$  is negative or positive.

**253.** We observe that  $\Omega$  and  $i$  do not depend on the curvatures  $a$ ,  $a'$  or  $b$ ,  $b'$  but on their sums  $a + a'$ ,  $b + b'$ . If, then, we replace the rocking body by another having the curvatures of its normal sections equal to the relative curvatures of the given bodies, and make this new body roll on a rough plane inclined to the horizon at an angle  $\gamma$ , the conditions of stability are unaltered. The equation of this new body is

$$2z = (a + a')x^2 + 2(b + b')xy + (c + c')y^2 + \&c. \dots\dots\dots (2)$$

The indicatrix is obtained by rejecting the terms included in the  $\&c.$ , and giving  $z$  any constant value. This conic may be called the relative indicatrix of the two bodies given by (1). It must be an ellipse for otherwise rolling would be impossible. The equation of the axis of  $y'$  is  $\omega_2 x = \omega_1 y$ , i.e.  $(a + a')x + (b + b')y = 0$ , which is conjugate of the axis of  $x$ . It follows that the axis of rotation  $Oy'$  and the tangent  $Ox$  to the arc of rolling are conjugate diameters in the relative indicatrix.

Let  $\rho$ ,  $\rho'$  be the radii of relative curvature of the normal sections drawn through the arc of rolling  $Ox$  and the conjugate  $Oy'$ ;  $\rho_1$ ,  $\rho_2$  the principal radii of curvature. Since each  $\rho$  is proportional to the square of the corresponding diameter of the indicatrix, it follows from a property of conjugates that  $\rho\rho' \sin^2 i = \rho_1\rho_2$ .

**254.** To discuss the sign of the moment  $M$ , we substitute for  $\Omega \sin i$  its value  $(a + a') ds$ , i.e.  $ds/\rho$ . The expression then becomes

$$M = \left( r \sin^2 \beta' - \frac{\rho_1 \rho_2}{\rho'} \cos \gamma \right) \frac{W ds}{\rho \sin i} \dots\dots\dots (3)$$

The equilibrium is stable or unstable for any given displacement according as the first factor is negative or positive.


If the rocking body rest on the summit of the fixed body, the centre of mass lies in the common normal  $Oz$  and therefore  $\beta' = \frac{1}{2}\pi$  and  $\gamma = 0$ . We then have

$$M = \left( r - \frac{\rho_1 \rho_2}{\rho'} \right) \frac{W ds}{\rho \sin i} \dots \dots \dots$$

Considering displacements in all directions, we see that if  $OG$ , i.e.  $r$ , the least radius of relative curvature of the arc of rolling, the equilibrium is stable, if  $OG$  is greater than the greatest radius of relative curvature of the fixed body, it is wholly unstable. If  $OG$  lies between these limits the equilibrium is stable for some displacements and unstable for others, the separating displacement being one in which the radius of curvature  $\rho'$  of the conjugate arc is equal to  $\frac{\rho_1 \rho_2}{r}$ .

Ex. A solid paraboloid of revolution is bounded by a plane perpendicular to the axis at a distance from the vertex equal to nine-eighths of the latus rectum. Prove that it will rest in stable equilibrium with one end of the latus rectum in contact with a horizontal plane. [Cox]

**255. Lagrange's proof of the principle of virtual work.** Let a body be acted on by any commensurable forces  $P, Q, R$  &c. at the points  $A, B, C$  &c. Let these forces be multiples  $l, m, n$  &c. of some force  $2K$ . At the point  $A$  of the body let a small smooth pulley be attached, and opposite to it at some point  $A'$  in space let an equal pulley be fixed so that  $AA'$  is the direction of the force  $P$ . A fine string be wound round these two pulleys so as to go round each of the other points  $B, C$  &c. once, and so on. It is clear that, if the tension of this string were  $K$ , the force exerted at  $A$  would be equal to the given force  $P$  and act in the same direction. Imagine similar strings to be placed at  $B, C$  &c. and opposite to them at  $B', C'$  &c. Let the same string go round the pulleys  $B, B'$   $m$  times, and round  $C, C'$   $n$  times, and so on. Let one extremity of this string be attached to a point  $O$  fixed in space. Let the other extremity of the string after passing over a smooth pulley  $D$  fixed in space be attached to a weight  $K$ . By this arrangement, all the forces  $P, Q, R$  &c. of the system have been replaced by the pressures due to the tension  $K$  of the string.



Suppose now the body receives any small displacement so that the points  $A, B, C$  &c. are made to approach  $A', B', C'$  &c. respectively by small spaces  $a, b, c$  which may be positive or negative. Since the string passes round the pulleys  $A, A'$   $l$  times, the string is shortened by  $2la$  when these points are brought nearer by a distance  $a$ . Similarly the string is shortened by

is in equilibrium, no possible displacement can permit the weight  $K$  to descend. Hence  $s=0$  and the virtual work of all the forces is equal to zero.

Lagrange goes on to remark that, if the quantity  $la+m\beta+\&c.$  instead of being negative, this condition would appear to be sufficient for equilibrium, for it is impossible that the weight  $K$  would *ascend* of itself. But he points out that, in any displacement the value of  $la+\&c.$  is negative, it will become positive by giving the system a displacement in an exactly opposite direction. This displacement would cause the weight  $K$  to descend, and thus equilibrium would be destroyed.

The argument concerning the descent of  $K$  has been admitted as sound by many eminent mathematicians. Yet it does not appear to be so evident or elementary as to entitle the principle of virtual work (thus proved) to become the basis of a science. It has also been objected that it is not true without further limitations, for if a heavy particle were placed in unstable equilibrium at the highest point of a fixed smooth sphere, a small displacement would enable the particle to descend notwithstanding that it is in equilibrium.

**256.** Conversely, if the equation  $la+\&c.=0$  holds for all possible infinitely small displacements of the system, the system will be in equilibrium. For the weight remains immovable in all these displacements so that there is no reason why the forces which act on the system should act so as to move the system in one direction or its opposite. The system therefore will be in equilibrium.

The mode in which Lagrange proves this converse is certainly open to many objections. For these we refer the reader to De Morgan's criticism in the article *Virtual Velocities* in *Knight's English Cyclopædia*. The writer of that article suggests another mode of arranging Lagrange's proof which obviates some of the objections usually made to it. But this new method is itself not free from objection.


## CHAPTER VII

### FORCES IN THREE DIMENSIONS

**257.** *To find the resultants of any number of forces acting on a body in three dimensions. Poinso's method.*

Let the forces be  $P_1, P_2$ , &c., and let them act at the points  $A_1, A_2$ , &c. Let  $O$  be any point arbitrarily chosen. It is required to reduce these forces to a single force acting at  $O$  and a couple.

Let the point  $O$  be taken as the origin of a system of rectangular coordinates. Let  $P$  be any one of the forces, let  $x = OM, y = MN, z = NA$  be the coordinates of its point of application  $A$ .



We begin by resolving  $P$  into its three axial components  $P_x, P_y, P_z$ ; we shall then transfer each of these (as in Art. 104) to the point  $O$  by introducing into the system the appropriate couples. At  $M$  apply two opposite forces each equal and parallel to  $P_x$ . At  $O$  apply two other opposite forces each also equal and parallel to  $P_x$ . Then since  $P_x$  may be supposed to act at  $N$ , the force  $P_x$  is equivalent to a force  $P_x$  acting at  $O$ , and two couples of moments are  $yP_x$  and  $-xP_x$ , and whose planes are respectively parallel to  $yz$  and  $xz$ . The signs  $+$  and  $-$  are given according to whether they tend to rotate the body in the positive or negative direction of the coordinate planes in which they act. In the same manner, drawing a perpendicular from  $A$  on the plane  $yz$ , we find that the component  $P_y$  may be replaced by an equal force



replaced by three forces  $X, Y, Z$  acting along the axes of coordinates, and three couples whose moments are  $L, M, N$ , and these axes are the axes of coordinates, where

$$\begin{aligned} X &= \Sigma P_x, & L &= \Sigma (yP_z - zP_y), \\ Y &= \Sigma P_y, & M &= \Sigma (zP_x - xP_z), \\ Z &= \Sigma P_z, & N &= \Sigma (xP_y - yP_x). \end{aligned}$$

These are called the *six components of the forces*.

The three components  $X, Y, Z$  may be compounded into a single force. Let  $R$  be its magnitude, and  $(l, m, n)$  the direction cosines of its positive direction, then

$$\begin{aligned} Rl &= X, & Rm &= Y, & Rn &= Z, \\ R^2 &= X^2 + Y^2 + Z^2. \end{aligned}$$

This force is called by Moigno the *principal force* at the point  $O$ .

The three components  $L, M, N$  in the same way may be compounded into a single couple whose moment  $G$  and the direction cosines  $(\lambda, \mu, \nu)$  of whose axis are given by

$$\begin{aligned} G\lambda &= L, & G\mu &= M, & G\nu &= N, \\ G^2 &= L^2 + M^2 + N^2. \end{aligned}$$

This couple  $G$  is called the *principal couple* at the point  $O$ . The components  $L, M, N$  of the principal couple are also called the *moments of the forces about the axes*.

**258.** The base of reference  $O$  to which the forces have been transferred, has been taken as the origin of coordinates. But when it is necessary to distinguish between these points we must modify the expressions for the components. Let some point  $O'$  whose coordinates are  $\xi, \eta, \zeta$  be the base of reference. The expressions for the six components for this new base may be deduced from those for the origin by writing  $x - \xi, y - \eta, z - \zeta$  for  $x, y, z$ .

The expressions for the components of the force  $R$  do not contain  $x, y, z$ , hence *the principal force  $R$  is the same in magnitude and direction whatever base is chosen*.

The expressions for the components of the couple  $G$  become

$$\begin{aligned} L' &= \Sigma \{(y - \eta) P_z - (z - \zeta) P_y\} = L - \eta Z + \zeta Y, \\ M' &= \Sigma \{(z - \zeta) P_x - (x - \xi) P_z\} = M - \zeta X + \xi Z, \\ N' &= \Sigma \{(x - \xi) P_y - (y - \eta) P_x\} = N - \xi Y + \eta X \end{aligned}$$

Art. 105 that the forces on a body can be reduced to a single force  $R$  and a single couple  $G$ . By the same reasoning as in Art. 104 it is necessary and sufficient for equilibrium that these separately vanish. We therefore have  $R=0$  and  $G=0$ .

If the axes of reference are at right angles, these lead to the six conditions

$$X=0, \quad Y=0, \quad Z=0, \quad L=0, \quad M=0, \quad N=0,$$

we may, however, put these results into a more convenient form.

In order to make the resultant force  $R$  zero, *it is necessary and sufficient that the sum of the resolutes of all the forces along any three straight lines (not all parallel to the same plane) be zero.* To prove this, let  $OA, OB, OC$  be parallel to the three straight lines. If the resolute of  $R$  along  $OA$  is zero, it is clear that either  $R$  is zero, or the direction of  $R$  is perpendicular to  $OA$ . If  $R$  is not zero, its direction is perpendicular to each of the three straight lines meeting in  $O$ , not all in one plane, which is impossible.

In the same way, since couples are resolved according to the same laws as forces, we infer that to make the principal couple  $G$  zero, it is necessary and sufficient that the component couple about all the forces about each of any three straight lines intersecting at the base  $O$  but not all in one plane, should be zero. It is presently seen that the moment of the component couple about any axis through  $O$  is also the moment of the forces about that axis, Art. 263.

Since a couple may be moved into a parallel plane without altering its effect, it is clear that, *when the force  $R$  is zero, the moments about all parallel straight lines are equal.* It is therefore sufficient for equilibrium that the *moment of the forces about any three straight lines (whether intersecting or not) should be equal, but all three must not be parallel to the same plane, and no two must be parallel to each other.* The method of finding these moments will be more fully explained a little further on.

**260. Components of a force.** Usually we suppose the force to be given when we know its magnitude and the equation of its line of action. We see from the results of the proposition

sentation is that the resulting effect of any number of forces is found by adding their several corresponding components.

If we wish to represent the line of action of the force apart from the force itself, we may regard the straight line as the seat of some force of given magnitude, and suppose the line itself determined by the six components of this chosen force. Let  $(l, m, n)$  be the direction cosines of the straight line,  $(x, y, z)$  the coordinates of any point on it. Then, if the force chosen is a unit force, the six components or coordinates\* of the line are

$$l, m, n, \lambda = yn - zm, \mu = zl - xn, \nu = xm - yl,$$

with the obvious relation

$$\lambda l + m\mu + n\nu = 0 \dots \dots \dots (1).$$

If a force  $P$  act along this straight line, its six components or coordinates are  $Pl, Pm, Pn; P\lambda, P\mu, P\nu$ .

If we compound several forces together, the six components become

$$X = \Sigma Pl, Y = \Sigma Pm, Z = \Sigma Pn; L = \Sigma P\lambda, M = \Sigma P\mu, N = \Sigma P\nu,$$

but the relation

$$XL + YM + ZN = 0 \dots \dots \dots (2)$$

is not necessarily true.

**261.** We have seen in Art. 257 that all these forces may be joined together so as to make a single force  $R$  and a couple  $G$ . This combination of a force and a couple has been called by Plücker a *dyname*. The six quantities  $X, Y, Z, L, M, N$  are the components of the dyname. The three former components are multiples of some unit force, the three latter of some unit couple.

It will be shown further on that when the coordinates of the dyname satisfy the condition (2), either the force  $R$  or the couple  $G$  of the dyname is zero.

✓ **262.** Ex. 1. The six components of a force are 1, 2, 7; 4, 5, -2. Show that the magnitude of the force is  $\sqrt{54}$ , and that the equations to its line of action are

$$(7y - 2z)/4 = (z - 7x)/5 = (2x - y)/(-2) = 1.$$

✓ Ex. 2. The six components of a dyname are 1, 2, 3; 4, 5, 6. Show that the magnitude of the force is  $\sqrt{14}$ , and that its direction cosines are proportional to 1, 2, 3. If this force act at the origin the magnitude of the couple is  $\sqrt{77}$ , and the direction cosines of its axis are proportional to 4, 5, 6.

\* The six coordinates of a line are described in Salmon's *Solid Geometry* (fourth edition, Art. 51) from an analytical point of view. See also Cayley, *Quart. Journal* 1827, 1828, 1829, 1830, 1831, 1832, 1833, 1834, 1835, 1836, 1837, 1838, 1839, 1840, 1841, 1842, 1843, 1844, 1845, 1846, 1847, 1848, 1849, 1850, 1851, 1852, 1853, 1854, 1855, 1856, 1857, 1858, 1859, 1860, 1861, 1862, 1863, 1864, 1865, 1866, 1867, 1868, 1869, 1870, 1871, 1872, 1873, 1874, 1875, 1876, 1877, 1878, 1879, 1880, 1881, 1882, 1883, 1884, 1885, 1886, 1887, 1888, 1889, 1890, 1891, 1892, 1893, 1894, 1895, 1896, 1897, 1898, 1899, 1900, 1901, 1902, 1903, 1904, 1905, 1906, 1907, 1908, 1909, 1910, 1911, 1912, 1913, 1914, 1915, 1916, 1917, 1918, 1919, 1920, 1921, 1922, 1923, 1924, 1925, 1926, 1927, 1928, 1929, 1930, 1931, 1932, 1933, 1934, 1935, 1936, 1937, 1938, 1939, 1940, 1941, 1942, 1943, 1944, 1945, 1946, 1947, 1948, 1949, 1950, 1951, 1952, 1953, 1954, 1955, 1956, 1957, 1958, 1959, 1960, 1961, 1962, 1963, 1964, 1965, 1966, 1967, 1968, 1969, 1970, 1971, 1972, 1973, 1974, 1975, 1976, 1977, 1978, 1979, 1980, 1981, 1982, 1983, 1984, 1985, 1986, 1987, 1988, 1989, 1990, 1991, 1992, 1993, 1994, 1995, 1996, 1997, 1998, 1999, 2000.

expressions are

$$L = \Sigma (yP_z - zP_y), \quad M = \Sigma (zP_x - xP_z), \quad N = \Sigma (xP_y - yP_x).$$

To show how far this definition agrees with that already given in Art. 113, let us examine how the expression for  $N$  has been obtained. The force  $P$  has been resolved into its components  $P_x, P_y, P_z$ ; the two former act in a plane perpendicular to the axis of  $z$ , hence by the definition given in Art. 113, the expressions  $yP_x$  and  $-xP_y$  are respectively equal to their moments about that axis. The latter  $P_z$  acts parallel to the axis of  $z$ , and if the moment of this component is defined to be zero, the expression  $N$  will become the moment of the forces about the axis of  $z$ . Let  $Q$  be the resultant of the two components  $P_x, P_y$ , then the moment of  $Q$  about the axis of  $z$  is equal to the sum of the moments of  $P_x$  and  $P_y$ , Art. 116.

Since any straight line may be taken as the axis of  $z$ , this explanation applies to all straight lines. It appears therefore that the moment of the component couple for any axis is the same as the moment of all the forces about that axis.

We thus arrive at the following definition of the moment of a force about any straight line. Let the straight line be called  $CD$ . *Resolve the force  $P$  into two components, one parallel and the other perpendicular to the straight line  $CD$ . The moment of the former is defined to be zero. The moment of the latter is obtained by multiplying its magnitude by the shortest distance between it and the given straight line  $CD$ .*

It is evident that this shortest distance is equal to the shortest distance between the original force  $P$  and the straight line  $CD$ , each being equal to the distance between  $CD$  and the plane of the components. Let  $r$  be the length of this shortest distance. Let  $\theta$  be the angle between the positive directions of the force  $P$  and the line  $CD$ , then the resolved part of the force  $P$  perpendicular to  $CD$  is  $P \sin \theta$ . We therefore find that *the moment of the force  $P$  about  $CD$  is equal to  $Pr \sin \theta$ .*

When the moments of several forces round the same straight line  $CD$  are to be added together, we must take care that these have their proper signs. Any direction of rotation round  $CD$

264. It follows from Art. 263 that, if two equal forces act along the positive directions of two straight lines  $AB$ ,  $CD$ , the moment of the former about  $CD$  is equal to the moment of the latter about  $AB$ .

The product  $r \sin \theta$  is sometimes called *the moment of either of the straight lines  $AB$ ,  $CD$  about the other*. Let  $i$  be the moment of one straight line about the other, and let either line be occupied by a force  $P$ . Then the moment of  $P$  about the other line is  $Pi$ .

265. In some cases it may be necessary to take account of the signs of  $r$  and  $\theta$ . Supposing the positive direction of the common perpendicular to  $AB$  and  $CD$  to have been already determined, the shortest distance  $r$  must be measured in that direction. The angle  $\theta$  must then be measured in any plane perpendicular to  $r$  from the projection of one line to the projection of the other in such a direction that when  $r$  and  $\sin \theta$  are positive, a positive force acting along either line will tend to produce rotation round the other in the positive direction. See Art. 97.

266. *Geometrical representation of  $i$ .* The volume of a tetrahedron is known\* to be equal to one-sixth of the continued product of the lengths of two opposite edges, the shortest distance between the edges and the sine of the angle between them. Let  $AB$ ,  $CD$  be any lengths conveniently situated on the two straight lines.


The mutual moment of the two lines is equal to  $\frac{6V}{AB \cdot CD}$ , where  $V$  is the volume of the tetrahedron whose opposite edges are  $AB$ ,  $CD$ .

*Analytical representation of  $i$ .* Let  $(fgh)$ ,  $(f'g'h')$  be the coordinates of  $A$ ,  $C$ , and  $(lmn)$ ,  $(l'm'n')$  the direction cosines of the positive directions of  $AB$ ,  $CD$ . The mutual moment of  $AB$ ,  $CD$ , is the determinant in the margin. The order of the terms in the determinant is as follows; if  $f$ ,  $g$ ,  $h$  precede  $f'$ ,  $g'$ ,  $h'$  in the first row, then  $l$ ,  $m$ ,  $n$  precedes  $l'$ ,  $m'$ ,  $n'$  in the order of the rows.

To prove this we take  $C$  as origin, and let  $x=f-f'$ ,  $y=g-g'$ ,  $z=h-h'$ . The required moment is then  $\lambda l' + \mu m' + \nu n'$ , where  $\lambda$ ,  $\mu$ ,  $\nu$  have the meanings given in Art. 260.

\* To find the volume of a tetrahedron. Pass a plane through  $CD$  and the shortest distance  $EF$  between  $CD$  and the opposite edge. Then since the tetrahedron  $ABCD$  is the sum or difference of the tetrahedrons whose vertices are  $A$  and  $B$  and common base is  $DEC$ , its volume is one-third the area  $DEC$  multiplied by  $AB \cdot \sin \theta$ , where  $\theta$  is the angle  $AB$  makes with the plane  $DEC$ .

If a straight line  $AB$  cut a plane in  $E$  and be at right angles to a straight line  $EF$  in that plane, its inclination to the plane is the angle it makes with a straight line drawn in the plane perpendicular to  $EF$ . Euc. xi, 11. But  $CD$  lies in the plane and is perpendicular to  $EF$ , hence  $\theta$  is equal to the angle between the opposite edges



Ex. 2. If  $(xyz)$ ,  $(x'y'z'u')$  are the tetrahedral coordinates of any two points  $H$ ,  $K$  on the line of action of a force  $P$ , show that the moment of the force about the edge  $AB$  of the tetrahedron, is  $P \cdot \frac{6V}{HK \cdot AB} \begin{vmatrix} z & z' \\ u & u' \end{vmatrix}$ .

If the force, when positive, acts from  $H$  towards  $K$  and the terms in the determinant are taken in the order shown, this expression gives the moment of the force round  $AB$  in the direction from the corner  $C$  to the corner  $D$ .

Ex. 3. If in a tetrahedron the mutual moments of the opposite edges are equal, prove that the products of their lengths are also equal. If  $(r, s, t)$  are the lengths of the lines joining the middle points of opposite edges and  $(\alpha, \beta, \gamma)$  are the angles at which they intersect, prove also that

$$r^4 - 2r^2s^2 \cos^2 \gamma + s^4 = s^4 - 2s^2t^2 \cos^2 \alpha + t^4 = t^4 - 2t^2r^2 \cos^2 \beta + r^4. \quad [\text{St John's, 1891.}]$$

Ex. 4. Two triangles  $ABC$  and  $A'B'C'$  are seen in perspective by an eye placed at  $O$ ; forces  $P, Q, R$  act in  $BC, CA$  and  $AB$ , another set  $P', Q', R'$  in  $C'B', A'C'$  and  $B'A'$  respectively, and the whole system is in equilibrium. Show that

$$\frac{\Delta \cdot P \cdot OA'}{BC \cdot AA'} = \frac{\Delta' \cdot P' \cdot OA}{B'C' \cdot AA'} = \frac{\Delta \cdot Q \cdot OB'}{CA \cdot BB'} = \frac{\Delta' \cdot Q' \cdot OB}{C'A' \cdot BB'} = \frac{\Delta \cdot R \cdot OC'}{AB \cdot CC'} = \frac{\Delta' \cdot R' \cdot OC}{A'B' \cdot CC'},$$

where  $\Delta$  and  $\Delta'$  are the volumes of the tetrahedra  $OABC$  and  $OA'B'C'$  respectively.


[Math. Tripos, 1883.]

The six lines  $OA, OB, OC, AB, BC, CA$  form a tetrahedron. If we equate to zero the sum of the moments of the six forces about the edge  $OA$ , we find that the first and second of the above given expressions are equal. In the same way taking moments about the edge  $AB$ , we find that the second and fourth are equal. It follows by symmetry that all the six expressions are equal. The moments may be found by using the rule given in Art. 266.

✓ **268. Problems on Equilibrium.** Ex. 1. A body, free to turn about a straight line as a fixed axis, is acted on by any forces. It is required to find the condition of equilibrium and the pressure on the axis.

Let the straight line be the axis of  $z$ , and let  $x, y$  be two perpendicular axes.

The pressures on the elements of length of the axis constitute a system of forces. If the body is free to slide smoothly along the axis, each of these pressures will act perpendicularly to the axis. But as this limitation does not simplify the result, we shall suppose the direction of the pressure to be perfectly general. Taking any arbitrary point  $B$  on the axis as a base of reference, each pressure may be transferred to act at  $B$ , by introducing a couple whose plane passes through the axis. All the pressures are therefore equivalent to a resultant pressure which acts at  $B$  together with a resultant couple whose plane passes through the axis. Let one of the forces of this couple act at  $B$  and let the arm be so altered (if necessary) that the other force acts at some other arbitrary point  $C$  of the axis. Then compounding the forces which act at  $B$ , we see that the pressures on all the



attached to its axis at three points by smooth hinges.

Let  $F_x, F_y, F_z$  and  $G_x, G_y, G_z$  be the resolutes of the pressures at  $B$  and  $C$  respectively. Let  $b, c$  be the ordinates of these points. Let  $X, Y, Z, L, M, N$  be the six components of the given forces. Then resolving parallel to the axes and taking moments as in Art. 257,

$$\left. \begin{aligned} F_x + G_x + X &= 0 \\ F_y + G_y + Y &= 0 \\ F_z + G_z + Z &= 0 \end{aligned} \right\}, \quad \left. \begin{aligned} -F_y b - G_y c + L &= 0 \\ F_x b + G_x c + M &= 0 \\ N &= 0 \end{aligned} \right\}.$$

The last equation determines the condition of equilibrium, and shows that the body will turn about the axis unless the moment of the given forces about it is zero.

We have therefore five equations to determine the six component pressures on the axis. The pressures  $F_x, F_y, G_x, G_y$  are obviously determinate, but only the sum of the components  $F_z, G_z$  can be found.



The solution of these equations will be simplified by a proper choice of the arbitrary points  $B$  and  $C$ . The position of the origin is generally determined by the circumstances of the problem. If we place  $B$  at the origin we have  $b=0$ , and the values of  $G_y, G_z$  become evident by inspection.

Suppose for example the body to be a heavy door constrained to turn round an axis inclined at an angle  $\alpha$  to the vertical. In this case, since the moment of the forces about the axis must be zero, the centre of gravity of the door must lie in the vertical plane through the axis. Let us take this plane as the plane of  $xz$ , the axis of the door being as before the axis of  $z$ . Let  $\bar{x}, 0, \bar{z}$  be the coordinates of the centre of gravity, and let  $W$  be the weight of the door. To simplify the moments we resolve  $W$  parallel to the axes; we therefore replace  $W$  by the two components  $W \sin \alpha$  and  $-W \cos \alpha$  acting at the centre of gravity parallel to the axes of  $x$  and  $z$ . We shall choose the arbitrary point  $B$  to be at the origin, while the other  $C$  is at a distance  $c$  from it. Resolving and taking moments as before, we have

$$\left. \begin{aligned} F_x + G_x + W \sin \alpha &= 0 \\ F_y + G_y &= 0 \\ F_z + G_z - W \cos \alpha &= 0 \end{aligned} \right\}, \quad \left. \begin{aligned} -G_y c &= 0 \\ G_x c + W \bar{z} \sin \alpha + W \bar{x} \cos \alpha &= 0 \end{aligned} \right\}.$$

It follows from these equations that  $F_y$  and  $G_y$  are both zero, so that the resultant pressures act in the vertical plane through the axis. The values of  $F_x, G_x$  and  $F_z + G_z$  may be easily found.

Ex. 2. Three equal spheres, whose centres are  $A, B, C$ , are placed on a smooth horizontal plane and fastened together by a string which surrounds them in the plane



perpendicular from  $D$  on the plane  $ABC$ , then  $3R \cos \angle ADN = W$ . Consider next the sphere whose centre is  $A$ ; the other two of the lower spheres exert no pressure on it. The resolved part of  $R$  in the direction  $NA$  balances the two tensions of the parts of the string parallel to  $AB$  and  $AC$ . Hence  $R \cos \angle DAN = 2T \cos \angle BAN$ . The angle  $\angle BAC = 60^\circ$ , and

$$\sin \angle ADN = \frac{AN}{AD} = \frac{2}{3} \frac{AM}{AD} = \frac{2}{3} \frac{2r \sin 60^\circ}{2r}.$$

We now easily find  $T$  in terms of  $W$ .

Ex. 3. Four equal spheres rest in contact at the bottom of a smooth spherical bowl, their centres being in a horizontal plane. Show that, if another equal sphere be placed upon them, the lower spheres will separate if the radius of the bowl be greater than  $(2\sqrt{13} + 1)$  times the radius of a sphere. [Math. Tripos, 1883.]

Ex. 4. Six thin uniform rods, of equal length and equal weight  $W$ , are connected by smooth hinge joints at their extremities so as to constitute the six edges of a regular tetrahedron; one face of the tetrahedron rests on a smooth horizontal plane. Show that the longitudinal strain of each of the rods of the lowest face is  $W/2\sqrt{6}$ . [Coll. Ex.]

Ex. 5. A heavy uniform ellipsoid is placed on three smooth pegs in the same horizontal plane, so that the pegs are at the extremities of a system of conjugate diameters. Prove that there will be equilibrium, and that the pressures on the pegs are one to another as the areas of the conjugate central sections. [Coll. Ex.]

Ex. 6. Four equal heavy rods are jointed to form a square. One side is held horizontal and the opposite one is acted on by a given couple whose axis is vertical. Show that in a position of equilibrium the lower rod makes an angle  $2 \sin^{-1} G/Wl$  with the upper,  $G$  being the couple, and  $W$  and  $l$  the weight and length of a rod. Find the action at either of the lower hinges. [Coll. Ex., 1880.]

Ex. 7. An equilateral triangular lamina, weight  $W$ , hangs in a horizontal position with its angles suspended from three points by vertical strings each equal in length to the diameter  $2a$  of the circle circumscribing the triangle. Prove that the couple required to keep the lamina at a height  $2(1-n)a$  above its initial position is  $Wa\sqrt{1-n^2}$ . [Coll. Ex., 1886.]

Ex. 8. A weightless rod, of length  $2l$ , rests in a given horizontal position with its ends on the curved surfaces of two horizontal smooth circular cylinders, each of radius  $a$ , which have their axes parallel and at a distance  $2c$ . The rod is acted on at its centre by a given force  $P$  and a couple. Find the couple when there is equilibrium, and prove that the magnitude of the couple will be least when  $P$  acts vertically, provided that  $c < l \sin \phi + \frac{1}{2}a\sqrt{2 \sec \frac{1}{2}\phi}$ , where  $\phi$  is the angle between the rod and the axes of the cylinders. [Math. Tripos, 1889.]

Ex. 9. A solid circular cylinder, of height  $h$  and radius  $a$ , is enclosed in a rigid hollow cylinder which it just fits, and is formed of an infinite number of parallel equally elastic threads, which will together support a weight  $W$  when stretched to a length  $2h$ . The ends of these strings are fastened firmly to two discs, one of which is then turned through an angle  $\alpha$  in its own plane: assuming each thread to form



from a fixed point by three equal strings each of length  $l$ . A very light smooth spherical shell of radius  $b$  is placed symmetrically on the top of them, and water poured very gently into it. Show that the greater the amount of water poured the closer must the three lower spheres be to one another in order that equilibrium may be possible, and that equilibrium will be impossible if the weight of the water poured in exceed  $nW$ , where  $n$  is the positive root of the equation

$$n^2(l-b)(l+2a+b) + (2n+3)(a^2-6ab-3b^2) = 0,$$

it being assumed that  $b$  is so small as to admit of the strings being straight.

[Math. Tripos, 1891]

**269.** Ex. 1. A heavy rod  $OAB$  can turn freely about a fixed point  $O$ , and rests over the top  $CAD$  of a rough wall. If  $OC$  be a perpendicular from  $O$  on the top of the wall, prove that the angle  $\theta$  which the rod makes with  $OC$  when the equilibrium is limiting is given by  $\mu = \tan \beta \sin \theta$ , where  $\beta$  is the angle  $OC$  makes with the perpendicular  $OE$  drawn from  $O$  to the vertical face of the wall.

To assist the description of the figure, let  $OAB$  be called the axis of  $x$ . Let  $y$  be normal to the plane  $AOC$ , and let  $z$  be perpendicular to  $x$  and  $y$ . The weight  $W$  of the rod acting at  $G$  is equivalent to  $W \cos \beta$  parallel to  $z$ , and  $W \sin \beta$  acting parallel to  $CO$ . This latter is equivalent to  $W \sin \beta \cos \theta$  and  $W \sin \beta \sin \theta$  parallel to  $x$  and  $y$  respectively.

The reaction  $R$  at  $A$  is perpendicular to both  $OA$  and  $CD$ , and is therefore parallel to  $z$ . The point  $A$  of the rod can only move perpendicularly to  $OA$ . The friction therefore acts, not along the top of the wall, but opposite to direction of motion, i.e. parallel to  $y$ .


Taking moments about  $y$  and  $z$  respectively, we have

$$W \cos \beta \cdot OG = R \cdot OA, \quad W \sin \beta \sin \theta \cdot OG = \mu R \cdot OA.$$

These give  $\mu = \tan \beta \sin \theta$ .

Ex. 2. Three equal heavy spheres, each of weight  $W$ , are placed on a rough ground just not touching each other. A fourth sphere of weight  $nW$  is placed on top touching all three. Show that there is equilibrium if the coefficient of friction between two spheres is greater than  $\tan \frac{1}{2}\alpha$ , and that between a sphere and the ground is greater than  $\tan \frac{1}{2}\alpha \cdot n/(n+3)$ , where  $\alpha$  is the inclination to the vertical of the straight line joining the centres of the upper and one lower sphere.

Ex. 3. A pole of uniform section and density rests with one end  $A$  on the ground (which is sufficiently rough to prevent any motion of that end) and with the other end against a rough vertical wall whose coefficient of friction is  $\mu$ . If  $AB$  be the limiting position of the pole for any position of  $A$ ,  $AN$  the perpendicular from  $A$  on the wall,  $\alpha$  the angle  $BAN$ , and  $\theta$  the inclination of  $BN$  to the vertical, prove that  $\tan \alpha \tan \theta$  is constant, and find the whole friction exerted at  $B$ . Find also the equation to the locus of  $B$  on the wall,  $N$  being fixed, and prove that the deviation of  $B$  from the vertical through  $N$  is greatest when  $\alpha = \theta = \tan^{-1} \sqrt{\mu}$ . [Coll. Ex. 18]



at the lower end if the vertical plane in which it lies makes an angle  $\theta$  with the wall given by  $k\mu_1 (\mu_2^2 \sin^2 \theta - \cos^2 \theta)^{\frac{1}{2}} = k - 2\mu_1 (4a^2 \sin^2 \theta - k^2)^{\frac{1}{2}}$ , and that the inclination of the tangential action at the upper end to the horizon is then  $\sec^{-1}(\mu_2 \tan \theta)$ .

[Math. Tripos, 1887.]

Ex. 5. A curtain is supported by an anchor ring capable of sliding on a horizontal cylinder by means of a hook fixed at that point of the ring which is lowest when the curtain is hanging. Show (1) that the ring may touch the cylinder at one or two points but not more, (2) that if there be double contact and the weight of the ring can be neglected the ring will not slip along the cylinder however it be pulled unless the coefficient of friction be less than  $\frac{(2a+b) \cos \theta}{(2a+b) \sin \theta - b}$ , in which  $b$  is the radius of the generating circle,  $a$  that of the circle described by its centre and  $\theta$  the inclination of the plane of this latter circle to the axis of the cylinder. [Math. T.]

For the sake of the perspective take the axis of the anchor ring as axis of  $z$ , and let the plane of the circle whose radius is  $a$  be the plane of  $xy$ . Let the axis of  $x$  pass through the hook. Let  $B, B'$  be the two points of contact of the cylinder and ring,  $B'$  being nearest the hook. Let  $(R, \mu R)$   $(R', \mu R')$  be the reactions at these points, then these four forces lie in the plane  $xz$ . Taking moments about an axis through the hook and solving, we find

$$\mu = \frac{(2a+b) \cos \theta - \rho b \cos \theta}{(2a+b) \sin \theta - b + \rho b (1 + \sin \theta)},$$

where  $\rho$  is the ratio of  $R'$  to  $R$ . As long as there is double contact  $R$  and  $R'$  are both positive. But if  $\mu$  is greater than the value given in the question, this equation shows that  $\rho$  must be negative.

Ex. 6. A solid heavy cone, placed with a generating line in contact with a rough vertical wall, can turn freely about its vertex which is fixed, and is acted on by a couple whose moment is  $L$  and whose plane is parallel to the base. Prove that in equilibrium the inclination  $\theta$  to the vertical of the generating line in contact with the wall is given by  $L = \frac{3}{4} W h \sin \theta \tan \alpha$ , where  $\alpha$  is the semi-vertical angle of the cone and  $h$  its altitude. If the rim only of the cone is rough, prove that the least value of the coefficient of friction is  $2 \tan \theta \cdot \operatorname{cosec} 2\alpha$ .

### *The central axis and the invariants.*

**270. Poinso't's Central Axis.** Any base  $O$  having been chosen, the forces of a system have been reduced to a force  $R$  acting at  $O$  and a couple  $G$ . We shall now examine whether this representation of the forces can be further simplified by a proper choice of the base.

Let  $\theta$  be the angle between the direction of the force  $R$  and the axis of the couple  $G$ . We may resolve  $G$  into two couples, one  $G \cos \theta$  whose plane is perpendicular to  $R$ , and

distance  $G \sin \theta / R$  from  $O$ .

We have therefore *reduced the system to a force  $R$  (acting in a direction parallel to the principal force at any base) together with a couple whose plane is perpendicular to the force*. The line of action of this force  $R$  is called Poinso't's central axis.

To construct *geometrically* the central axis when the couple  $G$  and the force  $R$  at any base of reference  $O$  are given, we notice that (1) the central axis is parallel to  $R$ , (2) it is at a distance  $G \sin \theta / R$  from  $R$ , (3) the perpendicular from  $O$  on the central axis is at right angles both to  $R$  and the axis of  $G$ , (4) the perpendicular from  $O$  must be so drawn that its foot is moved by the couple  $G \sin \theta$  in the same direction as that in which  $R$  acts.

**271. Screws and wrenches.** A body is said to be screwed along a straight line when it is rotated round this straight line as an axis through any small angle  $d\theta$ , and at the same time translated parallel to the axis through a small distance  $ds$ . The ratio  $ds/d\theta$  is called the pitch of the screw. If the pitch is uniform, it may also be defined as the space described along the axis when the angle of rotation is a radian, i.e. a unit of circular measure. The pitch of a screw is therefore a length. For the sake of brevity the axis of the screw is often called the screw.

The term *wrench* has been applied by Sir R. Ball to denote a force and a couple whose axis coincides with or is parallel to the force. The phrase *wrench on a screw* denotes a force directed along the axis of the screw and a couple in a plane perpendicular to the screw, the moment of the couple being equal to the product of the force and the pitch of the screw. The force is called the *intensity of the wrench*. When the pitch of the screw is zero the wrench is simply a force. When the pitch is infinite the wrench reduces to a couple. The phrase wrench on a screw is sometimes abbreviated into the single word, wrench.

A wrench is a dynam $\ddot{e}$  in which the direction of the force is perpendicular to the plane of the couple.

To determine a screw five quantities are necessary. Four are required to determine the position of the axis, for example the coordinates of the points in which it cuts two of the coordinate

**272.** Screws are distinguished as right or left-handed according to the direction in which the body is rotated for the same translation. Let an observer stand with his back along the axis, so that the translation is called positive when it is in the direction from the feet to the head. The screw is then called right or left-handed according as the rotation appears to be opposite to or the same as that of the hands of a watch ; see Art. 97.

As an example, the common corkscrew is a right-handed screw. As another example, let the reader push his two hands forward horizontally, turning at the same time his right thumb to the right and his left thumb to the left. The motion of the right hand will illustrate a right-handed screw, that of the left a left-handed screw.

In this chapter the figures are drawn in agreement with the system of coordinates usually adopted in solid geometry. The left-handed screw will therefore represent the conventions adopted to distinguish the positive and negative directions of rotation and translation. By interchanging the positions of the axes of  $x$  and  $y$  the figures may be adapted to the other system.

**273. The equivalent wrench.** *A system of forces is given by its six components  $X, Y, Z, L, M, N$  referred to any rectangular axes with the origin  $O$  as the base of reference. It is required to find analytical expressions for the equivalent wrench.*

It is obvious that the axis of the equivalent wrench is Poinso't's central axis, and that it is parallel to the principal force  $R$  at any base of reference. Hence

(1) the direction cosines of the central axis are

$$l = X/R, \quad m = Y/R, \quad n = Z/R,$$

(2) the force or intensity of the wrench is  $R$ .

(3) Let  $\Gamma$  be the required couple of the wrench. Then by Poinso't's theorem all the forces are statically equivalent to  $R$  and  $\Gamma$ , so that the moment of all the forces of the system about any straight line is equal to that of  $R$  and  $\Gamma$  about the same line. If this straight line be parallel to the central axis, the moment of  $R$  is zero and that of the couple is  $\Gamma$ . It follows that the *moment of the forces of a system about all straight lines parallel to the central axis are equal to the moment about the central axis.*

$$\therefore \Gamma R = LX + MY + NZ.$$

The pitch of the screw on which the wrench acts is therefore

$$p = \frac{\Gamma}{R} = \frac{LX + MY + NZ}{R^2}.$$

(4) Let  $(\xi\eta\zeta)$  be the coordinates of any point on the central axis. When this point is chosen as the base, the components  $L', M', N'$  of the couples are given in Art. 258 and these components are proportional to the direction cosines of the axis of the principal couple. We have therefore by (1)

$$\frac{L - \eta Z + \zeta Y}{X} = \frac{M - \zeta X + \xi Z}{Y} = \frac{N - \xi Y + \eta X}{Z}.$$

These are therefore the equations to the central axis.

If we multiply the numerator and denominator of each fraction by  $X, Y, Z$  respectively and add them together, we see that each fraction is equal to the expression found above for the pitch  $p$ .

274. If  $X, Y, Z$  are each equal to zero the principle on which these equations have been obtained becomes nugatory. But in this case the given system is equivalent to a resultant couple. Any straight line parallel to its axis is the central axis.

If the couple  $\Gamma = 0$ , the given system is equivalent to a single force  $R$ . Since the components  $L', M', N'$ , at any point  $(\xi\eta\zeta)$  of this force are zero, we have

$$L - \eta Z + \zeta Y = 0, \quad M - \zeta X + \xi Z = 0, \quad N - \xi Y + \eta X = 0.$$

Any two of these are the equations of the single resultant.


275. We may obtain the equations to the central axis in another way. The moments of the force  $R$  and the couple  $\Gamma$  about the axes are  $L, M, N$ . Hence the moments of the force  $R$  alone are  $L - \Gamma l, M - \Gamma m, N - \Gamma n$ , i.e. they are  $L - 2M - Yp, N - Zp$ . The six components of the force  $R$  are therefore  $X, Y, Z, L - 2M - Yp, N - Zp$ . These are the six coordinates of the central axis.

276. Conversely, the equivalent wrench being given, we may find the six components of the forces at any base of reference.

Let  $Oz$  be the given axis of the wrench, and let  $O'$  be any point at which the components are required. Let  $O'O$  be perpendicular on  $Oz$  and let  $OO' = r$ . Let  $O'C$  be parallel to  $Oz$  and  $O'B$  perpendicular to the plane  $O'Oz$ .

to  $O'C$ . Compounding these two couples we have a resultant couple  $G$  whose axis  $O'A$  lies in the plane  $BO'C$  and makes an angle  $\theta$  with  $O'C$ , where

$$G^2 = \Gamma^2 + R^2 r^2, \quad \tan \theta = Rr/\Gamma.$$



**277.** From these values of  $R$  and  $G$  we may draw obvious conclusions.

(1) We see that  $G$  is always numerically greater so that the principal couple  $G$  is least when the base of is on the central axis.

(2) Since  $OO'$  may be drawn in any direction from follows that the locus of the base at which the principal has a given value is a right circular cylinder whose ax central axis.

(3) The locus of the axis, viz.  $O'A$ , of the principal given magnitude is a system of hyperboloids of revolution

**278. Examples.** Ex. 1. The equivalent wrench being given, sh base on a given straight line at which the principal couple is least is which the straight line is intersected by the shortest distance between it central axis. Find also the base at which the axis of the principal co the least angle with the given straight line.

Ex. 2. The base being the origin of coordinates, show that the plane the force  $R$  and the axis of  $G$  is given by the determinantal equation in the margin. Show also that the minors of the first row, after division by  $R^2$ , are the coordinates of the foot of the perpendicular from the origin on the central axis. Thence find the equa central axis regarding it as a straight line drawn through this point par

Ex. 3. Twelve equal forces occupy the edges of a cube, the parallel f in the same direction: prove that their central axis is a diagonal. I are replaced by twelve equal couples whose axes occupy the edges, their central axis is parallel to a diagonal.

Ex. 4. Six equal forces act along the edges  $AB, BC, CA, DA, D$  regular tetrahedron: show that their central axis is the perpendicular corner  $D$  of the tetrahedron on the face  $ABC$ .

Ex. 5. Six forces act along the edges  $AB, BC, CA, AD, BD, CD$  hedron, each force being proportional to the length of the edge along w Show that their central axis is parallel to  $DG$  and is at a distance  $\frac{1}{3}$  from it, where  $\Delta$  is the area of the face  $ABC$ ,  $G$  its centre of gravity

plane drawn perpendicular to  $GG'$  in  $B_1, B_2, \dots B_n$  prove that the central axis intersects this plane in the centre of gravity of particles placed at  $B_1, B_2, \dots$  whose weights are proportional to the resolved parts of the forces parallel to  $GG'$  [Coll. Ex., 186]

Ex. 7. A system of forces intersects the plane of  $xy$  and a parallel plane  $z$  in the points  $A_1 A_2 \dots, A'_1 A'_2 \dots$  respectively; their magnitudes are  $a_1 \cdot A_1 A'_1, a_2 \cdot A_2 A'_2$  and the pitch of the equivalent wrench is  $p$ . Prove that the central axis intersects these planes in the points  $H, H'$  whose coordinates  $(\xi, \eta), (\xi', \eta')$  are given by

$$\xi' - x' = \xi - x = (y' - y) p / h, \quad \eta' - y' = \eta - y = -(x' - x) p / h,$$

where  $(xy)$  are the coordinates of the centre of gravity  $G$  of masses  $a_1, a_2, \dots$  placed at  $A_1 A_2 \dots$  and  $x'y'$  those of the centre of gravity  $G'$  of the same masses placed at  $A'_1 A'_2 \dots$

Show also that (1)  $GH$  is perpendicular to  $GK'$  and equal to  $GK' \cdot p / h$  where  $K$  is the projection of  $G'$  on the plane of  $xy$ , and (2)  $HH'$  is parallel to  $GG'$ .

Ex. 8. Prove that the trilinear coordinates  $\alpha\beta\gamma$  of the point in which the central axis of a system of forces cuts the plane of any triangle  $ABC$  are given by

$$Z\alpha = M_1 - X_1 p, \quad Z\beta = M_2 - X_2 p, \quad Z\gamma = M_3 - X_3 p,$$

where  $M_1, M_2, M_3$  are the moments of the forces about the sides,  $X_1, X_2, X_3$ , the resolute along the sides of the triangle,  $Z$  the resolute perpendicular to its plane and  $p$  is the pitch.

Regarding  $AB$  as the axis of  $x$  and the plane of the triangle as that of  $xy$ , the ordinate  $\eta$ , found by putting  $\zeta=0$  in the equation of the central axis, Art. 273, is the trilinear coordinate  $\gamma$ .

**279. Invariants of a system.** It follows from the theorem of Art. 273 that, whatever base is chosen and whatever the directions of the rectangular axes may be, the quantity  $I = LX + MY + NZ$  is invariable and equal to  $\Gamma R$ . The square of the resultant force, viz.  $R^2 = X^2 + Y^2 + Z^2$  is also invariable. *These two quantities, viz.  $I$  and  $R^2$  are called the invariants of a system.* When the invariants  $I$  and  $R^2$  are known, a third invariant, viz. the pitch  $p = I/R^2$ , can be immediately deduced.

If the forces of the system are such that the first of the invariants is zero, it follows that either  $R=0$  or  $\Gamma=0$ . The condition that the forces should be equivalent to either a single force or a single couple is therefore  $I=0$ . We may distinguish between these two cases by examining the second invariant. *If the forces are to be equivalent to a single force we must have as a second condition  $R$  not equal to zero.*

**280.** When two systems of forces  $P_1, P_2$  &c. and  $Q_1, Q_2$  &c. are given we form the two expressions

$$\sum P Q r \sin(P, Q), \quad \sum P Q \cos(P, Q).$$

• *On Screws and Wrenches.*

**284.** *To find the resultant wrench of two given wrenches, or two given forces. Analytical method.*

Let  $P, P'$  be the forces,  $p, p'$  the pitches of the given wrenches. Let  $\theta$  be the inclination of the two axes and  $h$  the shortest distance between them. It is clear that *if the resultant wrench of two given forces is required*, we merely put  $p = 0, p' = 0$  in the following process.

Let  $R$  be the force of the resultant wrench,  $\varpi$  its pitch. Equating the invariants of the given wrenches to those of the resultant, we have


$$\begin{aligned} R^2 \varpi &= P^2 p + P'^2 p' + PP' \{ (p + p') \cos \theta + h \sin \theta \}, \\ R^2 &= P^2 + P'^2 + 2PP' \cos \theta. \end{aligned}$$

These equations determine the magnitude of the resultant wrench. We easily deduce

$$R^2 \{ \varpi - \frac{1}{2} (p + p') \} = \frac{1}{2} (P^2 - P'^2) (p - p') + PP' h \sin \theta.$$

**285.** We have next to find the position in space of the axis of the resultant wrench. Let  $AA'$  be the shortest distance between the axes  $AF, A'F'$  of the given wrenches, the arrows indicating the positive directions in which the forces  $P, P'$  act. Since Poinsot's central axis is parallel to the resultant of the forces  $P, P'$ , transferred to any base *the central axis must be perpendicular to  $AA'$* . Again since the moment of both given wrenches about  $AA'$  is zero, the moment about the line of  $R$  and the couple  $\Gamma$  (whose axis has been proved perpendicular to  $AA'$ ) is also zero. This requires that *the central axis should intersect the shortest distance  $AA'$  in some point  $O$* .

Let  $AA'$  be taken as the axis of  $x$ , and let the required central axis be the axis of  $z$ . Let  $\gamma, \gamma'$  be the inclinations of  $AF, A'F'$  to the central axis, then  $\theta = \gamma + \gamma'$ . By resolving the forces



$$R \sin \gamma = P' \sin \theta, \quad R \cos \gamma = P + P' \cos \theta,$$



the two wrenches from the middle point of the shortest distance measured positively towards  $P$ . A formula equivalent to this was given in the Math. Tripos, 1887.


Ex. Prove that the central axis of two given forces  $P, P'$  divides their shortest  $AA'$  distance in the ratio  $P'(P' + P \cos \theta) : P(P + P' \cos \theta)$  which is independent of the length of  $AA'$ , the angle between the forces being  $\theta$ .

**286.** To find the resultant wrench of two wrenches whose axes intersect in some point  $A$ . The magnitudes of  $\Gamma$  and  $R$  are found by the same invariants as in the last proposition, but the determination of the position in space of the resultant axis is much simplified.

Let the resultant  $R$  of the forces  $P, P'$ , act at  $A$  in the direction  $AB$  and make angles  $\gamma, \gamma'$  with  $AF, AF'$ . Then  $R \sin \gamma = P' \sin \theta$ ,  $R \sin \gamma' = P \sin \theta$ . Following the rule given in Art. 270 to construct the central axis we find the component of the couples about a straight line  $AD$  drawn perpendicular to  $R$  in the plane of the forces. This component is

$$Pp \sin \gamma - P'p' \sin \gamma' = PP' \sin \theta (p - p')/R.$$


We now measure a distance  $AO$  in a direction normal to the plane of the forces equal to  $PP' \sin \theta (p - p')/R^2$ , and draw a parallel  $Oz$  to the direction of  $R$ . Then  $Oz$  is the central axis.



To determine on which side of the plane of the forces  $AO$  should be drawn, we notice that the couple  $Pp \sin \gamma$  should turn  $AO$  round  $A$  towards the direction of  $R$ .

**287. The Cylindroid.** This surface has been used by Sir R. Ball for the purpose of resolving and compounding wrenches. Following his line of argument we shall first examine a special case, and thence deduce the general solution.

To find the resultant of two wrenches of given intensities on screws of given pitches which intersect at right angles. Let the axes of these screws be the axes of  $x$  and  $y$ . Let  $X, Y$  be their forces;  $p, p'$  their pitches. Let  $R$  be the resultant of the forces  $X, Y$ , and let  $OA$  be its line of action. Let  $G$  be the resultant of the couples  $Xp, Yp'$  and let  $OB$  be its axis. Let the angle  $AOB = \phi$ . By resolving  $G$  into  $G \cos \phi$  about  $OA$  and  $G \sin \phi$



about a perpendicular to  $OA$ , it is clear (as in Art. 270) that  $G \cos \phi$  and  $R$  are together equivalent to a wrench having for its axis a straight line  $CD$  parallel to  $OA$  such that  $OC = (G \sin \phi)/R$ . The force along the axis is equal to  $R$  and the couple round it is equal to  $G \cos \phi$ .

Since  $G \cos \phi$  and  $G \sin \phi$  are the moments about  $OA$  of a force  $G$  perpendicular to  $OA$ , we see that, if  $\theta$  be the angle  $xOA$ ,

$$G \cos \phi = Xp \cos \theta + Yp' \sin \theta = R(p \cos^2 \theta + p' \sin^2 \theta)$$

$$G \sin \phi = -Xp \sin \theta + Yp' \cos \theta = R(p' - p) \sin \theta \cos \theta.$$

Let  $\rho$  be the pitch of the resultant wrench and  $z = OC$ , then

$$\left. \begin{aligned} \rho &= p \cos^2 \theta + p' \sin^2 \theta \\ z &= (p' - p) \sin \theta \cos \theta \end{aligned} \right\} \dots\dots\dots (1)$$

Also  $X = R \cos \theta$ ,  $Y = R \sin \theta$ .

If the wrenches on the axes  $Ox$ ,  $Oy$ , have given pitches  $p$ ,  $p'$ , and varying forces, the locus of the axis  $CD$  of the resultant wrench will be found by writing  $\tan \theta = y/x$  and eliminating  $\theta$  from the second of equations (1). We thus find

$$z(x^2 + y^2) - (p' - p)xy = 0 \dots\dots\dots (2)$$

This surface is called the cylindroid.

Describe a cylinder whose axis is the axis of  $z$ ; as  $CD$  turns round  $Oz$  beginning at  $Ox$  and ending at  $Oy$ , thus generating a quarter of the cylindroid, its intersection with the cylinder turns out a curve which is represented in the figure by the dotted line. In the next quarter of the surface, the dotted curve (not drawn) lies below the plane of  $xy$ , in the third quarter above and so on.

**288.** Each generating line of the cylindroid, such as  $CD$ , is the axis of a screw whose pitch is  $p \cos^2 \theta + p' \sin^2 \theta$ . Let us then describe the cylinder whose base is the conic  $px^2 + p'y^2 = H$ , where  $H$  is any constant. Let the generating line  $CD$  intersect the surface of the cylinder in  $D$ . Then the pitch of the screw whose axis is  $CD$  is obviously  $H/CD^2$ . The base of this cylinder has been called by Ball the pitch conic.

**289.** *The forces of any number of wrenches on a given cylinder being given, it is required to find the resultant wrench and the conditions of equilibrium.*

on the axes, it is clear that the moments of the force  $P$  about the axes are  $P \cos \theta \cdot p$ ,  $P \sin \theta \cdot p'$  and zero.

Taking all the wrenches, the six components are

$$\begin{aligned} X &= \Sigma P \cos \theta, & Y &= \Sigma P \sin \theta, & Z &= 0, \\ L &= \Sigma P \cos \theta \cdot p = Xp, & M &= \Sigma P \sin \theta \cdot p' = Yp', & N &= 0. \end{aligned}$$

These constitute two wrenches on the axes of  $x$  and  $y$ , with same two pitches as before.

By the definition of a cylindroid *the axis of the resultant wrench lies on the same cylindroid*. The pitch  $\rho$  and the altitude  $z$  of the resultant wrench are given by equations (1) of Art. 287.

**290.** The necessary and sufficient conditions of equilibrium are  $\Sigma P \cos \theta = 0$ ,  $\Sigma P \sin \theta = 0$ , for when these vanish all the conditions of equilibrium are satisfied. It immediately follows that *if the forces of wrenches on the same cylindroid when transferred to act at any one point are in equilibrium, then the wrenches themselves will be in equilibrium*.

For example, the wrenches on any three screws in the same cylindroid are in equilibrium if the force of each is proportional to the sine of the angle between the other two.

To find, also, the resultant wrench of two given wrenches on the same cylindroid we first find the resultant of their forces. The axis of the required wrench is parallel to this resultant axis and has the pitch appropriate to that axis.

**291.** We may use this theorem to find the resultant wrench of any two wrenches if we show that a unique cylindroid can be described so as to contain any two given screws.

To prove this, let  $CD$ ,  $C'D'$  be the axes of the two given screws, and let  $CC'$  be the shortest distance between them, then  $CC'$  must be the  $z$ -axis of the cylindroid. Let  $CC' = h$ , let  $\alpha$  be the inclination of the axes  $CD$ ,  $C'D'$  to each other, and  $\rho$ ,  $\rho'$  the pitches of the screws. These four quantities being given, we have to prove that one set of real values can be found for  $p$ ,  $p'$ ,  $(z, \theta)$ ,  $(z', \theta')$ . Taking the values given for  $\rho$ ,  $z$ ,  $\rho'$ ,  $z'$  in equations (1) of Art. 287 and joining to them the equations  $z - z' = h$ ,  $\theta - \theta' = \alpha$ , we can solve the six resulting equations. The result is that we find unique values for  $p$ ,  $p'$ , &c.

**292. Work of a wrench.** To find the work done by a wrench on a given screw when the body receives a virtual displacement


Let us first find the work done when a given *couple* is moved in its own plane from one position to another. This displacement may be constructed by first translating the couple parallel to itself until one extremity  $A$  of its arm  $AB$  assumes its new position, then rotating the translated couple about  $A$  until the other extremity  $B$  assumes its proper position. The work done by the two equal forces during the translation is clearly zero. The work done by the force at  $A$  during the rotation is also zero. It remains to find the work done by the force at  $B$ .

Let  $F$  be the force,  $a$  the length of the arm  $AB$ ,  $d\phi$  the angle of rotation. The work done by the force at  $B$  is evidently  $Fad\phi$ . If the angle of displacement is finite, the work done is found by integrating  $Fad\phi$ . Thus the *work done by a couple of moment is the product of the moment by the angle of rotation in its own plane*. See Art. 203.

Next let a couple be rotated about an axis in its own plane through any small angle  $d\phi$ . It is clear that the extremities of the arm begin to move perpendicular to the plane of the rotation. The virtual work done by each force is therefore zero.

**293.** Let us apply these two results to find the work done by a wrench twisted about any screw.

Let  $p, p'$  be the pitches of the screw and wrench respectively. Let  $\theta$  be the angle between their respective axes and let  $h$  be the shortest distance between them. We suppose that in the standard case, when  $\theta$  and  $h$  are positive, the positive direction of each axis is such that a force acting along it would produce rotation about the other axis in the positive direction; see Art. 265. Let  $R$  be the force of the wrench.



Take the axis of the screw as the axis of  $z$  and the shortest distance  $OH$  as the axis of  $x$ . Let  $HC$  and  $HB$  be drawn perpendicular to the axes of  $z$  and  $y$  respectively. The force  $R$  may be resolved into  $R \cos \theta$  along  $HC$  and  $R \sin \theta$  along  $HB$ . When the wrench is

couples  $Rp \cos \theta$  and  $Rp \sin \theta$  whose axes are  $HC$  and  $HB$ . The work of the former is  $Rp' \cos \theta d\phi$ , the work of the latter is zero. The whole work done is therefore

$$dW = Rd\phi \{(p + p') \cos \theta + h \sin \theta\}.$$

We notice that this is a symmetrical function of  $p$  and  $p'$ , so that if the two screws are interchanged the work is unaltered.

**294. Reciprocal screws.\*** Two screws are said to be reciprocal when a wrench acting on either does no work as the body is twisted about the other. The analytical condition that two screws are reciprocal is therefore

$$(p + p') \cos \theta + h \sin \theta = 0.$$

Thus, two intersecting screws are reciprocal when either they are at right angles or their pitches are equal and opposite.

It follows from the principle of virtual work that a body free to move only on a screw  $\alpha$  is in equilibrium if acted on by a wrench on any screw reciprocal to  $\alpha$ .

**295.** If a screw  $\sigma$  is reciprocal to each of two given screws, say  $\alpha$  and  $\beta$ , it is also reciprocal to every screw on the cylindroid containing  $\alpha$  and  $\beta$ . For a wrench on any third screw  $\gamma$  on this cylindroid may be replaced by two wrenches on the screws  $\alpha$  and  $\beta$ , if the forces on  $\alpha$  and  $\beta$  are the components of the force on  $\gamma$  (Art. 289). Since the virtual work of each of these when twisted along  $\sigma$  is zero, the screws  $\gamma$  and  $\sigma$  are reciprocal. We may say for brevity that the screw  $\sigma$  is reciprocal to the cylindroid.

**296.** A screw  $\sigma$  if reciprocal to a cylindroid must intersect one of the generators at right angles. The cylindroid, being a surface of the third order, will be cut by the screw  $\sigma$  in three points, and one screw of the cylindroid passes through each of these points. Each of these three screws intersects the screw  $\sigma$  and is reciprocal to it. It follows by Art. 294 that each of these is either perpendicular to  $\sigma$  or has a pitch equal and opposite to that of  $\sigma$ . But since the pitch  $\rho$  of a screw on the cylindroid is  $p \cos^2 \theta + p' \sin^2 \theta$  there are only two different screws on the same cylindroid of the same pitch, viz. those given by supplementary values of  $\theta$ . Hence the screw  $\sigma$  must intersect one of the three screws at right angles. Also, as it cannot be perpendicular to more than one screw on the cylindroid (unless it is the nodal line or  $z$  axis), the pitches of the two remaining screws must be each equal and opposite to that of  $\sigma$ .

**297. Ex. 1.** Show that the locus of a screw reciprocal to four screws (no three of which are on the same cylindroid) is a cylindroid.

Since a screw is determined by five quantities it is clear that, when the four conditions of reciprocity are fulfilled, the screw must *in general* be confined to a

through any two of its generators, then any screw on this cylindroid will all be reciprocal to the four given screws. The locus therefore would be, not a ruled surface, but a system of cylindroids.

Ex. 2. Prove that there is in general but one screw reciprocal to five screws. [As there are five conditions to be satisfied the number of screws is five. But if there were as many as two there would be a cylindroidal locus of screws.]

Ex. 3. Prove that any two reciprocal screws on the same cylindroid are parallel to conjugate diameters of the pitch conic.

Let  $\rho, \rho'$  be the pitches,  $z, z'$  the altitudes. Let  $z > z'$  and  $\theta > \theta'$ ; Art. 293. It will be seen that a force acting along the positive direction of the axis of the first screw would tend to produce rotation round the axis of the other in the negative direction. We therefore put  $h = z - z', \phi = -(\theta - \theta')$ . The condition that the screws are reciprocal is  $(\rho + \rho') \cos \phi + h \sin \phi = 0$ , Art. 294. Substituting for  $\rho, \rho', z, z'$  the values given in Art. 287, this reduces to  $p \cos \theta \cos \theta' + p' \sin \theta \sin \theta' = 0$ . This is the condition that the axes of the screws are parallel to conjugate diameters of the pitch conic, Art. 288.

### *On Conjugate Forces.*

**298. The nul plane.** *The locus of all the straight lines drawn through a given point  $O$ , and such that the moment of the system about each vanishes is a plane.*

This plane is called the *nul plane* of  $O$  and the point  $O$  is called the *nul point* of the plane. Any line about which the moment of the forces is zero is called a *nul line*.

To prove this proposition let us represent the system by a couple  $G$  and a force  $R$  at  $O$  as base. It is at once evident that the moment about a straight line through  $O$  cannot be zero unless it lies in the plane of the couple. *The nul plane may therefore also be defined as the plane of the principal couple at  $O$ .*

The names *nul-point* and *nul-plane* are due to Moebius, *Lehrbuch der Statische*, 1837. Instead of these the terms *pole* and *polar plane* have been used by Cremona, *Reciprocal Figures*, 1872, translated into French, 1885, into English, 1890. The term *focus* has also been used by Chasles, *Comptes Rendus*, 1843.

**299.** If any straight line in the nul plane of  $O$  and passing through  $O$  were a nul line, the moment of  $R$  about it would be zero. This requires that  $R$  should either be zero or

that the straight line  $AB$  is a nul line. Hence also the line  $AC$  must lie in the nul plane of  $B$ .

**301.** To find the equation to the nul plane of a given point  $(\xi\eta\zeta)$  referred to any system of rectangular axes.

It is clear that the direction cosines of the plane are proportional to the moments of the forces about axes meeting at the nul point. Hence by Art. 258 the required equation is

$$(L - \eta Z + \zeta Y)x + (M - \zeta X + \xi Z)y + (N - \xi Y + \eta X)z = L\xi + M\eta + N\zeta$$

Any straight line being given by its equations  $(x-f)/l = (y-g)/m = (z-h)/n$ , prove that it will be a nul line if

$$\begin{vmatrix} f & g & h \\ X & Y & Z \\ l & m & n \end{vmatrix} = Ll + Mm + Nn.$$

**302.** To find the nul point of a given plane we choose three points conveniently situated on it. The nul planes of these points intersect the given plane in the required nul point. Art. 300.


Ex. 1. If the system be referred to the central axis as the axis of  $z$ , prove that the coordinates of the nul point of the plane  $z = Ax + By + C$  are  $\xi = -pB$ ,  $\eta = -pA$ ,  $\zeta = C$ , where  $p$  is the pitch of the equivalent wrench.

Ex. 2. A plane intersects the central axis in  $C$  and makes an angle  $\phi$  with the axis. Show by reasoning similar to that of Art. 270, that the nul point  $O$  lies in the straight line  $CO$  drawn perpendicular to the central axis so that  $CO = \cot \phi \cdot \Gamma/K$ .

Ex. 3. The moments of the forces about the sides of a triangle  $ABC$  respectively  $M_1, M_2, M_3$ , and  $Z$  is the resolved force perpendicular to the plane of the triangle. Prove (1) that the trilinear coordinates of the nul point  $O$  of the system referred to the triangle  $ABC$  are  $M_1/Z, M_2/Z, M_3/Z$ ; (2) that the nul planes of the three corners  $A, B, C$  intersect the plane of the triangle in  $AO, BO, CO$  respectively.

**303. Conjugate forces.** Let  $O$  be any point on a given straight line  $OA$ . Let the system be reduced to a couple  $G$  and a force  $R$  at  $O$  as base. Pass a plane through  $R$  and the given straight line  $OA$ , and let it cut the plane  $BOC$  of the couple in  $OB$ .

Let us resolve the force  $R$  by *oblique resolution* into two forces, one of which  $F$  acts along  $OA$  and the other  $F'$  acts along  $OB$ . This force  $F'$  may be compounded with the forces of the couple into a single force which also acts in the plane of the couple. Its line



of action is parallel to  $OB$  and distant  $G/F'$  from it. It follows that *all the forces of the system are equivalent to some force  $F$  acting along any assumed straight line  $OA$  together with a second force  $F'$  which acts in the nul plane of the point  $O$ .* The forces are given by  $F \sin AOB = R \sin ROB$ ,  $F' \sin AOB = \bar{R} \sin ROA$ .

The forces  $F, F'$  are called *conjugate forces*, and their lines of action *conjugate lines*.

**304.** Since  $O$  is any point on the straight line  $OA$ , it follows that *when  $O$  travels along a straight line, the nul plane of  $O$  always passes through the conjugate and turns round it as an axis.*

**305.** *Vanishing of the Invariant  $I$ .* When the force  $R$  is zero or lies in the nul plane  $BOC$ , the system reduces to either a single couple or a single force. In both these cases every point in the plane  $BOC$  is a nul point.

If the system is equivalent to a single couple  $R=0$ , and if the assumed line  $OA$  is inclined to the plane of the couple the force  $F$  along it is zero; the conjugate is at infinity and its force also is zero. If  $OA$  is in the plane of the couple, the force along it forms one force of the couple while the conjugate is the other force, the distance between the conjugates, i.e. the arm of the couple, being arbitrary.

If the system is equivalent to a single resultant,  $OR$  lies in the plane  $BOC$ . If the assumed line  $OA$  does not intersect the single force, the force  $F$  along  $OA$  is zero, the conjugate being the single resultant. If  $OA$  intersects the single resultant, the conjugate is any line in their plane passing through that intersection, the conjugate forces being found by resolving the single resultant in their directions.

Conversely, since  $I = FF'r \sin \theta$ , (Art. 281) we see that *when the invariant is zero either one conjugate force is zero, or the two conjugates lie in one plane.*

**306.** *To find the conjugate of a nul line.* In this case  $OA$  lies in the nul plane of  $O$ , and if  $R$  is not zero and does not also lie in that plane the straight lines  $OA, OB$ , are opposite to each other, Art. 303. The components of  $R$ , viz.  $F$  and  $F'$ , are therefore both infinite so that the two forces  $F, F'$  act in opposite directions along the same straight line  $OA$ . Such lines may therefore be called *self-conjugate*. They have also been called *double lines* by Cremona.

In the limiting case when the invariant  $I$  is zero, any line lying in the plane of the single couple or intersecting the single resultant is a line of nul moment. We have seen above that their conjugates are indeterminate.



It follows that the conjugate of  $DE$  must also intersect them its force must be zero. If  $I$  is finite the conjugate force can also lie in that plane or be zero, it must therefore pass through the nul point  $O$ . If  $I = 0$  every point in the plane is a nul point and the theorem is again true.

**308.** To find the equation of the conjugate of the given line  
 $(x-f)/l = (y-g)/m = (z-h)/n \dots\dots\dots (1)$

It follows from Art. 304, that if any two points  $O, O'$  chosen on the given line  $OA$ , their nul planes intersect on the conjugate. The nul planes of the point  $(fgh)$  and of another point at infinity whose coordinates are proportional to  $l, m, n$  (Art. 301) respectively

$$(L-gZ+hY)x + (M-hX+fZ)y + (N-fY+gX)z = Lf + Mg + Nh \\ (-mZ+nY)x + (-nX+lZ)y + (-lY+mX)z = Ll + Mm + Nn.$$

These are the equations to the conjugate. They also take the form

$$\begin{vmatrix} x & y & z \\ X & Y & Z \\ f & g & h \end{vmatrix} = L(f-x) + M(g-y) + N(h-z), \quad \begin{vmatrix} x & y & z \\ X & Y & Z \\ l & m & n \end{vmatrix} = Ll + Mm + Nn$$

The line of action of the force  $F$  being given as above by the equations (1), an analytical expression for the magnitude of  $F$  can be found which may be used when the position and magnitude of the conjugate force  $F'$  are not required. If we reverse the force  $F$  and join it to the given system, the compound system will be equivalent to a single force. The invariant of the compound system is therefore equal to zero. If  $l, m, n$  are the actual direction cosines of the given line of action of the force  $F$ , the components of the compound system are

$$\begin{aligned} X' &= X - Fl, & L' &= L + Fmh - Fng, \\ Y' &= Y - Fm, & M' &= M + Fnf - Flh, \\ Z' &= Z - Fn, & N' &= N + Flg - Fmf. \end{aligned}$$

Equating the invariant  $L'X' + M'Y' + N'Z'$  to zero, we find


$$\frac{LX + MY + NZ}{F} = Ll + Mm + Nn - \begin{vmatrix} f & g & h \\ X & Y & Z \\ l & m & n \end{vmatrix}.$$

In this manner a unique value of  $F$  has been found. The value of  $F$  can be infinite when the right-hand side is zero; this occurs when the given line is a nul line, Art. 301.

The value of  $F$  being known, all the six components of the compound system are known. The magnitude and line of action of the single resultant  $F''$  may then be found by equations (4) of Art. 273, whence  $F'^2 = X'^2 + Y'^2 + Z'^2$  and  $\Gamma = 0$ .

**309.** *To determine the arrangement of the conjugate forces about the central axis.*

We know by Art. 285 that the central axis intersects at right angles the shortest distance between any two conjugates. Let  $Oz$  be the central axis;  $R, \Gamma$ , the given force and couple. Let  $F, F'$ , be two conjugate forces acting along  $AF, A'F'$ ;  $AA'$  being the shortest distance between them. Let  $OA = a, OA' = a'$  measured positively from  $O$  in opposite directions,  $h = a + a'$ .



The force  $R$  may be replaced by two parallel forces acting at  $A, A'$ , respectively equal to  $Ra'/h$  and  $Ra/h$ , Art. 79. The couple  $\Gamma$  is equivalent to two forces acting at the same points parallel to the axis of  $y$  equal to  $\pm \Gamma/h$ . Since the forces acting at  $A, A'$  have  $F, F'$  for their resultants, we find

$$\left. \begin{aligned} \Gamma &= Ra' \tan \gamma, & F^2 h^2 &= \Gamma^2 + R^2 a'^2 \\ \Gamma &= Ra \tan \gamma', & F'^2 h^2 &= \Gamma^2 + R^2 a^2 \end{aligned} \right\} \dots\dots\dots (1).$$

When any arbitrary line  $AF$  is chosen as the seat of one force,  $a$  and  $\gamma$  are given; these equations then determine  $F, F', \gamma', a'$ . We notice also that since the resolved parts of  $F, F'$  in the plane  $xy$  are equivalent to the couple  $\Gamma$ ,  $F \sin \gamma = F' \sin \gamma' = \Gamma/h$ .

**310.** If the figure is turned round  $Oz$  as an axis of revolution, the conjugates  $AF, A'F'$  describe co-axial hyperboloids of revolution whose real axes  $a, a'$  are connected by the equations (1). The imaginary axes are  $a \cot \gamma$  and  $a' \cot \gamma'$ ; it is

intersect in a nul line, whose locus when  $a$  varies is the paraboloid  $p$  is the pitch of the wrench.

Ex. Any two systems of forces being given show that the common system of conjugate lines real or imaginary. If  $OO' = 2c$  distance between the axes of the equivalent wrenches,  $C$  the mid-point, prove that the distances of the common conjugates from  $C$  are the roots of the quadratic  $x^2 + (p - p') \cot \theta x + pp' - c^2 - (p + p') c \cot \theta = 0$  where  $p, p'$  are the pitches and  $\theta$  the angle between the axes.

**312.** Ex. 1. If two straight lines intersect in a point  $O$ , their nul planes intersect, and lie in the nul plane of  $O$ . Art. 303.

Ex. 2. A transversal intersects a force and its conjugate. Prove that the intersection is the nul point of the plane which contains the two forces and the other force.

For every straight line drawn through one intersection to cut the other, a nul line, see also Art. 303.

Ex. 3. The locus of a straight line drawn through a given point  $O$  such that the moments about it of two conjugate forces  $F, F'$  have a given ratio  $\mu$  which becomes the nul plane of  $O$  when  $\mu = -1$ . Whatever the ratio  $\mu$  be, this plane passes through the intersection of the two planes which contain the forces, and makes angles  $\phi, \phi'$  with these two planes. Prove that the given ratio  $\mu$  is equal to  $Fp \sin \phi : F'p' \sin \phi'$ . Here  $p$  and  $p'$  are the distances of  $O$  from the given straight lines.

**313.** Ex. 1. Two arbitrary points  $A, B$  are taken on a nul line. Prove that the system can be reduced to two conjugate forces acting at  $A$  and  $B$  making a given angle  $\phi$  with  $AB$ . Prove also that if  $\phi$  is varied the nul plane at each point is the nul plane of the other point.

If  $\phi, \phi'$  are the angles the conjugate forces make with  $AB$ , prove that  $G \cot \phi + G' \cot \phi' = aX$ , where  $G, G'$  are the principal couples at  $A, B$  along  $AB$  and  $a = AB$ .

To prove this take  $A$  as base (Art. 257) and change the couples to  $B$  whose forces pass through  $A$  and  $B$ .

Ex. 2. Two planes being given which intersect in a nul line, prove that the system can be reduced to two conjugates, one in each plane. [Take the nul points of the planes.]

Ex. 3. If  $AM, BN$  are two nul lines, show that the system can be reduced to two finite conjugate forces intersecting both  $AM, BN$ .

Let  $A$  be any point on  $AM$ , the nul plane of  $A$  will pass through  $BN$  in some point  $B$ . The rest follows from Ex. 1.

**314.** The characteristic of a plane is the conjugate of the nul line through its point, Chasles, *Comptes Rendus*, 1843.

Let  $AB$  be the straight line,  $CD$  its conjugate. The axis of the principal couple at any point  $O$  on  $AB$  is perpendicular to the plane  $OCD$ , Art. 303. If the straight line  $AB$  were turned round  $CD$  as an axis of rotation through any small angle, each point  $O$  on  $AB$  would move a small space perpendicular to the plane  $OCD$ , i.e. it would move a small space along the axis of the principal couple. For these axes all intersect two straight lines, viz.  $AB$  and its consecutive position. These lines are all parallel to a plane which is perpendicular to  $CD$ . The locus is therefore a hyperbolic paraboloid.

### *Theorems on forces.*

**315. Three forces.** *If three forces are in equilibrium, they must lie in one plane.*

Let  $A$  and  $B$  be any two points on two of the forces. Since the moment about the straight line  $AB$  is zero, this straight line must intersect the third force in some point  $C$ . Let  $A$  be fixed and let  $B$  move along the second line; the straight line  $AB$  will describe a plane, and the second and third forces must lie in this plane. If we fix  $C$  and let  $B$  move as before, we see that the first force must also lie in the same plane.

Ex. 1. The forces of a system can be reduced to three forces  $F_1, F_2, F_3$  acting along the sides of an arbitrary triangle  $ABC$  together with three other forces  $Z_1, Z_2, Z_3$  which act at the corners  $A, B, C$  at right angles to the plane of the triangle.

Resolve each force  $P$  of the system into two, one in the plane  $ABC$  and the other perpendicular to that plane. The former can be replaced by three forces acting along the sides (Art. 120, Ex. 2), and the latter by three parallel forces at the corners (Art. 86, Ex. 1). If  $P$  is parallel to the plane  $ABC$  we can transfer it to act in the plane by introducing a couple. Turning the couple round in the plane we can include its forces among those normal to  $ABC$ .

Ex. 2. The forces of a system can be reduced to three forces which act at the corners of an arbitrary triangle and satisfy three other conditions.

Replace  $F_1$  by  $F_1 + u$  at  $B$  and  $-u$  at  $C$ ;  $F_2$  by  $F_2 + v$  at  $C$  and  $-v$  at  $A$ ;  $F_3 + w$  at  $A$  and  $-w$  at  $B$ . Compounding the forces at the corners, the arbitrary quantities  $u, v, w$  may be used to satisfy three conditions.

Ex. 3. A system of forces is reduced to three acting at fixed points  $A, B, C$ . If the force at  $A$  is fixed in direction, prove that each of the other two lies in a fixed plane. Show also that these planes intersect along the side  $BC$ .

[Coll. Ex., 1]

one system of generators. An infinite number of transversals be drawn to cut three of the forces, but each must intersect fourth force also, for otherwise the moment of the four forces about that transversal is not zero. Taking any three of the transversals as directors, the four forces lie on the corresponding hyperboloid.

The following theorems will serve as examples, as the proofs are only briefly given.

Ex. 1. If  $n$  forces act along generators of the same system and have a resultant, prove by drawing transversals that the resultant acts along a generator of the same system.

Ex. 2. When two of the forces  $P, P'$ , act along generators of one system and two  $Q, Q'$ , along generators of another system, they form a skew quadrilateral. The properties of such a combination of forces have been already considered in Art. 103. Their invariants are given in Arts. 317 and 323.

Prove, by drawing transversals through the intersection of  $P$  and  $Q'$ , that the four forces cannot be in equilibrium except when they lie in one plane.

Ex. 3. When three of the forces  $P_1, P_2, P_3$ , act along generators of one system and the fourth  $Q$  along a generator of the other system, prove that they cannot be in equilibrium except when all the forces lie in a plane. For if every transversal of  $P_1, P_2, P_3$  could intersect  $Q$ , this last would intersect all the generators of its own system.

Ex. 4. Four forces act along generators of the same system of a hyperboloid. Their magnitudes are such that if transferred parallel to themselves to act at any point they would be in equilibrium. Prove that they are in equilibrium when acting along the generators.

Let  $Q$  be any generator of the other system, which therefore intersects the four forces. Transfer the forces to act at any point of  $Q$ , then the transferred forces are in equilibrium and the axes of the four couples thus introduced are perpendicular to  $Q$ . The four forces are therefore equivalent to a resultant couple such that either its moment is zero or its axis is perpendicular to every position of  $Q$ . The latter supposition is impossible. Plücker and Darboux.

Ex. 5. If four forces  $P_1, P_2, P_3, P_4$  are in equilibrium, prove that the invariant of any two is equal to that of the remaining two (this theorem is due to Chasles). Also the invariant of any three of the forces is zero.

Reversing the directions of  $P_3, P_4$ , the forces  $P_1, P_2$  become equivalent to  $P_3, P_4$ . Their invariants are therefore equal.

**317.** *Analytical discussion of the hyperboloid.* Refer system to the axes of the hyperboloid as coordinate axes, and  $a, b, c \sqrt{-1}$ , be these axes. Let any generator be

$$\frac{x - a \cos \theta}{a \sin \theta} = \frac{y - b \sin \theta}{-b \cos \theta} = \frac{z}{\pm c},$$

where  $\theta$  is the eccentric angle of the intersection with the plane of  $xy$ , and the generator belongs to one system or the other according to the sign of  $c$ . Let  $P$  be the force along the generator,  $X, Y, Z, L, M, N$  its six components. We see that

$$X = \pm \frac{a}{c} Z \sin \theta, \quad Y = \mp \frac{b}{c} Z \cos \theta, \quad L = bZ \sin \theta, \quad M = -aZ \cos \theta, \quad N = \pm cZ$$

where all the upper signs are to be taken together.

**Ex. 1.** If four forces act along generators of the same system prove that the six equations of equilibrium reduce to the three  $\Sigma Z \sin \theta = 0$ ,  $\Sigma Z \cos \theta = 0$ ,  $\Sigma Z = 0$ . This gives an analytical proof of the theorem in Art. 316, Ex. 4.

**Ex. 2.** Prove that the invariant  $I$  of two forces which act along generators of the same system is  $I = \mp \frac{2ab}{c} Z_1 Z_2 \text{versin}(\theta_1 - \theta_2)$ . If the forces act along generators of different systems, their invariant is zero because the generators intersect. If several forces act along several generators, the invariant is the sum of the invariants taken two and two, Art. 281.

**Ex. 3.** When four generators of the same system are given, the ratios of the equilibrium forces are given by

$$\frac{Z_1^2}{\text{vers}(\theta_2 - \theta_3) \text{vers}(\theta_3 - \theta_4) \text{vers}(\theta_4 - \theta_2)} = \frac{Z_2^2}{\text{vers}(\theta_3 - \theta_4) \text{vers}(\theta_4 - \theta_1) \text{vers}(\theta_1 - \theta_3)}$$

These may be obtained by equating the invariants two and two, as in the proof of Cayley's theorem, Art. 316.

**Ex. 4.** Four forces in equilibrium act along four generators of a hyperboloid and intersect the plane of the real axes in  $A_1, A_2, A_3, A_4$ . Show that the real parts of the forces parallel to the imaginary axis are proportional to the areas of the triangles  $A_2 A_3 A_4, A_3 A_4 A_1$  &c., the forces at adjacent corners of the quadrilateral  $A_1 A_2 A_3 A_4$  having opposite signs.

**Ex. 5.** Forces act along generators of the same kind, say  $c$  positive. Show that the pitch  $p$  of the equivalent screw lies between  $-ab/c$  and the greater of the quantities  $bc/a$  and  $ca/b$ . For  $p = \frac{I}{R^2} = \frac{\Sigma L \cdot \Sigma X + \&c.}{(\Sigma X)^2 + \&c.} = abc \frac{\eta^2 + \xi^2 - 1}{a^2 \eta^2 + b^2 \xi^2 + c^2}$  where  $\eta, \xi$  have been written for  $\Sigma Z \cos \theta / \Sigma Z$  and  $\Sigma Z \sin \theta / \Sigma Z$ . We see at once that  $p$  is positive and  $p - bc/a$  negative if  $b > a$ .

**Ex. 6.** Forces act along generators of the same system and the pitch  $p$  of the equivalent screw lies between  $-ab/c$  and the greater of the quantities  $bc/a$  and  $ca/b$ .

Ex. 7. Forces act along generators of the same system and admit of a single resultant, which intersects the plane of  $xy$  in  $D$ . Prove that  $OD$  and the projection of the resultant force are parallel to conjugate diameters.

Ex. 8. Forces act upon a rigid body along generators of the same system of a hyperboloid. Prove that the necessary and sufficient condition of their being reducible to a single resultant is that their central axis should be parallel to one of the generating lines of the asymptotic cone. [Math. Tripos, 1877.]

Ex. 9. A system of forces have their directions along any non-intersecting generators of a hyperboloid of one sheet; show that the resultant couple at the centre of the hyperboloid lies in the diametral plane of the resultant force, and the principal moment is  $\frac{abcR}{a^2 + b^2 - c^2 - D_1^2 - D_2^2}$ ;  $D_1$  and  $D_2$  being the semi-axes of the section of the hyperboloid by the plane of the couple, and  $a, b, c$  the semi-axes of the surface, and  $R$  the resultant force. Explain the difficulty in the geometrical interpretation of these results for a single force. [Math. Tripos, 1880.]

**18. Relation of four forces to a tetrahedron.** Ex. 1. Forces act at the centres of the circles circumscribing the faces of a tetrahedron perpendicular to the faces and proportional to their areas. Prove that they are in equilibrium if they act either all inwards or all outwards.

Ex. 2. Forces act at the corners of a tetrahedron perpendicularly to the opposite faces and proportional to their areas. Prove that they are in equilibrium if they act either all inwards or all outwards. [Math. Tripos, 1881.]

Let  $ABCD$  be the tetrahedron,  $AK, BL$  &c. the perpendiculars. Since the product of each perpendicular into the area of the corresponding face is equal to six times the volume of the tetrahedron, the forces are inversely proportional to the perpendiculars along which they act. Let the forces be  $\mu/AK, \mu/BL$  &c.

Let us resolve the force  $\mu/AK$  into three components which act along the edges  $AC, AD$ . The component  $F$  which acts along  $AB$  is found by equating the moments perpendicular to the plane  $ACD$ . This gives  $F \frac{BL}{AB} = \frac{\mu}{AK} \cos \theta$ , where  $\theta$  is the angle between the perpendiculars  $AK$  and  $BL$ . In the same way we resolve the force  $\mu/BL$  into components along the edges. The component  $F'$  which acts along  $BA$  is found from  $F' \cdot \frac{AK}{AB} = \frac{\mu}{BL} \cos \theta$ . Hence  $F$  and  $F'$  are equal and opposite. In the same way it may be shown that the forces along all the other edges are equal and opposite. The system is therefore in equilibrium.

Ex. 3. Forces act at the centres of gravity of the four faces of a tetrahedron perpendicular to those faces and proportional to them in magnitude, all inwards or all outwards. Prove that they are in equilibrium.

Joining the centres of gravity we construct an inscribed tetrahedron, the faces of which are parallel to those of the former and proportional to them in area. The forces act at the corners of this new tetrahedron and are therefore in equilibrium.

**Ex. 5.** Forces act at the middle points of the edges of a closed polyhedron, in directions bisecting the angles between the adjacent faces, and having magnitudes proportional to the product of the length of the edge by the cosine of half the angle between the faces. Prove that they are in equilibrium.

Let forces act at the middle points of the sides of each face in the plane of the face perpendicularly to and proportional to the sides. These are in equilibrium by Art. 37. Compounding the forces at each edge the theorem follows.

**319. Normal forces on surfaces.** **Ex. 1.** Forces act normally at every element of a closed surface. Prove that they are in equilibrium if each force is either (1) proportional to the area of the element, or (2) proportional to the product of the area by  $\frac{1}{\rho} + \frac{1}{\rho'}$  where  $\rho, \rho'$  are the principal radii of curvature.

Since the surface may be regarded as the limiting case of a polyhedron, the first theorem follows from Ex. 4.

By drawing the lines of curvature the surface may be divided into rectangular elements which may be regarded as the faces of a polyhedron. The second theorem then follows from Ex. 5. Let  $ABCD$  be any element, the external angle between the faces which meet in  $BC$  is  $AB/\rho$ . The force across this edge is therefore  $\frac{1}{2}BC \cdot AB/\rho$  and ultimately acts perpendicularly to the element.

M. Joubert deduces the second of these theorems from the first. He also deduces from the second that normal forces proportional to the quotient of each elementary area by  $\rho\rho'$  are in equilibrium. *Liouville's J.* vol. XIII., 1848.

**Ex. 2.** One-eighth of an ellipsoid is cut off by the principal planes, and along the normal at any point a force acts proportional to the element of surface at that point. Show that all these forces are equivalent to a single force acting along the line  $a(x - 4a/3\pi) = b(y - 4b/3\pi) = c(z - 4c/3\pi)$ , where  $2a, 2b, 2c$  are the principal axes of the ellipsoid. [June Exam.]

**320. Five forces.** *If five finite non-intersecting forces are in equilibrium, they must intersect two straight lines which may be real or imaginary.* Möbius.

First, we shall prove that any four straight lines  $a, b, c, d$  can be cut by two transversals. For, describing the hyperboloid which has  $a, b, c$  for directors we notice that the line  $d$  cuts this hyperboloid in two points real or imaginary. One generator of the system opposite to  $a, b, c$  passes through each of these points and therefore intersects the straight lines  $a, b, c$  as well as  $d$ . Assuming this lemma we draw the two transversals of any four of the forces. Each of these must intersect the fifth force, for otherwise the moments about them would not be zero. These two transversals may be called the *directors* of the five forces.



**321.** Let the shortest distance between two straight lines be taken as axis of  $z$ . Let any five forces intersect these straight lines at distances  $(r_1 r_1')$   $(r_2 r_2')$  &c. from that axis, and let  $Z_1, Z_2$  &c. be the  $z$  resolutes of these forces respectively. Prove that the conditions of equilibrium are  $\Sigma Z = 0$ ,  $\Sigma Zr = 0$ ,  $\Sigma Zr' = 0$ ,  $\Sigma Zrr' = 0$ .

Let the origin bisect the shortest distance between the two directors of the forces, and let this shortest distance be  $2c$ . Let  $2\theta$  be the angle between the directors, and let the axes of  $x$  and  $y$  be its bisectors. The equation to any force may then be written

$$(x - r \cos \theta)/(r - r') \cos \theta = (y - r \sin \theta)/(r + r') \sin \theta = (z - c)/2c$$

Writing  $1/\mu^2 = (r - r')^2 \cos^2 \theta + (r + r')^2 \sin^2 \theta + 4c^2$ ,

and representing the forces by  $P_1 \dots P_5$ , the equations of equilibrium formed by resolving along the axes are

$$\Sigma P\mu(r - r') \cos \theta = 0, \quad \Sigma P\mu(r + r') \sin \theta = 0, \quad 2\Sigma P\mu c = 0.$$

The equations of moments are

$$\begin{aligned} \Sigma (yZ - zY) &= \Sigma P\mu(r - r')c \sin \theta = 0, \\ \Sigma (zX - xZ) &= -\Sigma P\mu(r + r')c \cos \theta = 0, \\ \Sigma (xY - yX) &= 2\Sigma P\mu r r' \sin \theta \cos \theta = 0. \end{aligned}$$

When  $c$  and  $\sin 2\theta$  are not zero, these six equations reduce to the four given above. These four equations determine the ratios of the five forces  $P_1 \dots P_5$  when the intersections of their lines of action with the directors are known.

**322.** Let the two directors be moved so that either their mutual inclination  $2\theta$  or their distance apart  $2c$  is altered, but let them continue to intersect the axis of  $z$  at right angles. It follows from these results that equilibrium will continue to exist provided (1) the forces always intersect the directors at the same distances from the axis of  $z$ , and (2) the  $z$  component of each is unchanged.

When five forces in equilibrium are given in one plane, which besides the three conditions of equilibrium also satisfy the condition  $\Sigma Zrr' = 0$ , we may by this theorem construct five forces in space which are also in equilibrium.

**323.** Ex. 1. Any number of forces intersect two directors in the points  $ABC \dots, A'B'C' \dots$ , prove that the invariant  $I = \sin 2\theta \Sigma Z_1 Z_2 \cdot AB \cdot A'B'/2c$ .

Ex. 2. Four forces act along the sides of a skew quadrilateral taken in order

$$\alpha | C'D' \cdot B'E' \cdot C'E' | = \beta | D'E' \cdot C'A' \cdot E'C' \cdot D'A' | = \alpha c.$$

Ex. 5. Show that the force along  $AA'$  is zero when the other two directors in the same anharmonic ratio. This is also a known property of four generators of a hyperboloid intersected by two fixed lines.

Ex. 6. Show that, if the algebraic sums of the moments of forces about (1) three, (2) four, (3) five straight lines are zero, the system (1) lies along one of the generators of a system of concentric hyperboloids, (2) intersects a fixed straight line at right angles, (3) is fixed. [M.]

Replace the system by two conjugate forces, one of which cuts the three straight lines. Then the other force also cuts the same three lines, and therefore rectilinear generators of a fixed hyperboloid. The force is fixed once by Art. 317, Ex. 6.

Choose one of the conjugates to cut the four given straight lines. The other also cuts the same four lines. Both these forces are fixed in position. By Art. 285 the central axis cuts the shortest distance at right angles.

If the moments about five straight lines are zero, we can by the same four forces obtain two straight lines each of which is cut at right angles by the central axis. The central axis is therefore fixed.

**324. Six forces\*.** Analytical view. *Force and position of six straight lines are in equilibrium. Show that, if five lines and a point on the sixth being given, the sixth line lies in a certain plane.*

Let a force  $P$  be given by its six components  $P\lambda, P\mu, P\nu$ , Art. 260. If  $(fgh)$  be any point on it, then

$$\lambda = gn - hm, \quad \mu = hl - fn, \quad \nu = fm - gk.$$

Let us suppose that each of the six forces  $P_1 \dots P_6$

\* The theorem that the locus of the sixth force is a plane is given in *Lehrbuch der Statik*, 1837. But he omitted to give a construction. This defect was supplied by Sylvester "sur l'involution des droites dans l'espace considérées comme des axes de rotation." *Comptes Rendus* 1864. Several theorems on the relative positions of the fifth and sixth lines, "involution" and "polar plane" are due to him. In a second volume he states as the criterion for the involution of six lines that the moments (12) &c. being replaced by secants, when the equations of the straight lines are given in their most general form. He mentions that Cayley had found a determinant which is the criterion, given by himself and which would do as well to define involution. It is given by Spottiswoode, *Comptes Rendus*, 1868. See also *Determinants*. Analytical and statical investigations connected with this are given by Cayley, "On the six coordinates of a line," *Camb. Math. J.* 1867. The extension of the determinant of Art. 327 to six lines is given by Sir R. Ball, *Theory of Screws*, 1876.

way, so that  $(l_1, m_1, n_1, \lambda_1, \mu_1, \nu_1)$  ( $l_2$ , &c.) &c. may be regarded as the coordinates of their several lines of action.

Since the six forces are in equilibrium, they must satisfy the six necessary and sufficient equations given in Art. 25. We have therefore

$$\Sigma Pl = 0, \quad \Sigma Pm = 0, \quad \Sigma Pn = 0; \quad \Sigma P\lambda = 0, \quad \Sigma P\mu = 0, \quad \Sigma P\nu = 0$$

These six equations will in general require that each of the forces  $P_1 \dots P_6$  should be zero. But if we eliminate the ratios of these forces we obtain a determinantal equation which is the condition that the forces should be finite. This determinant has for its six rows the six coordinates of the six given straight lines, viz.

$$\begin{vmatrix} l_1, m_1, n_1, g_1n_1 - h_1m_1, h_1l_1 - f_1n_1, f_1m_1 - g_1l_1 \\ l_2, \text{ \&c.} \end{vmatrix} = 0.$$

Let us suppose that five of the lines are given and that the sixth is to pass through a given point  $(f_6, g_6, h_6)$ . Let  $(x, y, z)$  be the current coordinates of the sixth line, then writing for  $(l_6, m_6, n_6)$  in the last row their ratios  $x - f_6, y - g_6, z - h_6$  this determinantal equation becomes the equation to the locus of the sixth line. It is clearly of the first degree and this proves that the locus of the sixth line is a plane.

**325.** When six lines are so placed that forces can be found to act along them and be in equilibrium, *the six lines are said to be in involution*. The plane which is the locus of the sixth line when a point  $O$  in the line is given is called *the polar plane of  $O$  with regard to the five given lines*.

When five lines are so placed that forces can be found to act along them and be in equilibrium, they are in involution with every line taken as a sixth and the force along that sixth is zero. This is briefly expressed by saying that the five lines are in involution.

When lines are in involution any force acting along one

Let  $(l, m, n, \lambda, \mu, \nu)$  be the six coordinates of its axis. Then, resolving parallel to the axes of coordinates and taking moments as before, we have

$$\begin{aligned}\Sigma Pl &= 0, & \Sigma Pm &= 0, & \Sigma Pn &= 0. \\ \Sigma P(\lambda + pl) &= 0, & \Sigma P(\mu + pm) &= 0, & \Sigma P(\nu + pn) &= 0.\end{aligned}$$

Eliminating the forces, we have the following six-rowed determinantal equation in which the first line only is written down.

$$\begin{vmatrix} l_1, m_1, n_1, & \lambda_1 + p_1 l_1, & \mu_1 + p_1 m_1, & \nu_1 + p_1 n_1 \\ \cdot & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot \end{vmatrix} = 0.$$

The other lines are repetitions of the first with different suffixes. This determinant has been called the *sexiant* by Ball.

*By giving to the pitches  $p_1 \dots p_6$  of these screws values either zero or infinity we can express the condition that  $m$  forces and  $n$  couples ( $m + n = 6$ ) connected with six given straight lines should be in equilibrium.*

**327.** If we take moments in turn for the six forces  $P_1 \dots P_6$  about their lines of action, we obtain six equations of the form

$$P_1 \cdot 0 + P_2(12) + P_3(13) + P_4(14) + P_5(15) + P_6(16) = 0,$$

where (12) represents the mutual moment of the lines of action of  $P_1, P_2$  (Art. 264). Eliminating the six forces, we obtain a determinant of six rows equated to zero. This is the necessary condition that the six lines should be in involution.

Taking any five of these equations, we can find the ratios of the six forces. Thus, if  $I_{12}$  represent the minor of the constituent in the first row and second column, we have

$$P_1/I_{11} = P_2/I_{12} = P_3/I_{13} = \&c.$$

Since by Salmon's higher algebra  $I_{11}I_{22} = I_{12}^2$ , we may deduce the more symmetrical ratios

$$P_1^2/I_{11} = P_2^2/I_{22} = P_3^2/I_{33} = \&c.$$

This symmetrical form for the ratios of the forces is given by Spottiswoode in the *Comptes Rendus* for 1868.

**328.** *We have thus two determinants to define involution. One expresses the condition in terms of the coordinates of the six lines, the other in terms of their mutual moments. These are not*

independent, for one determinant is the square of the other. This may be shown by squaring the first and remembering the expression for the mutual moment of two lines given in Ex. 1 of Art. 267.

**329.** *Let  $A, B, C, D, E, F$  be six lines not in involution, then any given force  $R$  may be replaced by six components acting along these six lines.*

Let  $l'm'n'\lambda'\mu'\nu'$  be the six coordinates of the line of action of  $R$ . If  $P_1 \dots P_6$  are the six equivalent forces on the given lines, we have by Art. 324  $\Sigma Pl = Rl'$ , &c.,  $\Sigma P\lambda = R\lambda'$ , &c. These six equations will determine real values for  $P_1 \dots P_6$ . They will be finite if the determinant of Art. 324 is not zero, i.e. if the given lines are not in involution.

We notice that the value of  $P_1$  is zero if the determinant formed by replacing  $l_1, m_1$ , &c. in the first row by  $l'm'$  &c. is zero, i.e. if the line of action of  $R$  is in involution with  $BCDEF$ .

Ex. Show that in general there is only one way of reducing a system of forces to six forces which act along six given straight lines. If the lines of action of five of the forces be given and the magnitude and point of application of the sixth, prove that the line of action of the sixth will lie on a certain right circular cone.

[Coll. Exam., 1887.]

**330.** *If the moments of a system of forces about six straight lines not in involution are zero, the forces are in equilibrium.*

If they are not in equilibrium let  $(\Gamma, R)$  be their equivalent wrench. Let the axis of this wrench be taken as the axis of  $z$ , and let the six lines make angles  $(\theta_1, \phi_1, \psi_1)$ ,  $(\theta_2, \phi_2, \psi_2)$ , &c. with the axes of  $z, x, y$ . Let  $(r_1, r_1', r_1'')$ ,  $(r_2, r_2', r_2'')$  &c. be the shortest distances between the six lines and the axes of  $z, x, y$ .

Since each of the six lines must be a nul line with regard to the wrench, we have for each  $\Gamma \cos \theta + Rr \sin \theta = 0$ . We shall now prove that, if these six equations can be satisfied by values of  $\Gamma$  and  $R$  other than zero, the six lines are in involution.

If forces  $P_1 \dots P_6$  can be found acting along these six lines in equilibrium, they must satisfy the six necessary and sufficient

the forces can be found. Hence the lines must be in involution.

If the lines are not in involution, they cannot all six be null lines of a wrench, i.e.  $\Gamma$  and  $R$  must both be zero. It follows that *six equations of moments about six straight lines are insufficient to express the conditions of equilibrium of a system if those six lines are in involution.*

**331.** *If a system of forces is such that its moment about each of  $m$  lines is zero, and its resolute along each of  $n$  lines is also zero, where  $m + n = 6$ , the system is in equilibrium, provided the six lines are such that forces acting along the  $m$  lines and couples having their axes placed along the  $n$  lines cannot be in equilibrium. The forces and couples are not to be all zero.*

For the sake of brevity, let us suppose that the moments of the system about each of the four lines 1, 2, 3, 4 is zero, and that the resolute along each of the lines 5 and 6 is zero. If the system is not in equilibrium, let  $(\Gamma, R)$  be the equivalent wrench. Let the axes of coordinates and the notation be the same as in Art. 330. We thus have given the four equations

$$\Gamma \cos \theta_1 + Rr_1 \sin \theta_1 = 0, \quad \Gamma \cos \theta_2 + Rr_2 \sin \theta_2 = 0, \quad \&c. = 0,$$

and the two resolutions  $R \cos \theta_5 = 0, \quad R \cos \theta_6 = 0.$

These six equations may be called the equations (A).

Let four forces  $P_1 \dots P_4$  act along the four lines 1...4 and let two couples  $M_5, M_6$  have their axes placed along the lines 5, 6. If these can be in equilibrium, they must satisfy the equations

$$P_1 \cos \theta_1 + \dots + P_4 \cos \theta_4 = 0,$$

$$P_1 r_1 \sin \theta_1 + \dots + P_4 r_4 \sin \theta_4 + M_5 \cos \theta_5 + M_6 \cos \theta_6 = 0,$$

with four other similar equations obtained by writing  $\phi$  and  $\psi$  for  $\theta$ . These six equations may be called the equations (B).

The equations (B) in general require that the four forces  $P_1 \dots P_4$  and the two couples  $M_5, M_6$  should be zero. But if the equations (A) can be satisfied by values of  $\Gamma$  and  $R$  which are not both zero, the six equations (B) are not independent. If we multiply the first by  $\Gamma$  and the second by  $R$  and add the products together the sum is evidently an identity by virtue of equations (A). The equations (B) are therefore equivalent to not more than

five equations, and thus forces  $P_1...P_4$  and couples  $M_5, M_6$ , not all zero, may be found to satisfy them.

It follows that, if the six lines are such that the forces  $P_1...P_6$  and the couples  $M_5, M_6$  cannot be in equilibrium, the values of  $P_1...P_6$  and  $R$  given by equations (A) must be zero, i.e. the given system is in equilibrium.

**332.** If four of the six given lines are occupied by the axes of couples, the remaining two having only zero couples or zero forces, it is possible to so choose the four couples that equilibrium shall exist, Art. 99. *It follows that  $m$  equations of moments and  $n$  equations of resolution are insufficient to express the conditions of equilibrium if  $m$  is less than three.*

**333.** We may also deduce the theorem of Art. 331 from that of Art. 330 by placing some of the lines at infinity.

The expression for the moment of a system of forces about a straight line drawn in the plane of  $xz$  parallel to  $x$  and at a distance  $l$  from it, is by Art. 29,  $L' = L + lY$ . If  $l$  be very great the condition  $L' = 0$  leads to  $Y = 0$ . It follows that to equate to zero the resolved part of the forces along  $y$  is the same thing as to equate to zero their moment about a straight line perpendicular to  $y$  but very distant from it. Now a zero force along such a line at infinity is equivalent to a couple round the axis of  $y$ . Since the axis of  $y$  is any straight line, it follows that if a system be such that its moments about  $m$  lines are each zero and its resolution along  $n$  lines are also each zero, where  $m + n = 6$ , then the system will be in equilibrium provided the six lines are such that  $m$  forces along the  $m$  lines and  $n$  couples round the  $n$  lines cannot be found which are in equilibrium.

**334.** Geometrical view. *Six forces are in equilibrium. When five of the lines of action of five are given, the possible positions of the sixth are the nul lines of two determinate forces acting along the two transversals of any four of the five.* From this we can deduce another proof of Möbius' theorem.

Let us represent the lines of action of the forces  $P_1...P_6$  by the numbers 1...6 and the mutual moments of the lines by the symbols (12), (34), &c. Art. 264.

Let  $a, b$  be the two transversals which intersect the four straight lines 1, 2, 3, 4 (Art. 320). Since the six forces  $P_1...P_6$  are in equilibrium, the moment of  $P_5$  and  $P_6$  about each of the

$$P_a(6a) + P_b(6b) = 0 \dots\dots\dots(3)$$

We notice that the positions of the transversals  $a$  and  $b$  depend on the positions of the lines 1, 2, 3, 4, and are independent of the magnitudes of the corresponding forces. The ratio of the forces applied to these transversals depends on the position of the lines relatively to  $a$  and  $b$ . The transversals  $a, b$  and the lines 5, 6 are so related that  $a, b$  are nul lines of the forces  $P_5, P_6$  and 5, 6 are nul lines of  $P_a, P_b$ .

It follows from this reasoning that when the forces  $P_1, P_2$  are varied, so that equilibrium always exists, the sixth line will always be a nul line of  $P_a, P_b$ . Hence if any point  $O$  in the line of action of  $P_6$  is given, that force must lie in the nul plane of  $O$  taken with regard to these two forces.

**335.** Any conjugate forces equivalent to  $P_a, P_b$  may also be used. Assume for example, any two points  $A$  and  $B$ , their nul planes with regard to these forces will intersect in some straight line  $CD$  which is the conjugate of  $AB$ . Art. 308. *Any straight line intersecting  $AB$  and  $CD$  will be a nul line and hence a possible position of the sixth force.*

**336.** The sixth line will remain in involution with the five given straight lines 1...5 as it revolves round  $O$  in the polar plane of  $O$ . The ratios of the forces  $P_1...P_6$  will however change.

Let the straight line joining  $O$  to the intersection of its polar plane with transversal  $a$  be taken as the sixth line. Then since the sixth line is a nul line of the forces which act along the transversals, it will also intersect the transversals  $b$  and  $c$ . Thus the polar plane of  $O$  intersects the transversals  $a$  and  $b$  in two points which lie in the same straight line with  $O$ .

The position in space of this straight line may be constructed when the positions of the straight lines 1, 2, 3, 4 and the point  $O$  are known. Let it be called the line of action of the point  $O$  with regard to the four lines 1, 2, 3, 4. To construct this line first find the two transversals  $a$  and  $b$ , we then pass a plane through  $O$  and each of these transversals. The intersection of these planes is the line  $c$ .

If we had begun by finding the two transversals  $a', b'$  of some other four of the five given lines say 1, 2, 3, 5, we must have arrived at the same plane as the polar plane of  $O$ . Thus by combining the forces in sets of four, we may arrive at such lines as  $c$ . All these lie in the polar plane of  $O$ , and any two will determine that plane.

When the four lines 1, 2, 3, 4 and the point  $O$  are given, the fifth line  $b$  is arbitrary, the polar plane of  $O$  passes through the fixed straight line  $c$ .

**337.** Since the forces  $P_1...P_6$  are in equilibrium the moment of  $P_5$  and  $P_6$  about each of the transversals  $a, b$  is zero. Hence as in Art. 334

$$P_5(5a) + P_6(6a) = 0, \quad P_5(5b) + P_6(6b) = 0 \dots\dots\dots(4)$$



is therefore greatest when the sixth line is perpendicular to  $c$ .

We have assumed that the moments (5a) and (5b) are not both zero, i.e. that the given straight lines are not so placed that they all intersect the same two right lines; see Art. 320. When this happens the lines 1, 2, 3, 4, 5 alone are in equilibrium. The equations (1) then show that the force  $P_6$  is zero when its line of action does not intersect the same directors.

**338.** Ex. 1. If  $A, B, C, D, E, F$  be six lines in involution, the polar plane of  $O$  with regard to  $A, B, C, D, E$  is the same as the polar plane of  $O$  with regard to  $A, B, C, D, F$ , the forces along  $E, F$  not being zero.

or let  $M$  be any straight line through  $O$  in the first polar plane, then a force along  $M$  can be replaced by five forces along  $A, B, C, D, E$ . But the force along  $E$  can be replaced by forces along  $A, B, C, D, F$ , hence the force along  $M$  is equivalent to forces along  $A, B, C, D, F$ , i.e.  $M$  lies in the second polar plane. The polar planes therefore coincide.

Ex. 2. Supposing two transversals, say  $a$  and  $b$ , to be known, we may take with regard to these the convenient system of coordinates used in Art. 321. Let  $2c$  be the least distance between the transversals,  $2\theta$  the angle between their directions.  $(1+\mu)/(1-\mu)$  be equal to the known ratio (5a) : (5b), i.e. to the ratio of the moments of the fifth force about the transversals  $a$  and  $b$  (Art. 334). Show that the polar plane of  $O$  is

$$x \sin \theta (h + \mu c) + y \cos \theta (\mu h + c) - z (f \sin \theta + \mu g \cos \theta) = c (\mu f \sin \theta + g \cos \theta).$$

is obtained by substituting in (2) of Art. 334 the Cartesian expression for a moment given in Art. 266.

### *Tetrahedral Coordinates.*

**339.** Show that the forces of any system can be reduced to six forces which act along the edges of any tetrahedron of finite volume.

Let  $ABCD$  be the tetrahedron, let any one force of the system intersect the face opposite  $D$  in the point  $D'$ . Resolve the force into oblique components, one along  $DD'$  and the other in the plane  $ABC$ . The former can be transferred to  $D$  and then resolved along the edges which meet at  $D$ . The second can be resolved into components which act along the sides of  $ABC$ .

We shall suppose that the positive directions of the edges are  $AB, BC, CA, AD, BD, CD$ ; the order of the letters being such that a positive force acting along any edge tends to produce rotation about the opposite edge in the same standard direction. See Art. 97. We shall represent the forces which act along these sides by the symbols  $F_{12}, F_{23}, F_{31}, F_{14}, F_{24}, F_{34}$ . The directions of the forces, when they are indicated by the order of the suffixes. When we wish to measure the force in the opposite directions, the suffixes are to be reversed, so that  $F_{21} = -F_{12}$ .

The ratios of the forces  $F_{12}$  &c. to the edges along which they act will be represented by  $f_{12}$  &c. The volume of the tetrahedron is  $V$ .

Ex. 1. Show that the six straight lines forming the edges of a tetrahedron are not in involution. For, if forces acting along these could be in equilibrium with respect to the edges, by taking moments about the edges, that each would be zero.

Ex. 2. A force  $P$  acts along the straight line joining the points  $H, K$ , whose tetrahedral coordinates are  $(x, y, z, u)$   $(x', y', z', u')$  in the direction  $H$  to  $K$ . This force is obliquely resolved into six components along the edges of the tetrahedron.

Let  $F_{12}$  be the component acting in the direction  $AB$ , show that the component  $F_{12}$  acting in the direction  $AB$  is  $P \frac{AB}{HK} \cdot \left| \begin{array}{ccc} x & y & z \\ x' & y' & z' \\ a & \beta & \gamma \end{array} \right|$

where the terms in the leading diagonal follow the order indicated by the directions  $HK, AB$ , of the forces.

To prove this we equate the moments of  $F_{12}$  and  $P$  about the edge  $CD$ . The result follows from the expression for the moment given in Art. 267, Ex. 2.

Ex. 3. Two unit forces act along the straight lines  $HK, LM$  in the directions  $H$  to  $K$  and  $L$  to  $M$ . If the tetrahedral coordinates of  $H, K, L, M$  are respectively  $(x, y, z, u)$ ,  $(x' &c.)$ ,  $(\alpha, \beta, \gamma, \delta)$ ,  $(\alpha', &c.)$ , prove that the moment of either about the other in the standard direction is  $\frac{6V\Delta}{HK \cdot MN}$  where  $\Delta$

is the determinant in the margin. The order of the rows is determined by the directions  $HK, LM$  in which the forces act; the order of the columns by the positive directions of the edges. This follows from Art. 266. Notice that this expression is the invariant  $I$  of the two unit forces.

Ex. 4. The nul plane of the point whose tetrahedral coordinates are  $(\alpha, \beta, \gamma, \delta)$  with regard to the six forces  $F_{12}$  &c. is

$$f_{12} \left| \begin{array}{cc} z, u \\ \gamma, \delta \end{array} \right| + f_{21} \left| \begin{array}{cc} x, u \\ \alpha, \delta \end{array} \right| + f_{31} \left| \begin{array}{cc} y, u \\ \beta, \delta \end{array} \right| + f_{14} \left| \begin{array}{cc} y, z \\ \beta, \gamma \end{array} \right| + f_{24} \left| \begin{array}{cc} z, x \\ \gamma, \alpha \end{array} \right| + f_{34} \left| \begin{array}{cc} x, y \\ \alpha, \beta \end{array} \right| = 0$$

The nul plane of the corner  $D$  is  $f_{23}x + f_{31}y + f_{12}z = 0$ . The areal coordinates of the nul point of the face  $ABC$  are proportional to  $f_{14}, f_{24}, f_{34}$ .

Ex. 5. Prove that the invariant  $I$  of the six forces is

$$I = 6V (f_{12}f_{34} + f_{23}f_{14} + f_{31}f_{24}).$$

Ex. 6. If the six forces have a single resultant prove that it intersects the face in its nul point. Thence find its equation by using Ex. 4.

Ex. 7. Prove that the central axis of the six forces intersects the face  $ABC$  in a point whose areal coordinates are proportional to  $f_{14} - p\alpha X_{23}/6V$ ,  $f_{24} - p\beta X_{13}/6V$ ,  $f_{34} - p\gamma X_{12}/6V$ , where  $p$  is the pitch, and  $X_{23}, X_{13}, X_{12}$  are the resolute coordinates of the sides  $a, b, c$  of the face.

## CHAPTER VIII

### GRAPHICAL STATICS

#### *Analytical view of reciprocal figures.*

**340.** Two plane rectilineal figures are said to be reciprocal\*, when (1) they consist of an equal number of straight lines or edges such that corresponding edges are parallel, (2) the edges which terminate in a point or corner of either figure correspond to lines which form a closed polygon or face in the other figure.

If either figure is turned round through a right angle the corresponding lines become perpendicular to each other but the figures are still called reciprocal.

Any figure being given, it cannot have a reciprocal unless (1) every corner has at least three edges meeting at it, (2) the figure can be resolved into faces such that each edge forms a base for two faces and two only.

The edges meeting at a corner in one figure correspond to the edges which form a closed polygon in the other. Since a closed polygon must have three sides at least, it follows at once that three edges at least must meet at each corner.

The edges of a figure can sometimes be combined together in different ways so as to make a variety of polygons. Only those

\* The following references will be found useful. Maxwell, *On reciprocal figures and diagrams of forces*, *Phil. Mag.* 1864; *Edin. Trans.* vol. xxvi. 1870. The three examples mentioned in Arts. 347 and 349 are given by him. Maxwell was the first to give the theory with any completeness. Cremona, *Le figure reciproche nella statica grafica*, 1872; a French translation has been published and an English version has been given by Prof. Beare, 1890. Fleeming Jenkin, *On the practical application of reciprocal figures to the calculation of strains on frameworks and some*

polygons which correspond to corners in the reciprocal figure to be regarded as faces. The figure is then said to be resolved into its faces. The side of any face corresponds to an edge terminated at the corresponding corner of the reciprocal figure. Since an edge can have only two ends, it is clear that two faces and only two must intersect in each edge.

**341. Maxwell's Theorem.** If the sides of a plane figure are the orthogonal projections of the edges of a closed polyhedron, that plane figure has a reciprocal which can be deduced by the following method.

Let one polyhedron be given and let its polar reciprocal be formed with respect to the paraboloid  $x^2 + y^2 = 2hz$ . Then we know that each face of either polyhedron is the polar plane of the corresponding corner of the other. Smith's *Geometry*, Art. 152.

We shall now prove that the orthogonal projections of these two polyhedrons on the plane of  $xy$  are reciprocal figures with their corresponding sides at right angles.

The intersection of two faces is an edge of one polyhedron, and the straight line joining the poles of these faces is an edge of the other. These edges correspond to each other. Consider the edges which meet at a corner  $A$  of one polyhedron. The corresponding edges of the second polyhedron lie in the polar plane of  $A$  and are perpendicular to the sides of the face which corresponds to that corner. Thus for every corner of one polyhedron there corresponds a face with as many sides as the corner has edges.

We shall next prove that the projection of each edge of one polyhedron is at right angles to the projection of the corresponding edge of the other. To prove this we write down the equations to the faces of one polyhedron which are the polar planes of the two corners  $(\xi\eta\zeta)$ ,  $(\xi'\eta'\zeta')$  of the other. These are

$$h(z + \zeta) = x\xi + y\eta, \quad h(z + \zeta') = x\xi' + y\eta'.$$

Eliminating  $z$ , we have the equation to the projection of an edge of the first polyhedron, viz.  $h(\zeta - \zeta') = x(\xi - \xi') + y(\eta - \eta')$ . The equation to the projection of the edge joining the two corners is  $(y - \eta)(\xi - \xi') - (x - \xi)(\eta - \eta') = 0$ . These two lines are evidently at right angles.

It is useful to notice that the pole of the plane  $z = Ax + By + C$  is the point whose coordinates are  $\xi = hA$ ,  $\eta = hB$ ,  $\zeta = -C$ .


**Ex.** Show that Maxwell's reciprocal is not altered (except in position) by moving the paraboloid parallel to itself, and remains similar when the latus rectum of the paraboloid is changed. What is the effect on the reciprocal figure of multiplying the coordinates of the corners of the primitive polyhedron so that its projection is unchanged?

**342. Cremona's Theorem.** Another construction has been given by Cremona. Let one polyhedron be given and let a second be derived from it by joining the poles of the faces of the first. The Cremona-pole of a given plane is the point which lies on the plane itself. If the edges of these two polyhedrons are orthogonally projected, these projections are reciprocal figures with their

*Geometrically*; let the plane intersect the axis of  $z$  in  $C$  and make an angle  $\phi$  with that axis. The pole  $O$  lies on a straight line  $CO$  drawn in the given plane perpendicular to the axis of  $z$  so that  $CO = h \cot \phi$ .

We easily deduce Cremona's construction from that of Maxwell. If we turn Maxwell's reciprocal figure round the axis of  $z$  through a right angle, the coordinates of the pole used by him become  $\xi = -hB$ ,  $\eta = hA$ ,  $\zeta = -C$ . If we also change the sign of  $\zeta$ , the coordinates become the same as those of the pole used in Cremona's construction. The effect of the rotation is that the corresponding lines in the orthogonal projections of the two polyhedra become parallel, instead of perpendicular. The effect of the change of sign in  $\zeta$  is that we replace the reciprocal polyhedron by its image formed by reflexion at the plane of  $xy$  as by a looking-glass. Since this last change does not affect the orthogonal projections on the plane of  $xy$ , it follows that the two constructions lead to the same reciprocal figures, except that the corresponding lines are in one case perpendicular to each other, in the other parallel.

**343.** *Example of a reciprocal figure.* The fig. 2 is composed of 8 corners, 18 edges and 12 triangular faces each having an angular point at  $O$  or  $O'$ . The hexagon enclosed by the six edges marked 1...6 not being included as a face, the figure may be regarded as the orthogonal projection of a polyhedron formed by placing two pyramids on a common base  $ABCDEF$  with their vertices on the same or on opposite sides. The figure therefore has a reciprocal.



To construct this reciprocal we draw the two polar planes of  $O$ ,  $O'$ ; they intersect in some line  $LMN...$  whose orthogonal projection is by Maxwell's theorem at right angles to that of  $OO'$ . In fig. 1, the projection has been turned round through a right angle so that corresponding lines are parallel. Accordingly the projection of the intersection  $LMN...$  has been drawn parallel to that of  $OO'$ . Since 6 edges meet at  $O$  and  $O'$ , their polar planes give the two hexagons 1...1'...6'. Since four edges meet at each of the other corners, the polar planes

condition is that whatever be the lengths of the ordinates because a face bounded by three straight lines must be plane. It is also clear that when a figure is the projection of a polyhedron the area enclosed in that figure must be covered *twice* (or an even number of times) by the faces.

**345.** Reciprocal figures are usually constructed by drawing straight lines parallel to the edges of the given figure, assuming of course the properties already proved. To sketch fig. 1, we first draw from an assumed point  $L$ , the straight lines  $LMN$ ,  $L21$ ,  $L2'1'$ , parallel respectively to  $OO'$ ,  $OA$ ,  $O'A$ . Assuming another point 2 on  $L1$  we draw  $22'$ ,  $2M$  parallel to  $AB$ ,  $OB$ , then in the figure of Art. 343  $2'M$  is parallel to  $O'B$ . The same is therefore true by similar figures (or by the properties of co-polar triangles) for all positions of the point 2 on  $L1$ . A point 3 being taken on  $2M$  we draw  $33'$ ,  $3N$ ,  $3'N$  parallel to  $BC$ ,  $OC$ ,  $O'C$ , and so on for the corners 4, 5, 6, the point 1 being known as the intersection of  $R6$  and  $L2$ . If any one of these corners were chosen differently, say if 6 were moved nearer  $Q$ , we obtain a new triangle  $R11'$  having its vertices on the straight lines  $LM$ ,  $L2$ ,  $L2'$ , and two sides  $R1$ ,  $R1'$ , parallel to their former directions. Hence by the properties of co-polar triangles the third side  $11'$  is also parallel to its former direction.

**346. Mechanical property of reciprocal figures.** Let two equal and opposite forces be made to act along each edge of a framework, one force at each end. If their magnitudes are proportional to the corresponding edges of the reciprocal figure, the forces at each corner are in equilibrium.

This theorem follows at once from the fact that the edges which meet at any corner in one figure are parallel to the sides of a closed polygon in the other figure.

For example, let figure 1 of Art. 343 represent a framework of 18 rods freely hinged at the corners, and let some of the rods be tightened so that the whole figure is in a state of strain. The stress along each rod is then determined by measuring the length of the corresponding edge of the reciprocal figure when that figure has been drawn. See also Art. 354.

**347.** Since each corner of a framework is in equilibrium under the action of the forces which meet at that corner, a corresponding polygon of forces can be drawn. There will thus be as many partial polygons as there are corners. When a reciprocal figure can be drawn, these polygons can be made to fit into each other so that every edge is represented once and once only in the complete force polygon. But if either of the conditions in Art. 340 were violated, so that a reciprocal diagram is impossible, the partial polygons may not fit completely into each other. The result would therefore be that some or more of

forces would be represented by equal and parallel lines placed in different parts of the figure. Nevertheless some of the partial polygons may be made to fit, just as a portion of the network may be regarded as the projection of a portion of some solid polyhedron. The force diagram thus imperfectly constructed may yet be of use to calculate the stresses.




Fig. 1.




Fig. 2.

As an example of this, consider the framework represented in fig. 1, in which the rods  $F, G; L, M; \&c.$  are supposed to cross without mutual action. If one rod is tightened, the resulting stresses along the others are determinate, yet a complete reciprocal figure cannot be constructed. The rod  $N$  forms an edge of four triangles, viz.  $NFH, NGI, NJL$ , and  $NKM$ , so that if there could be a reciprocal figure, the line corresponding to  $N$  would have four extremities, which is impossible. In this case we can draw a diagram, represented in fig. 2, in which each of the forces  $F, G, L, M, J, K$  are represented by two parallel lines.

**48. External forces.** Let us remove the six bars which form the outer polygon of fig. 1 in Art. 343 and also the connecting bars  $11', 22', \&c.$  We now act at the corners 1...6 of the remaining hexagon forces  $P_1...P_6$  to replace the stresses along the bars which have been removed. We thus have a framework consisting only of the bars 12, 23, &c. hinged at the corners and acted on by the external forces  $P_1...P_6$ . This figure resembles the funicular polygon described in Art. 140, except that the forces which act at the corners are not necessarily equal. When the external forces are given we modify the polygon in figure 2 to their magnitudes, see Art. 352. When therefore the stresses of a framework caused by the action of external forces acting at the corners, these stresses can be graphically deduced when we can complete the figure in such a manner that a reciprocal can be drawn. It is however not usual actually to complete the figure, the stresses which would exist in these additional bars if supplied are not required. It is sufficient to draw only so much of the figure as may be necessary to determine the stresses in the given framework.

**49.** A different mode of lettering the two figures is sometimes used, by which the reciprocity is more clearly

which meet in any corner  $A$  of fig. 3 are parallel to the sides which bound space  $A$  in fig. 4, and the sides which bound the space  $P$  are parallel to which meet at the corner marked  $P$ . Any side in one figure such as  $C$  is bounded by the spaces  $P$  and  $Q$  and is therefore parallel to the straight line  $L$  in the other figure. This method of lettering the figures is called Bow's system. *the economics of construction in relation to framed structures* (Spon, 1873).




Fig. 5.




Fig. 6.

Another method of lettering the two figures has been used by Maxwell. Corresponding lines are represented by the same letter, but with some distinguishing mark; thus large letters may be used in one figure and small ones in the other. This method is illustrated in the diagram, which represents two reciprocal figures.

**350.** *A rectilinear figure being given, show how to find a reciprocal.* This can be best explained by considering an example. In the case of fig. 3 or 4, where the faces are triangles, the reciprocal of either can be found by circumscribing circles about the faces. The straight lines which join the centres, two and two, are clearly perpendicular to the six sides of the given figure. One reciprocal having been thus constructed, any similar figure will also be reciprocal.

In more complicated cases such circles cannot be drawn. Let us consider how the reciprocal of fig. 5 in Art. 349 may be constructed. In drawing the reciprocal of a figure, it is generally convenient to begin with a corner at which three sides meet, for the reciprocal triangle corresponding to this corner will determine three lines of the reciprocal figure. By drawing the lines  $a, b, c$  parallel to  $A, B, C$  we construct the triangle reciprocal to the corner at which  $A, B, C$  meet. Through the intersection of  $b$  and  $c$  we draw a parallel  $e$  to  $E$ ;  $b, c, e$  form a triangle with  $E$ . In the same way  $d$  is drawn parallel to  $D$  through the intersection of  $a$  and  $b$ . We next notice that, since  $D, E, F, G$  form a polygon in one figure, the lines  $f$  and  $g$  may be constructed by drawing parallels to  $F$  and  $G$  through the intersection of  $e$  and  $d$ . Again the lines  $A, C, K, L$  form a closed polygon, hence the lines  $k, l, h$  must all pass through the intersection of  $a$  and  $c$ . The line  $i$  is drawn parallel to  $I$  through the intersection of  $a$  and  $c$ . Lastly the line  $j$  is drawn parallel to  $J$  through the intersection of  $g, k$ , and unl



**351.** Let  $C$  be the number of corners in the given figure,  $E$  the number of sides or edges,  $F$  the number of faces or polygons. Let  $C'$ ,  $E'$ ,  $F'$  be the number of corners, edges and faces in the reciprocal polygon. It follows from the definition in Art. 340 that  $E=E'$ ,  $C=F'$ ,  $F=C'$ .

The sides of the reciprocal figure are formed by drawing straight lines parallel to those of the given figure. Taking any straight line  $AB$  parallel to one of the lines of the figure for a base, we construct two new sides by drawing through  $A$  and  $B$  parallels to the corresponding lines in the given figure. Continuing this process, every new corner is determined by the intersection of two new sides. As in Art. 151, the assumption of the first line  $AB$  determines two corners, and the remaining  $C'-2$  corners are determined by drawing 2 ( $C'-2$ ) lines in addition to the assumed line  $AB$ . Hence if  $E'=2C'-3$  every corner is determined, and the figure is stiff. This is the condition that a diagram can be drawn in which the directions of the lines are arbitrarily given. If  $E'$  is less than  $2C'-3$ , the form of the figure is indeterminate or deformable. If  $E'$  is greater than  $2C'-3$ , the construction is impossible unless  $E'-2C'+3$  conditions among the directions of the lines are fulfilled.

In the first figure represented in Art. 349, there are four corners, four triangular faces and six edges; we have therefore in this figure  $C+F=E+2$ . Let another rectilinear figure be derived from this by drawing additional lines. The effect of drawing a line from a corner  $P$  to a point  $Q$  unconnected with the figure is to increase both  $C$  and  $E$  by unity. If we complete a new polygon by joining  $Q$  to another corner  $P'$ , we increase both  $F$  and  $E$  by unity. If we divide any face into two parts by joining two points on its sides, we again increase equally  $C+F$  and  $E$ . It follows, that if the relation  $C+F=E+2$  hold for any one figure, the same relation\* holds for all rectilinear figures derived from that one.

Considering both the given figure and the reciprocal, we have the relations

$$E=E', \quad C=F', \quad F=C', \quad C+F=E+2, \quad C'+F'=E'+2.$$

If the given figure is such that  $C=F$ , we have  $E=2C-2$ ,  $E'=2C'-2$ . In this case the number of corners in either figure is equal to the number of faces, and each figure has one edge more than is necessary to stiffen it. That either figure may be possible, a geometrical condition for each must exist connecting the edges. When the given figure can be regarded as the projection of a polyhedron, it then follows from Maxwell's theorem that a reciprocal figure can be drawn. The conditions just mentioned must therefore be satisfied.

If  $C < F$  as in Art. 343, we have  $E > 2C-2$ ,  $E' < 2C'-2$ ; on the same supposition the reciprocal figure is indeterminate. If  $C > F$  we have  $E < 2C-2$ ,  $E' > 2C'-2$ ; in this case the construction of the reciprocal figure is impossible unless  $C-F+1$  conditions are satisfied.

\* This is the same as the relation (first given by Euler) which connects the number of corners, faces and edges of any simply connected polyhedron. We notice that in any polygon  $C=E$  and  $E=1$  so that  $C+F=E+1$ . Assuming

$P_1, P_2, \dots, P_5$  being given, it is required to find their resultant.

The magnitude and direction of the resultant can be found by constructing a *diagram or polygon of forces* in the manner explained in Art. 36. We draw straight lines parallel and proportional to the given forces and place them end to end in any order. The straight line closing the polygon, taken in the proper direction, represents the resultant. Let the forces  $P_1 \dots P_5$  be represented by the lines 1...5, the line 6 then represents the resultant in magnitude and reversed direction.

In constructing this polygon no reference has been made to the points of application of the forces, so that the forces are not fully represented. It will therefore be necessary to use a second diagram. This second figure is sometimes called *the framework* and sometimes *the funicular polygon*.

From any point  $O$  taken arbitrarily in the force diagram we draw radii vectores to the corners. These radii vectores divide the figure into a series of triangles, the sides of which are used to resolve the forces  $P_1$  &c. in convenient directions by the use of the triangle of forces. The side joining  $O$  to any corner occurs in two triangles, and therefore represents two forces acting in opposite directions. No arrow has therefore been placed on that side. The arbitrary point  $O$  is usually called the *pole of the polygon*. The corners are represented by two figures; thus the intersection of the sides 1 and 2 is called the corner 12 and the straight line joining  $O$  to this corner is called the *polar radius* 12.

We are now in a position to construct the funicular polygon. Taking any arbitrary point  $L$  as the point of departure, we draw a straight line  $LA_1$  parallel to the polar radius 61 to meet the line of action of  $P_1$  in  $A_1$ . From  $A_1$  we draw  $A_1A_2$  parallel to the polar radius 12 to meet  $P_2$  in  $A_2$ ; then  $A_2A_3$  is drawn parallel to the polar radius 23 to meet  $P_3$  in  $A_3$ ; then  $A_3A_4$  and  $A_4A_5$  are drawn parallel to the polar radii 34 and 45. Finally  $A_5A_6$  is drawn parallel to 56 to meet  $A_1L$  (produced if necessary) in  $A_6$ . Then  $A_6$  is the required point of application of the resultant force.

To understand this, we notice that the force  $P_1$  at  $A_1$  is resolved by one of the triangles of the force polygon into two forces acting along  $LA_1$  and  $A_1A_2$  respectively. The latter combined

and the other along  $A_6A_5$ . These two must therefore intersect at a point on the resultant force. In the figure  $P_6$ , drawn parallel to the line 6, represents a force in equilibrium with  $P_1...P_5$ .




Fig. 1.




Fig. 2

If we take some point, other than  $L$ , as a point of departure we obtain a different funicular polygon having all its sides parallel to those of  $A_1A_2...A_6$ . In this way by drawing two funicular polygons we can obtain (if desired) two points on the line of action of the resultant.

If we take some point other than  $O$  as the pole in the force diagram, but keep the point of departure  $L$  unchanged, we obtain another funicular polygon whose sides are not parallel to those of  $A_1A_2...A_6$ . A few of these sides are represented by the dotted lines. But the resulting point  $A_6$  must still lie on the resultant. We thus arrive at a geometrical theorem, that *for all poles of the same force diagram the locus of  $A_6$  is a straight line*.

**353. Conditions of equilibrium.** In this way we see that whenever the force polygon is *not closed*, the given system of forces admits of a resultant whose position can be found by drawing one funicular polygon.

When the force polygon is closed the result is different. In order to use the same two figures as before let us suppose that the six forces  $P_1...P_6$  form the given system. Taking any arbitrary point  $L$ , we begin as before by drawing  $LA_1$  parallel to the line of action of the force  $P_1$ . Continuing the construction for the funicular polygon we arrive at a point  $A_6$  on the line of action of the force  $P_6$ . To complete the construction we draw a line through  $A_6$  parallel to the line of action of the force  $P_6$ . This line is the resultant of the system of forces.

the construction we have to draw a straight line from  $A_6$  parallel to the same polar 61 with which we began. This last straight line may be either coincident with, or parallel to, the straight line  $LA_1$  with which we began the construction. The whole system of forces has thus been reduced to two equal and opposite forces, one along  $A_1L$  and the other along its parallel drawn from  $A_6$ .

If these two lines coincide, the equal and opposite forces along them cancel each other. *The system is therefore in equilibrium. In this case the funicular polygon drawn (and therefore every funicular polygon which can be drawn) is a closed polygon.*


If these two straight lines are parallel, the forces have been reduced to two equal, parallel, and opposite forces. *The system is therefore equivalent to a couple. In this case the funicular polygon is unclosed.* The moment of this resultant couple is the product of either force into the distance between them.

**354.** If we suppose the straight lines  $A_1A_2$ ,  $A_2A_3$ , &c., joining the points of application of the forces to represent rods jointed at  $A_1$ ,  $A_2$ , &c., the forces by which these press on the hinges along their lengths, Art. 131. The figure has been so constructed that the reactions at each hinge balance the external force at that point. The combination of rods therefore forms a framework a part of which is in equilibrium under the action of the external forces, and the stresses in the several rods may be found by measuring the corresponding lines in the force diagram.

We notice that any set of forces acting at consecutive corners of the funicular polygon (such as  $P_4$ ,  $P_5$ ,  $P_6$ ) are statically equivalent to the tensions or reactions along the straight lines at the extreme corners (viz.  $A_3A_4$  and  $A_1A_6$ ). These sides must therefore intersect in the resultant of the set of forces chosen. Hence *whatever pole  $O$  is chosen and whatever point of departure  $L$  is taken, the locus of the intersection of any two corresponding sides of the funicular polygon (such as  $A_3A_4$  and  $A_1A_6$ ) is a straight line.* In a closed funicular polygon this straight line is the line of action of the resultant of either of the two sets of forces separated by the sides chosen. The locus of the intersection of any two

348 that if we complete the figure by drawing another funicular polygon depending to some other pole  $O$ , the whole figure becomes the projection of a tetrahedron and therefore admits of a reciprocal. And so it will be found that the stresses drawn to calculate the stresses of a framework are, in general, incomplete local figures. The parts essential to the problem in hand are sketched and the rest is omitted. The importance of the theory of reciprocal figures is that it enables us to investigate the relations of the several parts of the figure by pure geometry.

**356. Parallel forces.** When the forces are parallel, both the force diagram and the funicular polygon are simplified, see Art. 140. Thus let  $A_0A_1$ ,  $A_1A_2$ ,  $A_2A_3$ ,  $A_3A_4$  be light bars hinged together at  $A_1$ ,  $A_2$ ,  $A_3$ . Let the weights  $P_1$ ,  $P_2$ ,  $P_3$  act at  $A_1$ ,  $A_2$ ,  $A_3$ .



Here the force diagram is a straight line  $ab$  divided into segments representing the forces  $P_1$ ,  $P_2$ ,  $P_3$ . If  $Oa$ ,  $Ob$  be parallel to the extreme bars  $A_0A_1$ ,  $A_3A_4$ , then these lengths represent the tensions of these bars, and the lengths drawn from  $O$  to the corners 1, 2, 3 represent the tensions of the intervening bars.

To find the resultant of three given forces  $P_1$ ,  $P_2$ ,  $P_3$  we assume an arbitrary pole  $O$  in the force diagram and draw the corresponding funicular polygon  $A_0A_1...A_4$ . The extreme sides  $A_0A_1$ ,  $A_3A_4$  produced meet in a point on the line of action of the resultant. The magnitude is obviously the sum of the given forces and its direction is parallel to those forces.

**357.** The force polygon being given, and the point  $L$  of departure, let the pole be from any given position  $O$  along any straight line  $OO'$ . Prove (1) that each vertex of the funicular polygon turns round a fixed point, and (2) that all these fixed points lie in a straight line, which is parallel to the straight line  $OO'$ . This theorem follows from the ordinary polar properties of Maxwell's reciprocal polyhedra.

**358.** The following is a statical proof.

Referring to the figure of Art. 352, let  $L$ ,  $M$ ,  $N$  &c. be the points of intersection of corresponding sides of two polygons constructed with  $O$ ,  $O'$  respectively as poles.

Let a third funicular polygon be drawn corresponding to a third pole  $O''$  situated on  $OO'$ . If this funicular polygon beginning at  $L$  intersect the first in  $M'$ ,  $N'$ , &c., both  $LMN$  &c. and  $LM'N'$  &c. are parallel to  $OO'O''$ , hence  $M$  coincides with  $M'$ ,  $N$  with  $N'$ , and so on. The points  $M$ ,  $N$ , &c. are therefore common to all the funicular polygons.

*Find the locus of the pole  $O$  of a given force polygon that the corresponding funicular polygon starting from one given point  $M$  may pass through another given point  $N$ .* The locus is known to be a straight line parallel to  $MN$ : the object is to construct the straight line.

*Case 1.* If the given points  $M$ ,  $N$  lie between any two consecutive forces (say  $P_1, P_2$ ), we may take  $MN$  as the initial side  $A_1A_2$ . The pole  $O$  must therefore lie on the straight line drawn through the corner 12 of the given force polygon parallel to the given line  $A_1A_2$  (see Art. 352).

*Case 2.* Let the point  $M$  lie between any two forces (say  $P_1, P_2$ ) and  $N$  between any other two (say  $P_3, P_4$ ). We can remove the intervening force  $P_2$ , and replace it by two forces acting at  $M$  and  $N$  each parallel to  $P_2$ ; let these be  $Q_2, Q_2'$ , Art. 360. Similarly we can replace the other intervening force  $P_3$  by two forces, each parallel to  $P_3$ , acting also at  $M$  and  $N$ ; let these be  $Q_3, Q_3'$ . If we now adapt the given force polygon to these changes, the sides 2 and 3 only have to be altered. We have to draw forces parallel to  $Q_2, Q_3, Q_2', Q_3'$ , beginning at the terminal extremity of the force 1 and ending (necessarily) at the initial extremity of the force 4. The points  $M, N$  now lie between the two consecutive forces  $Q_3Q_2'$ , hence by Case 1 the locus of  $O$  is the straight line drawn parallel to  $MN$  through the intersection of these forces in the force diagram. [Lévy, *Statique Graphique*.]

*With given forces, show how to describe a funicular polygon to pass through any three given points  $L, M, N$ .*

We first find the locus of the pole  $O$  when the funicular polygon has to pass through  $L$  and  $M$ , and then the locus when it has to pass through  $L$  and  $N$ . The intersection is the required point.

*With given forces show how to describe a funicular polygon so that one side may be perpendicular to a given straight line.*

Suppose the side  $A_1A_2$  is to be perpendicular to a given straight line, then the polar radius 12 is also perpendicular to that line, Art. 352. Hence the pole  $O$  must lie on the straight line drawn through the corner 12 of the force polygon perpendicular to the given straight line.

*Ex.* Prove that, if the resultant of two of the forces is at right angles to the resultant of one of these and a third force of the system, a funicular polygon can be drawn with three right angles. [Coll. Ex., 1887.]

**358.** *If we remove any set of consecutive forces from a funicular polygon, and replace them by other forces statically equivalent to them, show that the sides bounding this set of forces remain fixed in position and direction though not in length.* Suppose we replace  $P_4, P_5$  by their resultant, then in the force diagram we replace the sides 45 by the straight line joining 34 to 56. The polar radii 34 and 56 are

the adjoining sides, each force and the two adjoining sides must lie in one plane. (2) the components of two consecutive forces along the side joining their points of application must be equal and opposite. When the forces lie in one plane the first condition is satisfied already and the second condition alone has to be added to, and this one condition suffices to find all the possible polygons.

When any one side  $A_1A_2$  of the polygon is chosen, the first condition in general determines all the other sides. To show this we notice that the plane through  $A_1A_2$  must cut  $P_3$  in  $A_3$ ; thus  $A_2A_3$  is determined and so on round the polygon. In general there are not sufficient constants left to satisfy the second condition, though in some special cases all the conditions might be satisfied together.

**EX. 1.** Prove the following construction to resolve a given force  $P_2$  at a given point  $A_2$  into two forces, each parallel to  $P_2$  and acting at two given points  $A_1, A_3$ . Let a length  $ac$  represent  $P_2$  in direction and magnitude on any given scale. Draw  $aO, cO$  parallel to  $A_2A_3, A_1A_2$  respectively, and their intersection  $O$  draw  $Ob$  parallel to  $A_1A_3$  to intersect  $ac$  in  $b$ . Then  $ab, bc$  represent the required components at  $A_3$  and  $A_1$ .

*Other construction.* Produce  $P_2$  to cut  $A_1A_3$  in  $N$ . Then  $A_1N$  and  $NA_3$  represent the forces at  $A_3$  and  $A_1$  respectively on the same scale that  $A_1A_3$  represents given force  $P_2$ . These would have to be reduced to the given scale by the method used in Euclid vi. 10.


**EX. 2.** Show that a given force  $P$  can be resolved in only one way into three forces which act along three given straight lines, the force and the given straight lines being in one plane. Prove also the following construction. Let the given straight lines form the triangle  $ABC$ , and let the given force  $P$  intersect the sides  $BC, CA$  in  $M, N$ . To find the force  $S$  which acts along any side  $AB$ , take  $Np$  to represent the force  $P$  in direction and magnitude, draw  $ps$  parallel to  $CN$  to intersect  $AB$  in  $s$ , then  $Ns$  represents the required force  $S$ . See Art. 120, Ex. 2.

Let  $Q, R, S$  be the forces which act along the sides. The sum of their moments about  $C$  must be equal to that of  $P$ . The moment of  $S$  about  $C$  is therefore equal to that of  $P$ . Since  $ps$  is parallel to  $CN$ , the areas  $CNp$  and  $CNs$  are equal, and therefore the moment of  $Ns$  about  $C$  is equal to that of  $P$ . Hence  $Ns$  represents  $S$ .

**EX. 3.** Show how to resolve a couple by graphic methods into three forces which shall act along three given straight lines in a plane parallel to that of the couple. Prove also the following construction. Move the couple parallel to itself until one of its forces passes through the corner  $C$  of the given triangle, and the other force intersect  $AB$  in  $N$ . Take  $Np$  to represent this second force, and draw  $ps$  parallel to  $CN$  to meet  $AB$  in  $s$ , then the required force along the side  $AB$  is represented by  $Ns$ .

**EX. 4.** A light horizontal rod  $A_0A_5$  is supported at its two ends  $A_0, A_5$  and has weights  $W_1, W_2, W_3, W_4$ , attached to any given points  $A_1, A_2, A_3, A_4$ . It is required to find by a graphical method the pressures on the points of support.

funicular polygon represented by  $A_0B_1...B_5$ . The polar radius  $Oc$  must be perpendicular to the line  $B_5A_0$  closing the funicular. Thus  $c$  has been found and therefore the two pressures  $R, R'$ .



If the rod is heavy, the pressures  $R, R'$  are not affected by collecting the weight of the rod at the centre of gravity. Drawing any funicular, with this additional weight into account, the pressures on the points of support can be found as before.

**362.** A light horizontal rod  $A_0A_5$  being supported at its two ends and with weights  $W_1...W_4$  at the points  $A_1...A_4$ , it is required to find the stress couple at any point  $M$ . Art. 145.

The pressures at the two ends having been determined, we describe a funicular polygon of these six forces, such that it passes through  $A_0$  and  $A_5$ . We shall prove that the stress couple at  $M$  is  $Hy$ , where  $y$  is the ordinate of the funicular at  $M$  and  $H$  is the horizontal tension.

Supposing the funicular polygon to be  $A_0C_1...C_4A_5$ , we notice that the rods represented by  $A_0C_1, C_1C_2...C_4A_5$  are in equilibrium under the action of weights  $W_1...W_4$ , the vertical pressures  $R, R'$ , and the horizontal thrusts  $A_1A_5$ , Art. 354. Taking moments about  $P$ , the extremity of the ordinate through  $M$ , for the portion  $A_0...P$ , we have  $Hy$  equal to the sum of the moments of the pressure  $R$ , and the weights  $W_1$ , &c. on one side of  $P$ , i.e.  $Hy$  is the bending moment of the rod at  $M$ . Art. 143.


To draw the funicular polygon which passes through the points  $A_1$  and  $A_5$ , take a pole  $O'$  at any point on a horizontal line through the point  $c$  in the pole diagram and then construct the polygon as before. Since  $cO$  is perpendicular to  $A_0B_5$ , it follows that, when  $O$  lies in  $cO'$ ,  $B_5$  must coincide with  $A_5$ . It is evident that  $O'c$  represents the horizontal tension.

If  $O'$  is moved along  $cO'$ , the funicular polygon and therefore both the horizontal tension  $cO'$  and the ordinate  $MP$  change. The product however, being equal to the bending moment at  $M$ , is not altered: a result which may be independently



**363. Frameworks.** *To show how the reactions along of a framework may be found by graphical methods, the forces being supposed to act at the corners.*

Let the given framework consist of a combination triangles, such as frequently occurs in iron roofs. Let  $P_1, P_2, P_3, P_4, P_5$  act at the corners  $A_1, A_2, A_3, A_4, A_5$ , the whole be in equilibrium. If these forces were parallel



of them might represent weights placed at the joints, which structure is supported on its two extremities  $A_1, A_3$ .

The five forces are in equilibrium, hence the five lines which represent them in the force diagram form a closed pentagon. We shall now sketch the lines corresponding to the stresses in the framework.

The framework, as described above, does not admit of being reciprocal; let us assume for the present that it can be made reciprocal by drawing the pentagon  $a_1...a_5$ ; Art. 355. The proper force diagram for this addition to the figure is discussed in Art. 365\*.

The side  $A_1A_5$  forms part of a quadrilateral  $A_1A_5a_5a_1$ . This quadrilateral corresponds to four lines in the reciprocal force diagram which meet in a point. Hence the reciprocal of the straight

$A_1A_5$  is a straight line drawn through the intersection of the consecutive forces 1, 5 parallel to  $A_1A_5$ . The same argument applies to every bar of the frame  $A_1A_2\dots A_5$ ; each is represented in the reciprocal by a straight line which passes through the junction of the consecutive forces at its extremities. This easy rule enables us to draw the reciprocal figure without difficulty. Thus the reciprocal of the side  $A_1A_2$  is a straight line drawn parallel to  $A_1A_2$  through the point of junction of the consecutive forces marked 1 and 2. These straight lines are marked in the force diagram with the suffixes of the straight lines to which they correspond in the framework.

The triangle representing the forces at  $A_1$  having now been constructed, we turn our attention to those at the next corner  $A_5$ . These will be represented by a quadrilateral. Following the rule, we draw 45 parallel to  $A_4A_5$  through the point of junction of the consecutive forces 4, 5. Thus three sides of the quadrilateral are known, viz. 5, 15, 45. Through the known intersection of 12 and 15 we draw a parallel to  $A_2A_5$  completing the quadrilateral. The sides are 5, 15, 25, 45.

Turning our attention to the corner  $A_4$ , we draw 34 by the rule and again we know three sides of the corresponding quadrilateral, viz. 34, 4 and 45. The fourth side is completed by drawing 24 through the known intersection of 45 and 25. The four sides are 4, 45, 24, 34.

The triangle corresponding to the corner  $A_3$  is completed by joining the known intersection of 34 and 24 to the point of junction of the consecutive forces 2, 3. By the rule this line should be parallel to the side  $A_2A_3$ . This serves as a partial verification of the correctness of the drawing.

Lastly the forces at the corner  $A_2$  must be represented by a pentagon, but looking at the figure we find that all the sides of this pentagon, viz. 2, 23, 24, 25, 12, have been already drawn.

The magnitudes of the reactions along the bars of the given

The former are called *ties* and the latter *thrusts*. Consider the corner  $A_1$ , the bars are parallel to the sides of the triangle 1, 12 and 15. The direction of the forces being known, those of 12 and 15 follow the usual rule for the triangle of forces. Hence at the point  $A_1$  the forces act in the direction 15, 21. Therefore  $A_1A_2$  is in a state of compression, i.e. it is a thrust, while  $A_1A_5$  is in a state of tension and is a tie. We may represent these states by placing arrows in the framework at  $A_1, A_2$  pointing *towards*  $A_1, A_2$  respectively and arrows at  $A_1, A_5$  pointing *from*  $A_1, A_5$  respectively. Another method has been suggested by Prof. R. H. Smith in his work on Graphics. He proposes to indicate ties by the sign + and struts by -. These marks may be placed on either diagram.

**365.** We should notice that the figure thus constructed, though sufficient to find the stresses in the rods, is not a complete reciprocal figure. To enable us to complete the figure we must first draw such a polygon  $a_1...a_5$ , cutting the lines of action of the forces, that the whole figure may admit of a reciprocal. *Statically*, we see that this polygon must be a funicular of the given forces, for otherwise the forces at the corners  $a_1...a_5$  would not be in equilibrium, Art. 354. *Geometrically*, the polygon should be such that the five quadrilaterals  $a_1a_2A_1A_2$ , &c. are the projections of plane faces of a polyhedron. This polyhedron is constructed by drawing ordinates at the corners. We know that, if we draw two funiculars  $a_1...a_5$  and  $b_1...b_5$  of the forces  $P_1...P_5$ , the five intersections of  $a_1a_2, b_1b_2$ ;  $a_2a_3, b_2b_3$ ; &c. lie in a straight line  $LMN$ , Art. 357. Referring to Art. 343 (where these funiculars are represented by 1...6 and 1'...6') we see that the five quadrilaterals  $a_1a_2b_1b_2$ , &c. may therefore be made the projections of plane faces. We construct the polyhedron by keeping  $a_1...a_5$  fixed and erecting ordinates at  $b_1...b_5$  proportional to their distances from  $LMN$ . Since the sides  $A_1A_2$ , &c. lie in the planes  $a_1a_2b_1b_2$ , &c. it follows that the five quadrilaterals  $a_1a_2A_1A_2$ , &c. are also the projections of plane faces. The ordinates at  $A_1...A_5$  may then be drawn.

Taking  $a_1...a_5$  to be a funicular polygon of the forces  $P_1...P_5$  the corresponding lines on the force diagram are the dotted lines drawn from the corresponding pole  $O$  to the points of junction of the forces. It is evident that these lines are practically separate from the rest of the figure. Unless therefore we wish to assure ourselves that the forces  $P_1...P_5$  are in equilibrium, it is unnecessary to draw either the funicular polygon  $a_1...a_5$  or the corresponding lines in the force diagram. *It is usual to omit this part of the figure.*

**366. Method of sections.** We shall now show how the reactions are found by the method of sections. Let it be required to

to the points  $B, C, D$  along the three rods respectively. Let us remove the rod on the right hand as being the more complicated, we have now to deduce  $Q, R, S$  from the conditions of equilibrium of the remaining structure.

In our example *not more than three bars were cut by the section*. If there are only three forces the problem is determinate. By Art. 360, Ex. 2, every system can be replaced by three forces acting along three given straight lines, and *this resolution can be effected by a graphical construction*.

These reactions may also be easily found by the ordinary rules of statics, as in Art. 120, where this problem is solved by taking moments about the intersections of these lines.

When the figure is so little complicated as the one we have just considered, either the method of the force diagram or the method of sections may be used indifferently. In general each has its own advantages. In the first we find the reactions by constructing one figure with the help of the parallel ruler, but if there be a large number of bars the diagram may be very complicated. In the second method or sections when only three reactions are required we find these without having to concern ourselves about the others, provided these three and no others lie on one line.

**367.** In these frameworks, each rod, when its own weight can be neglected, is in equilibrium under the action of two forces, one at each extremity. These forces therefore act along the length of the rod, and thus the rods are only slightly compressed. This is sometimes a matter of importance, for a rod will not yield without breaking, a tensional or compressing force when it would yield to a transverse force. The structure is therefore stronger than when rigid joints are relied on to produce stiffness.

In actual structures some of the external forces may not act at a joint. For instance, the weight of any rod acts at its centroid. In such cases the resultant force on any bar must be found either by drawing a funicular polygon or by the rules of statics. This resultant is to be resolved into two parallel forces acting one at each of the two joints to which the rod is attached.

This transformation of the forces which act on a rod cannot affect the distribution of stress over the rest of the structure, so that when these components are combined with the other forces which act at those joints the whole equilibrium of the rest of the structure on each rod has been taken account of. So far as the rod itself is concerned, it is supposed to be able to support, without sensibly changing, its own weight or any other forces which may act on it at points intermediate between its extremities.

**368. Indeterminate Tensions.** Let  $P_1, P_2, \dots, P_n$  be a system of forces in equilibrium. Let  $A_1 \dots A_n, A'_1 \dots A'_n$  be two funicular polygons of this system, the corresponding corners  $A_1, A'_1; A_2, A'_2$  &c.

be joined by rods. Let us also suppose that the external polygon is formed of rods in a

$A'_5$


way a frame has been constructed with tensions along the rods apart from all external forces. See Art. 237. From the property of funicular polygons proved in Art. 357 *the corresponding sides of this frame intersect in points all of which lie in a straight line.*

If there are only three forces the polygons become triangles. Since the forces  $P_1, P_2, P_3$  are in equilibrium the three straight lines  $A_1A_1', A_2A_2', A_3A_3'$  which join the corresponding angular points must meet in a point. Such triangles are called co-polar. We see therefore that co-polar triangles admit of indeterminate tensions.

Levy's theorem, given in Art. 238, follows also from this proposition. Taking only six forces, because the figure has been drawn for a hexagon, let  $(P_1, P_4), (P_2, P_5), (P_3, P_6)$  be three sets of equal and opposite balancing forces. Let  $A_1...A_6$  be any funicular polygon, but let the second funicular polygon be constructed so that  $A_1'$  coincides with  $A_4$ , and let the pole be so chosen that  $A_2'$  and  $A_3'$  coincide with  $A_5$  and  $A_6$ , Art. 357. It then follows that the second funicular coincides throughout with the first. The cross bars  $A_1A_4, A_2A_5, A_3A_6$  become the diagonals of the hexagon. Thus a frame of any even number of sides has been constructed in which the diagonals are in a state of thrust and the sides in tension.

**369. The line of pressure.** Let us suppose a series of connected bodies, such as the four represented in the figure, to be in equilibrium under the action of any forces, say the three  $P, Q, R$ . We suppose these bodies to be symmetrical about a plane which in the figure is taken to be the plane of the paper. The first body is hinged to some fixed support at  $A$  and also hinged at  $B$  to the body  $BCC'$ . This second body presses along its smooth plane surface  $CC'$  against a third body  $CC'D$ . This third body is hinged to a fourth body at  $D$ , and this last is hinged at  $E$  to a fixed point of support.

The pressure at  $A$  acts along some line  $Ap$  and intersects the force  $P$  at  $p$ . The resultant of these two must balance the action at the hinge  $B$ , and must therefore pass through  $B$ . This force acting at  $B$  intersects the force  $Q$  at  $q$ , and their resultant must balance the pressure at  $CC'$ . This resultant must therefore



cut  $CC'$  at right angles in some point  $M$ . Also the point  $M$  must lie within the area

and cuts at right angles the surface of pressure. This particular funicular polygon is called the line of pressure.

**370.** Let us take an ideal section, such as  $xy$ , which separates the whole system into two parts, and let it be required to find the resultant action across this section.

This action is really the resultant of the forces across each element of the sectional area. But since each portion of the system must act on the other portion in such a way as to keep that portion in equilibrium, we may also find the resultant from the general principle that it balances all the external forces which act on either of the two portions of the system: see also Art. 143. It immediately follows that the resultant action across  $xy$  is the force already described which acts along  $pq$ . Similar remarks apply to every section; we therefore infer that *the resultant action across any section is the force which acts along the corresponding side of the line of pressure.*

If we move the section  $xy$  from one end  $A$  of the system to the other  $B$ , there may be some difficulty in determining which is the "corresponding side of the line of pressure" when the section passes the point of application of a force. Suppose for example  $a$  to be the point of application of  $P$ . If a section as  $x'y'$  is ever so little to the left of  $a$ , the corresponding side is  $Ap$ , but when the section is ever so little on the right of  $a$ , the corresponding side is  $pq$ . *If the section is parallel to the force  $P$ , the side corresponding to any section is the side of the line of pressure intersected by that section.* When therefore the forces are all vertical it will be found more convenient to consider the actions across vertical sections than across those inclined.

The resultant action across any section such as  $x'y'$  does not necessarily pass within the area of that section. The reason is that this action is the resultant of all the small forces across all the elements of area. As some of these elementary forces across the same sectional area may be tensions and some pressures, the line of action of the resultant may lie outside the area. If the forces all act in the same direction like those across the section  $CC'$  (where two bodies press against each other), the resultant must pass within the boundary of the section. Sometimes it is more useful to move the resultant parallel to itself and apply it at any convenient point within the boundary; we must then of course *introduce a couple*. This is often done when the body  $AB$  is a thin rod. See Art. 142.

**371.** When the bodies are heavy we may find the action at any hinge or boundary between two bodies by the same rule. The weight of each body is to be collected at its centre of gravity and included in the list of external forces. The resultant action at any boundary is the force along the corresponding side of the funicular polygon.

But if the action across some section as  $xy$  is required, this partial funicular polygon will not suffice. We must now consider the body  $BCC'$  to be equivalent to two bodies separated by the plane  $xy$ . The weights of each of these portions may be collected at its own centre of gravity, and a funicular polygon may be drawn to suit this case. Thus, if  $Q$  is the weight of the body  $BCC'$  acting at its centre of gravity  $\beta$ , we remove  $Q$  and replace it by two weights acting at the respective centres of gravity of the portions  $Bxy$  and  $xyCC'$ . The funicular polygon will therefore have one more side than before. It also loses the corner on the force  $Q$  and gains two new corners which lie on the lines of action of these new weights. But since the action at  $B$  must still balance the external forces whose points of

application are on the left of  $B$ , and the action at  $M$  must still balance the forces on the right of  $CC'$ , it is clear that the sides  $pB$  and  $MD$  of the funicular polygon are not altered. Therefore the two corners of the new funicular polygon must lie respectively on  $Bq$  and  $qD$ . Thus the new polygon is inscribed in the former partial unicular polygon.

If we continue this process of separating the bodies into parts, we go on increasing the number of sides in the funicular polygon, but the side which passes through any real section is unchanged in position. Finally, when the bodies are subdivided into elements, the line of pressure becomes a curve. This curve will touch all the partial polygons of pressure at each hinge and at each real surface of separation.

### EXAMPLES

**372.** Ex. 1. A framework is constructed of eleven equal heavy bars. Nine of them form three equilateral triangles  $ABC$ ,  $BDE$ ,  $DFG$  with their bases  $AB$ ,  $BD$ ,  $DF$  hinged together in a horizontal straight line. The vertices  $C$ ,  $E$ ,  $G$  are joined by the remaining two bars. The Warren girder thus formed is supported at its two lower extremities  $A$ ,  $F$  and loaded at the upper points  $C$ ,  $E$ ,  $G$  with weights  $w_1$ ,  $w_2$ ,  $w_3$ . Construct a force diagram showing the stresses in the bars.

Ex. 2. A horizontal girder has four bays  $AB$ ,  $BC$ ,  $CD$ ,  $DE$  each 5 feet; it is stiffened by three vertical members  $BB'$ ,  $CC'$ ,  $DD'$  each 3 feet, by horizontal members  $B'C'$ ,  $C'D'$  and by oblique members  $AB'$ ,  $B'C$ ,  $CD'$ ,  $D'E$ . Find by a graphical construction the tensions and thrusts produced in the members when a uniformly distributed load  $W$  is supported by the girder. [St John's Coll., 1893.]

Ex. 3.  $ABCDEFGH$  is a jointed frame in a vertical plane, constructed as follows.  $ABCD$  and  $GFE$  are horizontal,  $A$  being vertically above  $G$ ;  $ABFG$ ,  $BCEF$  are squares;  $CD$  is equal to  $CE$ ; also  $BG$ ,  $CF$ ,  $DE$  are three diagonal stiffening bars. The frame is supported at the points  $A$  and  $G$ , while a weight is hung at  $D$ . Supposing the weights of each bar to act half at each of its ends, exhibit in a diagram the stresses in the various bars of the frame. Show that those in  $GF$  and  $BC$  are equal, likewise those in  $FE$  and  $CD$ , and determine which bars are struts and which are ties. The supporting force at  $A$  may be taken to be horizontal. [Coll. Ex., 1894.]

Ex. 4. A roof  $ABCD$  is of the form of half a regular hexagon; it is stiffened by two cross-beams  $AC$ ,  $BD$ ; and it rests on the walls at  $A$  and  $D$ . Find, by a stress diagram, the tensions and thrusts in its members produced by a uniform load of tiles. [St John's Coll., 1892.]

Ex. 5. A framework is composed of six light rods smoothly jointed so as to form a regular hexagon  $ABCDEF$  whose centre is at  $O$ . The points  $BF$ ,  $OA$ ,  $OC$ ,  $OE$  are also connected, without disturbing the regularity of the hexagon, by light rods of which the first two are to be regarded as having no contact with one another. If the framework be suspended from  $A$  and a weight  $W$  be attached to  $D$ , show by graphical methods that the thrust in  $BF$  will be  $W\sqrt{3}$ , and find the force along each of the other bars. [Trin. Coll., 1895.]

Ex. 6. A regular twelve-sided framework is formed by heavy loosely jointed rods and each angular point is connected by a light rod to a peg at the centre. The whole rests on the peg in a vertical plane with a diagonal vertical. Show that the stresses in the rods are indeterminate; and assuming that the horizontal rods are not under stress, draw a diagram in which lines are parallel to and proportional to the stress in each rod and calculate the stresses. [Coll. Ex., 1893.]

Ex. 7. The lines of action of six forces in equilibrium are known. One force is known, one other pair of the forces are in one known ratio, a second pair are in another known ratio. Find a graphic construction determining the magnitudes of the five undetermined forces. [Math. Tripos, 1895.]

Ex. 8.  $ABCD$  is a rhombus of jointed rods, and  $OB$ ,  $OD$  are two equal rods jointed to the rhombus at  $B$  and  $D$  and jointed at  $O$ . Supposing all the joints smooth and parallel forces, not in the same line, applied to the framework at  $O$ ,  $A$ ,  $C$ ; construct a force diagram. Show that for equilibrium the directions of the forces must be parallel to  $BD$ . [Math. Tripos, 1891.]

Ex. 9. Four forces act in the sides  $AB$ ,  $BC$ ,  $CD$ ,  $DA$  of a quadrilateral  $ABCD$ , and are proportional to those sides. Construct the funicular, one of whose sides joins the middle points of  $AB$  and  $BC$ , when the thrust in that side is represented by  $CA$  on the same scale as the given forces are represented by the sides of the quadrilateral. [St John's Coll., 1893.]

Ex. 10. Prove that if the lines of action of  $(n-1)$  forces be given, it is always possible to adjust their magnitudes so that the system of  $(n-1)$  forces and their resultant reversed can hold in equilibrium a framework of jointed bars in the form of an equiangular polygon of  $n$  sides, a force acting at each corner.

[St John's Coll., 1890.]

Ex. 11. Four points  $A$ ,  $B$ ,  $C$ ,  $D$  are in equilibrium under forces acting between every two: prove the following construction for a force diagram of the system. With focus  $D$  a conic is described touching the sides of the triangle  $ABC$ , and  $D'$  is its second focus;  $D'A'$ ,  $D'B'$ ,  $D'C'$  are drawn perpendicular to the sides of the triangle  $ABC$ ; then  $D'A'B'C'$  is a force diagram in which each side is perpendicular to the force it represents. [Math. Tripos.]

Let  $AD$  cut  $B'C'$  in  $P$ ; we notice (1) that  $AD$ ,  $AD'$  make equal angles with the tangents drawn from  $A$ , hence the angles  $PAC'$ ,  $B'AD'$  are equal; (2) that a circle can be described about  $D'B'C'A$ , hence the angles  $AC'P$ ,  $AD'B'$  are equal. It follows that the triangles  $PAC'$ ,  $B'AD'$  are equiangular. Hence  $AD$  is perpendicular to  $B'C'$ .

Ex. 12. Nine weightless rods are jointed together at their ends; six of them form the perimeter of a regular hexagon, and the other three each join one angular point to the opposite one; to each joint a weight  $W$  is attached, and the frame is hung in a vertical plane by strings attached to adjacent angles  $A$ ,  $B$ , so that  $AB$  is horizontal, and the strings bisect the hexagon angles externally. Find or show by a diagram the forces in all the rods. [Coll. Ex., 1887.]

Ex. 13. Two points  $P$ ,  $Q$  are taken within a hexagon  $ABCDEF$ , the point  $P$  is joined to the corners  $A$ ,  $B$ ,  $C$ ,  $D$ , and  $Q$  to the corners  $D$ ,  $E$ ,  $F$ ,  $A$ . Construct the reciprocal figure.



## CHAPTER IX

### CENTRE OF GRAVITY

**373. The centre of parallel forces.** It has been proved in Art. 82 that the resultant of any number of parallel forces  $P_1, P_2, \&c.$ , acting at definite points  $A_1, A_2, \&c.$ , rigidly connected together, is a force  $\Sigma P$ .

Let the rigid system of points be moved about in any manner in space; let the forces  $P_1, P_2, \&c.$  continue to act at these points, and let them retain unchanged their magnitudes and directions in space. It has also been proved that the line of action of the resultant always passes through a point fixed relatively to the points  $A_1, A_2, \&c.$  This point is therefore regarded as the point of application of the resultant. It is called the centre of the parallel forces. The chief property of this point is its *fixity* relative to the system of points  $A_1, A_2, \&c.$

When the forces  $P_1, P_2, \&c.$  are the weights of the particles of a body, the centre of parallel forces is called the centre of gravity. Thus the centre of gravity is a particular case of the centre of parallel forces.

**374. Definition of the centre of gravity.** We take as a system of parallel forces the weights of the several particles of a body. Each particle is supposed to be acted on by a force which is parallel to the vertical. This force is called gravity. The resultant of all these forces is the weight of the body. We infer from the theory of parallel forces that there is a certain point fixed in each body (or rigid system of bodies) such that in every position the line of action of the weight passes through that point. This point is called the centre of gravity\*.

\* The first idea of the centre of gravity is due to Archimedes, who flourished about 250 B.C. In his work on *Centres of gravity or aequiponderants* he determined the position of the centre of gravity of the parallelogram, the triangle, the ordinary rectilinear trapezium, the area of the parabola, the parabolic trapezium, &c. See the edition of his works in folio printed at the Clarendon Press, Oxford, 1792.

It is evident from this definition that if the centre of gravity of a body is supported the body will balance about it in *all* positions.

**375.** *A body has but one centre of gravity.* This is evident from the demonstration in the article already quoted. The following is an independent proof.

If possible let there be two such points, say *A* and *B*. As we turn the system into all positions, the resultant keeps its direction in space unaltered. Place the body so that the straight line *AB* is perpendicular to the direction of the resultant force. Then the line of action of that force cannot pass through both *A* and *B*.

**376.** Let  $(x_1, y_1, z_1)$ ,  $(x_2, y_2, z_2)$  &c. be the coordinates of the points of application of the parallel forces  $P_1, P_2$ , &c. respectively. Let these coordinates be referred to any axes, rectangular or oblique, but fixed in the system. By what has been already proved in Art. 80, the coordinates of the centre of parallel forces are

$$\bar{x} = \frac{\Sigma Px}{\Sigma P}, \quad \bar{y} = \frac{\Sigma Py}{\Sigma P}, \quad \bar{z} = \frac{\Sigma Pz}{\Sigma P}.$$

It is important to notice that, if all the forces were altered in the same ratio, the magnitude of the resultant would also be altered in the same ratio, but the coordinates of its point of application would not be changed.

**377.** When the weight of *any* two equal volumes of a substance are the same, the substance is said to be homogeneous or of uniform density. In such bodies the weights of different volumes are proportional to the volumes. The weight of any elementary volume  $dv$  may therefore be measured by the volume. Hence by Art. 376 we have

$$\bar{x} = \frac{\int dv \cdot x}{\int dv}, \quad \bar{y} = \frac{\int dv \cdot y}{\int dv}, \quad \bar{z} = \frac{\int dv \cdot z}{\int dv}.$$

We have here replaced the  $\Sigma$  by an integral, because the parallel forces we are considering are the weights of the elements of the body.

From these equations all trace of weight has disappeared. We might therefore call the point thus determined the *centre of volume*.

When the body is not homogeneous the weights of the elements are not proportional to their volumes. Let us represent the weight of a volume  $dv$  of the substance by  $\rho dv$ . Here  $\rho$  will be different for each element of the body, and will be known as a function of the coordinates of the element when the structure of

the body is given. For our present purpose the body is given when we know  $\rho$  as a function of  $x, y, z$ . We therefore have

$$\bar{x} = \frac{\int \rho dv \cdot x}{\int \rho dv}, \quad \bar{y} = \frac{\int \rho dv \cdot y}{\int \rho dv}, \quad \bar{z} = \frac{\int \rho dv \cdot z}{\int \rho dv}.$$

In these equations we may replace  $\rho$  by  $\kappa\rho$ , where  $\kappa$  is any quantity which is the same for all the elements of the body. All that is necessary is that  $\rho dv$  should be proportional to the weight of  $dv$ .

We may therefore define  $\rho$  to be the limiting ratio of the weight of a small volume (enclosing the point  $(xyz)$ ) to the weight of an equal volume of some standard homogeneous substance.

For the sake of brevity we shall speak of  $\rho$  as the density of the body. If the body is homogeneous the product of the density into the volume is called the mass. If heterogeneous, then  $\rho dv$  is the mass of the elementary volume  $dv$ , and  $\int \rho dv$  is the mass of the whole body. If we write  $dm = \rho dv$ , the equations become

$$\bar{x} = \frac{\int dm \cdot x}{\int dm}, \quad \bar{y} = \frac{\int dm \cdot y}{\int dm}, \quad \bar{z} = \frac{\int dm \cdot z}{\int dm}.$$

When we wish to regard the mass of an element as a quality of the body apart from its weight, we may speak of the point determined by these equations as the *centre of mass*.

**376.** Equations similar to these occur in other investigations besides those which relate to parallel forces. In such cases the quantity here denoted by  $P$  or  $m$  has some other meaning. Accordingly the point defined by these coordinates has had other names given to it, depending on the train of reasoning by which the equation has been reached. This may appear to complicate matters, but it has the advantage that the special name adopted in any case helps the reader to understand the particular property of the point to which attention is called.

We here arrive at the point as that particular case of the centre of parallel forces in which the forces are due to gravity. There may therefore be some propriety in using the term *centre of gravity*. There are also obvious advantages in using the short and colourless term of *centroid*. Another name, much used, is the *centre of inertia*. This expresses a dynamical property of the point which cannot be properly discussed in a treatise on statics.

**379.** The positions of the centres of gravity of many bodies are evident by inspection. Thus the centre of gravity of two equal particles is the middle point of the straight line which joins them. The centre of gravity of a uniform thin straight rod is at its middle point. The centre of gravity of a thin uniform circular disc is at its centre. Generally, if a body is symmetrical about a point, that point is the centre of gravity. If the body is symmetrical about an axis, the centre of gravity lies in that axis, and so on.

254 CENTRE OF GRAVITY CHAPTER. IX  
**380. Working rule.** To find the centre of gravity of any body or system of bodies, we proceed in the following manner. We divide the body or system into portions which may be either *finite in size or elementary*. But they must be such that we know both the mass and position of the centre of gravity of each. Let  $m_1, m_2, \&c.$  be the masses of these portions, and let the coordinates of their respective centres of gravity be  $(x_1, y_1, z_1), (x_2, y_2, z_2), \&c.$

The weight of each portion is the resultant of the weights of the elementary particles, and may be supposed to act at the centre of gravity of that portion (Art. 82). We may therefore regard the whole body as acted on by a system of parallel forces whose magnitudes are proportional to  $m_1, m_2, \&c.$ , and whose points of application are the centres of gravity of  $m_1, m_2, \&c.$  The position of the centre of gravity of the whole system is therefore found by substituting in the formulæ

$$\bar{x} = \frac{\sum mx}{\sum m}, \quad \bar{y} = \frac{\sum my}{\sum m}, \quad \bar{z} = \frac{\sum mz}{\sum m}.$$

**381.** In using this rule it is important to notice that *some of the masses may be negative*. Thus suppose one of the bodies is such that its mass and centre of gravity would be known if only a certain vacant space were filled up. We regard such a body as the difference of two bodies, one filling the whole volume of the body (including the vacant space) whose particles are acted on by gravity in the usual manner, the other filling the vacant space but such that its particles are acted on by forces equal and opposite to that of gravity. To represent this reversal of the direction of gravity it is sufficient to regard the mass of the latter body as negative. Since in the theory of parallel forces the forces may have any signs, it is clear that we may use the same formulæ to find the centre of gravity of this new system.

**382. Ex. 1.** A painter's palette is formed by cutting a small circle of radius  $b$  from a circular disc of radius  $a$ . It is required to find the distance of the centre of gravity of the remainder from the centre of the larger circle.

Let  $O$  and  $C$  be the centres of the larger and smaller circles respectively. Let  $OC = c$ . We take  $O$  as the origin and  $OC$  as the axis of  $x$ . The masses of the two circles are proportional to their areas; we therefore put  $m_1 = \pi a^2$ ,  $m_2 = -\pi b^2$ . The latter is regarded as negative because its material has been removed from the larger circle. The centres of gravity of the two circles are at their centres, hence  $x_1 = 0$ ,  $x_2 = c$ . We have therefore  $\bar{x} = \frac{\sum mx}{\sum m} = \frac{\pi a^2 \cdot 0 - \pi b^2 \cdot c}{\pi a^2 - \pi b^2} = \frac{-b^2 c}{a^2 - b^2}$ .

is at its middle point. The centre of gravity of each strip therefore lies in  $AD$ . Hence the centre of gravity of the whole triangle lies in  $AD$ ; see Art. 382, Ex. 2.

In the same way, if we draw  $BE$  from  $B$  to bisect  $AC$  in  $E$ , the centre of gravity lies in  $BE$ . The centre of gravity of the triangle is therefore at the intersection  $G$  of  $BE$  and  $AD$ .

Since  $D$  and  $E$  are the middle points of  $CB$  and  $CA$ , the triangle  $CED$  is similar to the triangle  $CAB$ . Hence  $ED$  is parallel to  $AB$  and is equal to one half of it. The triangles  $DEG$ ,  $ABG$  are therefore also similar, and  $DG : GA = ED : AB$ . Thus  $DG$  is one half of  $AG$ , and therefore  $DG$  is one third of  $AD$ .

**384.** We have thus obtained two rules to find the centre of gravity of a uniform triangle.

(1) We may draw two median straight lines from any two angular points to bisect the opposite sides. The centre of gravity lies at their intersection.

(2) We may draw one median line from any one angular point, say  $A$ , to bisect the opposite side in  $D$ . The centre of gravity  $G$  lies in  $AD$  so that  $AG = \frac{2}{3}AD$ .

It will be found useful to observe that the centre of gravity of the area of the triangle is the same as that of three equal particles placed one at each angular point of the triangle.

Let the mass of each particle be  $m$ . The centre of gravity of the particles at  $B$  and  $C$  is the point  $D$ . The centre of gravity of all three is the same as that of  $2m$  at  $D$  and  $m$  at  $A$ ; it therefore divides  $AD$  in the ratio  $1 : 2$  (Art. 382). But the point thus found is the centre of gravity of the triangle.

If the mass of each of these three particles is equal to one-third of the mass of the triangle, the resultant weight of the three particles is equal to the resultant weight of the triangle. And these two resultants have just been shown to have a common point of application. Hence *these three particles are equivalent to the triangle so far as all resolutions and moments of weights are concerned.*

Also, when we use the method of Art. 380 to find the centre of gravity of any figure composed of triangles, we may replace each of the triangles by three equivalent particles whose united mass is equal to that of the triangle. The centre of gravity of the

whole figure may then be found by applying the rule to this collection of particles.

✓ **385.** Ex. 1. The centre of gravity of the area of a triangle is the same as the centre of gravity of three equal particles placed one at each of the middle points of the sides.

Ex. 2. Lengths  $AP, BQ, CR$  are measured from the angular points of a triangle along the sides taken in order so that each length is proportional to the side along which it is measured. Show that the centre of gravity of three equal particles placed one at each of the points  $P, Q, R$  is the same as that of the triangle.

Prove also that the centres of gravity of the triangles  $APR, BQP, CRQ$ , lie on the sides of a fixed triangle, which is similar and equal to  $ABC$ .

Ex. 3. Lengths  $AP, BQ$ , &c. are measured from the corners of a polygon along the sides taken in order so that each length is proportional to the side along which it is measured, the sides not being necessarily in one plane. Show that the centre of gravity of equal particles placed at  $P, Q$ , &c. coincides with that of equal particles placed at the corners. Art. 79.

Ex. 4. Similar triangles  $ABP, BCQ$ , &c. are described on the sides  $AB, BC$ , &c. of a plane polygon taken in order. Show that the centre of gravity of equal weights placed at  $P, Q$ , &c. coincides with that of equal weights placed at  $A, B$ , &c.

Ex. 5. The perpendiculars from the angles  $A, B, C$  meet the sides of a triangle in  $P, Q, R$ : prove that the centre of gravity of six particles proportional respectively to  $\sin^2 A, \sin^2 B, \sin^2 C, \cos^2 A, \cos^2 B, \cos^2 C$ , placed at  $A, B, C, P, Q, R$ , coincides with that of the triangle  $PQR$ . [Math. Tripos, 1872.]

Ex. 6. A point  $G$  is taken inside a tetrahedron  $ABCD$ . Find by a geometrical construction the plane section which having its corners on the edges  $DA, DB, DC$ , has its centre of gravity at  $G$ . Find also the limiting positions of  $G$  that the construction may be possible.

✓ **386. Perimeter of a triangle.** Ex. 1. A triangle  $ABC$  is formed by three thin rods whose lengths are  $a, b, c$ . If  $H$  be the centre of gravity, prove that the areal coordinates of  $H$  are proportional to  $b+c, c+a, a+b$ .

Ex. 2. The centre of gravity of the perimeter of a triangle  $ABC$  is the centre of the circle inscribed in the triangle  $DEF$ , where  $D, E, F$  are the middle points of the sides of the triangle  $ABC$ . [Lock's Statics.]

Ex. 3. If  $H$  be the centre of gravity of the perimeter of a triangle,  $G$  the centre of gravity of the area,  $I$  the centre of the inscribed circle, prove that  $H, G, I$  are in one straight line, and that  $GH$  is one half of  $IG$ . If  $O$  be the centre of the circumscribing circle, and  $P$  the orthocentre, show also that the triangles  $IGP, HGO$  are similar.


Ex. 4. The sides of a polygon are of equal weight. Prove that the centre of gravity of the perimeter coincides with that of equal particles placed at the corners. Art. 385, Ex. 3.

**387. Quadrilateral areas.** To find the centre of gravity of any quadrilateral area  $ABCD$ .

Using the rule in Art. 380, we replace the triangle  $ADC$  by three particles situated at  $A, D, C$  respectively, each equal to

one-third of the mass of  $ADC$ . In the same way we replace triangle  $ABC$  by three masses at  $A, B, C$ , each one-third of mass of  $ABC$ . Each of the masses at  $A$  and  $C$  is therefore  $\frac{1}{3}M$  if  $M$  be the mass of the whole quadrilateral.

Consider next the masses at  $B$  and  $D$ ; call these  $m_1$  and  $m_2$ . Their united mass is also  $\frac{1}{3}M$ , but this total mass is unequally divided between the particles in the ratio of the triangles  $ABC : ADC$ , i.e. in the ratio  $BE : ED$ . To obtain a more



convenient distribution, let us replace these two masses by two others placed at  $B, D$ , and  $E$ . If the masses placed at  $B$  and  $D$  are each  $\frac{1}{3}M$  and the mass placed at  $E$  is  $-\frac{1}{3}M$ , the sum of the masses is the same as before. It is also clear that their centre of gravity is the same as that of the masses  $m_1$  and  $m_2$ . For by Art. 380

the distance of their centre of gravity from  $E$  is given by

$$\bar{x} = \frac{\sum mx}{\sum m} = \frac{\frac{1}{3}M \cdot BE - \frac{1}{3}M \cdot DE + \frac{1}{3}M \cdot 0}{\frac{1}{3}M}.$$

But the distance of the centre of gravity of the masses  $m_1, m_2$  from  $E$  is given by

$$\bar{x} = \frac{m_1 \cdot BE - m_2 \cdot DE}{m_1 + m_2} = \frac{BE^2 - DE^2}{BE + DE},$$

which is the same as before.

*The centre of gravity of the area of the quadrilateral is therefore the same as that of four equal particles, placed one at each angular point of the quadrilateral, together with a fifth particle of equal negative mass, placed at the intersection of the diagonals.*

We may put the result of this rule into an analytical form. Let  $(x_1, y_1), (x_2, y_2), \dots$  be the coordinates of the four angular

partly because the analytical result follows at once, and partly because these equivalent points are used in rigid dynamics to enable us to write down the moments and products of inertia of a quadrilateral.

We may replace the four particles at the angular points by four others, equal to these, placed at the middle points of the sides, or in any of the equivalent positions described in Art. 385.

**388.** Ex. 1. Prove the following *geometrical* construction for the centre of gravity of a quadrilateral area. Let  $P, Q$  be points in  $BD, AC$  such that  $QA, PB$  are equal respectively to  $EC, ED$ ; the centre of gravity of the quadrilateral coincides with that of the triangle  $EPQ$ . *Quarterly Journal of Mathematics*, vol. vi. 1864.

Ex. 2. A quadrilateral is divided into two triangles by one diagonal  $BD$ , and the centres of gravity of these triangles are  $M$  and  $N$ . Let  $MN$  cut  $BD$  in  $I$ , from the greater  $NI$  take  $NG$  equal to  $MI$  the lesser. Prove that  $G$  is the centre of gravity of the area of the quadrilateral. [Guldin.]

✓ Ex. 3. A trapezium has the two sides  $AB=a$  and  $CD=b$  parallel. Prove that the centre of gravity  $G$  of the quadrilateral area lies in the straight line joining the middle points  $M$  and  $N$  of  $AB$  and  $CD$ . Prove also that  $G$  divides  $MN$  so that  $MG : GN = a + 2b : 2a + b$ . [Archimedes and Guldin.]

Notice that the ratio  $MG : GN$  does not depend on the height of the trapezium but only on the lengths of the parallel sides. [Poinsot.]

Ex. 4. Show that the centre of gravity of the quadrilateral area  $ABCD$  coincides with that of four particles placed at the corners whose weights are respectively  $\beta + \gamma + \delta$ ,  $\gamma + \delta + \alpha$ ,  $\delta + \alpha + \beta$ ,  $\alpha + \beta + \gamma$  where  $\alpha, \beta, \gamma, \delta$  are the reciprocals of  $EA, EB, EC, ED$  and  $E$  is the intersection of the diagonals.

[Caius Coll. 1877.]

Ex. 5. Any corner  $C$  of a pentagonal area  $ABCDE$  is joined to the corners  $A, E$ , and the joining lines intersect  $EB, AD$  in  $F, G$ . Prove that the ordinate  $z$  of the centre of gravity of the pentagonal area is given by

$$3z = b + c + d - \frac{f + g - a - e}{1 - n}, \quad n = \frac{(b - f)(d - g)}{(b - e)(d - a)}$$

where  $a, b, c, d, e, f, g$  are the ordinates of  $A, B, C, D, E, F, G$ , referred to any plane of  $xy$ .

**389. Tetrahedron.** To find the centre of gravity of a tetrahedron  $ABCD$ .

Let us divide the tetrahedron into elementary slices by drawing planes parallel to one face. Let  $abc$  be one of these planes. Bisect  $BC$  in  $E$  and join  $DE$ , then, exactly as in the case of the




is the centre of gravity of the triangle  $abc$ . It therefore follows that the centre of gravity of every elementary slice lies in  $DF$ . Hence the centre of gravity of the whole tetrahedron lies in  $DF$ . Thus *the centre of gravity of a tetrahedron lies in the straight line which joins any angular point to the centre of gravity of the opposite face*.

Let  $K$  be the centre of gravity of the face  $BCD$ ; join  $AK$ . The centre of gravity also lies in  $AK$ . Now both  $DF$  and  $AK$  lie in the plane  $DAE$ , they therefore intersect and the intersection  $G$  is the required centre of gravity.

Exactly as in the corresponding theorem for a triangle, we have  $FK$  parallel to  $AD$  and  $=\frac{1}{3}AD$ . Hence from the similar triangles  $AGD$ ,  $KGF$ , we see that  $FG = \frac{1}{3}GD$ . Thus  $DG = \frac{3}{4}DF$ .

*To find the centre of gravity of a tetrahedron we join any corner (as  $D$ ) to the centre of gravity (as  $F$ ) of the opposite face. The centre of gravity  $G$  lies in  $DF$  so that  $DG = \frac{3}{4}DF$ .*



As in the case of a triangle, we may fix the position of the centre of gravity of a tetrahedron by means of some equivalent points. *The centre of gravity of a tetrahedron is the same as that of four equal particles placed one at each angular point.* The proof is exactly similar to that for a triangle.

**390. Pyramid and Cone.** *To find the centre of gravity of the volume of a pyramid on a plane rectilinear base.*

Proceeding as in the case of the tetrahedron, we divide the pyramid into elementary slices by drawing planes parallel to the base. These sections are all similar to the base. The centre of

of each tetrahedron, and therefore that of the pyramid, lies in a plane parallel to the base such that its distance from the vertex is  $\frac{3}{4}$  of the distance of the base.

Joining these two results together, we have the following rule to find the centre of gravity of a pyramid. *Join the vertex  $V$  to the centre of gravity  $F$  of the base and measure along  $VF$  from the vertex a length  $VG$  equal to three quarters of  $VF$ . Then  $G$  is the centre of gravity of the pyramid.*

When the base of the pyramid is curvilinear we regard the base as the limit of a polygon with an infinite number of elementary sides. We have therefore the following rule. *To find the centre of gravity of the volume of a cone on a circular or on an elliptic base; join the vertex  $V$  to the centre of gravity  $F$  of the base, and measure along  $VF$  from the vertex a length  $VG$  equal to three quarters of  $VF$ , then  $G$  is the centre of gravity of the cone.*

✓ **391.** Ex. 1. A cone whose semivertical angle is  $\tan^{-1} 1/\sqrt{2}$  is enclosed in the circumscribing sphere; show that it will rest in any position. [Math. T., 1851.]

Ex. 2. A pyramid, of which the base is a square, and the other faces equal isosceles triangles, is placed in the circumscribing spherical surface; prove that it will rest in any position if the cosine of the vertical angle of each of the triangular faces be  $\frac{2}{3}$ . [Math. Tripos, 1859.]

Ex. 3. A frustum of a tetrahedron is bounded by parallel faces  $ABC, A'B'C'$ . Prove that its centre of gravity  $G$  lies in the straight line joining the centres of gravity  $E, E'$  of the faces  $ABC, A'B'C'$  and is such that  $\frac{EG}{EE'} = \frac{1+2n+3n^2}{4(1+n+n^2)}$  where  $n$  is the ratio of any side of the triangle  $A'B'C'$  to the corresponding side of the triangle  $ABC$ . [Poinsot.]

Ex. 4. A frustum of a tetrahedron  $ABCD$  is bounded by faces  $ABC, A'B'C'$  not necessarily parallel. Find its centre of gravity.

Let  $DA, DB, DC$  be regarded as a system of oblique axes, let the distances of  $A, B, C, A', B', C'$  from  $D$  be  $a, b, c, a', b', c'$ . Then

$$\bar{x} = \frac{3}{4} \frac{a^2bc - a'^2b'c'}{abc - a'b'c'}, \quad \bar{y} = \frac{3}{4} \frac{ab^2c - a'b'^2c'}{abc - a'b'c'}, \quad \bar{z} = \frac{3}{4} \frac{abc^2 - a'b'c'^2}{abc - a'b'c'}.$$

To prove these results, we regard the tetrahedra as the difference of two tetrahedra whose volumes are as  $abc : a'b'c'$ .

Ex. 5. The top of a right cone, semivertical angle  $\alpha$ , cut off by a plane making an angle  $\beta$  with the axis, is placed on a perfectly rough inclined plane with the

corner. Prove also that the same theorem is true if we read faces for edges, Arts. 79 and 86.

Ex. 2. The centre of gravity of the four faces of a tetrahedron is the centre of the sphere inscribed in a tetrahedron whose corners are the centres of gravity of the faces of the original tetrahedron.

Ex. 3. If  $H$  be the centre of gravity of the faces of a tetrahedron,  $G$  the centre of gravity of the volume,  $I$  the centre of the inscribed sphere, then  $H, G, I$  are in one straight line and  $HG$  is equal to one third of  $GI$ .

Ex. 4. The straight lines which join the middle points of opposite edges of a tetrahedron are called *the median lines*. Show that the medians pass through the centre of gravity  $G$  of the volume and are bisected by it.

Place particles of equal weight at the corners  $A, B, C, D$ . The centres of gravity of the particles  $A, B$  and  $C, D$  are respectively at the middle points  $M, N$  of the edges  $AB, CD$ . Hence the centre of gravity of all four is at the middle point  $G$  of  $MN$ .

Ex. 5. A polyhedron circumscribes a sphere; show that the centres of gravity of the volume and of the surface, viz.  $G$  and  $H$ , and the centre  $O$  lie in the same straight line and that  $OG = \frac{2}{3}OH$ . [Liouville's J., 1843.]

**393. The isosceles tetrahedron.** An isosceles tetrahedron is one whose opposite edges are equal. It follows from this definition that the sides of any two faces are equal each to each.

Ex. 1. Show that the following five points are coincident, viz. (1) the centre of gravity of the volume, (2) the centre of gravity of the six edges, (3) the centre of gravity of the four faces, (4) the centre of the circumscribing sphere, (5) the centre of the inscribed sphere. Let this point be called  $G$ .

Ex. 2. Show that the medians pass through  $G$ , are bisected by it and are perpendicular to their corresponding edges. Show also that the three medians are at right angles and form a system of three rectangular axes. See Casey's *Spherical Trigonometry*, 1889, Art. 127.

Let  $M, N, P, Q, R, S$  be the middle points of the edges  $AB, CD, BD, AC, AD, BC$ . Then  $PR, QS$  are parallel to  $AB$  and each is half  $AB$ ; similarly  $PS, QR$  are parallel and equal to half  $CD$ . Since the opposite edges  $AB, CD$  are equal, it follows that  $PQRS$  is a rhombus, and therefore that the diagonals or medians  $PQ, RS$  are at right angles. The median  $MN$  being perpendicular to the plane containing  $PQ, RS$  is perpendicular to  $PR, QS$  and therefore to the edge  $AB$ .

**394. Double tetrahedra.** To find the centre of gravity of the solid bounded by six triangular faces, i.e. contained by two tetrahedra having a common face.

Let the common base be  $ABC$  and  $D, D'$  the vertices. Join  $DD'$ , and let it cut the base in  $E$ . We replace the tetrahedron  $ABCD$  by four particles, each one-fourth its mass situated at the points  $A, B, C, D$ .

Treating the other tetrahedron in the same way.

$D$

masses situated at  $D$  and  $D'$ , and each one-fourth that of the whole solid, together with a third particle situated at  $E$  of the same mass but taken negatively. The centre of gravity of the whole solid is the same as that of five equal particles placed at  $A, B, C, D, D'$  together with a sixth particle equal and opposite to any of the five placed at the intersection of  $DD'$  with the common face  $ABC$ .

**395.** Ex. The centre of gravity of a pyramid on a plane quadrilateral base is the same as that of five equal particles placed at the five apices, and a sixth equal but negative particle placed at the intersection of the diagonals of the base. [To prove this draw a plane through the vertex and a diagonal of the base; the solid then becomes two tetrahedra joined together at a common face.]

**396. Circular arc.** To find the centre of gravity of an arc of a circle.

Let  $ACB$  be the arc,  $O$  its centre. Let the radius  $OC$  bisect the arc, let  $OC = a$ , and the angle  $AOB = 2\alpha$ . Let  $PQ$  be any element of the arc, and let the angle  $POC = \theta$ . Then in the fundamental formula of Art. 380  $m = ad\theta$ ,  $x = a \cos \theta$ . If  $\bar{x}$  be the distance of the centre of gravity of the arc from  $O$ ,

$$\bar{x} = \frac{\sum m\bar{x}}{\sum m} = \frac{\int ad\theta \cdot a \cos \theta}{\int a d\theta} = a \frac{\sin \alpha}{\alpha},$$


since the limits of  $\theta$  are  $\theta = -\alpha$  and  $\theta = +\alpha$ . As this result is frequently used, it will be convenient to put it into a form which will be convenient for reference.

$$\left. \begin{array}{l} \text{Distance of C. G.} \\ \text{of arc from centre} \end{array} \right\} = \frac{\sin(\text{half angle})}{\text{half angle}} \cdot \text{rad.} = \frac{\text{chord}}{\text{arc}} \cdot \text{rad.}$$

This result was given by Wallis.

**397.** Ex. A series of  $2n$  straight lines are inscribed in a circular arc, each straight line subtending an angle  $2\theta$  at the centre. Prove that the distance of the centre of gravity from the centre is  $r \cos \theta \sin 2n\theta / 2n \sin \theta$ . Then deduce the centre of gravity of a circular arc of any angle. [Guldin's Problem]

**398. Centre of gravity of any arc.** The coordinates of the centre of gravity of the arc of any uniform plane curve are given by the formulæ



according as the equation to the curve is given in the Cartesian form  $y=f(x)$  or the polar form  $r=F(\theta)$ . If the curve be in two dimensions we have an expression for  $\bar{z}$  similar to those written above. The corresponding expressions for  $ds$  are given in works on the differential calculus.

**399.** The process of finding the centre of gravity of an arc is merely the substituting for  $ds$  from the given equation to the curve and then integrating. It seems unnecessary to give at length examples of what is merely integration, we shall therefore state only the results in a few cases likely to be useful.

✓ **Ex. 1.** The coordinates of the centre of gravity of an arc of the catenary  $y = \frac{c}{2}(e^{\frac{x}{c}} + e^{-\frac{x}{c}})$  from  $x=0$  to  $x=x$  are  $\bar{x} = x - \frac{c(y-c)}{s}$ ,  $\bar{y} = \frac{1}{2}\left(y + \frac{cx}{s}\right)$ .

These admit of a geometrical interpretation. Let  $PQ$  be any arc of a catenary. Let the tangents at  $P$  and  $Q$  meet in  $T$  and the normals at  $P$  and  $Q$  meet in  $N$ . If  $\bar{x}, \bar{y}$  be the coordinates of the centre of gravity of the arc  $PQ$ ,  $\bar{x}$ =abscissa of  $T$ , and  $\bar{y}$ =half the ordinate of  $N$ .

✓ **Ex. 2.** Find the centre of gravity of the arc  $OP$  of a cycloid between the vertex  $O$  where  $\phi=0$  and the point  $P$ , the equations to the curve being  $x=2a\phi+a\sin\phi$ ,  $y=a-a\cos\phi$ , and the arc  $OP$  being  $s=4a\sin\frac{\phi}{2}$ .

Result  $\bar{x}=2a\phi - \frac{2a(1-\cos\phi)^2(2+\cos\phi)}{3\sin\phi}$ , and  $\bar{y}=\frac{1}{3}y$ .

**Ex. 3.** If  $G$  be the centre of gravity of any arc  $AP$  of the lemniscate  $r^2=a^2\cos 2\theta$ , prove that  $OG$  bisects the angle  $AOP$ . One case of this is given in Walton's *Problems on Theoretical Mechanics*.

**Ex. 4.** The centre of gravity of any arc  $PQ$  of the curve  $r^3\sin 3\theta=a^3$  lies in the straight line joining the origin to the intersection of the tangents at  $P$  and  $Q$ .


**Ex. 5.** If the density at any point of the arc vary as  $r^{m-3}$ , prove that the centre of gravity of any arc  $PQ$  of the curve  $r^m\sin n\theta=a^n$  lies in the straight line joining the origin to the intersection of the tangents at  $P$  and  $Q$ .

**Ex. 6.** The locus of the centre of gravity of an arc of given length of the lemniscate  $r^2=a^2\cos 2\theta$  is a curve which is the inverse of a concentric ellipse.

[R. A. Robert's theorem]

**400. Sectors of circles.** To find the centre of gravity of a sector of a circle.

Let  $ACB$  be the arc of the sector,  $O$  its centre. As in Art. 399, let the radius  $OC$  bisect the arc,  $OC=a$  and the angle  $AOB=2\theta$ . We divide the sector into elementary triangles of equal area. Let  $OPQ$  be one of these triangles,  $P$  on the arc,  $Q$  on the radius  $OB$ .



anged at equal distances along an arc  $ab$  of a circle. These are represented in the figure by the row of dots. In the limit when the triangles are infinitely small this becomes a homogeneous arc of a circle. The distance of the centre of gravity of the sector from  $O$  is therefore given by the result in Art. 396, viz.

$$\bar{x} = \frac{\sin \alpha}{\alpha} \frac{2}{3} a = \frac{2}{3} \frac{\text{chord } AB}{\text{arc } AB} \cdot \text{radius } OC.$$

This result was given by Wallis.

**01. Ex.** *To find the coordinates of the centre of gravity of the area of a quadrant of a circle  $AOB$ .*

This is a particular case of the last article, viz. when  $\alpha = \frac{1}{2}\pi$ . If  $\bar{x}, \bar{y}$  be the coordinates of  $G$  referred to  $OA, OB$  as axes, we have  $\bar{x} = OG \cos \alpha = \frac{4a}{3\pi}$ ,  $\bar{y} = \frac{4a}{3\pi}$ .

**02. Ex.** The distance of the centre of gravity of the area of a segment of a circle measured from the centre is  $\frac{2}{3} \frac{a \sin^3 \alpha}{a - \sin \alpha \cos \alpha}$ , where  $a$  is the semiangle of the segment.

**403. Projection of areas.** *If any plane area is orthogonally projected on any other plane, the centre of gravity of the projection is the projection of the centre of gravity of the primitive area.*

Let the plane on which the projection is made be the plane of reference and let  $\alpha$  be the inclination of the two planes. Let  $dS$  be any element of the area of the primitive,  $d\Pi$  the area of its projection. Then by a known theorem in conics  $d\Pi = dS \cos \alpha$ . We also notice that the  $x$  and  $y$  coordinates of  $dS$  and  $d\Pi$  are the same because the projection is orthogonal. The coordinates of the centre of gravity of either area are known from  $\bar{x} = \frac{\sum mx}{\sum m}$ ,  $\bar{y} = \frac{\sum my}{\sum m}$ , where the  $m$  for one area is  $d\Pi$  and for the other is  $dS$ . Since they are in a constant ratio, the values of  $\bar{x}$  and  $\bar{y}$  are the same for each area.

In order to use effectively the method of projections we join to the two following well known theorems which are proved in geometry: (1) the projections of parallel straight lines are

relation in the form of ratios of lengths of parallel straight lines. To do this it may be necessary to draw parallels to some of the lines in the primitive if there are no parallels to them mentioned in the given relation. Having put the geometrical relation in the form of ratios, the same relation is true for the projected figure.

**404. Elliptic areas.** Since an elliptic area is well known to be the orthogonal projection of a circle, we can deduce the centre of gravity of the various parts of an ellipse from those of the corresponding parts of a circle. The circle used for this purpose is sometimes called in conics the *auxiliary circle*.

**405.** *To find the centre of gravity of an elliptic area.*

The coordinates of the centre of gravity of a quadrant  $AOB$  of a circle, referred to  $OA$ ,  $OB$  as axes, may be written in the form

$$\frac{\bar{x}}{OA} = \frac{\bar{y}}{OB} = \frac{4}{3\pi} \dots\dots\dots (1)$$

since  $OA$ ,  $OB$  are both radii. But  $\bar{x}$  and  $OA$  are parallel straight lines, and so also are  $\bar{y}$  and  $OB$ . Hence these relations hold in the projected figure also.

*If then  $OA$ ,  $OB$  are the major and minor semiaxes of an ellipse, the coordinates of the centre of gravity of the area of a quadrant are given by (1).*

If we make the plane on which we project intersect the quadrant of the circle in any straight line not one of the bounding radii the circular quadrant projects into an elliptic quadrant bounded by two conjugate diameters.

*If then  $OA$ ,  $OB$  are any two semiconjugates of an ellipse, the coordinates of the centre of gravity of the contained area are given by equations (1).*

The position of the centre of gravity of a semi-ellipse was first found by Guldin.

**406.** Ex. 1. A chord  $PQ$  of an ellipse, centre  $C$ , passes always through a fixed

x. 3. The area  $A$  of any elliptic sector  $POP'$  is  $A = \frac{1}{2} ab (\phi - \phi')$ , and the ordinates of the centre of gravity referred to the principal diameters, are

$$\frac{\bar{x}}{a} = \frac{2}{3} \frac{\sin \phi' - \sin \phi}{\phi' - \phi}, \quad \frac{\bar{y}}{b} = \frac{2}{3} \frac{\cos \phi - \cos \phi'}{\phi - \phi'},$$

where  $\phi, \phi'$  are the eccentric angles of  $P$  and  $P'$ .

x. 4. Show that the centre of gravity  $G'$  of the elliptic segment bounded by the chord  $PP'$  is given by  $OG' = \frac{3}{8} \frac{OA' \sin^3 \phi}{\phi - \sin \phi \cos \phi}$ , where  $OA'$  is the conjugate of  $PP'$  and  $\sin \phi$  is the ratio of  $PP'$  to the parallel diameter.

x. 5. The centre of gravity  $G$  of the area included between an ellipse and the tangents drawn from any point  $T$  in the diameter  $OA'$  produced is given by

$$\frac{OG}{OA'} = \frac{3}{8} \frac{\tan^2 \phi \sin \phi}{\tan \phi - \phi},$$

where  $\sin \phi$  is the ratio of half the chord  $PP'$  of contact to the semiconjugate of  $OT$ . Show also that the coordinates of  $G$  referred to the tangents  $TP, TP'$  as axes are

$$\frac{\bar{x}}{TP} = \frac{\bar{y}}{TP'} = \frac{1}{2} \frac{1}{\sin^2 \phi} \left( 1 - \frac{3}{8} \frac{\tan \phi \sin^2 \phi}{\tan \phi - \phi} \right).$$

In the parabola, we have by rejecting the higher powers of  $\phi$ ,  $\bar{x} = \frac{1}{6} TP$ ,  $\bar{y} = \frac{1}{6} TP'$ .

x. 6. The coordinates of the centre of gravity of the quadrilateral space bounded by arcs of four concentric and coaxial ellipses are

$$\bar{x} = \frac{2}{3} \frac{a_1^2 b_1 (\sin \phi_1' - \sin \phi_1) + a_2^2 b_2 (\sin \phi_2' - \sin \phi_2) + \&c.}{a_1 b_1 (\phi_1' - \phi_1) + a_2 b_2 (\phi_2' - \phi_2) + \&c.}$$

similar expression for  $\bar{y}$ .

**57. Analytical Aspect of Projections.** The geometrical method which has been used in projecting the ellipse into the circle, or conversely, is really equivalent to a change of coordinates. We write  $x = x', y = gy'$ , where  $g$  is a quantity at our disposal, which we so choose that the equation to the ellipse reduces to the simpler form of a circle. We can obviously extend this principle and apply it to any curve. Let us write  $x = fx', y = gy'$ ; we thus have *two* constants instead of one, as we please.

*Geometrically* this is equivalent to two successive projections. By writing  $y = gy'$  we project the primitive on a plane passing through the axis of  $x$ , and then by writing  $x = fx'$  we project the projection on another plane passing through the axis of  $y'$ . We may therefore in this generalized projection assume the two methods of projection already mentioned, and transform all formulæ relating to areas of parallel lengths from one figure to the other.

*Analytically*, let the equations to the several boundaries of any area  $A$  be referred into those of  $A'$  by writing  $x = fx', y = gy'$ . Let  $(\bar{x}, \bar{y})$ ,  $(\bar{x}', \bar{y}')$  be the coordinates of the centres of gravity of  $A$  and  $A'$ . Then we have

$$A = \iint dx dy = fg \iint dx' dy' = fg A'.$$



**408.** The method of projection does not apply so conveniently to find the centres of gravity of hyperbolic areas because we have to use imaginary projections. By projecting the rectangular hyperbola instead of the circle we may find the centre of gravity of any hyperbolic area.

We may however infer from any *general* proposition proved for the ellipse the corresponding theorem for the hyperbola by using the law of continuity. For example, (see Ex. 2, Art. 406) the centre of gravity of a sector of an ellipse  $x = x$  to  $x = a$  is given by  $\bar{x} = \frac{2}{3} ak / \sin^{-1} k$ , where  $k$  has been written for  $(1 - x^2/a^2)^{1/2}$  for the sake of brevity. This must be true also for the imaginary branches of the ellipse which originate in values of  $x > a$ . Put  $k = k' \sqrt{-1}$  and use the formulae of analytical trigonometry,  $\theta \sqrt{-1} = \log(\cos \theta + \sqrt{-1} \sin \theta)$ , where  $\theta = \sin^{-1} k$ ; we then find for the centre of gravity of a hyperbolic sector

$$\bar{x} = \frac{2}{3} \frac{k'}{\log(k' + \sqrt{k'^2 + 1})}, \text{ where } k' = \left\{ \left( \frac{x}{a} \right)^2 - 1 \right\}^{\frac{1}{2}}.$$


**409. Centre of gravity of any area.** After having obtained the fundamental formulæ of Art. 380 the discovery of the centre of gravity of any area is reduced to two processes. (1) We make a judicious choice of the element  $m$ , and (2) we have to effect the necessary integrations. The latter process is fully discussed in treatises on the integral calculus, in fact it is a part of that science rather than of statics. It will thus be unnecessary to do more here than make a few remarks on the choice of  $m$  and its special reference to centres of gravity.

If the centre of gravity of the area bounded by two ordinates  $Aa$ ,  $Bb$  be required, we put the equation of the curve into the form  $y = f(x)$ . We choose as our element the strip  $PQM$ . Here  $PM = y$  and  $m = ydx$ . The coordinates of the centre of gravity of  $m$  are  $x$  and  $\frac{1}{2}y$ . Hence, Art. 380, the formulæ to be used are

$$\bar{x} = \frac{\sum mx}{\sum m} = \frac{\int ydx \cdot x}{\int ydx}, \quad \bar{y} = \frac{\int ydx \cdot \frac{1}{2}y}{\int ydx}.$$

If the centre of gravity of the sectorial area  $AOB$  is wanted, we put the equation into the form  $r = f(\theta)$ . We choose as our element the triangular strip  $POQ$ . Here  $OP = r$ , and  $m = \frac{1}{2}r^2d\theta$ . Cartesian coordinates of the centre of gravity of  $m$  are  $\frac{2}{3}r \cos \theta$  and  $\frac{2}{3}r \sin \theta$ . The formulæ to be used are

$$\bar{x} = \frac{\int \frac{1}{2}r^2d\theta \cdot \frac{2}{3}r \cos \theta}{\int \frac{1}{2}r^2d\theta}, \quad \bar{y} = \frac{\int \frac{1}{2}r^2d\theta \cdot \frac{2}{3}r \sin \theta}{\int \frac{1}{2}r^2d\theta}.$$



0. If the figure whose centre of gravity is required is a triangle or quadrilateral whose sides are *curvilinear*, the proper choice for the element  $m$  will depend on the form of the curves.

If we join the angular points to the origin we have three or four sectors whose centres of gravity may be separately found and thence, by Art. 380, the centre of gravity of the figure. Sometimes the bounding curves are of the same kind so that when the process has been gone through for one sector the results for the other sectors may be inferred. In such cases the method is very advantageous.

For example, we have already seen how the area and centre of gravity of a quadrilateral bounded by four elliptic arcs could be immediately deduced from the area and centre of gravity of an elliptic sector. See Ex. 6, Art. 406.

Putting this in an analytical form, we have for a curvilinear triangle whose sides are  $r=f_1(\theta)$ ,  $r'=f_2(\theta')$ ,  $r''=f_3(\theta'')$ ,

$$\Sigma mx = \frac{1}{3} \int_a^\beta r^3 \cos \theta d\theta + \frac{1}{3} \int_\beta^\gamma r'^3 \cos \theta' d\theta' + \frac{1}{3} \int_\gamma^a r''^3 \cos \theta'' d\theta'',$$

$$\Sigma m = \frac{1}{2} \int_a^\beta r^2 d\theta + \frac{1}{2} \int_\beta^\gamma r'^2 d\theta' + \frac{1}{2} \int_\gamma^a r''^2 d\theta'',$$

$\alpha, \beta, \gamma$  are the inclinations of the radii vectores of the angular points to the axis of  $x$ . In forming these integrals we travel round the triangular figure taking the sides in order.

It might appear at first sight that we are adding together all the three sectors instead of adding some together and subtracting the others. But it will be clear on a little consideration that in those sectors which should be subtracted from the total the  $d\theta$  is made negative by taking the limits in the same order as we travel round the triangle.

Instead of joining the angular points to the origin we might draw perpendiculars from each vertex to the axis of  $x$ . We then have

$$\Sigma mx = \int_a^b xy dx + \int_b^c x'y' dx' + \int_c^a x''y'' dx'',$$

$a, b, c$  are the abscissæ of the angular points. As before, in taking the limits we travel round the sides in order.

1. Sometimes we may use *double integration*. Suppose we can express the boundaries of the figure in terms of both the opposite sides of a curvilinear quadrilateral in one form by an auxiliary quantity  $u$ . That is, let the one equation represent one boundary when  $u=a$ , and let the same equation represent the opposite boundary when  $u=b$ . Let this one equation be  $\phi(x, y, u)=0$ . It is always possible to do this or let  $f_1(x, y)=0$ ,  $f_2(x, y)=0$  be the boundaries, then

$$\phi = (u-a)f_1(x, y) + (u-b)f_2(x, y) = 0$$

represents one or the other according as  $u=a$  or  $u=b$ . But this particular form is not always a convenient mode of expressing  $\phi$ . In the same way let  $\psi(x, y, v)=0$  represent the other two boundaries when  $v=e$  and  $v=f$ .

When this has been accomplished we have only to follow the rules of the calculus. Assigning  $u$  and  $v$  small values between  $a$  and  $b$  and  $e$  and

To find the Jacobian it *may* be necessary to solve the equations  $\phi=0, \psi=0$ , to express  $x, y$  in terms of  $u, v$ . We then have  $J = \frac{dx}{du} \frac{dy}{dv} - \frac{dx}{dv} \frac{dy}{du}$ . Unless we been able in the first instance to express  $\phi$  and  $\psi$  so conveniently that this Jacobian takes a simple form when expressed in terms of  $u, v$ , this method may lead to a complicated analysis. The advantage of the method is that the limits of integration  $u=a$  to  $b, v=c$  to  $f$  are constants, so that the integrations may be performed in order or simultaneously.

**412. Ex. 1.** An area is cut off from a parabola by a diameter  $ON$  and the ordinate  $PN$ : prove that  $\bar{x} = \frac{2}{3}x, \bar{y} = \frac{2}{3}y$ .

**Ex. 2.** Two tangents  $TP, TP'$  are drawn to a parabola: show that the coordinates of the centre of gravity of the area between the curve and the tangents are  $\bar{x} = \frac{1}{3}TP, \bar{y} = \frac{1}{3}TP'$  referred to  $TP, TP'$  as axes. Art. 406, Ex. 5. [Walsh]

Regard the area as the difference between a triangle and a parabolic segment.

**Ex. 3.** The equations of a cycloid are  $x=a(1-\cos\theta), y=a(\theta+\sin\theta)$ . Show that the centre of gravity of half the area is given by  $\bar{x} = \frac{7}{8}a, \bar{y} = \frac{a}{2} \left( \pi - \frac{16}{9\pi} \right)$ . [Walsh]

**Ex. 4.** Find the centre of gravity of the half of either loop of the lemniscate  $r^2 = a^2 \cos 2\theta$  bounded by the axis. The result is

$$\bar{x} = \frac{\pi a}{4\sqrt{2}}, \quad \bar{y} = \frac{3 \log(\sqrt{2}+1) - \sqrt{2}}{6\sqrt{2}} a.$$

**Ex. 5.** Four parabolas whose equations are  $y^2 = a^2x, y^2 = b^2x, x^2 = a^2y, x^2 = b^2y$  intersect and form a quadrilateral space. Find the centre of gravity.

We take as the equations to the opposite sides  $y^2 = u^2x$  and  $x^2 = v^2y$ . Solving we find  $x=uv^2, y=u^2v$  and  $J=3u^2v^2$ . This gives by substitution

$$\bar{x} = \frac{9}{2v} \frac{(b^4 - a^4)(f^5 - e^5)}{(b^3 - a^3)(f^3 - e^3)}.$$

**Ex. 6.** The centre of gravity of the space bounded by two ellipses and two hyperbolas all confocal lies in the straight line

$$-\frac{y}{x} = \frac{(a_2 - a_1)(a_2' - a_1')(a_2^2 + a_1a_2 + a_1'^2 - a_2'^2 - a_1'a_2' - a_1'^2)}{(b_2 - b_1)(b_2' - b_1')(b_2^2 + b_1b_2 + b_1'^2 + b_2'^2 + b_1'b_2' + b_1'^2)},$$

where the unaccented letters denote the semiaxes of the ellipse and the accented letters those of the hyperbola.

We take as the equation to the opposite sides  $\frac{x^2}{u} + \frac{y^2}{u-h} = 1, \frac{x^2}{v} + \frac{y^2}{v-h} = 1$ , where  $u > h$  and  $v < h$ . These give  $hx^2 = uv, -hy^2 = (u-h)(v-h)$ , as shown in Salmon's *Conics*. The result then follows easily enough.

**Ex. 7.** If the density at any point of a circular disc whose radius is  $a$  varies directly as the distance from the centre, and a circle described on a radius as diameter be cut out, prove that the centre of inertia of the remainder will be

9. The curve for which the ordinate and abscissa of the centre of gravity of area included between the ordinates  $x=a$  and  $x=x$  are in the same ratio as the bounding ordinate  $y$  and abscissa  $x$  is given by the equation  $a^3y^3 - b^3x^3 = x^3y^3$ .

[Math. Tripos, 1871.]

**13. Pappus' Theorems.** Before treating of the centres of gravity of surfaces or volumes it seems proper to discuss a method by which the centres of gravity of the arcs and areas already mentioned may be used to find the surface or volume of a solid of revolution. The two following theorems were first given by Pappus at the end of the preface of his seventh book of *Mathematical Collections*.

Let any plane area revolve through any angle about an axis in its own plane, then


- 1) *The area of the surface generated by its perimeter is equal to the product of the perimeter into the length of the path described by the centre of gravity of the perimeter.*
- 2) *The volume of the solid generated by the area is equal to the product of the area into the length of the path described by the centre of gravity of the area.*

In both these theorems the axis is supposed not to intersect the perimeter or area.

**14.** Let  $AB$  be an arc of the curve, and let it lie in the plane. Let it revolve about the axis of  $z$  through any elementary angle  $d\theta$ . Any element  $PQ = ds$  of the perimeter is thus brought into the position  $P'Q'$ , and the area traced out by it is  $ds \cdot PP' = ds \cdot x d\theta$ . The whole area or surface traced out by the finite arc  $AB$  is  $d\theta \int x ds$ . But this is  $d\theta \cdot \bar{x}s$ , if  $s$  be the length of arc  $AB$  and  $\bar{x}$  the distance of its centre of gravity from the axis of  $z$ . If the arc now revolve again about  $Oz$  through any second elementary angle  $d\theta$ , an equal surface is again traced out. Hence, when the angle of rotation is  $\theta$ , the area is  $s \cdot \bar{x}\theta$ .  $\bar{x}\theta$  is the length of the path traced out by the centre of gravity of the arc. The first proposition is therefore proved.

by the whole area of the closed curve is  $d\theta \int x dA$ . But this is  $d\theta \cdot \bar{x}A$ , if  $A$  be the area of the curve and  $\bar{x}$  the distance of its centre of gravity from the axis of revolution. Integrating again for any finite value of  $\theta$ , we find that the volume generated is  $A \cdot \bar{x}\theta$ . This as before proves the theorem.

In both these proofs we have assumed that the whole of the curve lies on the same side of the axis of rotation. For suppose  $P_1$  and  $P_2$  were two points on the curve on opposite sides of the axis of  $z$ , then their abscissæ  $x_1$  and  $x_2$  would have opposite signs. Thus the elementary surfaces or volumes (having the factor  $xd\theta$ ) would also have opposite signs. The integral gives the sum of these elementary surfaces or volumes taken with their proper signs. It follows that, when the axis cuts the curve, Pappus' two rules give the *difference of the surfaces or volumes traced out by the two parts of the curve on opposite sides of the axis of revolution*.



**415. Ex. 1.** Find the surface and volume of a tore or anchor-ring.

This solid may be regarded as generated by a complete revolution of a circle about an axis in its own plane. Let  $a$  be the distance of the centre from the axis,  $b$  the radius of the generating circle. Then  $a > b$  if all the elements are to be regarded as positive. The arc of the generating circle is  $2\pi b$ , the length of the path described by its centre of gravity is  $2\pi a$ . The surface is therefore  $4\pi^2 ab$ . The area of the circle is  $\pi b^2$ , the length of the path described by its centre of gravity is  $2\pi a$ . The volume is therefore  $2\pi^2 ab^2$ .

**Ex. 2.** Find the volume of a solid sector of a sphere with a circular rim and also the area of its curved surface.

This solid may be regarded as generated by a complete revolution of a sector of a circle about one of the extreme radii. Let  $2\alpha$  be the angle of the sector,  $O$  its centre. The arc of the sector is  $2a\alpha$ . The length of the path described by its centre of gravity  $G$  is  $2\pi \cdot OG \sin \alpha$ , where  $OG = (a \sin \alpha)/\alpha$ . The spherical surface is therefore  $4\pi^2 a^2 \sin^2 \alpha$ . The area of the sector is  $a^2 \alpha$ . The length of the path of its

16. It should be noticed that for any elementary angle  $d\theta$  axis of rotation need only be an instantaneous axis. Suppose plane area to move so as always to be normal to the curve described by the centre of gravity of the area. Then as the centre of gravity describes the arc  $ds$ , the area  $A$  may be regarded as revolving round an axis through the centre of curvature of the path. Hence the elementary volume is  $A ds$ , and the volume described is the product of the area into the length of the path described by the centre of gravity of the area.

In the same way, if the area move so as always to be normal to the path described by the centre of gravity of the *perimeter*, the volume of the solid is the product of the arc into the length of the path of the centre of gravity of the perimeter.

17. When the axis of rotation does not lie in the plane of the curve, we can make a modification of Pappus' rule to find the volume generated by the motion of the area.

Let us suppose that the axis of rotation is parallel to the plane of the curve. Referring to the figure of Art. 414, let  $CL$  be the axis, and let  $RL$  be a perpendicular from any point  $R$  within the closed curve. The elementary area  $dA$  at  $R$  will describe a portion of a thin ring whose centre is at  $L$ . The length of this arc is  $\theta \cdot RL$ . The area of the normal section of this ring is  $dA \cos \phi$ , where  $\phi$  is the angle the normal  $RL$  to the ring makes with the area  $dA$ . The volume cut out is therefore  $RL \cdot \cos \phi \cdot \theta dA$ . But this is the same as  $x \theta dA$ . This is the same result as we obtained before when the axis of revolution was  $Oz$ .

If the element were to revolve round  $Oz$  it would trace out a ring of less radius than it actually does in its revolution round  $CL$ , and these rings would be differently situated in space. But the normal section of the larger ring is so much less than that of the smaller ring that the two volumes are equal.

We infer that Pappus' rule will apply to find the volume if we treat the *projection of the axis* on the plane of the curve as if it were the actual axis of rotation. The axis of rotation is to be the same for both axes.

If the area does not lie wholly on one side of the projection, it must be remembered that the volumes generated by the two parts on opposite sides of the projection have opposite signs.

Ex. 1. If the axis of revolution is inclined to the plane of the area at an angle  $\alpha$ , show that Pappus' rule will give the volume generated if we treat the projection of the axis on the plane as if it were the axis of revolution and regard the angle of rotation as  $\theta \cos \alpha$  instead of  $\theta$ .

Ex. 2. A quadrant of a circle makes a complete revolution about an axis


point between  $A_1$  and  $A_2$ . If it is either, the areas traced out by arcs on opposite sides of that point will have opposite signs.

Ex. 4. A solid is generated by the revolution of an area about the axis of  $z$  which lies in its own plane. The density  $D$  at any point  $P$  of the solid is a given function of  $z$  and  $\rho$ , where  $\rho$  is the distance of  $P$  from the axis. Prove that the mass may be found by Pappus' rule if we regard  $D$  as the surface density at any point  $P$  of the generating area where the coordinates of  $P$  are  $z$  and  $\rho$ .

**418. Areas on the surface of a right cone.** *To find the centre of gravity of the whole surface of a right cone excluding the base. Guldin's Theorem.*

Let  $O$  be the vertex,  $C$  the centre of the base, then  $OC$  is perpendicular to the plane of the base. The required centre of gravity lies in  $OC$ .

Divide the surface of the cone into elementary triangles by drawing straight lines from the vertex  $O$  to points  $a, b, c$ , &c. in the base. The centre of gravity of each triangle lies in a plane parallel to the base and dividing the sides  $Oa, Ob$ , &c. in the ratio  $2 : 1$ . The centre of gravity of the whole surface is therefore at the intersection of this plane with  $OC$ .



*The centre of gravity of the surface of a right cone is two-thirds of the way from the vertex to the centre of the base.*

Ex. Show that the same rule applies to find the centre of gravity of the whole curved surface of a right cone on an elliptic base or more generally on any base which is symmetrical about two diameters at right angles.

**419.** *To find the area and centre of gravity of a portion of the surface of a right cone on a circular base.*

Referring to the figure of Art. 418, let  $PQ = dS$  be an element of the surface of the cone,  $P'Q' = d\Pi$  its projection on the base. The angle between  $PQ$  and  $P'Q'$  is the same as the angle between

If we take the axis of the cone for the axis of  $z$ , it is clear that  $dS$  and  $d\Pi$  have the same coordinates of  $x$  and  $y$ . Hence, proceeding exactly as in Art. 403, we see that the projection of the centre of gravity of any portion of the surface of the cone on a plane perpendicular to the axis is the centre of gravity of the projection. We have yet to find the  $z$  coordinate of the centre of gravity. Taking any plane perpendicular to the axis as the plane of  $xy$ , we

$$\bar{z} = \frac{\sum mz}{\sum m} = \frac{\int dS z}{\int dS} = \frac{\int z d\Pi}{\int d\Pi};$$

the distance of the centre of gravity of any portion  $S$  of the surface from any plane perpendicular to the axis is equal to the distance of the centre of gravity of the projection  $\Pi$  of the cylindrical solid between  $S$  and its projection  $\Pi$  on the plane divided by the area  $\Pi$ .

These three results depend on the fact that the area of any element  $dS$  of the surface bears a constant ratio to its projection  $d\Pi$  on the plane of  $xy$ . This again implies that every tangent plane to the surface should make a constant angle with the plane of  $xy$ . Other surfaces besides right cones and planes possess this property. Any developable surface which is the envelope of a system of planes making a constant angle with the plane of  $xy$  will obviously satisfy the conditions.

Ex. 1. A cone of any form is intersected by a plane  $AB$ , and any straight line is drawn from the vertex to meet the section in  $H$ . Prove that the conical volume between the plane of the section and the vertex is equal to the product of  $\frac{1}{3}OH$  into the area of the section  $AB$  on a plane perpendicular to  $OH$ .

Ex. 2. A right cone, whose semi-angle is  $\alpha$ , is intersected by a plane  $AB$  cutting the axis in  $H$  and making an angle  $\beta$  with the axis. Show that, (1) the surface  $S$  of the cone between the elliptic section  $AB$  and the vertex  $O$  is equal to the product of the area of the section  $AB$  into  $\sin \beta \operatorname{cosec} \alpha$ ;


(2) the centre of gravity of the surface  $S$  lies in a straight line drawn parallel to the axis of the cone from the centre  $C$  of the section  $AB$ ;

(3) the distance of the centre of gravity of the surface  $S$  from  $C = \frac{1}{3}OH$ .

Since both the surface  $S$  and the section  $AB$  project into the same elliptic area on the plane of  $xy$ , the two first results follow from what has been proved above.

To prove the third result we divide the surface into elementary triangles by drawing straight lines from the vertex to the base  $AB$ . It follows, as in Art. 418, that the centre of gravity of the surface lies in a plane drawn parallel to the base through a trisecting point of  $OH$ .

Ex. 3. A right cylinder stands





volume of the cylinder between the plane  $AB$  and the base is equal to the product of the area of the base into the ordinate of the plane at the centre of gravity of the area.

By considering part of the perimeter of the base to be rectilinear and part curved, this gives the surface and volume of the portion of the cylinder cut off by two planes parallel to the axis and two transverse to the axis.


Ex. 4. A right cylinder stands on the base  $Ax^2 + By^2 = 1$ , and is intersected by the plane  $z = h + px + qy$ . Prove that the coordinates of the centre of gravity of the volume are given by  $4Ah\bar{x} = p$ ,  $4Bh\bar{y} = q$ ,  $2\bar{z} = h + p\bar{x} + q\bar{y}$ .

**420. Spherical Surfaces.** There are two projections of the spherical surface which have been found useful. We can project any portion of the surface on the circumscribing cylinder and on a central plane. We shall consider these in order.

Let the origin be at the centre of the sphere, and let the rectangular axes  $x, y, z$  cut the surface in  $A, B, C$ . Let the polar coordinates of any point  $P$  be as usual  $OP = a$ , the angle  $COP = \theta$  and the angle  $NOA = \phi$ . Let  $PL = \rho$  be a perpendicular on the axis of  $z$ , then  $OL = z$ .

Let a cylinder circumscribe the sphere and touch it along the circle of which  $AB$  is a quadrant. Any point  $P$  on the sphere is projected on the cylinder by producing  $LP$  to meet the cylinder in  $P'$ . According to this definition any point  $P$  and its projection  $P'$  are so related that their  $z$ 's and  $\phi$ 's are the same.

The area of any element  $PQR$  on the sphere is  $PQ \cdot QR$ , and this is equal to  $a \sin \theta d\phi \cdot a d\theta$ . The area of the projection on the cylinder, viz.  $P'Q'R'$  is  $P'Q' \cdot Q'R'$ , and this is  $ad\phi \cdot dz'$ , where  $z' = CL = a - a \cos \theta$ . Substituting for  $z'$ , we see



It follows from this result that the area of any finite portion of the spherical surface is equal to the area of its projection on any circumscribing cylinder. *This rule enables us to find many areas of the sphere which are useful to us.* Thus the area cut off from the sphere by any two parallel planes whose distance apart is  $h$  is equal to the area of a band on the cylinder whose breadth is  $h$ . The area on the sphere is therefore  $2\pi ah$ . We notice that this result is independent of the position of the planes, except that they must be parallel. Thus the area of a segment of a sphere whose height is  $h$  is  $2\pi ah$ .

21. This important theorem is used also in the construction of maps. The surface of a terrestrial globe are projected in the manner just described on a circumscribing cylinder. The cylinder is then unrolled on a plane. In this way the whole globe may be represented on a map of a rectangular form. *The advantage of this construction is that any equal areas on the globe are represented by equal areas on the map.* This is true for large or small areas in whatever part of the globe they may be situated. *The disadvantage of the construction is that any small figure on the map is not similar to the corresponding figure on the globe.* If the figure is situated near the curve of contact of the cylinder, the similarity is sufficiently close for practical purposes, but if the figure is situated nearer the pole of this curve of contact, the dissimilarity is more striking. Thus a small circle very near the pole is represented by an elongated oval. In some other systems of making maps, as for example Mercator's, any small figure on the map is made similar to the corresponding figure on the globe, but in that case equal areas on the map do not correspond to equal areas on the globe.

22. A map is made on the following principle. Any point  $O$  on the surface of the sphere of radius unity, and a corresponding point  $O'$  on a map being taken, the points  $P$ ,  $Q$  corresponding to the two points  $P$ ,  $Q$  on the globe are found by taking the lengths  $O'P' = a \tan \frac{1}{2}OP$ ,  $O'Q' = a \tan \frac{1}{2}OQ$ , the angle  $P'O'Q'$  being made equal to the angle  $POQ$ . Prove that any infinitely small corresponding portions on the sphere and on the map are similar. Show also that the scale of the map in the neighbourhood of any point  $P'$  varies as  $a^2 + O'P'^2$ .

When the tangents are replaced by sines in the relations given above, prove that the areas of corresponding portions have a constant ratio.

These are called the stereographic projection and the chordal construction.

22. The altitude of the centre of gravity of any portion of the sphere above the plane of contact is equal to the altitude of the centre of gravity of its projection on the circumscribing cylinder. To

the corresponding band on the cylinder, and is therefore half between the parallel planes, and lies on the perpendicular radius.

In the same way the *centre of gravity of a hollow thin hemisphere of uniform thickness bisects the middle radius.*

**423.** Ex. 1. A segment of a sphere of height  $h$  rests on a plane base: that the centre of gravity of the surface including the plane base is at a distance equal to  $ah/(4a-h)$  from the base, where  $a$  is the radius of the sphere.

Ex. 2. The distance of the centre of gravity of the surface of a lune from the axis is  $\frac{\pi a \sin \alpha}{4} \frac{1}{a}$ , where  $2\alpha$  is the angle of the lune.

Ex. 3. A bowl of uniform thin material in the form of a segment of a sphere closed by a circular lid of the same material and thickness, which is hinged at a diameter. If it be placed on a smooth horizontal plane with one half of the lid turned back over the other half, show that the plane of the lid will make with the horizontal plane an angle  $\phi$  given by  $3\pi \tan \phi = 4 \tan \frac{1}{2}\alpha$ ;  $\alpha$  being the angle the radius of the lid subtends at the centre of the sphere. [Math. Tripos, I]

**424.** To find the centre of gravity of any spherical triangle.

Let us begin by projecting any portion of the surface of the sphere on a central plane. Let this be the plane of  $xy$ . Let  $dS$  be any element of area,  $d\Pi$  its projection, let  $\theta$  be the angle the normal at  $dS$  makes with the axis of  $z$ . Then

$$d\Pi = dS \cos \theta = dS \cdot z/a.$$

Hence, integrating, we have  $a\Pi = S\bar{z}$ .

It follows that the distance of the centre of gravity of any portion  $S$  of the surface of

a sphere from a central plane  $= \frac{\Pi}{S} a$ , where


$\Pi$  is the projection of  $S$  on that plane\*.

This result follows from the equality  $\cos \theta = z/a$ . Other surfaces besides spheres possess this property. These surfaces are generated by the motion of a sphere of constant radius, whose centre moves in a straight line in the plane of  $xy$ . As an example an anchor ring or torus may be mentioned.

Let us now apply this Lemma to the spherical triangle. Let  $A, B, C$  be the vertices,  $a, b, c$  the sides, let  $O$  be the centre of the sphere,  $\rho$  its radius. Let  $CN$  be a perpendicular from  $C$  on the plane  $AOB$ , let  $AN, BN$  be the two elliptical arcs which are the projections of the sides  $AC, BC$  of the spherical triangle.

By the lemma,  $\bar{z} : \rho = \text{area } ANB : \text{area } ABC$ . Also

$$\begin{aligned} (\text{area } ANB) &= (\text{area } AOB) - (\text{area } AOC) \cos A - (\text{area } BOC) \cos B \\ &= \frac{1}{2}\rho^2 (c - b \cos A - a \cos B). \end{aligned}$$



formula gives the distance of the centre of gravity from the plane  $AOB$  joining any side  $AB$  of the triangle. The distances from the planes  $BOC$ ,  $COA$  joining the other sides are expressed by similar formulae.

x. 1. If  $p, q, r$  be the perpendicular arcs from the angular points  $A, B, C$  on opposite sides, and  $G$  the centre of gravity of the spherical triangle, prove that

$$\frac{\cos AOG}{a \sin p} = \frac{\cos BOG}{b \sin q} = \frac{\cos COG}{c \sin r} = \frac{1}{2E}.$$

is equivalent to the result given in Moigno's *Statique*.

x. 2. A surface is generated by the revolution of the catenary about its axis. This be the axis of  $z$  and let the plane generated by the directrix be that of  $xy$ . A portion  $S$  of its surface is projected orthogonally on the plane  $xy$ , and  $V$  is the volume of the cylindrical solid formed by the perpendiculars from the perimeter of  $S$ . Prove that the  $\bar{x}$  and  $\bar{y}$  of  $S$  and  $V$  are equal each to each, but the  $\bar{z}$  of the first is not equal to that of the second.


[Giulio, also Walton.]

425. **Any surfaces and solids of revolution.** A known curve revolves round an axis in its own plane which we shall take as the axis of  $z$ , and the angle of revolution is  $2\alpha$ . It is required to find the centres of gravity of the surface and volume generated.

It is clear that every point describes an arc of a circle whose centre is in the axis of  $z$ . Thus the whole solid is symmetrical about a plane passing through  $z$  and bisecting all these arcs. Let this be the plane of  $xz$ . The centres of gravity lie in this plane. Let  $PP'$  be half the arc described by  $P$ , the other half being behind the plane  $xz$  not drawn in the figure.

Let  $PQ=ds$  be any arc of the generating curve, then the area of the elementary band

described by  $ds$  is  $m=2\pi x ds$  by Pappus's theorem. Its centre of gravity lies in  $MP$  at a distance from  $M$  equal to  $(x \sin \alpha)/\alpha$ . Hence the coordinates of the centre of gravity of the surface are



$$\bar{x} = \frac{\sum mx}{\sum m} = \frac{\int x^2 ds}{\int ds} \cdot \frac{\sin \alpha}{\alpha}, \quad \bar{z} = \frac{\int xz ds}{\int ds}.$$

write for  $d\sigma$  either  $dx dz$  or  $r d\theta dr$  according as we choose to use Cartesian or polar coordinates, replacing the single integral by that for double integration.

It is evident that these integrals are those used in the higher Mathematics for the moments and products of inertia of the surfaces and areas. When therefore we have once learnt the rules to find these moments of inertia, we seldom have to perform any integration; we simply quote the results as being well known. These rules are usually studied in connection with rigid dynamics, and knowledge of them is essential for that science, but they are also given in some of the treatises on the integral calculus, for example in that by Prof. Williamson.

Ex. 1. A portion of an anchor ring is generated by the complete revolution of a quadrant of a circle (radius  $a$ ) about an axis parallel to one of the extreme radii and distant  $b$  from it. Prove that the distances of the centres of gravity of the curved surface and volume from the plane described by the other extreme radius

$$\frac{a(2b \pm a)}{\pi b \pm 2a} \text{ and } \frac{a(8b \pm 3a)}{2(3\pi b \pm 4a)}.$$

The axis of revolution is supposed not to cut the quadrant.

Ex. 2. A semi-ellipse revolves through one right angle about one of its bounding diameters. Show that the distance from the axis of the centre of gravity of the volume generated is  $3ab/4\sqrt{2r}$ , where  $2r$  is the length of the diameter.

Ex. 3. A triangular area makes a revolution through two right angles about one of its axes in its own plane. Prove that the distance of the centre of gravity of the volume from the axis is  $\frac{2}{\pi} \frac{a^2 + \beta^2 + \gamma^2}{a + \beta + \gamma}$ , where  $a, \beta, \gamma$  are the distances of the middle points of the sides from the axis.

Ex. 4. A circular area of radius  $a$  revolves about a line in its plane at a distance  $c$  from the centre, where  $c$  is greater than  $a$ . If  $2\alpha$  be the angle through which it revolves, find the volume generated and prove that the centre of gravity of the volume is at a distance from the line equal to  $(4c^2 + a^2) \sin \alpha / 4ca$ . [Coll. Ex., 1]

**426.** *To find the centre of gravity of a solid sector of a sphere with a circular rim.*

Referring to the figure of Art. 400, let  $OC$  be the minimum radius of the solid sector,  $N$  the centre of the rim,  $G$  the centre of gravity of the sector,  $V$  its volume,  $V_0$  the volume of the whole sphere.

whose centre of gravity is at  $p$  where  $Op = \frac{3}{4} OP$ . Hence, if  $G'$  be the centre of gravity of the surface,  $OG = \frac{3}{4} OG'$ . But  $OG' = \frac{1}{2} (ON + OC)$  by Art. 422. Hence the result follows. The volume  $V$  has been already found in Art. 415.

The centre of gravity of a solid hemisphere follows immediately from this result. Putting  $ON = 0$ , we see that *the centre of gravity of a solid hemisphere lies on the middle radius and is at a distance  $\frac{3}{8}$  of that radius from the centre.*

The centre of gravity of a solid octant also follows at once. There are four octants on one side of any central plane and the centre of gravity of each of these is at the same distance from that plane. Hence the centre of gravity of all four must be also at the same distance, and this has just been proved to be  $\frac{3}{8}a$ . Hence, *for any octant, the distance of the centre of gravity from any one of the three plane faces is  $\frac{3}{8}$  of the radius.*

**427.** Ex. 1. The centre of gravity and volume of a solid segment of a sphere bounded by a plane distant  $z$  from the centre  $O$  are given by

$$OG = \frac{3}{8} \frac{(a+z)^2}{2a+z}, \quad V = \frac{\pi}{3} (a-z)^2 (2a+z).$$

Ex. 2. Prove that in a sphere, whose density varies inversely as the distance from a point in the surface, the distance of the centre of gravity from that point bears to the diameter the ratio 2 : 5. [Math. Tripos, 1867.]

Ex. 3. Prove that the centre of gravity of a solid sphere, whose density varies inversely as the fifth power of the distance from an external point, is at the centre of the section of the sphere by the polar plane of the external point. [Math. Tripos, 1872.]

**428. Centres of gravity of volumes connected with the ellipsoid.** In order to deduce the centre of gravity of any portion of an ellipsoid from that of the corresponding portion of a sphere, we shall use an extension of that method of projections by which we passed from the areas of circles to those of ellipses.

One point  $(xyz)$  is said to be projected into another  $(x'y'z')$  when we write  $x = ax'$ ,  $y = by'$ ,  $z = cz'$ . The points are then said to correspond. Volumes  $V$ ,  $V'$  correspond when their boundaries are traced out by corresponding points. If  $(\bar{x}\bar{y}\bar{z})$ ,  $(\bar{x}'\bar{y}'\bar{z}')$  be the

We may also show\* that (1) parallel straight lines correspond to parallels, and (2) the ratio of the lengths of parallel straight lines is unaltered by projection. Thus the rule already explained in Art. 403 for areas is true also for solids.

We may apply these principles to an ellipsoidal solid. The equation to an ellipsoid of semi-axes  $a, b, c$  is changed into the equation to a concentric sphere by writing  $x = ax', y = by', z = cz'$ . It follows that all projective theorems may be transferred from the sphere to the ellipsoid.

✓ **429.** Ex. 1. Find the centre of gravity of a solid sector of an ellipsoid with elliptic rim.

Let  $O$  and  $N$  be the centres of the ellipsoid and of the rim. Then  $ON$  is a conjugate diameter of the plane of the rim. Let it cut the ellipsoid in  $C$ . The corresponding theorem for a spherical sector is given in Art. 426. Since the values of  $OG$  and  $V$  there given depend on the ratios of parallel lengths, they may transfer them to the ellipsoid. The centre of gravity  $G$  of the ellipsoidal sector therefore lies in  $ON$ , and we have

$$OG = \frac{3}{8} \frac{ON + OC}{2}, \quad V = \frac{CN}{2 \cdot OC} V_0.$$

Ex. 2. The coordinates of a solid octant of an ellipsoid bounded by three conjugate planes are  $\bar{x} = \frac{3}{8}a$ ,  $\bar{y} = \frac{3}{8}b$ ,  $\bar{z} = \frac{3}{8}c$ .

Ex. 3. The centre of gravity and volume of any solid segment of an ellipsoid are given by

$$OG = \frac{3}{8} \frac{(c+z)^2}{2c+z}, \quad V = \frac{(c-z)^2(2c+z)}{4c^3} V_0,$$

where  $2c$  is the conjugate diameter of the plane of the segment,  $z$  its ordinate measured along  $c$ , and  $V_0$  the volume of the whole ellipsoid.

**430.** Let us construct two concentric and coaxial ellipsoids forming between them a thin solid shell. Let  $(a, b, c)$ ,  $(a+da, b+db, c+dc)$  be the semi-axes of the ellipsoids,  $p$  and  $p+dp$  the perpendiculars on two parallel tangent planes. Let  $t=dp$  be the thickness of the shell at any point. Let  $d\sigma$  be an element of surface of one ellipsoid,  $d\Pi$  its projection on the plane of  $xy$ , then  $d\Pi =$

Ex. 1. Show that the ordinate  $\bar{z}$  of the centre of gravity of any portion of the shell is given by  $\bar{z}V = c^2 \int \frac{t}{p} d\Pi$ , where  $V$  is the volume of that portion of the shell.

Ex. 2. If the shell is bounded by similar ellipsoids, so that  $\frac{da}{a} = \frac{db}{b} = \frac{dc}{c}$ , prove that  $\bar{z} : c = \Pi dc : V$ .

If two parallel planes cut off a portion from this *thin* shell, prove that its centre of gravity lies in the common conjugate diameter and is equidistant from the two planes. Art. 428.

Ex. 3. If the shell is bounded by confocal ellipsoids, so that  $ada = bdb = cdc = p dp$ ,

show that 
$$\frac{\bar{z}}{c} = \frac{\Pi dc}{V} \left\{ 1 - \left( 1 - \frac{c^2}{a^2} \right) \frac{k_2^2}{a^2} - \left( 1 - \frac{c^2}{b^2} \right) \frac{k_1^2}{b^2} \right\},$$

where  $\Pi k_1^2$  and  $\Pi k_2^2$  are the moments of inertia of  $\Pi$  about the axes of  $x$  and  $y$  respectively, Art. 425.

Ex. 4. If the density of a shell bounded by concentric, similar, and similarly situated ellipsoids vary inversely as the cube of the distance from a point within the cavity, that point is the centre of gravity.

If the shell be thin, and the density vary inversely as the cube of the distance from an external point, the centre of gravity is in the polar plane of the point. At what point of the polar plane is the centre of gravity situated? [Math. T., 1880.]

Let the shell be thin, and let  $O$  be the point within the cavity. With  $O$  for vertex describe an elementary cone cutting off from the shell two elementary volumes. Let  $v$  and  $v'$  be these volumes, and  $r, r'$  their distances from  $O$ . By the properties of similar ellipsoids, we may show that  $v/r^2 = v'/r'^2$ . Let  $D, D'$  be the densities of these elements. Since  $D = \mu/r^3, D' = \mu/r'^3$ , we find  $vDr = v'D'r'$ , i.e. the centre of gravity of two elements is at  $O$ . It easily follows that the centre of gravity of the whole thin shell is at  $O$ . Joining many thin shells together, it also follows that the centre of gravity of a thick shell is at  $O$ .

Next, let  $O$  be an external point, and let the elementary cone whose vertex is at  $O$  intersect the polar plane of  $O$  in an element whose distance from  $O$  is  $\rho$ . Since  $\rho$  is the harmonic mean of  $r$  and  $r'$ , we easily find  $vDr + v'D'r' = (vD + v'D')\rho$ , i.e. the centre of gravity of the two elementary volumes  $v$  and  $v'$  lies in the polar plane of  $O$ . It follows that the centre of gravity of the shell lies in the polar plane of  $O$ .

Lastly, let any number of particles  $m_1, m_2, \&c.$ , attract the origin according to Newtonian law, and let the resultant attraction be a force  $X$  acting along the axis of  $x$ . If the coordinates of the particles be  $(x_1 y_1 z_1) \&c.$ , we find by resolution

$$\sum \frac{mx}{r^3} = X, \quad \sum \frac{my}{r^3} = 0, \quad \sum \frac{mz}{r^3} = 0.$$

The two latter equations show that, if the masses  $m_1, m_2, \&c.$  are divided by powers proportional to the cubes of their distances from the origin, the centre of gravity of the masses so altered lies in the line of action of the force  $X$ . The first equation shows the distance of the centre of gravity from the origin.

In this way many propositions on attractions may be translated into propositions on the centre of gravity, and vice versa.

It will be shown in the chapter on attractions that the resultant attraction of a homogeneous shell bounded by similar ellipsoids at an external point  $O$  is equal to the confocal ellipsoid passing through  $O$ . The centre of gravity of the



the differences we have to indicate arise only from the varying choice which we may make for the element  $m$ .

Let us first find the *centre of gravity of a volume*. For Cartesian coordinates we take  $m = dx dy dz$ , and replace the  $\Sigma$  by the sign of triple integration. We have then

$$\bar{x} = \frac{\iiint dx dy dz \cdot x}{\iiint dx dy dz}, \quad \bar{y} = \frac{\iiint dx dy dz \cdot y}{\iiint dx dy dz}, \quad \bar{z} = \frac{\iiint dx dy dz \cdot z}{\iiint dx dy dz}.$$

These formulae evidently hold for oblique axes also.

For polar coordinates we take  $m = r d\theta \cdot dr \cdot r \sin \theta d\phi$ , and  $x = r \sin \theta \cos \phi$ ,  $y = r \sin \theta \sin \phi$ ,  $z = r \cos \theta$ , and replace  $\Sigma$  by the sign of triple integration. These relations are proved in treatises on the integral calculus. We find

$$\bar{x} = \frac{\iiint r^3 \sin^2 \theta \cos \phi dr d\theta d\phi}{\iiint r^2 \sin \theta dr d\theta d\phi}, \quad \bar{y} = \frac{\iiint r^3 \sin^2 \theta \sin \phi dr d\theta d\phi}{\iiint r^2 \sin \theta dr d\theta d\phi}, \quad \bar{z} = \frac{\iiint r^3 \sin \theta \cos \theta dr d\theta d\phi}{\iiint r^2 \sin \theta dr d\theta d\phi}.$$

For cylindrical coordinates we have  $m = \rho d\phi \cdot d\rho \cdot dz$ , and  $x = \rho \cos \phi$ ,  $y = \rho \sin \phi$ . Hence

$$\bar{x} = \frac{\iiint \rho^2 \cos \phi d\phi d\rho dz}{\iiint \rho d\phi d\rho dz}, \quad \bar{y} = \frac{\iiint \rho^2 \sin \phi d\phi d\rho dz}{\iiint \rho d\phi d\rho dz}, \quad \bar{z} = \frac{\iiint \rho z d\phi d\rho dz}{\iiint \rho d\phi d\rho dz}.$$

Or again, if  $x, y, z$  be given functions of three auxiliary variables  $u, v, w$ , we can use the Jacobian form corresponding to that of Art. 411. We have then  $m = J du dv dw$ .

**432.** To find the *centre of gravity of the surface of a solid* we find the value of  $m$  suitable to the coordinates we wish to use.

If the equation to the surface is given in the Cartesian form  $z = f(x, y)$ , we project the element of surface on the plane of  $xy$ . The area of the projection is  $dx dy$ . If  $(\alpha \beta \gamma)$  be the direction angles of the normal to the element, the area of the element must be  $\sec \gamma dx dy$ . This therefore is our value of  $m$ . We find

$$\bar{x} = \frac{\iint \sec \gamma dx dy \cdot x}{\iint \sec \gamma dx dy}, \quad \bar{y} = \frac{\iint \sec \gamma dx dy \cdot y}{\iint \sec \gamma dx dy} \quad \&c.$$

Taking the equation to the normal, we find

$$\left( \frac{dx}{dz} \right)^2 + \left( \frac{dy}{dz} \right)^2 + 1 = 0$$

If the surface is given in polar coordinates  $r = f(\theta, \phi)$ , we have

$$m = r d\theta d\phi \left\{ \left( \frac{dr}{d\phi} \right)^2 + \sin^2 \theta \left( \frac{dr}{d\theta} \right)^2 + r^2 \sin^2 \theta \right\}^{\frac{1}{2}}.$$

**433.** In some cases it is more advantageous to divide the solid into larger elements. We should especially try to choose as our element some thin lamina or shell whose volume and centre of gravity have been already found. Suppose, for example, we wish to find  $\bar{x}$  for some solid. We take as the element a thin slice of the solid bounded by two planes perpendicular to  $x$ . If the boundary be a portion of an ellipse, triangle, or some other figure whose area  $A$  is known, we can use the formula

$$\bar{x} = \frac{\int A dx}{\int A dx}.$$

In this method we have *only a single instead of a triple sign of integration*. If the centre of gravity of  $A$  is known as well as its area, we can find  $\bar{y}$  and  $\bar{z}$  by using the same element.

To take another example, suppose the solid heterogeneous. Then instead of the thin slice just mentioned we might take as the element a thin stratum of homogeneous substance. If the mass and centre of gravity of this stratum be known, a single integration will suffice to find the centre of gravity of the whole solid. *This method will be found useful whenever the boundary of the whole solid is a stratum of uniform density*, for in that case the limits of the integral will be usually constants.


**434.** Ex. 1. Find the centre of gravity of an octant of the solid

$$\left( \frac{x}{a} \right)^n + \left( \frac{y}{b} \right)^n + \left( \frac{z}{c} \right)^n = 1.$$

From the symmetry of the case it will be sufficient to find  $\bar{z}$ . It will also evidently simplify matters if we clear the equation of the quantities  $a, b, c$ ; we therefore put  $x = ax'$ ,  $y = by'$ ,  $z = cz'$ , Art. 428.

If we take as our element a slice formed by planes parallel to  $xy$ , we shall require the area  $A$  of the section  $PMQ$ . This area is

$$A = [y'dx'] = [(1 - z'^n - x'^n)^{\frac{1}{n}} dx'],$$



We have now, 
$$\frac{\bar{z}}{c} = \frac{\int A dz' \cdot z'}{\int A dz'} = \frac{\int (1 - z'^n)^{\frac{2}{n}} dz' \cdot z'}{\int (1 - z'^n)^{\frac{2}{n}} dz'}, \quad \begin{cases} z'=0 \text{ to} \\ z'=1 \end{cases}.$$

If we put  $z'^n = \xi$  and write  $m$  for  $1/n$ , this reduces to

$$\frac{\bar{z}}{c} = \frac{\int (1 - \xi)^{2m} \xi^{2m-1} d\xi}{\int (1 - \xi)^{2m} \xi^{m-1} d\xi} = \frac{\Gamma(2m+1) \Gamma(2m)}{\Gamma(4m+1)} \frac{\Gamma(3m+1)}{\Gamma(2m+1) \Gamma(m)};$$

using the equation  $\Gamma(x+1) = x\Gamma(x)$ , this becomes

$$\frac{\bar{z}}{c} = \frac{3}{4} \frac{\Gamma(2m) \Gamma(3m)}{\Gamma(m) \Gamma(4m)}, \text{ where } m = \frac{1}{n}.$$

✓ Ex. 2. Find the centre of gravity of a hemisphere, the density at any point varying as the  $n$ th power of the distance from the centre.

Here we notice that any stratum of uniform density is a thin hemispherical shell, whose volume and centre of gravity are both known. We therefore take the stratum as the element. We have the further advantage that the limits are constants, because the external boundary of the solid is homogeneous.

Let the axis of  $z$  be along the middle radius, let  $(r, r+dr)$  be the radii of the shell, and let the density  $D = \mu r^n$ . Then  $m = 2\pi r^2 dr \cdot \mu r^n$ , also the ordinate of the centre of gravity is  $\frac{1}{2}r$ , see Art. 422. Hence

$$\bar{z} = \frac{\int 2\pi r^2 dr \mu r^n \frac{1}{2}r}{\int 2\pi r^2 dr \mu r^n} = \frac{1}{2} \frac{n+3}{n+4} \frac{a^{n+4} - b^{n+4}}{a^{n+3} - b^{n+3}}.$$

The limits of the integral have been taken from  $r=b$  to  $r=a$ , so that we have the centre of gravity of a *shell* whose internal and external radii are  $b$  and  $a$ .

In a hemisphere we put  $b=0$ . If  $n+3$  is positive, we then have  $\bar{z} = \frac{a}{2} \frac{n+3}{n+4}$ . In other cases we find  $\bar{z}=0$ . If either  $n+3$  or  $n+4$  is zero the integrals lead to logarithmic forms, but we still find  $\bar{z}=0$ .

✓ Ex. 3. Find the centre of gravity of the octant of an ellipsoid when the density at any point is  $D = \mu x^l y^m z^n$ .

To effect this we shall have to find the values of  $\Sigma mz$  and  $\Sigma m$ , which are the integrals of the form

$$\iiint x^l y^m z^n dx dy dz$$

for all elements within the solid. To simplify matters, we write  $(x/a)^2 = \xi$ , & the limits of the integral are now fixed by the plane  $\xi + \eta + \zeta = 1$ . But these integrals known as Dirichlet's integrals, and are to be found in treatises on Integral Calculus. The result is usually quoted in the form

$$\iiint \xi^{l-1} \eta^{m-1} \zeta^{n-1} d\xi d\eta d\zeta = \frac{\Gamma(l) \Gamma(m) \Gamma(n)}{\Gamma(l+m+n+1)},$$

though Liouville's extensions to ellipsoids and other surfaces are also given.  $\Gamma(p+1) = 1 \cdot 2 \cdot 3 \dots p$  when  $p$  is integral, and in all cases in which  $p$  is positive  $\Gamma(p+1) = p\Gamma(p)$ . Also  $\Gamma(\frac{1}{2}) = \sqrt{\pi}$ .

The result now follows from substitution: we find

If the density at any point of an octant of an ellipsoid is  $D = \mu xyz$ , show that  $\bar{z} = 16c/35$ .

Ex. 4. If the density at any point of an octant of an ellipsoid vary as the square of the distance from the centre, show that  $\bar{z} = \frac{5c}{16} \frac{a^2 + b^2 + 2c^2}{a^2 + b^2 + c^2}$ .

Ex. 5. To find the centre of gravity of a triangular area whose density at any point is  $D = \mu x^l y^m$ .

To determine  $\bar{x}$  and  $\bar{y}$  we have to find  $\Sigma m$ ,  $\Sigma mx$  and  $\Sigma my$ . All these are integrals of the form  $\iint x^l y^m dx dy$ . If  $y_1, y_2, y_3$  are the ordinates of the corners of the triangle and  $\Delta$  the area, it may be shown that

$$\iint y^n dx dy = \frac{2\Delta}{(n+1)(n+2)} \{y_1^n + y_1^{n-1}y_2 + y_1^{n-2}y_2^2 + \dots\} \dots\dots\dots (1),$$

where the right-hand side, after division by  $\Delta$ , is the arithmetic mean of the homogeneous products of  $y_1, y_2, y_3$ . Thus when the density is  $D = \mu y^n$  the ordinate  $\bar{y}$  may be found by a simple substitution.

If we take  $y + kx = 0$  as a new axis of  $x$ , (1) may be written in the form

$$\iint (y + kx)^n dx dy = \frac{2\Delta}{(n+1)(n+2)} \{(y_1 + kx_1)^n + (y_1 + kx_1)^{n-1}(y_2 + kx_2) + \dots\}.$$

Equating the coefficient of  $k$  on each side, we find

$$\iint nxy^{n-1} dx dy = \frac{2\Delta}{(n+1)(n+2)} \{nx_1y_1^{n-1} + (n-1)y_1^{n-2}y_2x_1 + \&c.\}.$$

In general, if  $H_n$  be the arithmetic mean of the homogeneous products of  $y_1, y_2, y_3$ , we have

$$\iint x^p \frac{d^p}{dy^p} y^n dx dy = \Delta \left( x_1 \frac{d}{dy_1} + x_2 \frac{d}{dy_2} + x_3 \frac{d}{dy_3} \right)^p H_n.$$

One corner of a triangle is at the origin; if the density vary as the cube of the distance from the axis of  $x$ , show that  $\bar{y} = \frac{2}{3} \frac{y_1^5 - y_2^5}{y_1^4 - y_2^4}$ . Also write down the value of  $\bar{x}$ .

The same method may be used to find the centre of gravity of a quadrilateral, a tetrahedron or a double tetrahedron, when the density is  $D = \mu x^l y^m z^n$ . See a paper by the author in the *Quarterly Journal of Mathematics*, 1886.

**435. Lagrange's two Theorems.** *Def.* If the mass of a particle be multiplied by the square of its distance from a given point  $O$ , the product is called the moment of inertia of the particle about, or with regard to, the point  $O$ . The moment of inertia of a system of particles is the sum of the moments of inertia of the several particles.

**436. Lagrange's first Theorem.** The moment of inertia of a system of particles about any point  $O$  is equal to their moment of

referred to  $O$  as origin. Let  $\bar{x}, \bar{y}, \bar{z}$  be the coordinates of the centre of gravity  $G$ . Also let  $x = \bar{x} + x', y = \bar{y} + y', \&c.$  Now

$$\begin{aligned}\Sigma (m \cdot OA^2) &= \Sigma m \{(\bar{x} + x')^2 + (\bar{y} + y')^2 + (\bar{z} + z')^2\} \\ &= \Sigma m \cdot OG^2 + 2\bar{x}\Sigma mx' + 2\bar{y}\Sigma my' + 2\bar{z}\Sigma mz' + \Sigma (m \cdot GA^2)\end{aligned}$$

Since the origin of the accented coordinates is the centre of gravity, we have  $\Sigma mx' = 0, \Sigma my' = 0, \Sigma mz' = 0$ . Hence putting  $M = \Sigma m$ , we have  $\Sigma (m \cdot OA^2) = M \cdot OG^2 + \Sigma (m \cdot GA^2) \dots$

This equation expresses Lagrange's theorem in an analytical form.

We notice that the moment of inertia of the body about a point  $O$  is least when that point is at the centre of gravity.

An important extension of this theorem is required in dynamics. It is shown that, if  $f(x, y, z)$  be any quadratic function of the coordinates of a particle, then

$$\Sigma mf(x, y, z) = Mf(\bar{x}, \bar{y}, \bar{z}) + \Sigma mf(x', y', z').$$

**437. Lagrange's second Theorem.** If  $m, m'$  be the masses of any two particles,  $AA'$  the distance between them, the theorem may be analytically stated thus

$$\Sigma (mm' \cdot AA'^2) = M \Sigma (m \cdot GA^2) \dots \dots \dots$$

The sum of the continued products of the masses taken together and the square of the distance between them is equal to the product of the whole mass by the moment of inertia about the centre of gravity.

This may be easily deduced from Lagrange's first theorem. We have by (A)

$$\Sigma m_\alpha OA_\alpha^2 = M \cdot OG^2 + \Sigma m_\alpha GA_\alpha^2,$$

where  $\Sigma$  implies summation for all values of  $\alpha$ . Putting  $O$  an arbitrary point  $O$  successively at  $A_1, A_2, \&c.$  we have

$$\Sigma m_\alpha A_1 A_\alpha^2 = M \cdot A_1 G^2 + \Sigma m_\alpha GA_\alpha^2,$$

$$\Sigma m_\alpha A_2 A_\alpha^2 = M \cdot A_2 G^2 + \Sigma m_\alpha GA_\alpha^2,$$

$$\&c. = \&c.$$

Multiplying these respectively by  $m_1, m_2, \&c.$  and adding the products together, we have

half the right-hand side. But the terms on the right-hand side are the same. Hence

$$\Sigma m_{\alpha} m_{\beta} \cdot A_{\alpha} A_{\beta}^2 = M \Sigma m_{\alpha} \cdot G A_{\alpha}^2.$$

**438.** Ex. Let the symbol  $[ABC]$  represent the area of the triangle formed by joining the three points  $A, B, C$ . Let  $[ABCD]$  represent the volume of the tetrahedron formed by joining the four points in space  $A, B, C, D$ . We may extend the analytical expression for the area and volume to any number of points by the same notation. We then have the following extensions of Lagrange's two theorems

$$\Sigma m_{\alpha} O A_{\alpha}^2 = M \cdot OG^2 + \Sigma m_{\alpha} G A_{\alpha}^2$$

$$\Sigma m_{\alpha} m_{\beta} [O A_{\alpha} A_{\beta}]^2 = M \Sigma m_{\alpha} [O G A_{\alpha}]^2 + \Sigma m_{\alpha} m_{\beta} [G A_{\alpha} A_{\beta}]^2$$

$$\Sigma m_{\alpha} m_{\beta} m_{\gamma} [O A_{\alpha} A_{\beta} A_{\gamma}]^2 = M \Sigma m_{\alpha} m_{\beta} [O G A_{\alpha} A_{\beta}]^2 + \Sigma m_{\alpha} m_{\beta} m_{\gamma} [G A_{\alpha} A_{\beta} A_{\gamma}]^2$$

$$\&c. = \&c.$$

$$\Sigma m_{\alpha} m_{\beta} A_{\alpha} A_{\beta}^2 = M \Sigma m_{\alpha} G A_{\alpha}^2$$

$$\Sigma m_{\alpha} m_{\beta} m_{\gamma} [A_{\alpha} A_{\beta} A_{\gamma}]^2 = M \Sigma m_{\alpha} m_{\beta} [G A_{\alpha} A_{\beta}]^2$$

$$\Sigma m_{\alpha} m_{\beta} m_{\gamma} m_{\delta} [A_{\alpha} A_{\beta} A_{\gamma} A_{\delta}]^2 = M \Sigma m_{\alpha} m_{\beta} m_{\gamma} [G A_{\alpha} A_{\beta} A_{\gamma}]^2$$

$$\&c. = \&c.$$

The first of each of these sets of equations is of course a repetition of Lagrange's equations. The remaining equations are due to Franklin.

[*American Journal of Mathematics*, Vol. x., 1888.]

**439. Application to pure geometry.** The property that every body has but one centre of gravity\* may be used to assist us in discovering new geometrical theorems. The general method may be described in a few words. We place weights of the proper magnitudes at certain points in the figure. By combining these in several different orders we find different constructions for the centre of gravity. All these must give the same point. The following are a few examples.

Ex. 1. The two straight lines which join the middle points of the opposite sides of a quadrilateral and the straight line which joins the middle points of the two diagonals, intersect in one point and are bisected at that point. [Coll. Exam.]

Ex. 2. The centre of gravity of four particles of equal weight in the same plane is the centre of the conic which bisects the lines joining each pair of points.

[Only one chord of a conic is bisected at a given point, unless that point is the centre. Since, by the last example, three chords are bisected at the same point, that point is the centre.] [Caius Coll.]

Ex. 3. Through each edge of a tetrahedron a plane is drawn bisecting the angle

Place weights at the corners proportional to the areas of the opposite faces. The centre of gravity of these four weights lies in each of the three straight lines.

**440.** The theorems on the centre of gravity are also useful in helping us to remember the relations of certain points, much used in our geometrical figures, to the other points and lines in the construction. For instance, when the results of Ex. 1 have been noticed, the distance of the centre of the inscribed conic from any straight line can be written down at once by taking moments about that line.

**Ex. 1.** The areal equation to the conic inscribed in the triangle of reference is  $\sqrt{lx} + \sqrt{my} + \sqrt{nz} = 0$ ; show that the centre of the conic is the centre of gravity of three particles placed at the middle points of the sides, whose weights are proportional to  $l, m, n$ . It is also the centre of gravity of three particles whose weights are proportional to  $m+n, n+l, l+m$ , placed either at the points of contact or at the corners of the triangle.

Let the conic touch the sides in  $D, E, F$ , then  $D$  and  $E$  divide  $BC$  and  $AC$  in the ratios  $m:n$  and  $l:n$ . Let  $\xi, \eta, \zeta$  be the weights placed at  $A, B, C$  whose centre of gravity is the centre. Then  $\xi, \eta$  are respectively equivalent to  $\xi(l+n)/n$  and  $\eta(m+n)/n$  placed at  $E$  and  $D$  together with some weight at  $C$ , Art. 79. But the straight line joining  $C$  to the centre  $O$  bisects  $DE$ , we see by taking moments about  $CO$  that the weights  $D$  and  $E$  are equal. Hence  $\xi$  and  $\eta$  are proportional to  $m+n$  and  $n+l$ .

If the conic is a parabola  $l+m+n=0$ , because the weights must reduce to a couple. Hence the far extremity of the principal diameter, and therefore the focus, is the centre of gravity of weights  $l, m, n$  placed at the corners  $A, B, C$ . Since the product of the perpendiculars from the foci on all tangents are equal, the near focus is the centre of gravity of three weights  $a^2/l, b^2/m, c^2/n$  placed at the corners.

**Ex. 2.** The areal equation to the conic circumscribed about a triangle is  $lyz + mzx + nxy = 0$ . Show that its centre is the centre of gravity of six particles placed at the corners whose weights are proportional to  $l^2, m^2, n^2$ , and at the middle points of the sides whose weights are  $-2mn, -2nl, -2lm$ .

**Ex. 3.** Three particles of equal weight are placed at the corners of a triangle and a fourth particle of negative weight is placed at the centre of the circumscribed circle. Show that the centre of gravity of all four is the centre of the nine-point circle or the orthocentre, according as the weight of the fourth particle is numerically equal to or double that of any one of the particles at the corners.

**Ex. 4.** The equation to a conic being  $Ap^2 + Bq^2 + Cr^2 + 2Dqr + 2Erp + 2Frp$  in tangential coordinates, show that the centre of the conic is the centre of gravity of three weights proportional to  $A+E+F, B+F+D, C+D+E$  placed at the corners. For other theorems see a paper by the author in the *Quarterly Journal*, Vol. 1866.

**441.** Theorems concerning the resolution and composition of forces may be

Ex. 2.  $ABCD$  is a quadrilateral, whose opposite sides meet in  $X$  and  $Y$ . Show that the bisectors of the angles  $X$ ,  $Y$ , the bisectors of the angles  $B$ ,  $D$  and the bisectors of the angles  $A$ ,  $C$  intersect on a straight line, certain restrictions being made as to which pairs of bisectors are taken. See figure in Art. 132.

[Apply four equal forces to act along the sides of the quadrilateral, and find their resultant by combining them in different orders.] [Math. Tripos, 1882.]

Ex. 3. Prove, by mechanical considerations, that the locus of the centres of all ellipses inscribed in the same quadrilateral is the straight line joining the middle points of any two diagonals. [Coll. Exam.]

Let  $A$ ,  $B$ ,  $C$ ,  $D$  be the corners taken in order. Apply forces along  $AB$ ,  $AD$ ,  $CB$ ,  $CD$  proportional to these lengths. The tangents measured from each corner to the adjacent points of contact represent forces whose resultant passes through the centre. Since these eight forces make up the four forces  $AB$ ,  $AD$ ,  $CB$ ,  $CD$ , the resultant passes through the centre. Again the resultant of  $AB$ ,  $AD$  and also that of  $CB$ ,  $CD$  bisect the diagonal  $BD$ . Similarly the resultant force bisects the other diagonal.

Ex. 4. If  $X$ ,  $Y$  are the intersections of the opposite sides of a quadrilateral  $ABCD$ , prove that the ratio of the perpendiculars drawn from  $X$  and  $Y$  on the diagonal  $AC$  is equal to the ratio of the perpendiculars on the diagonal  $BD$ . Show also that each of these ratios is equal to the ratio of  $AB \cdot CD \sin Y$  to  $AD \cdot BC \sin X$ . See figure of Art. 132.



## CHAPTER X

### ON STRINGS

**442. The Catenary.** The strings considered in this chapter are supposed to be perfectly flexible. By this we mean that the resultant action across any section of the string consists of a single force whose line of action is along a tangent to the length of the string. Any normal section is considered to be so small that the string may be regarded as a curved line, so that we may speak of its tangent, or its osculating plane.


The resultant action across any section of the string is called its tension, and in what follows will be represented by the letter  $T$ . This force may theoretically be positive or negative, but it is obvious that an actual string can only pull. The positive sign is given to the tension when it exerts a pull on any object instead of a push.

The weight of an element of length  $ds$  is represented by  $w ds$ . In a uniform string  $w$  is the weight of a unit of length. If the string is not uniform,  $w$  is the weight of a unit of length of an imaginary string, such that any element of it (whose length is  $ds$ ) is similar and equal to the particular element  $ds$  of the actual string.

**443.** *A heavy uniform string is suspended from two points  $A$ ,  $B$ , and is in equilibrium in a vertical plane.*

Let  $C$  be the lowest point of the catenary, i.e. the point at which the tangent is horizontal. Take some horizontal straight line  $Ox$  as the axis of  $x$ , whose distance from  $C$  we may afterwards choose at pleasure. Draw  $CO$  perpendicular to it, and let  $O$  be the origin. Let  $\psi$  be the angle the tangent at any point  $P$  makes with  $Ox$ . Let  $T_0$  and  $T$  be the tensions at  $C$  and  $P$ , and let  $CP = s$ . In the figure the axis of  $x$ , which is afterwards taken to represent the directrix, has been placed nearer the curve than it really is in order to save space.

The length  $CP$  of the string is in equilibrium under three forces, viz. the tensions  $T_0$  and  $T$  acting at  $C$  and  $P$  in the directions of the arrows, and its weight  $ws$  acting at the centre of gravity  $G$  of the arc  $CP$ .



Resolving horizontally, we have

$$T \cos \psi = T_0 \dots \dots \dots (1).$$

Resolving vertically, we have

$$T \sin \psi = ws \dots \dots \dots (2).$$

Dividing one of these equations by the other,

$$\frac{dy}{dx} = \tan \psi = \frac{ws}{T_0} \dots \dots \dots (3).$$

(Erd. 1691) but without the analysis, apparently wishing to leave some laurels gathered by those who followed. David Gregory published a solution some years after in the *Phil. Trans.* 1697.

It is the custom of geometers to rise from one difficulty to another, and even to invent new ones in order to have the pleasure of surmounting them. Bernoulli was never in possession of the solution of his problem of the chainette considered in the simplest case, than he proceeded to more difficult ones. He supposed next that the string was heterogeneous and enquired what should be the law of density if the curve should be of any given form, and what would be the curve if the string were extensible. He soon after published his solution, but reserved his

If the string is uniform  $w$  is constant, and it is then convenient to write  $T_0 = wc$ . To find the curve we must integrate the differential equation (3). We have

$$\left(\frac{ds}{dy}\right)^2 = 1 + \left(\frac{dx}{dy}\right)^2 = 1 + \frac{c^2}{s^2}.$$

$$\therefore dy = \pm \frac{s ds}{\sqrt{(s^2 + c^2)}}; \quad \therefore y + A = \pm \sqrt{(s^2 + c^2)}.$$

We must take the upper sign, for it is clear from (3) that, as  $x$  and  $s$  increase,  $y$  must also increase. When  $s = 0$ ,  $y + A$  Hence, if the axis of  $x$  is chosen to be at a distance  $c$  below the lowest point  $C$  of the string, we shall have  $A = 0$ . The equation now takes the form

$$y^2 = s^2 + c^2 \dots \dots \dots (4)$$

Substituting this value of  $y$  in (3), we find  $\frac{cds}{\sqrt{(s^2 + c^2)}} = dx$ ,

where the radical is to have the positive sign. Integrating,

$$c \log \{s + \sqrt{(s^2 + c^2)}\} = x + B.$$

But  $x$  and  $s$  vanish together, hence  $B = c \log c$ .

From this equation we find  $\sqrt{(s^2 + c^2)} + s = ce^{\frac{x}{c}}$ .

Inverting this and rationalizing the denominator in the usual manner, we have

$$\sqrt{(s^2 + c^2)} - s = ce^{-\frac{x}{c}}.$$

Adding and subtracting we deduce by (4)

$$c \cosh \frac{x}{c} = y = \frac{c}{2} \left( e^{\frac{x}{c}} + e^{-\frac{x}{c}} \right), \quad s = \frac{c}{2} \left( e^{\frac{x}{c}} - e^{-\frac{x}{c}} \right) \dots \dots \dots (5)$$

The first of these is the Cartesian equation to the common catenary. The straight lines which have here been taken as axes of  $x$  and  $y$  are called respectively the *directrix* and the *axis of the catenary*. The point  $C$  is called the *vertex*.

Adding the squares of (1) and (2), we have by help of (4)

$$T^2 = w^2 (s^2 + c^2) = w^2 y^2;$$

stant tension at any point is equal to  $wy$ , where  $y$  is the ordinate measured from the directrix.

444. Referring to the figure, let  $PN$  be the ordinate of  $P$ , then  $T = w \cdot PN$ . Draw  $NL$  perpendicular to the tangent at  $P$ , then the angle  $PNL = \psi$ . Hence

$$PL = PN \cdot \sin \psi = s \text{ by (2),}$$

$$NL = PN \cdot \cos \psi = c \text{ by (1).}$$

These two geometrical properties of the curve may also be deduced from its Cartesian equation (5). By differentiating (3) find

$$\frac{1}{\cos^2 \psi} \frac{d\psi}{ds} = \frac{1}{c}, \quad \therefore \rho = \frac{c}{\cos^2 \psi} \dots\dots\dots (7).$$

We easily deduce from the right-angled triangle  $PNH$ , that the length of the normal, viz.  $PH$ , between the curve and the directrix is equal to the radius of curvature, viz.  $\rho$ , at  $P$ .

It will be noticed that these equations contain only one determined constant, viz.  $c$ ; and when this is given the form of the curve is absolutely determined. Its position in space depends on the positions of the straight lines called its directrix and axis. This constant  $c$  is called *the parameter of the catenary*. Two arcs of catenaries which have their parameters equal are said to be arcs of equal catenaries.

Since  $\rho \cos^2 \psi = c$ , it is clear that  $c$  is large or small according to whether the curve is flat or much curved near its vertex. Thus if the string is suspended from two points  $A, B$  in the same horizontal line, then  $c$  is very large or very small compared with the distance between  $A$  and  $B$  according as the string is tight or loose.

The relations between the quantities  $y, s, c, \rho, \psi$  and  $T$  in the common catenary may be easily remembered by referring to the rectilinear figure  $PLNH$ . We have  $y = PN, PL = s, NL = c, PH = \rho, T = w \cdot PN$  and the angles  $LNP, NPH$  are each equal to  $\psi$ . Thus the important relations (1), (2), (3), (4), and (7) follow from the properties of a right-angled triangle.

445. Since the three forces, viz., the tensions at  $A$  and  $B$  and the weight are in equilibrium, it follows that their lines of action must meet in a point. Hence the

vertical, and be nearly straight, show that  $c$  is very large.

Let  $\psi, \psi'$  be the inclinations at  $A$  and  $B$ , and  $l$  the length of the string.  
 $l = s - s' = c (\tan \psi - \tan \psi')$ . Since  $\psi$  and  $\psi'$  are nearly equal,  $c$  is large compared with  $l$ .

✓ Ex. 3. A heavy uniform string  $AB$  of length  $l$  is suspended from a fixed point  $A$ , while the other extremity  $B$  is pulled horizontally by a given force  $F = wa$ .

that the horizontal and vertical distances between  $A$  and  $B$  are  $a \log \frac{l + \sqrt{l^2 + a^2}}{a}$  and  $\sqrt{(l^2 + a^2)} - a$  respectively.

✓ Ex. 4. The extremities  $A$  and  $B$  of a heavy string of length  $2l$  are attached to two small rings which can slide on a fixed horizontal wire. Each of these rings is acted on by a horizontal force  $F = wl$ . Show that the distance apart of the rings is  $2l \log (1 + \sqrt{2})$ .

✓ Ex. 5. If the inclination  $\psi$  of the tangent at any point  $P$  of the catenary is taken as the independent variable, prove that

$$x = c \log \tan \left( \frac{\pi}{4} + \frac{\psi}{2} \right), \quad y = \frac{c}{\cos \psi}, \quad s = c \tan \psi, \quad \rho = \frac{c}{\cos^2 \psi}.$$

✓ If  $\bar{x}, \bar{y}$  be the coordinates of the centre of gravity of the arc measured from the vertex up to the point  $P$ , prove also that  $\bar{x} = x - c \tan \frac{\psi}{2}$ ,  $\bar{y} = \frac{1}{2} \left( \frac{c}{\cos \psi} + x \cot \psi \right)$ .

447. If the position in space of the points  $A$  and  $B$  of suspension and the length of the string or chain are given, we may obtain sufficient equations to determine the parameter  $c$  of the catenary, and the positions in space of its directrix and vertex.

Let the given point  $A$  be taken as an origin of coordinates, and let the horizontal and vertical distances from  $A$  to the other extremity  $B$  be  $h$  and  $k$  respectively. Let  $l$  be the length of the string  $AB$ . These three quantities are therefore given. Let  $(x, y)$  be the coordinates of  $A$ ,  $(x+h, y+k)$  be the coordinates of  $B$  referred to the directrix and the catenary. Then  $x, y, c$  are the three quantities to be found. By Art. 443,

$$y = \frac{c}{2} \left( e^{\frac{x}{c}} + e^{-\frac{x}{c}} \right), \quad y+k = \frac{c}{2} \left( e^{\frac{x+h}{c}} + e^{-\frac{x+h}{c}} \right) \dots\dots\dots$$

Also by Art. 443, since  $l$  is the algebraic difference of the arcs  $CA, CB$ ,


$$l = \frac{c}{2} \left( e^{\frac{x+h}{c}} - e^{-\frac{x+h}{c}} \right) - \frac{c}{2} \left( e^{\frac{x}{c}} - e^{-\frac{x}{c}} \right) \dots\dots\dots$$

If  $C$  lie between  $A$  and  $B$ ,  $x$  will be negative.

These three equations are sufficient to determine  $x, y$  and  $c$ . They may however be solved in finite terms. We may eliminate  $x, y$  in the following manner.

Writing  $u = e^{\frac{x}{c}}, v = e^{\frac{h}{c}}$ , we find from (A) and (B)

$$\left. \begin{aligned} k &= \frac{c}{2} \left( u - \frac{1}{uv} \right) (v-1) \\ l &= \frac{c}{2} \left( u - \frac{1}{uv} \right) (v-1) \end{aligned} \right\} \dots\dots\dots (C).$$



We notice that  $v$  contains only  $c$  and the known quantity  $h$ . Hence, subtracting the squares of these equations in order to eliminate  $u$ , we find

$$\pm \sqrt{(l^2 - k^2)} = c \left( e^{\frac{h}{2c}} - e^{-\frac{h}{2c}} \right) \dots \dots \dots (D).$$

This agrees with the equation given by Poisson in his *Traité de Mécanique*.

The value of  $c$  has to be found from this equation. It gives two real finite values of  $c$ , one positive and the other negative but numerically equal. A negative value for  $c$  would make  $y$  negative and would therefore correspond to a catenary with its concavity downwards. It is therefore clear that the positive value of  $c$  is to be taken.

To analyse the equation (D), we let  $c = 1/\gamma$ , and arrange the terms of the equation in the form

$$z = e^{m\gamma} - e^{-m\gamma} - a\gamma = 0 \dots \dots \dots (E),$$

so that  $a$  and  $m$  are both positive. We have  $a^2 = l^2 - k^2$ , and  $2m = h$ . Since the length  $l$  of the string must be longer than the straight line joining the points of suspension, it is clear that  $a$  must be greater than  $2m$ . By differentiation,

$$\frac{dz}{d\gamma} = m(e^{m\gamma} + e^{-m\gamma}) - a.$$

Thus  $dz/d\gamma$  is negative when  $\gamma = 0$ , so that, as  $\gamma$  increases from zero,  $z$  is at first zero, then becomes negative and finally becomes positive for large values of  $\gamma$ . There is therefore some one value of  $\gamma$ , say  $\gamma = i$ , at which  $z = 0$ . If there could be another, say  $\gamma = i'$ , then  $dz/d\gamma$  must vanish twice, once between  $\gamma = 0$  and  $\gamma = i$ , and again between  $\gamma = i$  and  $\gamma = i'$ . We shall now show that this is impossible. By differentiating twice we have

$$\frac{d^2z}{d\gamma^2} = m^2(e^{m\gamma} - e^{-m\gamma});$$

thus  $d^2z/d\gamma^2$  is positive when  $\gamma$  is greater than zero. Hence  $dz/d\gamma$  continually increases with  $\gamma$  from its initial value  $2m - a$  when  $\gamma = 0$ . It therefore cannot vanish twice when  $\gamma$  is positive. It appears from this reasoning that the equation gives only one positive value of  $c$ .

The solitary positive value of  $c$  having been found from (D), we can form a simple equation to find  $u$  by adding one of the equations (C) to the other. In this way we find one real value of  $x$ . The value of  $y$  is then found from the first of the equations (A). Thus it appears that, *when a uniform string is suspended from two fixed points of support, there is only one position of equilibrium.*

The equation (D) can be solved by approximation when  $h/c$  is so small that we can expand the exponentials and retain only the first powers of  $h/c$  which do not disappear of themselves. This occurs when  $c$  is large, i.e. when the string is nearly tight. In such cases, however, it will be found more convenient to resume the problem from the beginning rather than to quote the equations (D) or (E).

✓ 448. Ex. 1. A uniform string of length  $l$  is suspended from two points  $A$  and



If the weight of the ring is much greater than the weight of the string, each is nearly tight. Thus  $a/c$  is small, but  $x/c$  is not necessarily small, for the point  $C$  may be at a considerable distance from  $D$ . If we expand the terms containing the exponent  $a/c$  and eliminate those containing  $x/c$ , we find

$$c = W a / 2w \sqrt{l^2 - a^2} \text{ nearly.}$$

The contrary holds if the weight of the ring is much smaller than the weight of the string. If  $W$  were zero the two catenaries  $BD$  and  $DA$  would be continuous, the vertex would be at  $D$ . Hence when  $W$  is very small, the vertex will be near  $D$  and therefore  $x/a$  will be small. But  $a/c$  is not necessarily small. Expanding the terms with small exponentials, we find from (2) that  $x = W/2w$ . Then

$$l = \frac{c}{2} \left( e^{\frac{a}{c}} - e^{-\frac{a}{c}} \right) + \frac{W}{2w} \left\{ \frac{1}{2} \left( e^{\frac{a}{c}} + e^{-\frac{a}{c}} \right) - 1 \right\}.$$

If the weight  $W$  were absent this equation would reduce to the one already discussed above. If  $\gamma$  be the change produced in the value of  $c$  there found by adding weight  $W$ , we find, by writing  $c + \gamma$  for  $c$  in the first term on the right-hand side,

$$\left( l - \frac{ak}{c} \right) \gamma + \frac{W}{2w} (k - c) = 0, \text{ where } k \text{ is the ordinate of } B \text{ before the addition of } W.$$

If the weight  $W$  had been attached to any point  $D$  of the string not its middle point,  $AD$ ,  $BD$  would still form catenaries, whose positions could be found in a similar manner. We may notice that, however different the two strings may appear, the catenaries have equal parameters. For consider the equilibrium of the ring at  $W$ ; we see, by resolving horizontally that the weight of each catenary must be the same.

If the string be passed through a fine smooth ring fixed in space through which it could slide freely, the two strings on each side must have their tensions equal. Hence the two catenaries have the same directrix. The parameters are not necessarily equal, for the difference between the horizontal tensions of the two catenaries is equal to the horizontal pressure on the ring, which need not be zero.

Ex. 4. A heavy string of length  $l$  is suspended from two points  $A, A'$  in the same horizontal line, and passes through a smooth ring  $D$  fixed in space. If  $DN$  be perpendicular from  $D$  on  $AA'$  and  $NA = h$ ,  $NA' = h'$ ,  $DN = k$ , prove that the parameters  $c, c'$  may be obtained from

$$4c^2 = l^2 \left\{ \cosh \frac{h'}{2c'} \operatorname{cosech} \left( \frac{h}{2c} + \frac{h'}{2c'} \right) \right\}^2 - k^2 \left( \operatorname{cosech} \frac{h}{2c} \right)^2,$$

the similar equation with the accented and unaccented letters interchanged.

Ex. 5. A portion  $AC$  of a uniform heavy chain rests extended in the form of a straight line on a rough horizontal plane, while the other portion  $CB$  hangs in the form of a catenary from a given point  $B$  above the plane. The whole chain is on the point of motion towards the vertical through  $B$ . If  $l$  be the length of the whole chain and  $h$  be the altitude of  $B$  above the plane, show that the parameter  $c$  of the catenary is equal to

$$\mu (l + \mu h) - \mu \sqrt{(u^2 + 1) h^2 + 2\mu h l}.$$



weight; which slide on smooth rods intersecting in a vertical plane, and are at the same angle  $\alpha$  to the vertical: find the condition that the tension at the lowest point may be equal to half the weight of the chain; and, in that case, find the vertical distance of the rings from the point of intersection of the rods in terms of  $2l \log(\sqrt{2} + 1)$ , where  $2l$  is the length of the chain. [Math. Tripos, 1856.]

Ex. 9. A heavy string of uniform density and thickness is suspended from two points in the same horizontal plane. A weight, an  $n$ th part of the weight of the string, is attached to its lowest point; show that, if  $\theta, \phi$  be the inclinations to the vertical of the tangents at the highest and lowest points of the string,  $\tan \phi = (1 + n) \tan \theta$ . [Math. Tripos, 1858.]

Ex. 10. If  $\alpha, \beta$  be the angles which a string of length  $l$  makes with the vertical at the points of support, show that the height of one point above the other is  $l \cos \frac{1}{2}(\alpha + \beta) / \cos \frac{1}{2}(\alpha - \beta)$ . [Pet. Coll., 1855.]

Ex. 11. A heavy endless string passes over two small smooth fixed pegs in the same horizontal line, and a small smooth ring without weight binds together the upper and lower portions of the string: prove that the ratio of the cosines of the angles which the portions of the string at either peg make with the horizon, is equal to the ratio of the tangents of the angles which the portions of the string at the ring make with the vertical. [Math. Tripos, 1872.]

Ex. 12.  $A$  and  $B$  are two smooth pegs in the same horizontal line, and  $C$  is a smooth peg vertically below the middle point of  $AB$ ; an endless string hangs over them forming three catenaries  $AB, BC$ , and  $CA$ : if the lowest point of the catenary  $AB$  coincides with  $C$ , prove that the pegs  $A, B$  divide the whole string into three parts in the ratio of  $2w + w'$  to  $2w - w'$ , where  $w$  and  $w'$  are the vertical components of the pressures on  $A$  and  $C$  respectively. [Math. Tripos, 1870.]

Ex. 13. An endless uniform chain is hung over two small smooth pegs in the same horizontal line. Show that, when it is in a position of equilibrium, the ratio of the distance between the vertices of the two catenaries to half the length of the chain is the tangent of half the angle of inclination of the portions near the pegs. [Math. Tripos, 1855.]

Ex. 14. A heavy uniform string of length  $4l$  passes through two small smooth rings resting on a fixed horizontal bar. Prove that, if one of the rings be kept stationary, the other being held at any other point of the bar, the locus of the position of equilibrium of that end of the string which is the further from the stationary ring may be represented by the equation  $x = 2\sqrt{(ly)} \log \frac{l}{y}$ . [Coll. Ex.]

Ex. 15. A heavy uniform string is suspended from two points  $A$  and  $B$  in the same horizontal line, and to any point  $P$  of the string a heavy particle is attached. Prove that the two portions of the string are parts of equal Catenaries. Prove also that the portion of the tangent at  $A$  intercepted between the verticals through  $P$  and the centre of gravity of the string is divided by the tangent at  $B$  in a ratio independent of the position of  $P$ .

If  $\theta, \phi$  be the angles the tangents at  $P$  make with the horizon,  $\alpha$  and  $\beta$  those made by the tangents at  $A$  and  $B$ , show that  $\frac{\tan \theta + \tan \phi}{\tan \alpha + \tan \beta}$  is constant for all positions of  $P$ .

Ex. 16. A heavy uniform string hangs over two smooth pegs in the same horizontal line. If the length of each portion which hangs freely be equal to the length between the pegs, prove that the whole length of the string is to the distance between the pegs as  $\sqrt{3}$  to  $\log \sqrt{3}$ . Compare also the pressures on each peg with the weight of the string.

Ex. 17. A uniform endless string of length  $l$  is placed symmetrically over a smooth cube which is fixed with one diagonal vertical. Prove that the string will slip over the cube unless the side of the cube is greater than  $\frac{1}{3}l\sqrt{2} \log(1+\sqrt{2})$ .

[Emm. Coll., 1891.]

Ex. 18. An endless inextensible string hangs in two festoons over two small pegs in the same horizontal line. Prove that, if  $\theta$  be the inclination to the vertical of one branch of the string at its highest point, the inclination of the other branch at the same point must be either  $\theta$  or  $\phi$ , where  $\phi$  has only one value and is a function of  $\theta$  only. If  $\cot \frac{1}{2}\theta = e^{\sec \theta}$ , then  $\phi = \theta$ .

[Coll. Ex.]

Ex. 19. Four smooth pegs are placed in a vertical plane so as to form a square, the diagonals being one vertical and one horizontal. Round the pegs an endless string is passed so as to pass over the three upper and under the lower one. If the strings make with the vertical angles equal to  $\alpha$  at the upper pegs,  $\beta$  and  $\gamma$  at each of the middle and  $\delta$  at the lower peg, prove the following relations:

$$\sin \beta \log \cot \frac{1}{2}\alpha \tan \frac{1}{2}\beta = \sin \gamma \log \cot \frac{1}{2}\gamma \tan \frac{1}{2}\delta,$$

$$\sin \beta \sin \delta + \sin \alpha \sin \gamma = 2 \sin \alpha \sin \delta.$$

[Caius Coll.]

Ex. 20. A bar of length  $2a$  has its ends fastened to those of a heavy string of length  $2l$ , by which it is hung symmetrically over a peg. The weight of the bar is  $n$  times, and the horizontal tension  $\frac{1}{2}m$  times the weight of the string. Show that

$$m^2 + n^2 = \left\{ (n+1) \operatorname{cosech} \frac{a}{ml} - n \coth \frac{a}{ml} \right\}^2. \quad [\text{Coll. Ex., 1889.}]$$

Ex. 21. One end of a heavy chain is attached to the extremity of a fixed rod, the other end is fastened to a small smooth ring which slides on the rod: prove that the position of equilibrium  $\log \{ \cot \frac{1}{2}\theta \cot (\frac{1}{4}\pi - \frac{1}{2}\psi) \} = \cot \theta (\sec \psi - \operatorname{cosec} \theta)$ , being the inclination of the rod to the horizon, and  $\psi$  that of the chain at its highest point.

[Coll. Ex.]

Ex. 22. A string of length  $\pi a$  is fastened to two points at a distance apart equal to  $2a$ , and is repelled by a force perpendicular to the line joining the points and varying inversely as the square of the distance from it. Show that the form of the string is a semi-circle.

[Coll. Ex., 1882.]

Ex. 23. A chain, of length  $2l$  and weight  $2W$ , hangs with one end  $A$  attached to a fixed point in a smooth horizontal wire, and the other end  $B$  attached to a smooth ring which slides along the wire. Initially  $A$  and  $B$  are together. Show that the work done in drawing the ring along the wire till the chain at  $A$  is inclined at an angle of  $45^\circ$  to the vertical is  $Wl(1 - \sqrt{2} + \log 1 + \sqrt{2})$ .

[Coll. Ex., 1883.]

Ex. 24. Determine if the catenary is the only curve such that, if  $AB$  be any arc

See Ex. 22  
p. 269  
no. 19  
for link.

**449. Stability of equilibrium.** Some problems on the equilibrium of strings may be conveniently solved by using the principle that the depth of centre of gravity below some fixed straight line is a maximum or minimum, 218. If the curve of the string be varied from its form as a catenary, the use of principle will require the calculus of variations. But if we restrict the arbitrary displacements to be such that the string retains its form as a catenary, though the parameter  $c$  may be varied, the problem may be solved by the ordinary processes of the differential calculus.

This method presents some advantages when we desire to know whether equilibrium is stable or not. We know, by Art. 218, that *the equilibrium will be stable or unstable according as the depth of the centre of gravity below some fixed horizontal plane is a true maximum or minimum.*

Ex. 1. A string of length  $2l$  hangs over two smooth pegs which are in the same horizontal plane and at a distance  $2a$  apart. The two ends of the string are free, its central portion hangs in a catenary. Show that equilibrium is impossible unless  $l$  be at least equal to  $ae$ ; and that, if  $l > ae$ , the catenary in the position of stable equilibrium for symmetrical displacements will be defined by that root of  $ce^c$  which is greater than  $a$ . [Math. Tripos, 1891]

Let  $2s$  be the length of the string between the pegs. Taking the horizontal line joining the pegs for the axis of  $x$ , we easily find (Art. 399) that the depth of the centre of gravity of the catenary and the two parts hanging over the pegs is given by

$$2l\bar{y} = sy - ca + (l-s)^2.$$

Substituting for  $y$  and  $s$  their values in terms of  $c$ , we find

$$2l \frac{d\bar{y}}{dc} = \left( c - \frac{l}{\rho} \right) \frac{\rho^2 (c-a) - (c+a)}{c},$$

where  $\rho$  stands for  $\frac{a}{e^c}$ . It is easy to see that the second factor on the right-hand side is negative for all positive values of  $c$ . Equating  $d\bar{y}/dc$  to zero, we find that the possible positions of equilibrium are given by  $l = cp$ . To find the least value of  $l$  given by this equation we put  $dl/dc = 0$ ; this gives  $c = a$ , so that  $l$  must be equal to or greater than  $ae$ .

For any value of  $l$  greater than  $ae$  there are two possible values of  $c$ , one greater and the other less than  $a$ . To determine which of these two catenaries is stable we examine the sign of the second differential coefficient, Art. 220. We easily find

$$\text{when } l = cp, \quad 2l \frac{d^2\bar{y}}{dc^2} = (c-a) \frac{\rho^2 (c-a) - (c+a)}{c^2}.$$

In order that the equilibrium may be stable, this expression must be negative. This requires that  $c$  should be greater than  $a$ .

Ex. 2. A heavy string of given length has one extremity attached to a fixed point  $A$ , and hangs over a small smooth peg  $B$  on the same level with  $A$ , the other extremity of the string being free. Show that, if the length of the string ex-

this problem may be solved in a manner similar to that used Art. 443 for a homogeneous chain. Since the equations (1) (2) of that article are obtained by simple resolutions, they will be true with some slight modifications when the string is not uniform. In our case the weight of the string measured from the lowest point is  $\int w ds$  between the limits  $s = 0, s = s$ , Art. 442. We obtain therefore by the same resolutions

$$T \cos \psi = T_0 \dots\dots (1), \quad T \sin \psi = \int w ds \dots\dots (2).$$

Dividing one of these by the other as before, we find

$$\int w ds = T_0 \tan \psi, \quad \therefore w = \frac{T_0}{\rho \cos^2 \psi} \dots\dots (3).$$

Substituting for  $\rho$  and  $\tan \psi$ , their Cartesian values

$$w = T_0 \frac{d^2 y}{dx^2} \frac{dx}{ds} = T_0 \left\{ 1 + \left( \frac{dy}{dx} \right)^2 \right\}^{-\frac{1}{2}} \frac{d^2 y}{dx^2} \dots\dots (4).$$

Conversely, when the law of density is known, say  $w = f(s)$ , equation (3) gives a relation between  $s$  and  $dy/dx$  which we write in the form  $dy/dx = f_1(s)$ . We easily deduce from this

$$s = \int \{1 + (f_1(s))^2\}^{-\frac{1}{2}} ds, \quad y = \int \{1 + (f_1(s))^2\}^{-\frac{1}{2}} f_1(s) ds,$$

since  $x$  and  $y$  can be expressed in terms of an auxiliary variable  $s$  which has a geometrical meaning.

1. Prove that the tension at any point  $P$  of the heterogeneous catenary is equal to the weight of a uniform chain whose length is the projection of the radius of curvature on the vertical and whose density is the same as that of the catenary.

2. A straight line  $BR$  is drawn through any fixed point  $B$  in the axis of  $y$  perpendicular to the normal at  $P$  to the curve, cutting the axis of  $x$  in  $R$ . Prove that the tension at  $P$  is  $(T_0/c)$  times the length  $BR$  and (2) the weight of the arc  $OP$ , measured from the lowest point  $O$ , is  $(T_0/c)$  times the length  $OR$ , where  $OB = c$  and  $T_0$  is the horizontal tension; Art. 35.

1. **Cycloidal chain.** A heterogeneous chain hangs in the form of a cycloid under the action of gravity: find the law of density.

For a cycloid we have  $\rho = 4a \cos \psi$  and  $s = 4a \sin \psi$ , where  $a$  is the radius of the


circle. Substituting, we find

$$w = \frac{T_0}{4a} \sec^3 \psi = \frac{16a^2 T_0}{(16a^2 - s^2)^{\frac{3}{2}}}.$$

The chief interest connected with this chain is that, when slightly disturbed from its position of equilibrium, it makes small oscillations whose periods and amplitudes can be investigated.

Ex. Drawing the usual figure for a cycloid, let  $O$  be the lowest point of the curve,  $B$  the middle point of the line joining the cusps. Let the normal at point  $P$  of the curve intersect the line joining the cusps in  $M$ , and let  $BR$  be drawn through  $B$  parallel to  $MP$  to intersect the horizontal through  $O$  in  $R$ . Prove that the centre of gravity of the arc  $OP$  is the intersection of  $BR$  with the vertical through  $M$ . We find  $\bar{x} = 2a\psi$ ,  $\bar{y} = 2a\psi \cot \psi$ , if  $B$  is the origin.

**452. Parabolic chain.** A heavy chain  $AOB$  is suspended from another chain  $DCE$  by vertical strings, which are so numerous that every element of  $AOB$  is attached to the corresponding element of  $DCE$ . If the weights of  $DCE$  and of the vertical strings are inconsiderable compared with that of  $AOB$ , find the form of the chain  $DCE$  that the chain  $AOB$  may be horizontal in the position of equilibrium.



The tensions at  $O$ ,  $M$  of the chain  $AOB$  being equal and horizontal, the weight of the length  $OM$  is supported by the tensions at  $C$  and  $P$  of the chain  $DCE$ . Thus  $PC$  may be regarded as a heterogeneous heavy chain, such that the weight of any length  $PC$  is  $mx$ . Resolving horizontally and vertically for this portion of the chain, we

$$T \cos \psi = T_0, \quad T \sin \psi = mx.$$

Dividing one of these by the other,

$$mx = T_0 \tan \psi = T_0 dy/dx, \quad \therefore \frac{1}{2}mx^2 = T_0(y - c).$$

The form of the chain  $DCE$  is therefore a parabola.

One point of interest connected with this result is that the chain  $AOB$  might be replaced by a uniform heavy bar to represent the roadway of a bridge. The tensions of the chains due to the weight of the bridge would not then tend to break or distort the roadway. It is only necessary that the roadway should be strong enough to support the weight of the additional weights due to carriages. But this would not be true if the light chain  $DCE$  were not in the form of a parabola.

The results are more complicated if the weight of the chain  $DCE$  is taken into account, and if the chains of support, instead of being vertical, are arranged in some other way.

This problem was first discussed by Nicolas Fuss, *Nova Acta Petropolitana*, Tom. 12, 1794. It was proposed to erect a bridge across the Neva suspending the roadway by vertical chains from four chains stretched across the river. He decided that the chains of his day could not support the necessary tension without breaking.

Ex. 1. Prove that in the parabolic catenary the tension at any point

Ex. 3. The centre of gravity  $G$  of an arc bounded by any chord lies in the diameter bisecting the chord, and  $PG = \frac{1}{3}PN$  where the diameter cuts the parabola  $P$  and the chord in  $N$ .

Ex. 4. Referring to the figure, we notice that, since the tensions at  $C$  and  $P$  support the weight of the roadway  $OM$ , the tangents at  $C$  and  $P$  must intersect in a point vertically over the centre of gravity of  $OM$ . Thence deduce that the curve  $CP$  is a parabola.

Ex. 5. If the weight of any element  $ds$  of the string  $DCPE$  is represented by  $ds + ndx$ , show that the catenary is given by  $x = \int \frac{cdz}{n + \sqrt{1+z^2}}$ , where  $z$  is the tangent of the inclination of the tangent to the horizon, and  $c$  is a constant. [Fuss.]

Ex. 6. Prove that the form of the curve of the chain of a suspension bridge when the weight of the rods is taken into account, but the weight of the rest of the bridge neglected, is the orthogonal projection of a catenary, the rods being supposed vertical and equidistant. [Math. Tripos, 1880.]

**453. The Catenary of equal strength.** A heavy chain, suspended from two fixed points, is such that the area of its section is proportional to the tension. Find the form of the chain.

If  $wds$  be the weight of an element  $ds$ , the conditions of the question require that  $T = cw$ , where  $c$  is some constant. The equations (1) and (2) of Art. 450 now

$$\text{become} \quad T \cos \psi = T_0, \quad T \sin \psi = \frac{1}{c} T ds.$$

Substituting in the second equation the value of  $T$  given by the first, we have  $\sin \psi = \sec \psi ds$ . Differentiating, we find  $c \sec^2 \psi = \sec \psi ds/d\psi$  and  $\therefore \rho \cos \psi = c$ . *my 2*

This result also easily follows from the intrinsic equation of equilibrium (2) given in Art. 454. We have  $T ds/\rho = wds \cos \psi$ . But when the string is equally strong throughout  $T = cw$ , hence  $\rho \cos \psi = c$ . The projection of the radius of curvature on the vertical is therefore constant and equal to  $c$ .

To deduce the Cartesian equation we substitute for  $\rho$  and  $\cos \psi$ ,

$$\left\{ 1 + \left( \frac{dy}{dx} \right)^2 \right\}^{-1} \frac{d^2y}{dx^2} = \frac{1}{c}, \quad \therefore \tan^{-1} \frac{dy}{dx} = \frac{x}{c} + A.$$

The origin be taken at the lowest point, the constant  $A$  is zero. We then find

$$y = c \log \sec \frac{x}{c}.$$

Tracing this curve, we see that the ordinate  $y$  increases from zero as  $x$  increases in zero positively or negatively, and that there are two vertical asymptotes given by  $x = \pm \frac{1}{2}\pi c$ . When  $x$  lies between  $\frac{1}{2}\pi c$  and  $\frac{3}{2}\pi c$ , the ordinate is imaginary; when  $x$  lies between  $\frac{3}{2}\pi c$  and  $\frac{5}{2}\pi c$ , the curve is the same as that between  $x = \pm \frac{1}{2}\pi c$ . For larger values of  $x$ , the ordinate is again imaginary and so on. The curve therefore consists of an infinite number of branches all equal and similar to that between  $x = \pm \frac{1}{2}\pi c$ . This is therefore the only part of the curve which it is necessary to

curvature and (2) the weight of the arc  $OP$  is  $(T_0/c)$  times the projection of the arc of curvature on the horizontal.

This curve was called the catenary of equal strength by Davies Gilbert, invented it on the occasion of the erection of the suspension bridge across Menai Straits. See *Phil. Trans.* 1826, part iii., page 202. In the first volume of *Liouville's Journal*, 1836, there is a note by G. Coriolis on the "chânette" of resistance. Coriolis does not appear to have been aware that this form of chain had already been discussed several years before.

X Ex. 1. Prove (1)  $x = c\psi$ , (2)  $s = c \log \tan \frac{1}{2}(\pi + 2\psi)$ . Use  $\rho = \frac{ds}{d\psi}$ ; i.e.  $\rho = \frac{ds}{d\psi}$

Ex. 2. Prove that the depth of the centre of gravity of any arc below the intersection of the normals at its extremities is constant and equal to  $c$ . Prove that its abscissa is equal to that of the intersection of the tangents at the points.

Ex. 3. The distance between the points of support of a catenary of uniform strength is  $a$ , and the length of the chain is  $l$ . Show that the parameter  $c$  must

✓ found from  $\tanh \frac{l}{4c} = \tan \frac{a}{4c}$ . Show also that this equation gives a positive value of  $c$  greater than  $a/\pi$ . Use  $s = c \log \tan \frac{1}{2}(\pi + 2\psi)$ .

Ex. 4. Show that the horizontal projection of the span is in every case less than  $\pi$  times the greatest length of uniform chain of the same material that can be hung by one end. Assume the strength of any part of the chain to be proportional to the mass per unit of length. [Kelvin, Math. Tripos, 1887.]

If  $L$  be the length of uniform chain spoken of, the tension at the point of support is its weight, i.e.  $wL$ . Again, the tension at any point of the heterogeneous chain is  $cw$ , hence  $c$  must be less than  $L$ . Hence the span must be less than  $\pi L$ .

454. **String under any Forces.** To form the general intrinsic equations of equilibrium of a string under the action of any forces. Let  $A$  be any fixed point of reference on the string. Let  $AP = s$ ,  $AQ = s + ds$ . Let  $T$  be the tension at  $P$ ; then, since  $T$  is a function of  $s$ ,  $T + dT$  is the tension at  $Q$ .

Let the impressed forces on the element  $PQ$  be resolved along the tangent, radius of curvature, and binormal at  $P$ . Thus  $Fds$  is the force on  $ds$  resolved along the tangent in the direction in which  $s$  is measured;  $Gds$  is the force on  $ds$  resolved along the radius of curvature  $\rho$  in the direction in which  $\rho$  is measured, i.e. inwards;  $Hds$  is the force on  $ds$  resolved perpendicular to the plane of the curve at  $P$ , and estimated positive in either direction of the binormal. These three directions are called the principal






Let  $ds$  be the length of any element  $PQ$  of the string. Let the forces on this element when resolved parallel to the positive directions of the axes be  $Xds$ ,  $Yds$ ,  $Zds$ . The element is in equilibrium under the action of the tensions at  $P$  and  $Q$  and these three impressed forces.

Let us resolve all these parallel to the axis of  $x$ . The resolved tension at  $P$  is  $T \frac{dx}{ds}$ , and pulls the element  $PQ$  towards the left hand. At  $Q$ ,  $s$  has become  $s + ds$ , the horizontal tension at  $Q$  is therefore

$$\left(T \frac{dx}{ds}\right) + \frac{d}{ds} \left(T \frac{dx}{ds}\right) ds,$$

and this pulls the element  $PQ$  towards the right-hand side. Taking both these and the force  $Xds$ , we have

$$\frac{d}{ds} \left(T \frac{dx}{ds}\right) ds + Xds = 0.$$



Treating the other components in the same way, we find

$$\left. \begin{aligned} \frac{d}{ds} \left(T \frac{dx}{ds}\right) + X &= 0 \\ \frac{d}{ds} \left(T \frac{dy}{ds}\right) + Y &= 0 \\ \frac{d}{ds} \left(T \frac{dz}{ds}\right) + Z &= 0 \end{aligned} \right\}.$$

**456. Ex. 1.** Show that the polar equations of equilibrium of a string in one plane under forces  $Pds$ ,  $Qds$ , acting along and perpendicular to the radius vector, are

$$\frac{d}{ds} (T \cos \phi) - \frac{T}{r} \sin^2 \phi + P = 0, \quad \frac{d}{ds} (T \sin \phi) + \frac{T}{r} \sin \phi \cos \phi + Q = 0,$$

where  $\cos \phi = dr/ds$  and  $\sin \phi = r d\theta/ds$ . Thence deduce the equations of equilibrium of a string in space of three dimensions, referred to cylindrical coordinates.

\* The equations of equilibrium of a string under the action of any forces in two dimensions were given in a Cartesian form by Nicolas Fuss, *Nova Acta Petropolitanae*, 1796. He gives two solutions, one by moments, and another by considering the tension. In this second solution, after resolving parallel to the axes, he deduces algebraically equations equivalent to those obtained by resolving along the tangent and normal. He goes on to apply his equations to the chainette and other circles.

Ex. 3. The extremities of a string of given length are attached to two given points, and each element  $ds$  of the string is acted on by a repulsive force tending directly from the axis of  $z$  and equal to  $2\mu r ds$ . If  $(r\theta z)$  be the cylindrical coordinates any point, prove that

$$T = A - \mu r^2, \quad \left(\frac{dr}{dz}\right)^2 = C \left(1 - \frac{\mu}{A} r^2\right)^2 - \frac{B^2}{r^2} - 1.$$

Show how the five arbitrary constants are determined. Explain how a helix in certain cases, the solution.

Ex. 4. A heavy chain is suspended from two points, and hangs partly immersed in a fluid. Show that the curvatures of the portions just inside and just outside the surface of the fluid are as  $D - D'$  to  $D$ , where  $D$  and  $D'$  are the densities of the chain and fluid. [St John's Coll.]

The weights of the elements just above and just below the surface of the fluid are proportional to  $Dds$  and  $(D - D')ds$ . If  $T$  be the tension, the resolved parts of these weights along the normal must be  $Tds/\rho$  and  $Tds/\rho'$ . Hence  $D/(D - D') = \rho'/\rho$ .

Ex. 5. A heavy string is suspended from two fixed points  $A$  and  $B$ , and the density is such that the form of the string is an equiangular spiral. Show that the density at any point  $P$  is inversely proportional to  $r \cos^2 \psi$ , where  $r$  is the distance of  $P$  from the pole, and  $\psi$  is the angle which the tangent at  $P$  makes with the horizon. [Trin. Coll., 1881.]

Ex. 6. A heavy string, which is not uniform, is suspended from two fixed points. Prove that the catenary formed of a given uniform string which touches at any point the curve in which the string hangs and has the same tension at that point will be of invariable dimensions.

**457. Constrained Strings.** *A string rests on a curve of any form in one plane, and is acted on by forces at its extremities. It is required to find the conditions of equilibrium and the tension at any point.*

There are four cases of this proposition which are of considerable importance; we shall consider these in order.

Let us first suppose that the weight of the string is so slight that it may be neglected compared with the forces applied at the extremities of the string. Let us also suppose that the curve is perfectly smooth. The forces on an element  $ds$  are merely the tensions at its ends and the reaction or pressure of the curve. Let  $Rds$  be this pressure, then  $R$  is the pressure per unit of length of the string. For the sake of brevity this is usually expressed by saying that  $R$  is the pressure at the element. It is usual to estimate the pressure of the curve on the string as positive when it acts in the direction opposite to that in which the radius of

Resolving along the tangent and normal to the string, we have

by Art. 454,  $\frac{dT}{ds} = 0$ ,  $T \frac{ds}{\rho} - R ds = 0$ .

We infer from these equations that, *when a light string rests on a smooth curve, the tension is constant, and the pressure at any point varies as the curvature.*

**458.** This theorem has a wider range than would perhaps appear at first sight. Since the curve may be of any form, the result includes the case of a string in equilibrium under any forces which are at every point normal to the curve. Supposing the normal forces given, the form of the curve can be found from the result just proved, viz. that at every point the curvature is proportional to the normal force.

As an example we may consider Bernoulli's problem; to find the form of a rectangular sail, two opposite sides of which are fixed so as to be parallel to each other and perpendicular to the direction of the wind. The weight of the sail is neglected compared with the pressure produced by the wind. Let us enquire what is the curve formed by a plane section of the sail drawn perpendicular to the fixed sides.

Two answers may be given to this question according as the wind after acting on the sail immediately finds an issue, or remains to press on the sail like a gas in equilibrium. On the former hypothesis we assume as the law of resistance, that the pressure of the wind on any element of the sail acts along the normal to the element and is proportional to the square of the resolved velocity of the wind. We have therefore  $R = w \cos^2 \psi$ , where  $\psi$  is the angle the normal to the section of the sail makes with the direction of the wind, and  $w$  is a constant. This gives  $c/\rho = \cos^2 \psi$ . By Art. 444 we infer that the curve is a catenary, whose axis is in the direction of the wind, and whose directrix is vertical.

If the air presses on the sail like a gas in equilibrium, the pressure on each side of the sail is equal in all directions by the laws of hydrostatics, but the pressure is greater on one side than on the other. We have therefore  $R$  equal to this constant difference, hence also  $\rho$  is constant, and the required curve is a circle.

**Ex. 1.** A "square sail" of a ship is fastened to the mast by two yard-arms, and in such that when filled with wind every section by a horizontal plane is a straight line parallel to the yards. Show that, assuming the ordinary law of resistance, it will have the greatest effect in propelling the ship when  $3 \sin(\alpha - 2\phi) - \sin \alpha = 0$ , where  $\alpha$  is the angle between the direction from which the wind comes and the ship's keel, and  $\phi$  is the angle between the yard and the ship's keel. [Caius Coll.]


**Ex. 2.** A light string has one end fixed at the vertex of a smooth cycloid; prove that as the string, while taut, is wound on the curve, the line of action of the resultant pressure on the string is always the same.

the element  $ds$ . Let  $\psi$  be the angle the tangent  $PK$  at  $P$  makes with the horizontal.

The element  $PQ$  is in equilibrium under the action of  $wds$  acting along the ordinate  $PN$ ,  $Rds$  along the normal  $PG$ , and the tensions at  $P$  and  $Q$ . Resolving along the tangent and normal at  $P$ , we have

$$dT - wds \sin \psi = 0 \quad \dots\dots(1),$$

$$-wds \cos \psi - Rds = 0 \quad \dots\dots(2).$$



Since  $\sin \psi = dy/ds$ , the first equation gives by integration


$$T = wy + C \quad \dots\dots\dots(3).$$

Hence, if  $T_1, T_2$  be the tensions at two points whose ordinates are  $y_1, y_2$ ,

$$T_2 - T_1 = w(y_2 - y_1).$$

This important result may be stated thus, *If a heavy string lies on a smooth curve, the difference of the tensions at any two points is equal to the weight of a string whose length is the vertical distance between the points.*

60. It may be remarked that this result has been obtained by resolving along the tangent to the string, and is altogether independent of the truth of the second equation. If then the whole length of the string does not lie on the curve, but if



if it be free and stretch across to and over some other curve, the result still holds. Thus if the string  $ABCD$  stretch round

In the same way the tension is a maximum at the highest point. Also no point of the string, such as  $C$  or  $C'$ , can be beneath the horizontal line joining the free extremities.

To determine the pressure at any point  $P$  (see fig. of Art. 4) we write the equation (2) in the form

$$R\rho = T - w\rho \cos \psi,$$

where the pressure  $R$  of the curve on the string, when position acts outwards, i.e. in the direction opposite to that in which the radius of curvature  $\rho$  is measured, Art. 457. If  $T_1$  be the tension at any fixed point  $A$ , and  $z$  the altitude of any point  $P$  above  $A$ , we have by (3)  $T = T_1 + wz$ . It therefore follows that

$$R\rho = T_1 + w(z - \rho \cos \psi).$$

If we measure a length  $PS = \rho$  along the normal at  $P$  outwards, the point  $S$  may be called the *anti-centre*. It is clear that  $z - \rho \cos \psi$  is the altitude of  $S$  above  $A$ . Hence, if a heavy string rest on a smooth curve, the value of  $R\rho$  at any point  $P$  exceeds the tension at  $A$  by the weight of a string whose length is the altitude of the anti-centre of  $P$  above  $A$ .

If the extremity  $A$  be free, as in the figure of this article, the tension at any point  $B$  is equal to  $w$  multiplied by the altitude of the anti-centre of  $B$  above  $A$ . If part of the string is free, as at  $C$  and  $C'$ , the pressure  $R$  is zero. Hence the anti-centres of curvature all lie in the straight line joining the free extremities  $A$  and  $D$ . *This is the common directrix of all the catenaries.*

In these equations  $Rds$  is the pressure outwards of the curve on the string. It is clear that, if  $R$  were negative and the string rest on the convex side, the string would leave the curve and equilibrium could not exist. At any such point as  $B$ , the anti-centre is above  $B$  and  $R$  is clearly positive. But at such a point as  $E$  the anti-centre is below  $E$ , and if it were also below the straight line joining the free extremities the pressure at  $E$  would be negative. If the string rest on the concave side of the curve, these conditions are reversed. In general, it is necessary for equilibrium that  $R\rho$  should be positive.

*directrix of the string.* No part of the string can be below the directrix, and the free ends, if there are any, must lie on it.

*be the outward pressure of the curve on the string,  $R_p$  is equal to  $w y'$ , where  $y'$  is the altitude of the anti-centre of  $P$  above the directrix.* It is therefore necessary that at every point of the curve the anti-centre should be above or below the directrix according as the string is on the convex or concave side of the curve.

1. Show that the locus of the anti-centre of a circle is another circle.
2. Show that the coordinates of the anti-centre at any point  $P$  of an ellipse referred to its axes are given by  $ax = 2a^2 \cos \phi - c^2 \cos^3 \phi$   $by = 2b^2 \sin \phi + c^2 \sin^3 \phi$ ,  $c^2 = a^2 - b^2$ , and  $\phi$  is the eccentric angle of  $P$ .
3. If  $S$  be the anti-centre at any point  $P$  of a curve, show that the normal locus of  $S$  makes with  $PS$  an angle  $\theta$  given by  $\tan \theta = \frac{1}{2} dp/ds$ .

It should be noticed that at the points where the string leaves the curve, both the curvature of the string and the pressure  $R$  may change abruptly. Thus in the figure of Art. 460 at a point a little below  $F$  the radius of curvature of the string is infinite and  $R$  is zero. At a point a little above  $F$  the curvature of the string is the same as that of the body  $N$ , and the pressure  $R$  is equal to  $w$ . At such a point as  $E$  the abrupt change in the value of the product  $R\rho$  (in accordance with the rule of Art. 460) is equal to the weight of a string whose length is the vertical distance between the anti-centres on each side of the point.

When the external forces which act on the string are such that their magnitudes per unit of length are finite, an abrupt change of tension cannot occur. If the tensions on each side of any point could differ by a finite quantity, an infinitesimal element of string containing the point would be in equilibrium under the influence of unequal forces acting in opposite directions. In the same way there can be no abrupt change in the direction of the tangent except at a point where the tension is zero or if the tangents on each side of any point made a finite angle with each other the element of string at that point would be in equilibrium under the action of the finite tensions not opposed to each other.

Ex. 1. A heavy string (length  $2l$ ) passes completely round a smooth horizontal cylinder (radius  $a$ ) with the two ends hanging freely down on each side. The parts of the string on the upper semi-circumference are close together, so that the whole string may be regarded as lying in a vertical plane perpendicular to the



axis of the cylinder. Find the position of rest and the least length of string consistent with equilibrium.

*First*, let us suppose that the string is in contact with the circle along the lower semi-circumference as well as the upper. Then a length  $l - \frac{3}{2}\pi a$  hangs vertically on each side. Let  $D$  be the lowest point of the circle, the anti-centre of  $D$  is at a distance  $2a$  below the centre  $O$  of the circle. Hence, unless  $l - \frac{3}{2}\pi a > 2a$ , the string cannot rest in contact with the circle.

*Secondly*, let us suppose that a portion of the string hangs freely in the form of a catenary. Let  $P'$  be one of the points of contact of the catenary with the circle. Let  $P$  be any point on the catenary, drawn in the figure merely to show the triangle  $PLN$ , Art. 444. Let the angle  $P'OD = \psi$ , so that  $\psi$  is the inclination of the tangent at  $P'$  to the horizon. Let  $x, y$  be the coordinates of  $P'$ ,  $s = CP'$ . By examining triangle  $PLN$ , we see that  $y = c \sec \psi$ ,  $s = c \tan \psi$ . Since  $x = a \sin \psi$ , we have by Art. 443

$$\sec \psi + \tan \psi = e^{\frac{a \sin \psi}{c}} \dots \dots \dots (1)$$

As already explained, the free extremities  $A, B$  of the string are on a level with the directrix, Art. 460. Hence  $BF = y + a \cos \psi$ ; also the arc  $FE = \pi a$ ,  $EP' = (\frac{1}{2}\pi - \psi)$  and  $P'C = s$ . The sum of these four quantities is  $l$ ,

$$\therefore c (\sec \psi + \tan \psi) + a \cos \psi - a \psi + \frac{3}{2}\pi a = l \dots \dots \dots (2)$$

Putting  $v = \frac{1}{2} \log \frac{1 + \sin \psi}{1 - \sin \psi}$ , we find from (1) and (2)

$$c = \frac{a \sin \psi}{v} \quad \frac{l}{a} = \sqrt{\frac{1 + \sin \psi}{1 - \sin \psi}} \left( \frac{\sin \psi}{v} + 1 - \sin \psi \right) - \psi + \frac{3}{2}\pi.$$

The second of these equations gives the length of the string corresponding to any given position of equilibrium.

To find the least value of  $l$  consistent with equilibrium, we equate to zero the differential coefficient of  $l$ . As this leads to some rather long reductions, the results only are here stated. Noticing that  $dv/d\psi = \sec \psi$ , we find

$$\frac{1}{a} \frac{dl}{d\psi} = \frac{(1-v)(v \cos^2 \psi - \sin \psi)}{v^2(1 - \sin \psi)} = 0.$$

By expanding  $v$  in powers of  $\sin \psi$ , we may show that  $(v \cos^2 \psi - \sin \psi)$  is never zero and does not vanish for any value of  $\sin \psi$  between zero and unity. Equating to zero the factor  $(1-v)$ , we find that  $\sin \psi = (e^2 - 1)/(e^2 + 1)$ . As  $dl/d\psi$  changes from  $-$  to  $+$  as  $\sin \psi$  increases, we see that  $l$  is a minimum. Effecting the numerical calculations, we have  $\psi = .86$ ; and  $l - \frac{3}{2}\pi a = (e - \psi) a$ , which reduces to  $(1.85) a$ .

For any given value of  $l$ , greater than this minimum, there are two positions of equilibrium. In one a portion of the string hangs freely in the form of a catenary; in the other the string fits closely to the cylinder or hangs free according to the given value of  $l - \frac{3}{2}\pi a$  is greater or less than  $2a$ .

Ex. 2. A uniform chain, having its ends fastened together, is hung round the circumference of a vertical circle. If  $a$  be the radius of the circle,  $2a\gamma$  the weight which the string touches, and  $l$  the whole length, prove

See above.

**463. Rough curve, light string.** *To consider the case in which the weight of the string is inconsiderable, but the curve is rough.* Referring to the figure of Art. 459, we shall suppose the extremities  $A$  and  $B$  to be acted on by unequal forces  $F, F'$ . Our object is to find the conditions of limiting equilibrium; let us then suppose the string is on the point of motion in the direction  $AB$ . The friction on every element  $PQ$  is equal to  $\mu Rds$ , where  $\mu$  is the coefficient of friction. This force acts in the direction opposite to the motion, viz. from  $B$  to  $A$ .

Introducing this force into the equations obtained in Art. 459 and resolving the forces along the tangent and normal, and omitting terms containing the weight of the element, we have

$$dT - \mu Rds = 0 \dots (1), \quad T \frac{ds}{\rho} - Rds = 0 \dots (2).$$

Eliminating  $R$ , we find,  $\frac{dT}{T} = \mu \frac{ds}{\rho} = \mu d\psi$ ;

$$\therefore \log T = \mu\psi + A, \quad \therefore T = Be^{\mu\psi},$$

where  $A$  and  $B$  are undetermined constants. If  $T_1, T_2$  be the tensions at two points at which the tangents make angles  $\psi_1, \psi_2$  with the axis of  $x$ , this equation gives

$$T_2 = T_1 e^{\mu(\psi_2 - \psi_1)} \dots (3).$$

It will be found useful to put the result in the form of a rule. *A light string rests on a rough curve in a state bordering on motion, the ratio of the tensions at any two points is equal to  $e$  to the power of  $\mu$  times the angle between the tangents or between the normals at those points.*

The sign to be given to  $\mu$  in this equation depends on the direction in which friction acts. In using the rule, however, no difficulty arises from this ambiguity; for (1) it is evident that that tension is the greater of the two which is opposed to the friction, and (2) it must be the ratio of the greater tension to the lesser (not the lesser to the greater) which is equal to the exponential with the given index.

To determine the angle between the tangents; let a straight line, starting from a point coincident with one tangent, roll on the string until it coincides with the other tangent; the angle between the two tangents is then the angle between the two normals.



$\psi$ 's of  $A$  and  $B$  are therefore  $f(s)$  and  $f(s+l)$ . Hence, by taking the logarithms of equation (3),

$$\log F_2 - \log F_1 = \mu \{f(s+l) - f(s)\}.$$

From this equation  $s$  must be found. The other limiting position may be found by writing  $-\mu$  for  $\mu$ .

**465.** It should be noticed that the equation (3) of Art. 463 is independent of the size of the curve. Suppose a *heavy string to pass through a small rough ring or over a small peg*, and to be in a state bordering on motion; the weight of the portion of string on the pulley may sometimes be neglected compared with the tensions of the string on either side. If the strings on either side make a finite angle with each other, the pressures and therefore the frictions will not be small, and cannot be neglected. We infer that, *when a heavy tight string passes through a small rough ring, the ratio of the tensions on each side is given by the same rule as that for a light string.*

**466.** Ex. 1. A rope is wound twice round a rough post, and the extremities are acted on by forces  $F, F'$ . Find the ratio of  $F : F'$  when the rope is on the point of slipping. [Here the angle between the tangents is  $4\pi$ , hence the ratio of the greater force to the other is  $e^{4\pi\mu}$ .]

Ex. 2. A circle has its plane vertical, and is pressed against a vertical wall by a string fixed to a point in the wall above the circle. The string sustains a weight  $P$ , the coefficient of friction between the string and circle is  $\mu$ , and the wall is perfectly rough. When the circle is on the point of sliding, prove that, if  $W$  be the weight of the circle and  $\theta$  the angle between the string and the wall,  $P(1 + \cos \theta) e^{\mu\theta} = W + 2P$ .  
[Coll. Exam.]

Ex. 3. A light string is placed over a rough vertical circle, and a uniform heavy rod, whose length is equal to the diameter of the circle, has one end attached to each end of the string, and rests in a horizontal position. Find within what points on the rod a given mass may be placed, without disturbing the equilibrium of the system: and show that the given mass may be placed anywhere on the rod, provided the ratio of its weight to that of the rod does not exceed  $\frac{1}{2}(e^{\mu\pi} - 1)$ , where  $\mu$  is the coefficient of friction between the string and the circle. [Coll. Exam., 1880.]

Ex. 4. A string, whose weight is neglected, passes over a rough fixed horizontal cylinder and is attached to a weight  $W$ ;  $P$  is the weight which will just raise  $W$ , and  $P'$  the weight which will just sustain  $W$ ; show that, if  $R, R'$  are the corresponding resultant pressures of the string on the cylinder,  $P : P' :: R^2 : R'^2$ . [Math. T., 1880.]

Ex. 5. A band without weight passes tightly round the circumference of two unequal rough wheels. One wheel is fixed while the other is made to turn slowly

Ex. 6. On the top of a rough fixed sphere (radius  $c$ ) is placed a heavy particle, which are tied two equally heavy particles by light strings each of length  $c\theta$ ; show that, when the latter particles are as near together as possible, the planes of the strings make with one another an angle  $\phi$ , where  $2 \sin(\theta - \lambda) \cos \frac{\phi}{2} = \sin \lambda \cdot e^{\theta \tan \lambda}$ , and  $\lambda$  is the angle of friction between the particles and the sphere, and between the strings and the sphere. [Coll. Exam., 1887.]

Ex. 7. A uniform heavy string of length  $2l$  passes through two given small fixed rings  $A, B$  in the same horizontal line. Supposing the string to be on the point of slipping inwards at both  $A$  and  $B$ , find the position of equilibrium.

If  $2s$  be the portion of the string between the pegs,  $y$  the ordinate of the catenary at either peg, the tensions at the two sides of either ring are proportional to  $y$  and  $-s$ . Referring to the triangle  $PLN$  in the figure of Art. 443, we see that the angle through which the string has been turned is the supplement of the least angle whose sine is  $c/y$ . Hence we have by (3)  $\log \frac{y}{l-s} = \left( \pi - \sin^{-1} \frac{c}{y} \right) \mu$ . Also if  $2a$  be the known distance between the rings, we have  $x=a$ . Substituting for  $y$  and  $s$  their values in terms of  $x$  or  $a$  given in Art. 443, we have an equation to find  $c$ . Hence  $a$  and  $s$  may be found.

Ex. 8.  $A, B, C$  are three rough points in a vertical plane;  $P, Q, R$  are the greatest weights which can be severally supported by a weight  $W$  when connected with it by strings passing over  $A, B, C$ , over  $A, B$ , and over  $B, C$  respectively. Show that the coefficient of friction at  $B$  is  $\frac{1}{\pi} \log \frac{QR}{PW}$ . [Math. Tripos, 1851.]

Let  $\alpha, \beta, \gamma$  be the angles through which the string is bent at  $ABC$ , their sum is  $\pi$ . By Art. 463  $\log P/W, \log Q/W, \log R/W$  are respectively equal to  $\mu\alpha + \mu'\beta + \mu''\gamma, \mu\alpha + \mu'(\beta + \gamma), \mu'(\alpha + \beta) + \mu''\gamma$ . The result follows by substitution. It is supposed that  $B$  lies between the verticals through  $A$  and  $C$ .

Ex. 9. A string, whose length is  $l$ , is hung over two rough pegs at a distance  $a$  apart in a horizontal line. If one free end of the string is as much as possible lower than the other, the inclination to the vertical of the tangent to the string at either peg is given by the equation  $\frac{l}{a} \sin \theta \cdot \log \cot \frac{\theta}{2} = \cos \theta + \cosh \mu (\pi - \theta)$ . [St John's Coll., 1881.]

Ex. 10. An endless uniform heavy chain is passed round two rough pegs in the same horizontal line, being partly supported by a smooth peg situated midway in the line between the other pegs, so that the chain hangs in three festoons. If  $\alpha, \beta$  be the angles which the tangents at one of the rough pegs make with the vertical, and  $\mu$  is the coefficient of friction, prove that the limiting values of  $\alpha$  and  $\beta$  are given by the equation  $e^{\pm \mu(\pi - \alpha + \beta)} = 2 \frac{\sin \alpha \log \cot \frac{1}{2} \alpha}{\sin \beta \log \cot \frac{1}{2} \beta}$ . [Math. Tripos, 1879.]

**467. Rough curve, heavy string.** We shall now consider the general case in which both the weight of the string and the

In applying these equations to other forms of the string we must remember that the friction is  $\mu$  times the pressure taken positively. Thus as the string is heavy it might lie on the concave side of the curve. We must then change the sign of  $R$  in the second equation, but not in the first.

We shall presently have occasion to write  $\rho = ds/d\psi$ . If the figure is not so drawn that  $s$  and  $\psi$  increase together, we shall have  $\rho = -ds/d\psi$ . To solve these equations, we eliminate  $R$ ,

$$\therefore \frac{dT}{d\psi} - \mu T = w\rho (\sin \psi - \mu \cos \psi) \dots \dots \dots (3).$$

This is one of the standard forms in the theory of differential equations. According to rule we multiply by  $e^{-\mu\psi}$  and integrate;

$$\therefore Te^{-\mu\psi} = \int w\rho (\sin \psi - \mu \cos \psi) e^{-\mu\psi} d\psi + C \dots \dots \dots (4).$$

We cannot effect this integration until the form of the curve is given. By using the rules of the differential calculus we first express  $\rho$  as a function of  $\psi$ . Then substituting and integrating, we find

$$Te^{-\mu\psi} = f(\psi) + C \dots \dots \dots (5).$$

The value of  $T$  having been found by this equation,  $R$  follows from either (1) or (2). *It should be noticed that we have not assumed that the string is necessarily uniform.*

The pressure at any point is given by the equation

$$R\rho = T - w\rho \cos \psi.$$

It may be noticed that this is the same as the corresponding equation for a heavy string on a smooth curve, Art. 460.

If the string is not on the point of motion, we replace the term  $-\mu Rds$  in (1) by  $-Fds$ , where  $F$  is the friction per unit of length.

Ex. If the string is uniform and of finite length, and if the extremities are acted on by forces  $P_1$ ,  $P_2$ , prove that the whole friction called into play is  $\int Fds = P_2 - P_1 - wz$ , where  $z = y_2 - y_1$ , so that  $z$  is the vertical distance between the extremities of the string.

**468.** It appears from the last article that the determination of the circumstances of the equilibrium of a heavy string on a rough curve depends on the integral

$$I = \int w\rho e^{-\mu\psi} (\sin \psi - \mu \cos \psi) d\psi.$$

If the curve is a cycloid with its base inclined to the horizon at any angle, we have  $\rho = 4a \cos(\psi - \alpha)$ , where  $a$  is the radius of the generating circle. More generally, if the curve is such that  $w\rho$  can be expanded in a series of *positive integral powers* of  $\sin \psi$  and  $\cos \psi$ , we can express  $w\rho(\sin \psi - \mu \cos \psi)$  in a series of sines and cosines of multiple angles. In this case the integral can be found by a method similar to that used for the circle.

If the curve is a catenary we have  $\rho \cos^2 \psi = c$  and  $I = wc \sec \psi e^{-\mu \psi}$ . More generally, if the curve is such that  $\rho = a \cos^n \psi$ , where  $n$  is a *positive or negative integer*, we may find  $I$  by a formula of reduction. We easily see that

$$\begin{aligned} & \{\mu^2 + (n+1)^2\} I_n - (n-1)(n+2) I_{n-2} \\ &= wa (\cos \psi)^{n-1} e^{-\mu \psi} \{n+2 - \mu(n+2) \sin \psi \cos \psi - (n+1 - \mu^2) \cos^2 \psi\}. \end{aligned}$$

**469.** Ex. 1. A heavy string occupies a quadrant of the upper half of a rough vertical circle in a state bordering on motion. Prove that the radius through the lower extremity makes an angle  $\alpha$  with the vertical given by  $\tan(\alpha - 2\epsilon) = e^{-\frac{1}{2}\mu\pi}$ , where  $\mu = \tan \epsilon$ .

Ex. 2. A heavy string, resting on a rough vertical circle with one extremity at the highest point, is on the point of motion. If the length of the string is equal to the quadrant, prove that  $\frac{1}{2}\pi \tan \epsilon = \log \tan 2\epsilon$ . [Coll. Ex., 1881.]

Ex. 3. A single moveable pulley, of weight  $W$ , is just supported by a power  $P$ , which is applied at one end of a cord which goes under the pulley and is then fastened to a fixed point; show that, if  $\phi$  be the angle subtended at the centre by the part of the string in contact with the pulley,  $\phi$  is given by the equation

$$P(1 - 2e^{\mu\phi} \cos \phi + e^{2\mu\phi})^{\frac{1}{2}} = W. \quad [\text{Coll. Ex., 1882.}]$$

Ex. 4. If a heavy string be laid on a rough catenary, with its vertex upwards and its axis vertical, so that one extremity is at the vertex, the string will just rest if its length be equal to the parameter of the catenary, provided the coefficient of friction be  $(2 \log 2)/\pi$ . [Coll. Ex., 1885.]

Ex. 5. A heavy string  $AB$  is placed on the concave side of a rough cycloidal curve whose base is inclined at an angle  $\alpha$  to the horizon, with one extremity  $A$  at the lowest point and the other  $B$  at the vertex. Prove that the string will be in a state bordering on motion if  $\frac{\tan \epsilon - 2 \tan \alpha}{\tan \epsilon + (1 - 3 \cos^2 \epsilon) \tan \alpha} = e^{\alpha \tan \epsilon}$ , where  $\tan \epsilon$  is the coefficient of friction.

Ex. 6. A heavy string rests on a rough cycloid with its base horizontal and its axis vertical. The normals at the extremities of the string make with the vertical angles each equal to  $\alpha$ , which is also the angle of friction between string and cycloid. If, when the cycloid is tilted about one end till the base makes an angle  $\alpha$  with the horizontal, the string is on the point of motion, show that

$$3 - 2 \sec^2 \alpha = e^{-2\alpha \tan \alpha}.$$

Let the form be known in which a heterogeneous unconstrained string, supported at each end, rests in equilibrium in one plane under the action of any forces. Let this known curve be  $y=f(x)$ . Let us now suppose this string to be placed in the same position on a rough curve fixed in space whose equation is also  $y=f(x)$ ; the extremities of the string be acted on by forces such that the string is on the point of slipping, then

$$(T + G\rho) e^{-\mu\psi} = C, \quad R\rho e^{-\mu\psi} = C \dots\dots\dots (1)$$

where  $C$  is constant throughout the length of the string. Here, as in Art. 467,  $Gds$  is the resolved normal force inwards on the element  $ds$ . The standard is the same as that taken in Art. 467. The string is just slipping in that direction along the curve in which the  $\psi$  of any point of the string increases. Also the pressure  $R$  of the curve on the string, when positive, acts outwards. If either of these assumptions is reversed, the sign of  $\mu$  must be changed. In order that the string may not leave the curve, the sign of  $C$  should be such that  $R$  acts towards the curve towards that side on which the string lies.

To prove these results, we refer to equations (1) and (2) Art. 454. Introducing the pressure  $R$  into these equations, we have

$$dT + Fds - \mu Rds = 0, \quad \frac{Tds}{\rho} + Gds - Rds = 0 \dots\dots\dots (2)$$

Eliminating  $R$ , as in Art. 467  $Te^{-\mu\psi} = -\int (F - \mu G) \rho e^{-\mu\psi} d\psi + C \dots\dots\dots (3)$

When the string is hanging freely,  $R=0$ ; by eliminating  $T$  between the equations (2) we find that  $F\rho = \frac{d}{d\psi}(G\rho)$  is true along the curve. When the string is constrained to lie on a curve which possesses this property, we can substitute the value of  $F\rho$  in the equation (3). We then find  $Te^{-\mu\psi} = -e^{-\mu\psi}G\rho + C$ . The result to be proved follows immediately, the second is obtained by substituting the value of  $T$  in the second of equations (2).

**471.** Ex. 1. A uniform heavy string  $AB$  is placed on the upper side of a rough curve whose form is a catenary with its directrix horizontal. If the lower extremity is at the vertex, find the least force  $F$  which, acting at the upper extremity, will just move the string.

At the upper end of the string we have  $T=F$ ,  $G=-g \cos \psi$ , at the lower end  $G=-g$ ,  $\psi=0$ . Hence by Art. 470  $(F - gp \cos \psi) e^{\pm \mu\psi} = -gc$ ,  $\therefore F = g(y - ce^{\pm \mu\psi})$ . The upper sign of  $\mu$  gives the larger value of  $F$ , i.e. the force which will just move the string upwards, the lower sign gives the force which will just sustain the string. Instead of quoting equation (1), the reader should deduce this result from the equations of equilibrium.

**Ex. 2.** A uniform string  $AB$  rests on the circumference of a rough circle under the action of a central force tending to a point  $O$  situated at the opposite extremity of the diameter through  $A$ . If the force of attraction varies as the inverse cube of the distance, prove that the force  $F$  acting at  $A$  necessary to prevent the string from slipping is  $F = k(\sec^2 \beta e^{-2\mu\beta} - 1)$ , where  $\beta$  is the angle  $AOB$ ,  $\frac{2k}{a}$  the force at  $A$ , and  $a$  is the diameter.

**472. Endless and other strings.** When a heavy inextensible string rests in equilibrium in contact with a smooth curve without singularities in a vertical plane, the pressure and tension can be found as in Art. 459, with one undetermined constant. This constant is usually found by equating to zero the tension at the free extremity. If, however, the string is either endless or has both its extremities attached to the curve and is tightened at pleasure, there is nothing to determine the constant.

Let us suppose the string to be in contact along the under side of the curve. Let the string be gradually loosed until its length exceeds the length of the arc in contact by an infinitely small quantity. The string is then just on the point of leaving the curve at some unknown point  $Q$ , and is then said to *just fit* the curve. If the length of the string were still further increased a finite portion of the string would be off the curve and hang in the form of a catenary. In the same way if the portion of the string under consideration rest with its weight supported on the upper and concave side of the curve, we may conceive the string to be gradually tightened until it separates from the curve at some point  $Q$ . If still further tightened or shortened a finite part of the string would hang in the form of a catenary, while the remainder would still rest on the curve.

To determine the position of the point  $Q$  we notice that the pressure of the curve on the string measured towards that side on which the string lies must be positive at every point of the curve and zero at  $Q$ . The pressure thus measured is therefore a minimum at  $Q$ .

Referring to Art. 460, the *outward pressure*  $R$  is given by

$$R\rho = T_0 + w(y - \rho \cos \psi) \dots \dots \dots (1).$$

Differentiating, and remembering that both  $R$  and  $dR/ds$  are zero at  $Q$ , we find

$$0 = \frac{dy}{ds} - \cos \psi \frac{d\rho}{ds} + \rho \sin \psi \frac{d\psi}{ds},$$

except when  $\rho$  is infinite at the point thus determined. Since  $dy/ds = \sin \psi$  and

$$\rho = ds/d\psi, \text{ this gives at once } 2 \tan \psi = \frac{d\rho}{ds} \dots \dots \dots (2).$$

This equation determines the points at which  $R\rho$  is a maximum, a minimum, or stationary. When both  $R$  and  $dR/ds$  are zero, we have

$$\rho \frac{d^2 R}{ds^2} = \frac{d^2 R \rho}{ds^2} = \cos \psi \left( \frac{2}{\rho} - \frac{d^2 \rho}{ds^2} \right) + \sin \psi \frac{1}{\rho} \frac{d\rho}{ds}.$$

The sign of this expression determines whether  $R$  is a maximum or a minimum. When the length of the string is finite, some of these maxima or minima may be excluded as being beyond the given limits. But we must then also take into consideration the extremities of the string, for it is manifest that the pressure at either end may be less than that at any point between the limits of the string. *The required point  $Q$  is that one of all these points at which the pressure measured towards the string is least.* The undetermined constant  $T_0$  is then found by making the pressure zero at this point.

the constant  $T_0$  be determined by making the statical directrix pass through that anti-centre, Art. 460. If  $R$  represent the outward pressure on the string,  $R\rho$  is then positive at every point of the string and equal to zero at  $Q$ . The string therefore leaves the curve at  $Q$ .

Next, let the string rest on the upper and concave side of a curve. If gradually tightened it will leave the curve at the point  $Q$  whose anti-centre is highest. For, choosing the constant  $T_0$  so that the statical directrix passes through the anti-centre, and assuming that the whole string is still above the directrix (Art. 460), the value of  $R\rho$  is negative at every point of the string and equal to zero at  $Q$ .

✓ **473.** Ex. 1. A heavy string *just fits* round a vertical circle: show that the tension at the highest point is three times that at the lowest.

Let  $T_0, T_1$  be the tensions at the lowest and highest points, and let  $a$  be the radius. Then  $T_1 - T_0 = 2wa$ . Since  $\rho$  is constant the only solution of (2) is  $\psi = 0$ , and this makes the outward pressure  $R$  a minimum. The pressure is therefore zero at the lowest point. The weight, viz.  $w ds$ , of the lowest element is therefore supported by the tensions at each end, i.e.  $w ds = T_0 ds/a$ . These equations give  $T_0 = wa$ , and  $\therefore T_1 = 3wa$ .

We may obtain the result more simply by using the geometrical rule given in the last article. The locus of the anti-centre is obviously another circle of radius  $2a$  and concentric with the given circle. Taking the tangent at its lowest point for the statical directrix, the altitudes of the highest and lowest points of the given circle are as 3 : 1, Art. 460. The tensions at these points are therefore also in the same ratio. We see also that if the string be slightly loosened, it will begin to leave the curve *at the lowest point*.

Ex. 2. A heavy string (length  $2l$ ) rests on the inner or concave side of a segment of a smooth sphere (radius  $a$ , angle  $2\beta$ ) and hangs down symmetrically over the smooth rim which is in a horizontal plane. Find the conditions of equilibrium.

Since every point of the string must be above the statical directrix, it will be seen on drawing a figure that  $l > a(\beta + 1 - \cos \beta)$ . Since the string rests on the concave side, the outward pressure  $R$  must be negative and therefore every point of the anti-centric curve must be below the statical directrix, hence  $l < a(\beta + \cos \beta)$ . These two conditions require that  $\beta$  should be less than  $\frac{1}{3}\pi$ . If the second inequality be reversed the string will leave the spherical segment *at the highest point*.

Ex. 3. A heavy string is attached to two points of the arc of a catenary with its axis vertical, and rests against its under surface. If the string is gradually loosed, show that it will leave the curve at every point at the same instant.

Ex. 4. A heavy string has one end fastened to the lowest point of the arc of a cycloid with the axis vertical and the vertex at the lowest point. The string envelopes the arc outside up to the cusp, and passing over a small smooth pulley has the other end hanging freely. Prove that the least length of the string hanging down which is consistent with equilibrium is equal to six times the radius of the generating circle. Find also in this case the resultant pressure on the cycloid.

[Queens' Coll.]

Ex. 5. A heavy string just fits the under surface of a cycloidal arc, the extremi-


the catenary curve coincident, and (2) that the fluorescent arc is situated at a point of the curve determined by  $2 \tan \psi = d\rho/ds$ .

Ex. 7. A string is bound tightly round a smooth ellipse, and is acted on by a central repulsive force in the focus varying directly as the square of the distance. Find the law of variation of the tension, and prove that, if the string be slightly loosened, it will leave the curve at the points at a distance from the focus equal to three times the semi-major axis, provided the eccentricity be greater than  $3/4$ . If the eccentricity be less than  $3/4$ , where will it leave the curve? [Coll. Ex., 1887.]

**474. Central forces.** A string of given length is attached to two fixed points, and is under the action of a central force. Find the relation between the form of the curve and the law of force.

The arc be measured from any fixed point  $A$  on the string in the direction  $AB$ , and let  $s = AP$ .

$O$  be the centre of force, and  $Fds$  be the force on the element  $ds$  estimated positive when acting in the positive direction of the radius vector, i.e. when the force is repulsive.



The element  $PQ$  is in equilibrium under the action of the tensions  $T$  and  $T + dT$  and the central force  $Fds$ . Resolving along the tangent at  $P$ , we have

$$dT + Fds \cos \phi = 0,$$

where  $\phi$  is the radial angle, i.e. the angle  $OPA$ . Since  $\cos \phi = dr/ds$ ,

reduces to 
$$\frac{dT}{dr} + F = 0 \dots \dots \dots (1).$$

We might obtain a second equation by resolving the same forces along the normal at  $P$ , but the result is more easily found by taking the moment of the forces which act on the finite portion of the string  $AP$ . This portion is in equilibrium under the action of the tensions  $T_0$ ,  $T$  and the central force tending from  $O$  on each element. Taking moments about  $O$ , these latter disappear; we therefore have

$$Tp = A \dots \dots \dots (2),$$

where  $p$  is the perpendicular from  $O$  on the tangent at  $P$ , and  $A$  the moment about  $O$  of the tension  $T_0$ .

Let the tangents at any two points  $A$ ,  $B$  of the curve meet in  $C$ . Then the arc



$R$  of the central forces on all the elements. *This resultant force must therefore act along the straight line joining the centre of force  $O$  to the intersection  $C$  of the tangents at  $A$  and  $B$ .* Also if  $OY$ ,  $OZ$  are the perpendiculars from  $O$  on the tangents at  $A$  and  $B$ , we see by compounding the tensions that  $R = A \cdot \frac{YZ}{OY \cdot OZ}$ .

As the point  $P$  moves from  $A$  to  $B$ , the foot of the perpendicular on the tangent at  $P$  traces out the pedal curve. This curve, when sketched, exhibits to the eye the magnitude of the tension at all points of the catenary.

#### 475. Two cases have now to be considered.

*First.* Suppose the form of the string to be given, and let the force be required. By known theorems in the differential calculus we can express the equation to the curve in the form  $p = \psi(r)$ . The equations (1) and (2) then give

$$T = \frac{A}{\psi(r)}, \quad F = \frac{A\psi'(r)}{\psi(r)^2} \dots\dots\dots (3)$$

The constant  $A$  remains indeterminate, for it is evident that the equilibrium would not be affected if the magnitude of the central force were increased in any given ratio. The tension at any point of the string and the pressures on the fixed points of suspension would be increased in the same ratio.

*Secondly.* Suppose that the force is given, and that the form of the curve is required. Eliminating  $T$  between (1) and (2) we

find 
$$\frac{A}{p} = B - \int F dr \dots\dots\dots (4)$$

This differential equation has now to be solved. Put  $u = B - \int F dr = f(u)$ ; we find by a theorem in the differential calculus

$$A^2 \left\{ u^2 + \left( \frac{du}{d\theta} \right)^2 \right\} = (B - fu)^2 \dots\dots\dots (5)$$

Separating the variables, we have

$$\int \frac{\pm A du}{\{(B - fu)^2 - A^2 u^2\}^{\frac{1}{2}}} = \theta + C \dots\dots\dots (6)$$

When this integration has been effected the polar equation

nts. We have also given the length of the string. To use  
s datum we must find the length of the arc. We easily find

$$(ds)^2 = (dr)^2 + (r d\theta)^2 = \frac{1}{u^4} \{ (du)^2 + (u d\theta)^2 \}.$$

Substituting from (5), we have

$$s = \int \frac{(B - fu) du}{u^2 \{ (B - fu)^2 - A^2 u^2 \}^{\frac{1}{2}}} \dots\dots\dots (7).$$

Taking this between the given limits of  $u$ , and equating the  
ult to the given length of the string, we have a third equation  
ind the three constants.

The equation (6) agrees with that given by John Bernoulli, *Opera Omnia*, *Tomus*  
*rtus*, p. 238. He applies the equation to the case in which the force varies  
rsely as the  $n$ th power of the distance, and briefly discusses the curves when  
and  $n=2$ .

476. Ex. 1. A string is in equilibrium under the action of a central force.  
be the force at any point per unit of length, prove that the tension at that  
 $t = F\chi$ , where  $\chi$  is the semi-chord of curvature through the centre of force.  
v also that  $F = A \frac{r}{p^2}$ , where  $A$  is a constant.


Ex. 2. A uniform string is in equilibrium in the form of an arc of a circle under  
influence of a centre of force situated at any point  $O$ . Find the law of force.  
 $C$  be the centre,  $OC = c$ ,  $CP = a$ . Then  $2ap = r^2 + a^2 - c^2$ ,

$$\therefore F = -A \frac{d}{dr} \frac{1}{p} = 4aA \frac{r}{(r^2 + a^2 - c^2)^2}.$$

f the centre of force is situated at any point of the arc not occupied by the  
g the law of force is the inverse cube of the distance.

ince  $Tp = A$ ,  $A$  is positive, hence  $F$  is  
ive, i.e. the force must be repulsive. If the  
re of force is outside the circle,  $p$  is negative  
hat part of the arc nearest  $O$  which is cut off  
he polar line of  $O$ . If the string occupy this  
of the arc,  $A$  is negative and the force  $F$   
be attractive.

We have taken  $r$  or  $u$  as the independent  
ble. If the centre of force be at the centre  
e circle, this would be an impossible sup-  
ition. This case therefore requires a separate  
tigation. It is however clear that the string



$n > 1$ . Show that the form of the string between  $A$  and  $B$  is  $r^{n-2} = b^{n-2} \cos(n-2)\theta$ . If  $n=2$  the curve is an equiangular spiral.

Ex. 5. A closed string surrounds a centre of force  $= \mu u^n$ , where  $n > 1$  and  $< 2$ . Show that, as the length of the string is indefinitely increased so that one apse becomes infinitely distant from the centre of force, the equilibrium form of the string tends to become  $r^{n-2} = b^{n-2} \cos(n-2)\theta$ . If  $n = \frac{3}{2}$  the form of the curve is a parabola.

Ex. 6. A uniform string of length  $2l$  is attached to two fixed points  $A, B$  at equal distances from a centre  $O$  of repulsive force  $= \mu u^2$ . If  $OA = OB = b$  and the angle  $AOB = 2\beta$ , prove that the equation to the string is

$$\frac{M}{r} = 1 + \frac{\cos(\theta \sin \alpha)}{\cos \alpha},$$

where the real and imaginary values of  $M$  and  $\alpha$  are determined from the equations

$$\frac{M}{b} = 1 + \frac{\cos(\beta \sin \alpha)}{\cos \alpha} \quad \sin \alpha = \pm \frac{b}{l} \sin(\beta \sin \alpha).$$

The equations (1) and (2) of Art. 474 become here  $dT = \mu du$ ,  $Tp = A$ .

Proceeding as explained in Art. 475, we find  $\pm \int \frac{A du}{\{(B + \mu u)^2 - A^2 u^2\}^{\frac{1}{2}}} = \theta + C$ .

This integral is one of the standards in the integral calculus, and assumes different forms according as  $A^2 - \mu^2$  is positive, negative or zero. Taking the first assumption, we have after a slight reduction

$$\frac{A^2 - \mu^2}{B} u = \mu \pm A \cos \left( 1 - \frac{\mu^2}{A^2} \right)^{\frac{1}{2}} (\theta + C).$$

The formula really includes all cases, for when  $A^2 - \mu^2$  is negative we may write for the sine of the imaginary angle on the right-hand side its exponential value.

Proceeding to find the arc in the manner already explained, we easily arrive at

$$Bs = \pm \{(Br + \mu)^2 - A^2\}^{\frac{1}{2}} + D,$$

where the radical must have opposite signs on opposite sides of an apse.

The conditions of the question require that the string should be symmetrical about the straight line determined by  $\theta = 0$ . We have therefore  $C = 0$  and  $D = 0$ .

Putting  $A = \mu \sec \alpha$ , the equation to the curve reduces to  $\frac{\mu \tan^2 \alpha}{B} \frac{1}{r} = 1 \pm \frac{\cos(\theta \sin \alpha)}{\cos \alpha}$ .

We also have

$$B^2 l^2 = (Bb + \mu)^2 - \mu^2 \sec^2 \alpha.$$

Eliminating  $B$  between these equations, we find  $l \sin \alpha = \pm b \sin(\beta \sin \alpha)$ . We now put  $M$  for the coefficient of  $1/r$  and include the double sign in the value of  $\alpha$ . Since  $r = b$  when  $\theta = \pm \beta$  the three results given above have been obtained.

Ex. 7. A string is in equilibrium in the form of a closed curve about a centre of repulsive force  $= \mu u^2$ . Show that the form of the curve is a circle.

Referring to the last example, we notice that, since  $r$  is unaltered when  $\theta$  is increased by  $2\pi$ ,  $r$  must be a trigonometrical function of  $\theta$ . Hence  $\sin \alpha = 1$  or  $0$ . Putting  $M \cos \alpha = M'$ , the first makes  $M'/r = \cos \theta$ , which is not a closed curve, the second gives  $M = r$ , which is a circle.

Ex. 8. If the curve be a parabola, and the centre of force at the focus, and if

Ex. 11. Show that the *catenary of equal strength* for a central force which varies as the inverse distance is  $r^n \cos n\theta = a^n$ , where  $1 - n$  is the ratio of the line density to the tension. Show also that this system of curves includes the circle, the rectangular hyperbola, the lemniscate, and when  $n$  is zero the equiangular spiral.

[O. Bonnet, *Liouville's J.*, 1844.]

Ex. 12. A string is placed on a smooth plane curve under the action of a central force  $F$ , tending to a point in the same plane; prove that, if the curve be such that a particle could freely describe it under the action of that force, the pressure of the string on the curve referred to a unit of length will be equal to  $\frac{F \sin \phi}{2} + \frac{c}{\rho}$ , where  $\phi$  is the angle which the radius vector from the centre of force makes with the tangent,  $\rho$  is the radius of curvature, and  $c$  is an arbitrary constant.

If the curve be an equiangular spiral with the centre of force in the pole, and if one end of the string rest freely on the spiral at a distance  $a$  from the pole, then the pressure is equal to  $\frac{\mu \sin \phi}{2r} \left( \frac{1}{r^2} + \frac{1}{a^2} \right)$ . [Math. Tripos, 1860.]

Ex. 13. A free uniform string, in equilibrium under the action of a repulsive central force  $F$ , has a form such that a particle could freely describe it under a central force  $F'$  tending to the same centre. Show that  $F = kpF'$ , where  $k$  is a constant. If  $v$  be the velocity of the particle and  $T$  the tension of the string, show that  $T = kp v^2$ . See Art. 476, Ex. 1.

Ex. 14. It is known that a particle can describe a rectangular hyperbola about a repulsive central force which varies as the distance and tends from the centre of the curve. Thence show that a string can be in equilibrium in the form of a rectangular hyperbola under an attractive central force which is constant in magnitude and tends to the centre of the curve. Show also that the tension varies as the distance from the centre.

For a comparison of the free equilibrium of a uniform string with the free motion of a particle under the action of a central force, see a paper by Prof. Townsend in the *Quarterly Journal of Mathematics*, vol. XIII., 1873.

477. When there are two centres of force the equations of equilibrium are best obtained by resolving along the tangent and normal. Let  $r, r'$  be the distances of any point  $P$  of the string from the centres of force;  $F, F'$  the central forces, which are to be regarded as functions of  $r, r'$  respectively. Let  $p, p'$  be the perpendiculars from the centres of force on the tangent at  $P$ . We then have

$$dT + Fdr + F'dr' = 0 \dots (1), \quad \frac{T}{\rho} - F \frac{p}{r} - F' \frac{p'}{r'} = 0 \dots (2).$$

The first equation gives  $T = B - \int Fdr - \int F'dr' \dots \dots \dots (3).$

We may suppose the lower limits of these integrals to correspond to any given point on the string. If this be done  $B$  will be the tension at  $P_0$ . Substituting the value of  $T$  thus obtained from (1) and (2) and remembering that  $\rho = r dr / dp$ ,

$$\frac{d}{dr} (p F dr) + \frac{d}{dr'} (p' F' dr') = B \dots \dots \dots (4):$$

on the other hand, if we find  $T$  from (2) and substitute in (1), we find after reduction

$$\frac{1}{p} d \left( \frac{F p^2 \rho}{r} \right) + \frac{1}{p'} d \left( \frac{F' p'^2 \rho}{r'} \right) = 0 \dots \dots \dots (5).$$

Thus of the four elements, viz. (1) the force  $F$ , (2) the force  $F'$ , (3) the tension  $T$ , (4) the equation to the curve, if any two are given, sufficient equations have now been found to discover the other two.

Ex. 1. A string can be in equilibrium in the form of a given curve under the action of each of two different centres of force. Show that it is in equilibrium under the joint action of both centres of force, and that the tension at any point is equal to the sum of the tensions due to the forces acting separately.

Ex. 2. Prove that a uniform string will be in equilibrium in the form of the curve  $r^2 = 2a^2 \cos 2\theta$  under the action of equal centres of repulsive force situated at the points,  $(a, 0)$ ,  $(-a, 0)$ , the force of each per unit of length at a distance  $R$  being  $\mu/R$ . Prove also that the tension at all points will be the same and equal to  $\frac{2}{3}\mu$ .

[Coll. Ex., 1891.]

**478. String on a surface.** *A string rests on a smooth surface under the action of any forces. To find the position of equilibrium.*

Let the equation to the surface be  $f(x, y, z) = 0$ . Let  $Rds$  be the outward pressure of the surface on the string. Let  $(l, m, n)$  be the direction cosines of the inward direction of the normal. By known theorems in solid geometry,  $l, m, n$  are proportional to the partial differential coefficients of  $f(x, y, z)$  with regard to  $x, y, z$  respectively.

If the equations are required to be in Cartesian coordinates, we deduce them at once from those given in Art. 455 by including  $R$  among the impressed forces. We thus have

$$\left. \begin{aligned} \frac{d}{ds} \left( T \frac{dx}{ds} \right) + X - Rl &= 0 \\ \frac{d}{ds} \left( T \frac{dy}{ds} \right) + Y - Rm &= 0 \\ \frac{d}{ds} \left( T \frac{dz}{ds} \right) + Z - Rn &= 0 \end{aligned} \right\}.$$

We have here one more unknown quantity, viz.  $R$ , than we had in Art. 455 but we have also one more equation, viz. the

the element  $PQ$  is in equilibrium under the action of (1) the forces  $Xds, Yds, Zds$  acting parallel to the axes of coordinates, which are not drawn in the figure, (2) the reaction  $Rds$  along  $NP$ , the tensions at  $P$  and  $Q$ , which have been proved in Art. 454 to be equivalent to  $dT$  along  $PQ$  and  $Tds/\rho$  along  $PC$ .


Resolving these forces along the tangent  $PA$ , we have

$$dT + Xds \frac{dx}{ds} + Yds \frac{dy}{ds} + Zds \frac{dz}{ds} = 0,$$

$$\therefore T + \int (Xdx + Ydy + Zdz) = A \dots\dots\dots(1).$$

The forces are said to be *conservative*, when their components  $X, Y, Z$  are respectively partial differential coefficients with regard to  $x, y, z$ , of some function  $W$  which may be called the work function, Art. 209. Assuming this to be the case, the integral in (1) is equal to the work of the forces. It

follows from this equation that the tension of the string plus the work of the forces is the same at all points of the string. Taking the integral between limits for any two points  $P, P'$  of the string, we see that the difference of the tensions at two points  $P, P'$  is independent of the length or form of the string joining those points and is equal to the difference of the works at the points  $P', P$  taken in reverse order.



It follows from this equation that the tension of the string plus the work of the forces is the same at all points of the string. Taking the integral between limits for any two points  $P, P'$  of the string, we see that the difference of the tensions at two points  $P, P'$  is independent of the length or form of the string joining those points and is equal to the difference of the works at the points  $P', P$  taken in reverse order.

We shall suppose that, while  $\rho$  is measured inwards along  $PC$ , the pressure  $R$  of the surface on the string is measured outwards along  $NP$ , Art. 457. We shall also suppose that  $(l, m, n)$  are the direction cosines of the normal  $PN$  measured inwards. With this understanding we now resolve the forces along the normal  $PN$  to the surface; we find

$$\frac{Tds}{\rho} \cos \chi + Xds l + Yds m + Zds n - Rds = 0.$$

By a theorem in solid geometry, if  $\rho'$  be the radius of curvature of the section of the surface made by the plane  $NP$ , i.e. by

a plane containing the normal to the surface and the tangent to the string, then  $\rho' \cos \chi = \rho$ . We therefore have

$$\frac{T}{\rho} + Xl + Ym + Zn = R \dots\dots\dots (2)$$

It follows from this equation that *the resultant pressure on the surface is equal to the normal pressure due to the tension plus the pressure due to the resolved part of the forces*. The tension at any point  $P$  having been found by (1), the pressure on the surface follows by (2), provided we know the direction of the tangent to the string. This last is necessary in order to find the value of

Lastly, let us resolve the forces along the tangent  $PB$  to the surface. Let  $\lambda, \mu, \nu$  be the direction cosines of  $PB$ . Since  $PN$  is at right angles to both  $PN$  and  $PA$ , these direction cosines may be found from the two equations

$$\lambda f_x + \mu f_y + \nu f_z = 0, \quad \lambda \frac{dx}{ds} + \mu \frac{dy}{ds} + \nu \frac{dz}{ds} = 0.$$

We then have by the resolution

$$\frac{T}{\rho} \sin \chi + X\lambda + Y\mu + Z\nu = 0 \dots\dots\dots (3)$$


**Ex.** An endless string lies along a central circular section of a smooth ellipsoid. Prove that  $b^4 F^2 = T^2 (b^2 - p^2)$ , where  $F$  is the force per unit of length which acts transversely to the string in the tangent plane is required to keep the string in place,  $p$  is the perpendicular from the centre on the tangent plane and  $b$  is the mean semi-axis. [Trin. Coll., 18

**480. Geodesics.** If any portion of the string is not acted on by external forces, we have for that portion  $X = 0, Y = 0, Z = 0$ . The equation (1) then shows that *the tension of the string is constant*. The equation (2) shows that *the pressure at any point is proportional to the curvature of the surface along the string*. The equation (3) (assuming the string not to be a straight line) shows that  $\chi = 0$ , i.e. at every point *the osculating plane of the curve contains the normal to the surface*. Such a curve is called a *geodesic* in solid geometry.

Conversely, if the string rest on the surface in the form

moves along the string the concavity changes from one side of the string to the other. Such a point may be regarded as a point of geodesic inflexion. It follows from the equation (3) that *a string stretched on a surface can have a point of geodesic inflexion only when the force transverse to the string and tangential to the surface is zero.*

**481. A string on a surface of revolution.** When the surface on which the string rests is one of revolution, we can replace the rather complicated equation (3) of Art. 479 by a much simpler one obtained by taking moments about the axis of figure. If also the resultant force on each element is either parallel to or intersects the axis of figure, there is a further simplification. This includes the useful case in which the only force on the string is its weight, and the axis of figure of the surface is vertical.



Let the axis of figure be the axis of  $z$ , and let  $(r, \theta, \phi)$  be the polar coordinates and  $(r', \phi, z)$  the cylindrical coordinates of any point on the string, so that in the figure  $r' = ON$ ,  $z = PN$ , and  $\phi =$  the angle  $NOx$ . Then from the equation to the surface we have  $z = f(r')$ . Let the forces on the element  $ds$  be  $Pds$ ,  $Qds$ ,  $Zds$  when resolved respectively parallel to  $r'$ ,  $r'd\phi$ , and  $z$ .

We shall now take moments about the axis of figure. The moment of  $R$  is clearly zero. To find the moment of  $T$ , we resolve it perpendicular to the axis and multiply the result by the arm  $r'$ . In this way we find that the moment is  $Tr' \sin \psi$ , where  $\psi$  is the angle the tangent to the string makes with the tangent to the generating curve of the surface, i.e.  $\psi$  is the curvilinear angle  $OPA$ . The equation of moments is therefore

$$d(Tr' \sin \psi) + Qr'ds = 0 \dots\dots\dots(4).$$

We also have by resolving along the tangent as in Art. 479



to  $xy$  in  $Q$ . Then  $PQ = PP' \sin \psi$ , i.e.  $r'd\phi = ds \cdot \sin \psi$ . We therefore have

$$(r'd\phi)^2 = \{(dr')^2 + (r'd\phi)^2 + (dz)^2\} \sin^2 \psi \dots\dots\dots(6).$$

Eliminating  $T$  and  $\sin \psi$  between (4), (5) and (6) we have an equation from which the form of the string can be deduced.

If the only force acting on the string is gravity, and if the axis is vertical, the equations take the simple forms

$$Tr' \sin \psi = wB, \quad T = w(z + A) \dots\dots\dots(7).$$

Eliminating  $T$  and  $\sin \psi$ , by help of (6), we have

$$(z + A)^2 r'^2 = B^2 \left\{ 1 + \left( \frac{dr'}{r'd\phi} \right)^2 + \left( \frac{dz}{r'd\phi} \right)^2 \right\} \dots\dots\dots(8).$$

Substituting for  $z$  from the equation of the surface, viz.  $z = f(r')$ , this becomes the polar differential equation of the projection of the string on a horizontal plane. The outward normal pressure of the surface on the string may be deduced from equation (2) of Art. 479.

**482. Heavy string on a sphere.** Using polar coordinates referred to the centre  $O$  as origin, the fundamental equations take the simple forms

$$T \sin \theta \sin \psi = wB', \quad T = w(a \cos \theta + A),$$

$$(\sin \theta d\phi)^2 = \{(\sin \theta d\phi)^2 + (d\theta)^2\} \sin^2 \psi, \quad Ra = w(2a \cos \theta + A),$$

where  $\psi$  is the angle the string makes with the meridian arc drawn through the summit and  $B = aB'$ . These give as the differential equation \* of the string

$$\left( \frac{d\theta}{d\phi} \right)^2 + \sin^2 \theta = \sin^4 \theta \left( \frac{a \cos \theta + A}{B'} \right)^2.$$

The tension at any point  $P = wz$  where  $z$  is the altitude of  $P$  above a fixed horizontal plane called the directrix plane, and every point of the string must be above this plane. The plane is situated at a depth  $A$  below the centre of the sphere. At each point  $P$  let the normal  $OP$  be produced to cut in some point  $S$  a concentric sphere whose radius is twice that of the given sphere. The point  $S$  is the anti-centre of  $P$ , and the outward pressure on the string is  $wz'/a$  where  $z'$  is the altitude of  $S$  above the directrix plane. As already explained every anti-centre must lie above or below the directrix plane according as the string lies on the convex or concave side of the sphere, Art. 460.

The values of the constants  $A, B$  depend on the conditions at the ends of the string. We see that  $B' = 0$ , (1) if either end is free, for then  $T$  vanishes at that end, (2) if the string pass through the summit of the sphere, for then  $\sin \theta$  vanishes, (3) if a meridian can be drawn from the summit to touch the sphere, for  $\sin \psi = 0$  at the point of contact. In all these cases,  $\sin \psi$  vanishes throughout the string,

equations yield only two available values of  $\cos \theta$ ; for tracing the two curves a common abscissa is  $\xi = \cos \theta$  and whose ordinates are the reciprocals of the values of  $T$ , we have an ellipse and a rectangular hyperbola, which, since  $T$  must be positive, give only two intersections. Let  $\theta = \alpha$ ,  $\theta = \beta$  be the meridian distances of the highest and lowest points of the string, both being positive. Then

$$-\frac{2A}{a} = \frac{\sin 2\alpha - \sin 2\beta}{\sin \alpha - \sin \beta}, \quad -\frac{B'}{a} = \sin \alpha \sin \beta \frac{\cos \alpha - \cos \beta}{\sin \alpha - \sin \beta}.$$

It follows that the directrix plane passes through the centre of the sphere when  $\alpha$  and  $\beta$  are complementary. In general the tensions, and therefore the depths of the directrix plane below the highest and lowest points, are inversely as the distances of these points of the string from the vertical diameter.

It has been proved in Art. 480, that the string can have a point of geodesic equilibrium when the transverse tangential force is zero. This requires that the meridian drawn from the summit should touch the string, and this, we have already seen, cannot occur. It follows that *the string must be concave throughout its length on the same side.*

When the form of the string is a circle its plane must be either horizontal or vertical, and in the latter case it must pass through the centre of the sphere. To prove this we trace the string a virtual displacement without changing its form, it is easy to see that the altitude of the centre of gravity can be a max-min only in the cases mentioned. In both cases the altitude is a maximum and the equilibrium is therefore unstable. Art. 218. In the same way it may be shown that *any position of equilibrium of a heavy free string on a smooth sphere is unstable.*

1. A heavy uniform chain, attached to two fixed points on a smooth sphere, is drawn up just so tight that the lowest point just touches the sphere. Show that the pressure at any point is proportional to the vertical height of the point above the lowest point of the string. [Coll. Ex., 1892.]

2. A string rests on a smooth sphere, cutting all the sections through a vertical diameter at a constant angle. Show that it would so rest if acted on by a force varying inversely as the square of the distance from the given diameter, and that the tension varies inversely as that distance. [Coll. Exam., 1884.]


3. A string can rest under gravity on a sphere in a smooth undulating groove lying between two small circles whose angular distances from the highest point of the sphere are complementary, without pressing on the sides of the groove. Prove that the acute angle at which the string cuts the vertical meridian is such that the points at which  $\psi$  is a minimum occur at angular distances  $\frac{1}{4}\pi$  from the highest point and find the value of  $\psi$  at these points. [Math. T., 1889.]

**3. String on a Cylindrical Surface.** Ex. 1. A heavy string is in equilibrium on a cylindrical surface whose generators are vertical, the extremities of the string being attached to two fixed points on the surface. Find the circumstances of equilibrium.

Let  $PQ = ds$  be any element,  $w ds$  its weight. Let the axis of  $z$  be parallel to the generators, and let  $s$  be measured in the direction opposite to gravity. Resolving

along a tangent to the string, we have as in (1) Art. 479,  $T - wz = A$ . Resolved vertically, we have by Art. 478,  $\frac{d}{ds} \left( T \frac{dz}{ds} \right) - w = 0$ . These are the same

equations to determine the equilibrium of a heavy string in a vertical plane. The constants, also, of integration are determined by the same conditions in each case. We see therefore that *if the cylinder is developed on a vertical plane, the equilibrium of the string is not disturbed*. The circumstances of the equilibrium may therefore be deduced from the ordinary properties of a catenary.



To find the pressure on the cylinder, we either resolve along the normal at  $P$  to the surface, or quote the general found in Art. 479. We thus find  $R = T/\rho'$ , also  $\frac{1}{\rho'} = \frac{\cos^2 \psi}{\rho_1} + \frac{\sin^2 \psi}{\infty} = \frac{\cos^2 \psi}{\rho_1}$ . Euler's theorem on curvature, where  $\rho_1$  is the radius of curvature at  $M$  section  $AMN$  of the cylinder made by a horizontal plane, and  $\psi$  is the angle the tangent at  $P$  to the string makes with the horizontal plane.

Ex. 2. If a string be suspended symmetrically by two tacks upon a vertical cylinder, and if  $z_1, z_2, z_3 \dots$  be the distances above the lowest point of the catenary at which the string crosses itself, then  $z_1 z_{2n+1} = (z_{n+1} - z_n)^2$ . [Math. Tripos, 1885.]

Ex. 3. If an endless chain be placed round a rough circular cylinder, and pulled at a point in it parallel to the axis, prove that, if the chain be on the verge of slipping, the curve formed by it on the cylinder when developed will be a parabola, and find the length of the chain when this takes place. [Math. Tripos, 1885.]

Ex. 4. A heavy uniform string rests on the surface of a smooth right circular cylinder, whose radius is  $a$  and whose axis is horizontal. If  $(a, \theta, z)$  be the cylindrical coordinates of a point on the string,  $\theta$  being measured from the vertical, prove that

$$T = w(b + a \cos \theta), \quad z = \int \frac{acd\theta}{\{(b + a \cos \theta)^2 - c^2\}^{\frac{1}{2}}}, \quad \text{where } b \text{ and } c \text{ are two constants.}$$

It is clear that the tension resolved parallel to  $z$  is constant, i.e.  $T dz/ds$  is constant. Combining this result with the value of  $T$  found in Art. 483, Ex. 1, we obtain the second result in the question.

Ex. 5. The extremities of a heavy string are attached to two small rings which can slide freely on a rod which is placed along the highest generator of a circular horizontal cylinder, and are held apart by two forces each equal to  $wL$ . If the lowest point of the string just reaches to a level with the axis of the cylinder, and if  $a$  be the distance between the rings and  $L$  the length of the string, prove that

$$\frac{D}{4a} = \int \frac{d\psi}{\sqrt{(3 + \sin^2 \psi)}}, \quad \frac{L}{8a} = \int \frac{d\psi}{\sqrt{(3 + \sin^2 \psi)} \frac{1}{1 + \sin^2 \psi}},$$

string at any point to the axis is  $\sec^{-1}(1+z/a)$ , where  $z$  is the height of the point above the axis, supposing the string cuts the highest generator at an angle of  $60^\circ$ .

[June Exam.]

Ex. 7. A heavy uniform string has its two ends fastened to points in the highest generator of a smooth horizontal cylinder of radius  $a$ , and is of such a length that its lowest point just touches the cylinder. Prove that, if the cylinder be developed, the origin being at one of the fixed points, the curve on which the string lay is given by  $c^2 \left( \frac{dy}{dx} \right)^2 = a^2 \cos^2 \frac{y}{a} + 2ac \cos \frac{y}{a}$ . [Math. T., 1883.]

**484. String on a right cone.** Ex. 1. A string has its extremities attached to two fixed points on the surface of a right cone, and is in equilibrium under the action of a centre of repulsive force  $F$  at the vertex. Show that the equilibrium is not disturbed by developing the cone and string on a plane passing through the centre of force.

Let the vertex  $O$  be the origin,  $(r', \theta', z)$  the cylindrical coordinates of any point  $P$  on the string. Let  $OP=r$ . Taking moments about the axis and resolving along the tangent, we have as in Art. 481,

$$Tr' \sin \psi = B, \quad T + \int F dr = C \dots\dots\dots(1).$$

We may imagine the cone divided along a generator and together with the string on its surface unwrapped on a plane. Let  $(r, \theta)$  be the polar coordinates of the position of  $P$  in this plane. Let  $p$  be the perpendicular from  $O$  on the tangent to the unwrapped string, then  $p = r \sin \psi$ . The equations (1) become

$$Tp = B', \quad T + \int F dr = C \dots\dots\dots(2).$$

These are the equations of equilibrium of a string in one plane under the action of a central force, and the constants of integration are determined by the same conditions in each case. We may therefore transfer the results obtained in Art. 474 to the string on the cone. In transferring these results we notice that the point  $(r, \theta)$  on the plane corresponds to  $(r'\theta'z)$  on the cone, where  $r' = r \sin \alpha$ ,  $\theta' \sin \alpha = \theta$ ,  $z = r \cos \alpha$ .

The pressure  $R$  is given by  $R = \frac{T}{\rho'} = \frac{\sin \phi}{r'^2} \cdot \frac{B \cos \alpha}{\sin^2 \alpha}$ , since  $\frac{1}{\rho'} = \frac{\cos^2 \phi}{\omega} + \frac{\sin^2 \phi}{r' \sec \alpha}$  by Euler's theorem on curvature. Art. 479.

Ex. 2. The two extremities of a string, whose length is  $2l$ , are attached to the same point  $A$  on the surface of a right cone. The equation to the projection of the string on a plane perpendicular to the axis is  $\pi r' = l \cos(\theta' \sin \alpha)$ , the point  $A$  being given by  $\theta' = \pi$ . Show that the string will rest in equilibrium under the influence of a centre of force in the vertex varying inversely as the cube of the distance.

Ex. 3. A heavy uniform string has its ends fastened to two points on the surface of a right circular cone whose axis is vertical and vertex upwards, the string lying on the surface of the cone. Prove that, if the cone be developed into a plane, the curve on which the string lay is given by  $p(a+br)=1$ , the

The required conditions may be deduced from the equilibrium of a smooth surface by introducing the limiting friction. The pressure of the surface on the element  $ds$  being  $Rds$ , the limiting friction will be  $\mu Rds$ . This friction acts in some direction lying in the tangent plane to the surface. See figure of Art. 479. Let  $\psi$  be the angle  $SPA$ . Resolving along the principal axis at any point of the string exactly as in Art. 479, we have

$$\left. \begin{aligned} dT + Xdx + Ydy + Zdz + \mu Rds \cos \psi &= 0 \\ \frac{T}{\rho'} + Xl + Ym + Zn - R &= 0 \\ \frac{T}{\rho'} \tan \chi + X\lambda + Y\mu + Z\nu + \mu R \sin \psi &= 0 \end{aligned} \right\}.$$

These three equations express the conditions of equilibrium.

**486.** The simplest case is that in which the applied forces can be neglected compared with the tension. We then have putting zero for  $X, Y, Z$ ,

$$\left. \begin{aligned} \frac{dT}{ds} + \mu R \cos \psi &= 0 \\ \frac{T}{\rho'} &= R \\ \frac{T}{\rho'} \tan \chi + \mu R \sin \psi &= 0 \end{aligned} \right\}.$$

It easily follows from these equations that  $\tan \chi + \mu \sin \psi = 0$ . This requires that  $\tan \chi$  should be less than  $\mu$ ; thus equilibrium is impossible if the string be placed on the surface so that the osculating plane at any point makes an angle with the normal greater than  $\tan^{-1} \mu$ . Eliminating  $\psi$  and  $R$  from these equations

$$\frac{dT}{ds} + \frac{T}{\rho'} (\mu^2 - \tan^2 \chi)^{\frac{1}{2}} = 0,$$

$$\therefore \log T = C - \int \frac{ds}{\rho'} (\mu^2 - \tan^2 \chi)^{\frac{1}{2}}.$$

Thus, when the string is laid on the surface in a given form and is bordering on motion, the tension at any point can be found

If a light string rest on a rough surface in a state bordering on motion, and the form of the string be a geodesic, then (1) the friction at any point acts along the tangent to the string, and (2) the ratio of the tensions at any two points is equal to  $e$  to the power of  $\pm \mu$  times the sum of the infinitesimal angles turned through by the tangent which moves from one point to the other.

The conditions of equilibrium of a string on a rough surface are given in Jellett's *Theory of Friction*. He deduces from these the equations obtained in Art. 486.

**487.** Ex. 1. A fine string of inconsiderable weight is wound round a rigid circular cylinder in the form of a helix, and is acted on by two forces  $F, F'$  at its extremities. Show that, when the string borders on motion,  $\log \frac{F'}{F} = \pm \mu \frac{\cos^2 \alpha}{a}$  where  $s$  is the length of the string in contact with the cylinder,  $a$  the angle of the helix and  $a$  the radius of the cylinder.

Since the helix is a geodesic, this result follows from the equations of Art. 486 by writing for  $1/\rho'$  its value  $\cos^2 \alpha/a$  given by Euler's theorem on curvature.


Ex. 2. A heavy string  $AB$ , initially without tension, rests on a rough horizontal plane in the form of a circular arc. Find the least force  $F$  which, applied along a tangent at one extremity  $B$ , will just move the string.

Let  $O$  be the centre of the arc, let the angle  $\angle AOP = \theta$ , the arc  $AP = s$ . Let the element  $PQ$  of the string begin to move in some direction  $PP'$ , where  $P'PQ = \psi$ ; then by the nature of friction the angle  $\psi$  must be less than a right angle. The friction at  $P$  therefore acts in the opposite direction, viz.  $P'P$ , and is equal to  $\mu v ds$ . The equations of equilibrium are

$$\left. \begin{aligned} dT - \mu v ds \cos \psi &= 0 \\ T d\theta - \mu v ds \sin \psi &= 0 \end{aligned} \right\} \dots\dots\dots(1).$$

Substituting in the first equation the value of  $T$  given by the second, we have, since  $ds = a d\theta$ ,  $d\psi = d\theta$ , and therefore  $\psi = \theta + C \dots\dots\dots(2).$

We have by substituting in (1)  $T = \mu v a \sin(\theta + C).$



If every element of the string border on motion, the equations (1) hold throughout the length. Since  $T$  must be zero when  $\theta = 0$ , we find that  $C = 0$ . Hence,  $aa$  be the given length of the string  $AB$ , the force required to just move it is given by  $F = \mu v a \sin a$ . It is evident that this result does not hold if the length of the string exceed a quadrant, for then  $\psi$  at the elements near  $B$  would be greater than a right angle.

Supposing the arc  $AB$  to be greater than a quadrant, let the force  $F$  acting at  $B$  increase gradually from zero. When  $F = \mu v a \sin a$ , where  $a < \frac{1}{2}\pi$ , it follows from what precedes that a finite arc  $EB$ , terminating at  $B$  and subtending at  $O$  an angle  $EOB$  equal to  $a$ , is bordering on motion, and that the tension at  $E$  is zero. When  $F = \mu v a$  the resolved part of the tension at  $B$  along the normal is  $\mu v a d\theta$ , and is just

uming up, the force required to move the string is  $P = \mu aw \sin \alpha$  if the  
 han a quadrant. If the length exceed a quadrant, the force is  $\mu aw$ ,  
 egin to move at the extremity at which the force is applied. See A

Ex. 3. If a weightless string stretched by two weights lie in one plane a  
 rough sphere of radius  $a$ , show that the distance of the plane from the  
 cannot exceed  $a \sin \epsilon$ , where  $\epsilon$  is the angle of friction. [St John's Coll.

**488. Virtual Work.** The equations of equilibrium of a string r  
 deduced from the principle of virtual work by taking each element separate  
 following the general method indicated in Art. 203. In fact the left-hand  
 the  $x$  equation given in Art. 455, after multiplication by  $ds \cdot dx$ , is the  
 moment resulting from a displacement  $dx$ . This method requires that the t  
 at the ends of the element should be included as part of the impressed force  
 principle may also be expressed as a max-min condition (Art. 212) in  
 which includes only the given external forces. As an example of this  
 consider the following problem.

A heterogeneous string of given length  $l$ , fixed at its extremities  $A, B$ , is  
 equilibrium in one plane in a field of force whose potential is  $V$ . It is req  
 find the form of the string.

Supposing  $m = f(s)$  to be the line density at a point whose arc distance  
 is  $s$ , the work function for the whole string is  $\int V m ds$ , the limits being 0 to  
 shall take the arc  $s$  as the independent variable and regard  $x, y$  as two func  
 $s$  connected by the equation

$$\left(\frac{dx}{ds}\right)^2 + \left(\frac{dy}{ds}\right)^2 = 1 \dots\dots\dots$$

Following Lagrange's rule we remove the restriction (1) and make

$$u = \int \left\{ V m + \lambda \left( \left(\frac{dx}{ds}\right)^2 + \left(\frac{dy}{ds}\right)^2 - 1 \right) \right\} ds \dots\dots\dots$$

a max-min for all variations of  $x$  and  $y$ , the quantity  $\lambda$  being an arbitrary fun  
 of  $s$ , afterwards chosen to make the resulting values of  $x, y$  satisfy the conditio

As the limits are fixed, there is no obvious advantage in varying all the  
 nates. We shall therefore take the variation of  $u$  on the supposition that  $\lambda$   
 variable and  $s$  constant. We have

$$\delta u = \int \left\{ m \left( \frac{dV}{dx} \delta x + \frac{dV}{dy} \delta y \right) + 2\lambda \left( \frac{dx}{ds} \frac{d\delta x}{ds} + \frac{dy}{ds} \frac{d\delta y}{ds} \right) \right\} ds.$$

Integrating the third and fourth terms by parts and remembering that  
 vanish at the fixed ends of the string, we find

$$\delta u = \int \left\{ \left( m \frac{dV}{dx} - 2 \frac{d}{ds} \left( \lambda \frac{dx}{ds} \right) \right) \delta x + \left( m \frac{dV}{dy} - 2 \frac{d}{ds} \left( \lambda \frac{dy}{ds} \right) \right) \delta y \right\} ds.$$

At a max-min, this must be zero for all values of  $\delta x, \delta y$ , hence

$$\frac{dV}{dx} - 2 \frac{d}{ds} \left( \lambda \frac{dx}{ds} \right) = 0, \quad \frac{dV}{dy} - 2 \frac{d}{ds} \left( \lambda \frac{dy}{ds} \right) = 0$$

may be determined as functions of  $s$ . It is evident that these agree with the equations already found in Art. 455, with  $-2\lambda$  written for  $T$ .

We may also deduce the value of  $\lambda$  by multiplying the equations (3) respectively by  $dx/ds$  and  $dy/ds$  and adding. We then find

$$m \frac{dV}{ds} = \frac{1}{\lambda} \frac{d}{ds} \lambda^2 \left\{ \left( \frac{dx}{ds} \right)^2 + \left( \frac{dy}{ds} \right)^2 \right\} = 2 \frac{d\lambda}{ds},$$

which agrees with the equation to determine the tension in Art. 479.

If the string is in three dimensions and constrained to rest on a smooth surface, we make  $\int V m ds$  a max-min subject to the two conditions

$$x'^2 + y'^2 + z'^2 - 1 = 0, \quad F(x, y, z) = 0 \dots \dots \dots (I),$$

where accents denote differentiations with regard to  $s$ . Following the same method as before we make

$$u = \int \{ Vm + \lambda (x'^2 + y'^2 + z'^2 - 1) + \mu F(x, y, z) \} ds$$

a max-min. Varying only  $x, y, z$  and integrating by parts exactly as before, we find on equating the coefficients of  $\delta x, \delta y, \delta z$  to zero

$$m \frac{dV}{dx} - 2 \frac{d}{ds} \left( \lambda \frac{dx}{ds} \right) + \mu \frac{dF}{dx} = 0, \quad \&c. = 0, \quad \&c. = 0 \dots \dots \dots (II),$$

the two latter equations being obtained from the first by writing  $y$  and  $z$  respectively for  $x$ . These three equations joined to the conditions (I) determine  $x, y, z, \lambda, \mu$  in terms of  $s$ . These agree with the equations obtained in Art. 478, when  $-2\lambda$  and  $-\mu (F_x^2 + F_y^2 + F_z^2)^{\frac{1}{2}}$  are written for  $T$  and  $R$ .

**489. Elastic Strings.** The theory of elastic strings depends on a theorem which is usually called *Hooke's law*. This may be briefly enunciated in the following manner. Let an extensible string uniform in the direction of its length have a natural length  $l_1$ . Let this string be stretched by the application of two forces at its extremities, and let these forces be each equal to  $T$ . Let the stretched length of the string be  $l$ . Then it is found by experiment that the extension  $l - l_1$  bears to the force  $T$  a ratio which is constant for the same string.

If the natural or unstretched length of the string were doubled so as to be  $2l_1$ , the force  $T$  being the same as before, it is clear that each of the lengths  $l_1$  would be stretched exactly as before to a length  $l$ . The extension of this string of double length will therefore be twice that of the single string. More generally, we infer that the extension must be proportional to the natural length when the stretching force is the same.



the same extension that each string alone would require. It follows that the force required to produce a given extension is proportional to the area of the section of the unstretched string. The coefficient  $E$  is therefore proportional to the area of the section of the string when unstretched. The value of  $E$  when referred to a sectional area equal to the unit of area is called *Young's modulus*.

To find the meaning of the constant  $E$ , let us suppose that the string can be stretched to twice its natural length without violating Hooke's law. We then have  $l = 2l_1$ , and therefore  $E = T$ . Thus  $E$  is a force, it is the force which would theoretically stretch the string to twice its natural length.

**490.** This law governs the extension of other substances besides elastic strings. It applies also to the compression and elongation of elastic rods. It is the basis of the mathematical theory of elastic solids. But at present we are not concerned with its application except to strings, wires, and such like bodies.

The law is true only when the extension does not exceed certain limits, called the limits of elasticity. When the stretching is too great the body either breaks or receives such a permanent change of structure that it does not return to its original length when the stretching force is removed. In all that follows, we shall suppose this limit not to be passed.

The reader will find tables of the values of Young's modulus and the limits of elasticity for various substances given in the article *Elasticity*, written by Sir W. Thomson (Lord Kelvin), for the *Encyclopædia Britannica*.

**491. Ex. 1.** A uniform rod  $AB$ , suspended by two equal vertical elastic strings, rests in a horizontal line; a fly alights on the rod at  $C$ , its middle point, and the rod is thereupon depressed a distance  $h$ ; if the fly walk along the rod, then when he arrives at  $P$ , the depression of  $P$  below its original level is  $2h(AP^2 + BP^2)/AB^2$ , and the depression of  $Q$ , any other point of the rod, is  $2h(AP \cdot AQ + BP \cdot BQ)/AB^2$ .

[St John's Coll., 1887.]

**Ex. 2.** A heavy lamina is supported by three slightly extensible threads, whose unstretched lengths are equal, tied to three points forming a triangle  $ABC$ . Show that when it assumes its position of equilibrium the plane of the lamina will meet what would be its position in case the threads were inelastic in the line whose areal equation is  $xx_1/E + yy_1/F + zz_1/G = 0$ , where  $E, F, G$  are the moduli and  $x, y, z$

*492. A uniform heavy elastic string is suspended by one extremity and has a weight  $W$  attached to the other extremity. Find the position of equilibrium and the tension at any point.*

Let  $OA_1$  be the unstretched string,  $P_1Q_1$  any element of length. Let  $OA$  be the stretched string,  $PQ$  the corresponding position of  $P_1Q_1$ . Let  $w$  be the weight of a unit of length of unstretched string,  $l_1 = OA_1$ ,  $x_1 = OP_1$ ;  $l = OA$ ,  $x = OP$ . The tension  $T$  at  $P$  clearly supports the weight of  $PA$  and  $W$ . Hence

$$T = w(l_1 - x_1) + W \dots \dots \dots (1).$$

If  $PA$  were equally stretched throughout we could apply Hooke's law to the finite length  $PA$ . But as this is not the case we must apply the law to an elementary length  $PQ$ . We have therefore

$$dx - dx_1 = dx_1 \epsilon T \dots \dots \dots (2)$$

where  $\epsilon$  has been written for the reciprocal of  $E$ .

Eliminating  $T$ , 
$$\frac{dx}{dx_1} = 1 + \epsilon \{w(l_1 - x_1) + W\}.$$

Integrating, 
$$x = x_1 + \epsilon \{w(l_1 x_1 - \frac{1}{2} x_1^2) + W x_1\} + C.$$

The constant  $C$  introduced in the integration is clearly zero, since  $x_1$  and  $x$  must vanish together. Putting  $x_1 = l_1$ , we find

$$l - l_1 = \frac{1}{2} \epsilon \cdot w l_1^2 + \epsilon W l_1.$$

If the string had no weight, the extension due to  $W$  would be  $\epsilon W l_1$ . If there were no weight  $W$  at the lower end, the extension would be  $\frac{1}{2} \epsilon w l_1^2$ . Hence the extension due to the weight of the string is equal to that due to half its weight attached to the lowest point. We also see that the extension due to the weight of the string and the attached weight is the sum of the extensions due to each of them treated separately.

Ex. 1. A heavy elastic string  $OA$  placed on a rough inclined plane and the line of greatest slope is attached by one extremity  $O$  to a fixed point, and the weight  $W$  fastened to the other extremity  $A$ . Find the greatest length of the stretched string consistent with equilibrium.

line of greatest slope. Supposing the inclination of the plane to be less than  $\tan^{-1} \mu$ , find the greatest length to which the string could be stretched consistent with equilibrium. Compare also the stretching of the different elements of the string.

The frictions near the lower end  $A$  of the string will act down the plane, and those near the upper end  $A'$  will act up the plane. There is some point  $O$  separating the string into two portions  $OA$ ,  $OA'$  in which the frictions act in opposite directions. Each of these portions may be treated separately by the method used in the preceding example. An additional equation, necessary to find the unstretched length  $z$  of the string, is obtained by equating the tensions at  $O$  due to the two portions. The result is

$$z = \frac{l_1}{2} \left( 1 - \frac{\tan \alpha}{\mu} \right), \quad l - l_1 = \frac{1}{2} \epsilon \mu v \cos \alpha l_1^2 \left( 1 - \frac{\tan^2 \alpha}{\mu^2} \right).$$

✓ Ex. 3. A series of elastic strings of unstretched lengths  $l_1, l_2, l_3, \dots$  are fastened together in order, and suspended from a point,  $l_1$  being the lowest. Show that the total extension is

$$\frac{1}{2} (\epsilon_1 w_1 l_1^2 + \epsilon_2 w_2 l_2^2 + \dots) + w_1 l_1 (\epsilon_2 l_2 + \epsilon_3 l_3 + \dots) + w_2 l_2 (\epsilon_3 l_3 + \dots) + \&c.,$$

where  $w_1, w_2, \&c.$  are the weights per unit of length of unstretched string,  $\epsilon_1, \epsilon_2, \&c.$  the reciprocals of the moduli of elasticity. [Coll. Exam., 1895.]

493. **Work of an elastic string.** If the length of a homogeneous elastic string be altered by the action of an external force, the work done by the tension is the product of the compression of the string and the arithmetic mean of the initial and final tensions.

In the standard case let the length be increased from  $a$  to  $a'$ ; then  $a - a'$  is the shortening or compression of the string. Before, let  $l_1$  be the unstretched or natural length.

By referring to Art. 197, we see that the work required is

$$- \int T dl = - \int E \frac{l - l_1}{l_1} dl = - E \frac{(a' - l_1)^2 - (a - l_1)^2}{2l_1},$$

the limits of the integral being from  $l = a$  to  $l = a'$ . This result may be put into the form  $\frac{1}{2} (T_1 + T_2) (a - a')$ , where  $T_1$  and  $T_2$  represent the values of  $T$  when  $a$  and  $a'$  are written for  $l$ . The rule follows immediately. See the author's *Rigid Dynamics* 1895.

This rule is of considerable use in dynamics where the length of the string undergoes many changes in the course of the motion. It is important to notice that the rule holds even if the string becomes slack in the interval, provided it is tight in the initial and final states. If the string is slack in either terminal state, we may still use the same rule provided we suppose the string to have its natural

1, so that when the string (of length  $a$ ) is just taut it shall be vertical. Show the work which must be spent in turning the wheel so as just to lift the mass from the ground is  $Mga + Ea \log E/(E + Mg)$ , where  $E$  is the tension which would stretch the string to length  $a$ , neglecting the weight of the string. [Math. Tripos.]

3. A disc of radius  $r$  is connected by  $n$  parallel equal elastic strings, of unstretched length  $l_1$ , to an equal fixed disc; the wrench necessary to maintain the discs at a distance  $x$  apart with the moveable one turned through an angle  $\theta$  about a common axis, consists of a force  $X$  and a couple  $L$  given by

$$X = nE x \left( \frac{1}{l_1} - \frac{1}{\xi} \right), \quad L = 2nEr^2 \sin \theta \left( \frac{1}{l_1} - \frac{1}{\xi} \right),$$

$$\xi^2 = x^2 + 4r^2 \sin^2 \frac{1}{2} \theta.$$

[Coll. Exam., 1885.]

The disc being moved to a distance  $x$  from the other and turned round through an angle  $\theta$ , we first show that the length of each string is changed from  $l_1$  to  $\xi$ . By the rule above, the work function is  $W = n \cdot \frac{1}{2} T (\xi - l_1) = nE (\xi - l_1)^2 / 2l_1$ .

In Art. 208 we have  $Xdx + Ld\theta = \frac{dW}{dx} dx + \frac{dW}{d\theta} d\theta$ .

Effecting the differentiations  $X = dW/dx$ ,  $L = dW/d\theta$ , we obtain the results given.

**4. Heavy elastic string on a smooth curve.** Ex. 1. A heavy elastic string is stretched over a smooth curve in a vertical plane: show that the difference between the values of  $T + T^2/2E$  at any two points of the string is equal to the weight of a portion of the string whose unstretched length is the vertical distance between the points. It follows from this theorem that any two points at which the tensions are equal are on the same level.

If  $ds_1$  is the unstretched length of any element  $ds$  of the string, we have by Hooke's law  $ds_1 = dsE/(T + E)$ . If then  $w$  is the weight per unit of unstretched length, the weight of any element  $ds$  of the stretched string is equal to  $w'ds$ , where  $w' = wE/(T + E)$ . Let us now form the equations of equilibrium, using the same method and reasoning as in Art. 459, where a similar problem is discussed for an inextensible string. We evidently arrive at the same equations (1) and (2) with  $w'$  instead of  $w$ . Substituting for  $w'$  and integrating, we find that (1) leads to the result given above.

2. A heavy elastic string is stretched on a smooth curve in a vertical plane:

$$\text{that} \quad T + \frac{T^2}{2E} = wy, \quad R\rho - \frac{T^2}{2E} = wy',$$

where  $T$  is the tension at any point  $P$ ,  $R$  the outward pressure of the curve on the string per unit of length of unstretched string,  $w$  the weight of a unit of length of unstretched string, and  $y, y'$  the altitudes of  $P$  and its anti-centre above a fixed horizontal line called the *statical directrix* of the string, Art. 460. Show also that the free ends of the string can be below the directrix, and that the free ends, if there are any, must lie on it.

equation  $\left(\frac{dy}{ds}\right)^2 = \frac{b}{2y+b}$ , where  $y$  is the vertical height above the free extremity and  $b$  the natural length of a portion of the string whose weight is the coefficient of elasticity. If the natural length of each vertical portion be  $l$ , and if  $(l+b)^2 = 2ab$  and if the curve be a circle of radius  $a$ , prove that the natural length of the portion in contact with the curve is  $2\sqrt{ab} \log(\sqrt{2}+1)$ . [June Exam., 1891]

X Ex. 5. An elastic string, uniform when unstretched, lies at rest in a smooth circular tube under the action of an attracting force ( $\mu r$ ) tending to a centre on the circumference of the tube diametrically opposite to the middle point of the string. If the string when in equilibrium just occupies a semicircle, prove that the greatest tension is  $\{\lambda(\lambda + 2\mu\rho a^2)\}^{\frac{1}{2}} - \lambda$ , where  $\lambda$  is the modulus of elasticity,  $a$  the radius of the tube,  $\rho$  the mass of a unit of length of the unstretched string. [Trinity Coll., 1891]

Ex. 6. An infinite elastic string, whose weight per unit of length when unstretched is  $m$ , and which requires a tension  $ma$  to stretch any part of it to double its length (when on a smooth table), is placed on a rough table (coefficient of friction  $\mu$ ) along a straight line perpendicular to its edge. The string just reaches the edge, which is smooth. A weight  $\frac{1}{2}ma\mu$  is attached to the end and let hang over the edge. In equilibrium the weight takes up its position of rest quietly, so that no part of the string re-contacts the table after having been once stretched, show that the distance of the weight below the edge of the table is  $\frac{1}{3}a\mu(3\mu+4)$ , and that beyond a distance  $\frac{1}{2}a(\mu+2)$  from the edge of the table the string is unstretched. [Trinity Coll., 1891]

✓ 495. **Light elastic string on a rough curve.** Ex. 1. An elastic string of modulus  $\lambda$  is stretched over a rough curve so that all the elements border on motion. No external forces act on the string except the tensions  $F, F'$  at its extremities, and the weight  $w$ . Prove that  $\frac{F'}{F} = e^{\pm\mu\psi}$ , where  $\psi$  is the angle between the normals to the curve at its extremities. This follows by the same reasoning as in Art. 463.

X Ex. 2. An elastic string (modulus  $\lambda$ ) is stretched round a rough circular cylinder so that every element of it is just on the point of slipping; if  $T, T'$  are the tensions at its extremities, the ratio of the stretched to the unstretched length is

$$\log \frac{T'}{T} : \log \frac{T'(T+\lambda)}{T(T'+\lambda)}. \quad [\text{St John's Coll., 1891}]$$

Ex. 3. An endless cord, such as a cord of a window blind, is just long enough to pass over two very small fixed pulleys, the parts of the cord between the pulleys being parallel. The cord is twisted, the amount of twisting or torsion being different in the two parts, and the portions in contact with the pulleys being untwisted. If the pulleys be made to turn slowly through a complete revolution of the string, show that the quotient of the difference by the sum of the torsions decreased in the ratio  $e^4 : 1$ . [Math. Tripos, 1891]

✓ Ex. 4. An elastic band, whose unstretched length  $= 2a$ , is placed round four rough pegs  $A, B, C, D$ , which constitute the angular points of a square of side  $a$ .

es,  $\mu$  the coefficient of friction, and  $T$  the tension with which the strap is on. [Math. Tripos, 1879.]

x. 6. A rough circular cylinder (radius  $a$ ) is placed with its axis horizontal, a string, whose natural length is  $l$ , is fastened to a point  $Q$  on the highest part of the cylinder and to an external point  $P$  at a distance  $l$  from  $Q$ ,  $PQ$  being horizontal and perpendicular to the axis of the cylinder; the cylinder is then slowly rolled upon its fixed axis in the direction away from  $P$ ; show that the string will be continually along the whole of the length in contact with the cylinder until the natural length of the part wound up  $= a/\mu$ , when all slipping will cease, and up to this stage the relation between  $S$  and  $\theta$  (the angle turned through by the cylinder) is  $le^{\mu\phi} = (l - a\phi)e^{\mu\theta} + a\phi$ , where  $S = a\phi$ . [Coll. Exam., 1880.]

496. **Elastic string, any forces.** *To form the equations of equilibrium of an elastic string under the action of any forces.*

Let  $ds_1$  be the unstretched length of any element  $ds$  of the string. Then by Hooke's law  $ds = ds_1(T + E)/E$ . The forces on an element, due to the attraction of other bodies, will be proportional to the unstretched length. Let then the resolved parts of these forces along the principal axes of the string be  $Fds_1$ ,  $Gds_1$ ,  $Hds_1$ , as in Art. 454. The equations of equilibrium (1), (2), and (3) of that article are obtained by equating to zero the resolved parts of the forces along the principal axes of the curve; these equations will therefore apply to the elastic string if we replace  $Gds$ ,  $Hds$ , by  $Fds_1$ ,  $Gds_1$ ,  $Hds_1$ . The equations of equilibrium of the elastic string may therefore be derived from those for an inextensible string by treating the forces as

$$Fds \frac{E}{T + E}, \quad Gds \frac{E}{T + E}, \quad Hds \frac{E}{T + E},$$

reducing all the impressed forces in the ratio  $E : T + E$ .

497. Suppose, for example, that the string rests on any smooth surface. The equation along the tangent to the string (as in Art. 479) gives

$$\left(1 + \frac{T}{E}\right) dT + Xdx + Ydy + Zdz = 0. \quad \therefore T + \frac{T^2}{2E} + \int (Xdx + Ydy + Zdz) = C.$$

It follows that  $T + T^2/2E$  + the work function of the forces is constant along the length of the string, Art. 479.

x. *When gravity is the only force acting, show that the equations of equi-*

anti-centre  $S$  above a certain horizontal plane,  $\theta$  the angle the vertical makes with the plane containing the normal to the surface and the tangent to the string, and  $w$  the weight of a unit of unstretched length. If  $PS$  be a length measured outwards along the normal to the surface equal to the radius of curvature of a normal section of the surface drawn through the tangent at  $P$  to the string,  $S$  is the anti-centre of  $P$ .

If the surface is one of revolution with its axis vertical, we replace the third equation by  $Tr' \sin \psi = B$ , where  $r'$  is the distance of  $P$  from the axis of the surface,  $\psi$  the angle the tangent to the string makes with the meridian and  $B$  is a constant. See Art. 481.

**498.** To take another example, suppose that the elastic string is under the action of a central force. Taking moments about the centre of force, and resolving along the tangent to the string, we find, after integration,

$$Tp = A, \quad T + \frac{T^2}{2E} + \int F dr = C.$$

These equations may be treated in a manner somewhat similar to that adopted for inelastic strings.

**499.** Ex. 1. An elastic string rests in equilibrium in the form of an arc of a circle under the influence of a centre of force at any unoccupied point of the circle.

Show that the law of force is  $F = \frac{\mu}{r^3} \left( 1 + \frac{\mu}{2E} \frac{1}{r^2} \right)$ .

Ex. 2. An elastic string, whose elements repel each other with a force proportional to the product of their masses into the square of their distance, rests in equilibrium on a smooth horizontal plane. If  $T$  be the tension at a point whose distance from one extremity is  $y$ , show that  $\frac{d^4}{dy^4} (T + E)^2 + \frac{c^2}{T + E} = 0$ , where  $c$  is a constant depending on the nature of the string. Explain also how the constants of integration are to be determined.

Ex. 3. An elastic string, whose elements repel each other with a force which varies as the distance, rests on a smooth horizontal plane. If  $2l_1$  and  $2l$  be the unstretched and stretched lengths of the string, show that  $cl = \tan c l_1$ , where  $E c^2 dx$  is the force due to the whole string on an element whose unstretched length is  $dx$  when placed at a unit of distance from the middle point of the string.

Ex. 4. A uniform elastic string lying on a rough horizontal plane is fixed to two points, and forms a curve every part of which is on the point of motion. Show that the tension is given by the equation  $\left( 1 + \frac{t}{\lambda} \right)^2 \left\{ \left( \frac{dt}{d\psi} \right)^2 + t^2 \right\} = \mu^2 w^2 \rho^2$ , where  $w$  is the weight per unit of length of the unstretched string,  $\mu$  the coefficient of friction and  $\rho$  the radius of curvature. [Math. Tripos, 1881.]

Ex. 5. An elastic string has its two ends fastened to points on the surface of a

We may here use the same method as that employed in Art. 493 to determine the form of equilibrium of an inelastic string. Referring to the figure of that article, let the unstretched length be  $CP$  (i.e. the arc measured from the lowest point up to any point  $P$ ), and let the rest of the notation be the same as before. Consider the equilibrium of the finite portion  $CP$ ;

$$T \cos \psi = T_0 \dots\dots (1), \quad T \sin \psi = ws_1 \dots\dots (2),$$

$$\therefore \frac{dy}{dx} = \tan \psi = \frac{ws_1}{T_0} = \frac{s_1}{c} \dots\dots\dots (3).$$

From these equations we may deduce expressions for  $x$  and  $y$  in terms of some subsidiary variable. Since  $s_1 = c \tan \psi$  by (3), it will be convenient to choose either  $s_1$  or  $\psi$  as this new variable.

Adding the squares of (1) and (2), we have

$$T^2 = w^2 (c^2 + s_1^2) \dots\dots\dots (4).$$

Since  $dx/ds = \cos \psi$  and  $dy/ds = \sin \psi$ , we have by (1) and (2)

$$x = \int \frac{T_0}{T} ds = \int \frac{wc}{T} \left(1 + \frac{T}{E}\right) ds_1 = \frac{wc}{E} s_1 + c \log \frac{s_1 + \sqrt{(c^2 + s_1^2)}}{c},$$

$$y = \int \frac{ws_1}{T} ds = w \int \frac{s_1}{T} \left(1 + \frac{T}{E}\right) ds_1 = \frac{w}{2E} (c^2 + s_1^2) + \sqrt{(c^2 + s_1^2)},$$

where the constants of integration have been chosen to make  $x=0$  and  $y=c+c^2w/2E$  at the lowest point of the elastic catenary. The axis of  $x$  is then the statical directrix, Art. 494, Ex. 2.

EX. 1. Prove the following geometrical properties of the elastic catenary

$$(1) \quad wy = T + \frac{T^2}{2E}, \quad (2) \quad \rho = \frac{c^2 + s_1^2}{c} \left\{ 1 + \frac{w}{E} \sqrt{(c^2 + s_1^2)} \right\},$$

$$(3) \quad s = s_1 + \frac{w}{2E} \left\{ s_1 \sqrt{(c^2 + s_1^2)} + c^2 \log \frac{s_1 + \sqrt{(c^2 + s_1^2)}}{c} \right\},$$

which reduce to known properties of the common catenary when  $E$  is made infinite.

EX. 2. Let  $M, M'$  be two points taken on the ordinate  $PN$  so that  $MM'$  is bisected in  $N$  by the statical directrix and let each half be equal to  $T^2/2Ew$ . If  $M$  be above the directrix draw  $ML$  perpendicular to the tangent at  $P$ . Show that  $PM, s_1 = PL, c = ML, w.MN = T^2/2E$  and that  $M'$  is the projection of the centre on the ordinate.



## CHAPTER XI

### THE MACHINES

502. It is usual to regard the complex machines as constructed of certain simple combinations of cords, rods and planes. These combinations are called the *mechanical powers*. Though given variously by different authors, they are generally said to be six in number, viz. the lever, the pulley, the wheel and axle, the inclined plane, the wedge and the screw\*.

**Mechanical advantage.** In the simplest cases they are usually considered as acted on by two forces. One of these, viz. the force applied to work the machine, is usually called *the power*. The other, viz. the force to be overcome, or the weight to be raised, is called *the weight*. The ratio of the weight to the power is called the *mechanical advantage* of the machine.

503. As a first approximation, we suppose that the several parts of the machine are smooth, the cords used perfectly flexible, the solid parts of the machine rigid and so on. In some of the machines these suppositions are nearly true, but in others they are far from correct. It is therefore necessary, as a second approximation, to modify these suppositions. We take such account as we can of the roughness of the surfaces in contact, the rigidity of the cords and the flexibility of the materials. After these corrections have been made, our result is still only an approximation to the truth, for the corrections cannot be accurately made. For example, in making allowance for friction we assume that the bodies in contact are equally rough throughout, and that the coefficient of friction is properly known. The results however thus obtained are much nearer the real state of things than our first approximation.

force  $P$  acting at one extremity of the combination produce at the other extremity such that it could be balanced by a force  $Q$  acting at the same point. Then, for this machine,  $P$  may be regarded as the power and  $Q$  as the weight.

Let the machine be made to work, so that its several parts make small displacements consistent with their geometrical relations. Such a displacement is called an *actual displacement* of the machine. Taking this as a virtual displacement, the work done by the force  $P$  is equal to that of the force  $Q$  together with the work done against the resistances of the machine. These resistances are the frictions, in overcoming which some of the work done by the force  $P$  is said to be wasted or lost. The work done by the force  $Q$  is called the *useful work* of the machine. *The efficiency of a machine is the ratio of the useful work to that done by the power in causing the machine to receive any small actual displacement.* It follows that the efficiency of a machine would be unity if all parts were perfectly smooth, the solid parts perfectly rigid, and there were no friction.

In all existing machines however the efficiency is necessarily less than unity.

**Ex.** In any machine for raising a weight show that, if the weight is suspended by friction when the machine is left free, the efficiency is less than half. If however a force  $P$  be required to raise the weight, and a force  $P'$  be required to prevent it from descending, show that the efficiency will be  $(P + P')/2P$ , and that the machine is to be itself accurately balanced. [St John's Coll., 1884.]



When the force  $P$  just raises a weight  $Q$ , the friction acts in opposition to the force  $P$ ; on the contrary it assists  $P'$  in supporting  $Q$ . The frictions in the two cases are evidently the same in magnitude, being the extreme amounts which can be put into play. Let  $x, y$  be the virtual displacements of the points of application of  $P, Q$  when the machine is worked, and let the same small displacement be taken in each case. Let  $U$  be the work of the frictions. Then  $Px = Qy + U$ , and  $P'y = Qy - U$ . The efficiency of the machine is measured by the ratio  $Qy/Px$ . Subtracting  $U$ , we easily obtain the result given. If any of the resistances, other than friction, have no superior limit, but continually increase with the increase of displacement, it is easy to see by the same reasoning that the efficiency will be less than the value found above.

**3. The lever.** A lever is a rigid rod, straight or bent,

When the forces act in any directions at any points of the body, the problem is one in three dimensions, the solution of which is given in Art. 268. In what follows we shall also neglect the friction at the axis, as that case has already been considered in Art. 179.

**507.** *To find the conditions of equilibrium of two forces acting on a lever in a plane perpendicular to its axis.*

The axis of the lever is regarded in the first approximation as a straight line; let  $C$  be its intersection with the plane of the forces.



Let the forces be  $P$  and  $Q$ . Let them act at  $A$  and  $B$  on the arms  $CA$ ,  $CB$  in the directions  $DA$ ,  $DB$ . When the lever is in its position of equilibrium, the forces  $P$ ,  $Q$  and the reaction at the fulcrum must form a system of forces in equilibrium. Hence the resultant of  $P$  and  $Q$  must act along  $DC$ , and be balanced by the pressure on the fulcrum.

The conditions of equilibrium follow at once from the principles stated in Art. 111. Let  $CM$ ,  $CN$  be perpendiculars drawn from  $C$  on the lines of action of the forces. Taking moments about  $C$ , we have  $P \cdot CM - Q \cdot CN = 0$ . It follows that in a lever, *the power and the weight are to each other inversely as the perpendiculars drawn from the fulcrum on their lines of action.*

**508.** *To find the pressure on the fulcrum,* we find the resultant of the two forces  $P$ ,  $Q$  by any one of the various methods usually employed to compound forces. For example, if the position of  $D$  be known, let  $\phi$  be the angle  $ADB$ ; we then have  $R^2 = P^2 + Q^2 + 2PQ \cos \phi$ , where  $R$  is the required pressure.

Let  $CA = a$ ,  $CB = b$ , and let  $\alpha$ ,  $\beta$  be the angles the directions of the forces  $P$ ,  $Q$  make with the arms  $CA$ ,  $CB$ . Let  $\gamma$  be the angle  $ACB$ . If these quantities are known, we may find the pressure by another method. Let  $\theta$  be the angle the line of action of  $P$  makes with the line  $CA$ . Let  $\phi$  be the angle the line of action of  $Q$  makes with the line  $CB$ . Let  $\psi$  be the angle the line of action of the resultant  $R$  makes with the line  $CD$ . Then

resolutions will sometimes be more convenient than those given above as levers.

9. When several forces act on the lever, we find the condition of equilibrium requiring that the sum of their moments about the fulcrum, each moment being taken with its proper sign. The moments are taken about the fulcrum to avoid introducing into the equation the reaction at the axis.

To find the pressure on the fulcrum we transfer each force parallel to itself, in the perpendicular to the axis, to act at the fulcrum. We thus obtain a system of forces acting at a single point, viz. the intersection of the axis with the plane of the lever. The resultant of these is the pressure on the axis.

10. In the investigation the weight of the lever itself has been supposed to be negligible compared with the forces  $P$  and  $Q$ . If this cannot be neglected, let  $W$  be the weight of the lever. There are now three forces acting on the body instead of two. These are  $P$ ,  $Q$  acting at  $A$  and  $B$ , and  $W$  acting at the centre of gravity  $G$  of the lever. Let the fulcrum be horizontal, and let  $CL$  be the perpendicular distance between the fulcrum and the vertical through  $G$ . Let us also suppose that in the standard figure the weight  $W$  and the force  $P$  tend to turn the lever round the fulcrum in the same direction. The equation of moments now becomes  $P \cdot CM - Q \cdot CN + W \cdot CL = 0$ . The pressure on the fulcrum is found by resolving the forces  $P$ ,  $Q$ ,  $W$ .

11. Levers are usually divided into three kinds according to the relative positions of the power, the weight, and the fulcrum. In the first kind, the fulcrum is between the power and the weight. In the second kind the weight acts between the fulcrum and the power, and in the third kind the power acts between the fulcrum and the weight. The investigation in Art 507 applies to all three kinds, the only difference being in the signs given to the forces and the arms, in resolving and finding moments.

12. The mechanical advantage of the lever is measured by the ratio  $Q:P$ . This ratio has been proved to be equal to  $CN:CM$ . By applying the power so that its perpendicular distance from the fulcrum is greater than that of the weight, all power may be made to balance a large weight. Thus a crowbar when used to move a body is a lever of the second kind. The ground is the fulcrum, the weight is near the fulcrum, and the power is applied at the extreme end of the bar.

13. If the lever be slightly displaced by turning it round its fulcrum through a small angle, the points of application  $A$ ,  $B$  of the forces  $P$ ,  $Q$  are moved through small arcs  $AA'$ ,  $BB'$ , whose ends are on the fulcrum. Thus the actual displacements of the points of application of the power and the weight are proportional to their distances from the fulcrum. It is however the resolved part of the displacement  $AA'$  in the direction of the force  $P$  which

If then mechanical advantage is gained by arranging the lever so that the weight is greater than the power, the displacement of the weight is less, in the same ratio, than that of the power, the displacement being resolved in the direction of its own force. It follows that *what is gained in power is lost in speed*.

**514.** The reader may easily call to mind numerous instances in which levers are used. As examples of levers of the first kind we may mention the common balance, pokers, &c.

Wheelbarrows, nutcrackers, &c. are examples of levers of the second kind. In these the weight is greater than the power. They are used when we wish to multiply the force at our disposal.


In levers of the third kind the weight is less than the power, but the velocity of displacement of the weight is greater than that of the power. Such levers therefore are used when economy of force is a consideration subordinate to the speed of working.

**515.** The most striking example of levers of the third kind is found in the animal economy. The limbs of animals are generally levers of this description. The socket of the bone is the fulcrum; a strong muscle attached to the bone near the socket is the power; and the weight of the limb, together with whatever resistance is opposed to its motion, is the weight. A slight contraction of the muscle in this case gives a considerable motion to the limb: this effect is particularly conspicuous in the motion of the arms and legs in the human body. A very inconsiderable contraction of the muscles at the shoulders and hips giving a wide sweep to the limbs from which the body derives so much activity.

The treddle of the turning lathe is a lever of the third kind. The hinge which attaches it to the floor is the fulcrum, the foot applied to it near the hinge is the power, and the crank upon the axis of the fly-wheel, with which its extremity is connected, is the weight.

Tongs are levers of this kind, as also the shears used in shearing sheep. In these cases the power is the hand placed immediately below the fulcrum or point where the two levers are connected. *Capt. Kater's Mechanics*.


**516.** The principle of virtual work may be conveniently used to investigate the conditions of equilibrium in the lever. Let  $P$ ,  $Q$  be two forces acting at  $A$  and  $B$ , and let  $C$  be the fulcrum. If the lever be displaced round  $C$  through a small angle  $\delta\theta$ , so that  $A$ ,  $B$  come into the positions  $A'$ ,  $B'$ , we have



$$P \cdot AA' \sin \alpha = Q \cdot BB' \sin \beta = 0$$

principle of virtual

In this balance  
our rods  $AA'$ ,  $A'B'$ ,  
 $BA$  are hinged at  
extremities and  
a parallelogram.  
sides  $AB$ ,  $A'B'$  are  
hinged at the  
s  $C$ ,  $C'$  to a fixed



rod  $CCC'$ . The line  $CC'$  must be parallel to  $AA'$  and  $BB'$ , but need not  
necessarily be equidistant from them. Two more rods  $MM'$ ,  $NN'$  are rigidly  
fixed to  $AA'$ ,  $BB'$  so as to be at right angles to them. These support the weights  
and  $Q$  suspended in scale-pans from any two points  $H$  and  $K$ . As the combina-  
turns smoothly round the supports  $C$ ,  $C'$ , the rods  $AA'$ ,  $BB'$  remain always  
parallel, and  $MM'$ ,  $NN'$  are always horizontal.

The peculiarity of the machine is that, if the weights  $P$ ,  $Q$  balance in any one  
position, the equilibrium is not disturbed by moving either of the weights along the  
supporting rods  $MM'$ ,  $NN'$ . It may also be remarked that, if the machine be turned  
round its two supports  $C$ ,  $C'$  so that one of the rods  $MM'$ ,  $NN'$  descends and the  
other ascends, the two weights continue to balance each other.

To show this, let the equal lengths  $CA$ ,  $C'A'$  be denoted by  $a$ , and the equal lengths  
 $C'B$  by  $b$ . Let the inclination to the horizon of the parallel rods  $AB$ ,  $A'B'$  be  
 $\theta$ . If the machine is displaced so that the angle  $\theta$  is increased by  $d\theta$ , the rod  $AA'$   
descends a vertical space  $a \cos \theta d\theta$ , and the rod  $BB'$  ascends a space  $b \cos \theta d\theta$ .  
If the weights of all the parts of the machine are neglected in comparison with  
the weights  $P$  and  $Q$ , we have by the principle of virtual work  $Pa \cos \theta d\theta = Qb \cos \theta d\theta$ . This  
gives  $Pa = Qb$ ; thus the condition of equilibrium is independent of the positions  
at which  $P$  and  $Q$  act on the supporting rods, and is also independent of the  
inclination  $\theta$  of the rods  $AB$ ,  $A'B'$  to the horizon.

The balance is so constructed that the weights  $P$ ,  $Q$  are equal, when in equili-  
brium, we can detect whether any difference in weight exists between two given  
weights by simply attaching them to any points of the supporting rods. The  
advantage of the balance is that no special care is necessary to place them at equal  
distances from the fulcrum.

Ex. 1. If the weights of the rods  $AB$ ,  $A'B'$  are  $w$ ,  $w'$  and the weights of the  
scale-pans  $AA'M'$ ,  $BB'N'$  are  $W$ ,  $W'$ , prove that the condition of equilibrium is

$$(P + W) a - (Q + W') b + \frac{1}{2} (w + w') (a - b) = 0.$$

Prove also that, if the weights  $P$ ,  $Q$  balance in one position, they will as before  
balance in all positions. Find also the point of application of the resultant pressure  
on the stand  $EF$  on the supporting table.


Ex. 2. If the balance be at rest and horizontal, prove that the horizontal  
pressure on either support bears to either weight the ratio of the difference of the  
horizontal distances of the centres of gravity of the weights from the central plane  
of balance to the distance between the supports. [Math. Tripos, 1874.]

Let  $X$ ,  $Y$ ,  $X'$ ,  $Y'$  be the horizontal and vertical components of the reactions at

$A, A'$ . By taking moments about  $A'$  for the system  $AM'A'$  we have  $Xa =$  where  $AA' = a, MH = h$ . We have also  $X + X' = 0, Y + Y' = P$ . Thus  $X, X'$  known while the separate values of  $Y$  and  $Y'$  are indeterminate, Arts. 268, Similarly if  $X_1, Y_1; X'_1, Y'_1$ , are the corresponding components at the points  $B$  we have  $X_1a = Pk$  where  $NK = k$ . Since the rod  $AB$  is acted on by  $X, Y; X_1, Y_1$  (reversed) at the extremities, the horizontal component of pressure at the pin  $X = X_1$ , which at once leads to the given result.

**518. The Common Balance.** In the common balance two equal scale-pans  $E, F$  are suspended by equal fine strings from the extremities  $A, B$  of a straight rod or beam. The rod  $AB$  can turn freely about a fulcrum  $O$ , with which it is connected by a short rod  $OC$  which bisects  $AB$  at right angles. The centre of gravity  $G$  of the beam  $AOB$  lies in the rod  $OC$ , and therefore, when the beam is in equilibrium, the empty scales are in equilibrium, the straight line  $AB$  is horizontal.

The bodies to be weighed are placed in the scale-pans, and if their weights are unequal, the horizontality of the beam  $AB$  is disturbed. The centre of gravity  $G$  of the beam is now no longer under the point of support, and in the new position of equilibrium the inclination  $\theta$  of the rod  $AB$  to the horizon is such that the moment of the weight of the beam about the fulcrum  $O$  is equal to that of the weight of the bodies and the scale-pans. It is therefore evident that the fulcrum should not coincide with the centre of gravity of the beam.



Let  $P, Q$  be the weights in the scales  $E$  and  $F$ ,  $w$  the weight of either scale-pan,  $H$  be the weight of the beam  $AOB$ . Let  $OG = h, OC = c, AB = 2a$ . Let  $\theta$  be the inclination of  $AB$  to the horizon when the system is in equilibrium. Taking moments about  $O$ , we have

$$(P + w)(a \cos \theta + c \sin \theta) - (Q + w)(a \cos \theta - c \sin \theta) + Hh \sin \theta = 0.$$

The coefficient of  $P + w$  in this equation is the length of the perpendicular from  $O$  on the vertical  $AE$ , and is easily found by projecting the broken line  $OC, CA$  on the horizontal. The other coefficients are found in the same way. We therefore have

$$\tan \theta = \frac{(Q - P)a}{(P + Q + 2w)c + Hh}.$$

For a minute account of a balance with illustrative diagrams the reader is referred to the tract, "The theory and use of a physical balance," by J. Walker, 18

**519.** A good balance has three requisites. The first is that when loaded with equal weights in the pans the rod  $AB$  should be horizontal. This is secured by making the arms  $AC, CB$  equal. To determine when the beam is horizontal

beam. If the balance is so constructed that  $h$  and  $c$  have opposite signs, the sensibility can be greatly increased. This requires that the fulcrum  $O$  should lie between  $G$  and  $C$ .

The third requisite of a balance is usually called *stability*. When the balance is disturbed, it should return readily to its horizontal position. The beam oscillates about its position of equilibrium, and the quicker the oscillation the sooner can it be determined by the eye whether the mean position of the beam is or is not horizontal. The balance should be so constructed that the times of oscillation are as short as possible. The discovery of the nature of the oscillation is a problem in dynamics, and cannot properly be discussed from a statical point of view.

**520.** Ex. 1. If one arm of a common balance, whose weight can be neglected, is longer than the other, prove that the true weight of a body is the geometric mean of the apparent weights when weighed first in one scale and then in the other. [Coll. Exam., 1881]

Ex. 2. A balance has its arms unequal in length and weight. A certain article appears to weigh  $Q_1$  or  $Q_2$  according as it is put in the one scale or the other. Similarly another article appears to weigh  $R_1$  or  $R_2$ . Find the true weights of these articles; and show that if an article appears to weigh the same in whichever scale it is put, its weight is  $\frac{Q_1 R_2 - Q_2 R_1}{Q_1 - Q_2 - R_1 + R_2}$ . [Coll. Exam., 1881]

Ex. 3. In a false balance a weight  $P$  appears to weigh  $Q$ , and a weight  $P'$  weighs  $Q'$ : prove that the real weight  $X$  of what appears to weigh  $Y$  is given by  $X(Q - Q') = Y(P - P') + P'Q - PQ'$ . [Math. Tripos, 1877]

Ex. 4. A true balance is in equilibrium with unequal weights  $P, Q$  in its scales. If a small weight be added to  $P$ , the consequent vertical displacement of  $Q$  is equal to that which would be the vertical displacement of  $P$  were the same small weight to be added to  $Q$  instead of to  $P$ . [Math. Tripos, 1877]

Looking at the expression for  $\tan \theta$  in Art. 518, we notice that the changes produced in  $\theta$  by altering either  $P$  or  $Q$  by the same small quantity are equal with opposite signs. The effect of increasing  $P$  or  $Q$  is therefore to turn the balance the one way or the other through the same small angle. The vertical displacements of the weights are therefore equal in the two cases.

Ex. 5. If the tongue of the balance be very slightly out of adjustment, prove that the true weight of a body is nearly the arithmetic mean of its apparent weights when weighed in the opposite scales. [Coll. Exam., 1881]

Ex. 6. A delicate balance, whose beam was originally suspended by a knife-edged portion of itself (higher than its centre of gravity) resting upon a horizontal agate plate, has its knife-edge worn down a distance  $\epsilon$  so that it becomes curved (curvature  $= 1/r$ ), and has a corresponding hollow made in the agate plate (curvature  $= 1/\rho$ ). If slightly different weights  $P$  and  $Q$  be placed in the scales (whose weights may be neglected), show that the reciprocal of the sensibility is increased by  $(P + Q + W) \left( \epsilon + \frac{r\rho}{r + \rho} \right) \frac{1}{r\rho}$ . [Coll. Exam., 1891]



**521. The Steelyards.** The common steelyard is a lever  $ACB$  with unequal arms  $AC$ ,  $CB$ , the fulcrum being situated at a point a little above  $C$ . The body  $Q$  to be weighed is suspended from the extremity  $B$  of the shorter arm, and a given weight  $P$  is moved along the longer arm  $CA$  to some point  $H$  such that the system balances. Let  $G$  be the centre of gravity of the beam,  $w$  its weight. The three weights,  $P$  acting at  $H$ ,  $w$  at  $G$ , and  $Q$  at  $B$  are in equilibrium. Taking moments about  $C$ , we have

$$P \cdot HC + w \cdot GC = Q \cdot CB \dots \dots \dots (1).$$



Let  $D$  be a point on the shorter arm  $CB$ , such that  $w \cdot GC = P \cdot CD$ ; the equation (1) then becomes  $P \cdot HD = Q \cdot CB \dots \dots \dots (2).$

Thus the weight of  $Q$  is determined by measuring the distance  $HD$ . To effect this easily, we measure from  $D$  towards  $A$  a series of lengths  $DE_1$ ,  $E_1E_2$ ,  $E_2E_3$ , &c. each equal to  $CB$ . The weight of the body  $Q$  is therefore equal to  $P$ ,  $2P$ ,  $3P$ , &c. according as the weight  $P$  is placed at the points  $E_1$ ,  $E_2$ ,  $E_3$ , &c. when the system is in equilibrium. The intervals  $E_1E_2$ ,  $E_2E_3$ , &c. are usually graduated into smaller divisions, so that the length  $HD$  can be easily read. The points  $E_1$ ,  $E_2$ , &c. are marked 1, 2, &c. in the figure.

An instrument of this form was used by the Romans and is therefore often called the Roman steelyard.

**522.** In the Danish steelyard the weights  $P$  and  $Q$  act at fixed points of the lever, but the fulcrum or point of support  $C$  is made to slide along the rod  $AB$  until the system balances. The weight  $P$ , being fixed, can be conveniently joined to that of the lever. Let, then,  $P'$  be the weight of the instrument, so that  $P' = P + w$ , and let  $G$  be the centre of gravity. Taking moments about  $C$ , we evidently have  $P' \cdot GC = Q \cdot CB$ , and  $\therefore BC = \frac{P' \cdot BG}{P' + Q}$ . This expression enables us to calculate the values of  $BC$  when  $Q = P'$ ,  $2P'$ ,  $3P'$ , &c. Marking these points of the rod  $AB$  with the figures 1, 2, 3, &c., the weight of any body placed at  $B$  can be read off when the place of the fulcrum  $C$  has been found by trial.

If  $C$ ,  $C'$  be two successive marks of graduation when the weights suspended at  $B$  are  $Q$  and  $Q + S$ , we easily find that  $\frac{1}{BC'} - \frac{1}{BC} = \frac{S}{P' \cdot BG}$ ; since the right-hand side



body to be weighed is heavier than the fixed weight the pressure on the point of contact is less than in the balance. The steelyard is therefore better adapted to weigh large weights. There is on the other hand this advantage in the balance, by using numerous small weights the reading can be effected with greater accuracy than by subdividing the arm of the steelyard.

Ex. 1. The weight of a common steelyard is  $w$ , and the distance of its fulcrum from the point from which the weight hangs is  $a$  when the instrument is in its normal adjustment; the fulcrum is displaced to a distance  $a + a'$  from this end; show that the correction to be applied to give the true weight of a body which in the uncorrected instrument appears to weigh  $W$  is  $(W + P + w)a'/(a + a')$ ,  $P$  being the weight of the moveable weight. [Math. Tripos, 1881]

Ex. 2. In a weighing machine constructed on the principle of the common steelyard the pounds are read off by graduations reaching from 0 to 14, and the weights are by weights hung at the end of the arm; if the weight corresponding to one pound is 7 oz., the moveable weight  $\frac{1}{2}$  lb., and the length of the arm one foot, prove that the distances between the graduations are  $\frac{1}{4}$  in. [Math. Tripos.]

Ex. 3. In graduating a steelyard to weigh pounds, marks are made with a file, the weight  $x$  being removed for each notch. With the moveable weight  $P$  at the end of the beam,  $n$  lbs. can be weighed after the graduation is completed,  $(n + 1)$  lbs. when it is begun. Show that  $n(n + 1)x = 2P$ , and find the error made in weighing  $n$  lbs. The centre of gravity of the steelyard is originally under the point of suspension. [Coll. Exam., 1885.]

Ex. 4. Show that, if a steelyard be constructed with a given rod whose weight is considerable compared with that of the sliding weight, the sensibility varies inversely as the sum of the sliding weight and the greatest weight which can be weighed. [Math. Tripos, 1854.]

Ex. 5. A common steelyard is graduated on the assumptions that its weight is negligible and that the moveable weight is  $W$ , both which assumptions are incorrect. If two masses whose real weights are  $P$  and  $R$  appear to weigh  $P + X$  and  $R + Y$ , then show that the weight of the steelyard and the moveable weight are less than their assumed values by  $\frac{W}{D}(X - Y)$  and  $\frac{Q}{D}(X - Y) + \frac{a}{bD}(PY - RX)$ , where  $b$ ,  $a$  are the distances from the fulcrum to the centre of gravity of the bar and to the point of attachment of the substance to be weighed, and  $D = P - R + X - Y$ . [Math. Tripos, 1887.]

Ex. 6. The sum of the weight of a certain Roman steelyard and of its moveable weight is  $S$ , the fulcrum is at the point  $C$  and the body to be weighed is hung at the point  $B$ . The steelyard is graduated and after graduation the fulcrum is shifted to the point  $B$  to another point  $C'$ . A body is then weighed, the old graduation being used, and the apparent weight is  $W$ . Prove that the true weight is greater than the apparent weight by  $(S + W)CC'/BC'$ . [Trin. Coll., 1889.]

Ex. 7. If, on a common steelyard, the moveable weight  $P$ , which forms the sliding weight, be increased in the ratio  $1 + k : 1$ , prove that the consequent error in  $Q$ , the

**Ex. 9.** An old Danish steelyard, originally of weight  $W$  lbs., and accurately graduated, is found coated with rust. In consequence of the rust, the apparent weights of two known weights of  $X$  lbs. and  $Y$  lbs. are found when weighed by the steelyard to be  $(X-x)$  lbs.,  $(Y-y)$  lbs. respectively. Prove that the centre of gravity of the rust divides the graduated arm in the ratio  $W(x-y) : Yx - Xy$ ; and that its weight is, to a first approximation,  $\frac{W+Y}{X-Y}x + \frac{W+X}{Y-X}y$ . [Math. Tripos, 1885]

**Ex. 10.** A brass figure  $ABDC$ , of uniform thickness, bounded by a circular arc  $BDC$  (greater than a semicircle) and two tangents  $AB$ ,  $AC$  inclined at an angle  $2\alpha$  is used as a letter-weigher as follows. The centre of the circle,  $O$ , is a fixed point about which the machine can turn freely, and a weight  $P$  is attached to the point  $B$ , the weight of the machine itself being  $w$ . The letter to be weighed is suspended from a clasp (whose weight may be neglected) at  $D$  on the rim of the circle,  $CD$  being perpendicular to  $OA$ . The circle is graduated, and is read by a pointer which hangs vertically from  $O$ : when there is no letter attached, the point  $A$  is vertically below  $O$  and the pointer indicates zero. Obtain a formula for the graduation of the circle, and show that, if  $P = \frac{1}{3}w \sin^2 \alpha$ , the reading of the machine will be  $\frac{1}{3}w$  when  $OA$  makes with the vertical an angle equal to  $\tan^{-1} \left\{ \frac{(\pi + 2\alpha) \sin^2 \alpha + 2 \sin \alpha \cos \alpha}{(\pi + 2\alpha) \sin^3 \alpha + 2 \cos \alpha} \right\}$ . [Math. Tripos, 1877]

**525. The Pulley.** The common pulley consists of a wheel which can turn freely on its axis. A rope or cord runs in a groove formed on the edge of the wheel, and is acted on by two forces  $P$  and  $P'$  one at each end. If the pulley is smooth and the weight of the string infinitesimal, the tension is necessarily the same throughout the arc of contact. It follows that the forces  $P$ ,  $P'$  acting at the extremities of the string are equal to each other and to the tension. See fig. 1 of Art. 527. The same thing is true if the pulley is rough and circular, but can turn freely about a smooth axis; Art. 197.

**526.** When the axis of the pulley is fixed one of the forces  $P$ ,  $Q$  is the power and the other is the weight. Thus a fixed pulley has no mechanical advantage in the technical sense. A movable machine, however, which enables us to give the most advantageous direction to the moving power is as useful as one which enables a small power to support a large weight.

**527.** A movable pulley can however be used to obtain

vertical (Art. 27). Let  $\alpha$  be the inclination of either string to vertical, then

$$2P \cos \alpha = Q.$$

Fig. 1.





Fig. 2.



mechanical advantage is therefore  $2 \cos \alpha$ . Unless  $\alpha$  is less than  $60^\circ$  the mechanical advantage is less than unity. When the strings are parallel, we have  $2P = Q$ .

**Ex. 1.** In the single moveable pulley with parallel strings a weight  $W$  is supported by another weight  $P$  attached to the free end of the string and hanging over a fixed pulley. Show that, in whatever position the weights hang, the position of their centre of gravity is the same. [Math. Tripos, 1854.]

**Ex. 2.** A string is attached to the centre of a heavy circular pulley of radius  $r$  and is then passed over a fixed peg, then under the pulley, and afterwards over a second fixed peg vertically over the point where the string leaves the pulley and has a weight  $W$  attached to its extremity. The second peg is in the same horizontal line as the first peg and at a distance  $\frac{5}{3}r$  from it. If there is equilibrium, prove that the weight of the pulley is  $\frac{5}{2}W$ , and find the distance between the first peg and the centre of the pulley. [Coll. Exam., 1886.]

**Ex. 3.** An endless string without weight hangs at rest over two pegs in the same horizontal plane, with a heavy pulley in each festoon of the string; if the weight of one pulley be double that of the other, show that the angle between the tangents of the upper festoon must be greater than  $120^\circ$ . [Math. Tripos, 1857.]

**29.** Systems of pulleys may be divided into two classes, (1) those in which a single rope is used; and (2) those in which there are several distinct ropes. We begin with the first of these systems.

Two blocks are placed opposite each other, containing the

weight of the lower block; we then have  $Q + W$  supported by  $2n$  tensions. Since the tension of the string is the same throughout, and equal to  $P$ , we have by resolving vertically  $2nP = Q + W$ .

If the pulleys were all of the same size, and exactly under each other, some difficulty might arise in their arrangement so that the cords should not interfere with each other. For this, and other reasons, the parts of the string not in contact with the pulleys cannot be strictly parallel. Except when the two blocks are very close to each other the error arising from treating the strings as parallel is very slight, and may evidently be neglected when we take no account of the other imperfections of the machine; Art. 503.

We may also deduce the relation between the power and the weight from the principle of virtual work. If the lower block, together with the weight  $Q$ , receive a virtual displacement upwards equal to  $q$ , it is clear that each string is slackened by the same space  $q$ . To tighten the string,  $P$  must descend a space  $q$  for each separate portion of string, i.e.  $P$  must descend a space  $2nq$ . We have therefore by the principle of work


$$P \cdot 2nq = (Q + W) q.$$

The result follows immediately.

**530.** In some arrangements of this system the pulleys on each block have a common axis, but each pulley turns on the axis independently of the others. This change however does not affect the truth of the relation just established between the power and the weight.

When the system works, it is clear that all the pulleys, if of equal size, do not move with equal angular velocities. To give greater steadiness to the several parts of the machine, it has been suggested that the pulleys in each block should not only have a common axis, but be of such radii that each turns with the same angular velocity. When this has been effected, the pulleys in each block may be welded into one and the string made to run in grooves cut out of the same wheel.

To understand how this may be done, we notice that if the lower block rises one foot, each string would be slackened one foot. To tighten the string between  $C$  and  $F$  on the right hand the pulley  $F$  must be turned round so that one foot of string may pass over it. The string on the left hand between  $C$  and  $E$  is now



black. This mode of arranging the pulleys is due to White. It is not now used.

1. Ex. In that system of pulleys in which the same cord passes round all pulleys it is found that on account of the rigidity of the cord and the friction on the axle a weight of  $P$  lbs. requires  $aP + p$  lbs. to lift it by a cord passing over one pulley. Prove that when there are  $n$  parallel cords in the above system a weight of  $P$  can support a weight  $Q = a \frac{a^n - 1}{a - 1} P + \frac{a(a^n - 1) - n(a - 1)}{(a - 1)^2} p$ , and find the additional weight required to be added to  $P$  to raise  $Q$ . [Math. Tripos, 1884.]

The rigidity of cordage was made the subject of many experiments by Coulomb, and the discussion of these would require too much space, but the general result may be shortly stated. Suppose a cord  $ABCD$  to pass over a pulley of radius  $r$ , touching it at  $B$  and  $C$ , and moving in the direction  $ABCD$ . Then the rigidity of the portion  $AB$  of the cord which is about to be rolled on the pulley may be allowed for, by regarding the cord as perfectly flexible and applying an opposing couple to the pulley whose moment is  $a + bT$ , where  $a$  and  $b$  are constants which depend on the nature and size of the cord, but are sensibly independent of the velocity. If  $T'$  be the tension of the portion  $CD$  of the cord which is unwound from the pulley, its rigidity may be represented in the same way by the application of a couple equal to  $a' + b'T'$ . The values of  $a'$ ,  $b'$  are so much less than those of  $a$ ,  $b$ , that this last correction is generally omitted. Taking moments about the centre this gives  $T' - T = \frac{a + bT}{r}$ , where  $r$  is the radius.

32. When several cords are used pulleys may be combined in various ways to produce mechanical advantage. Two systems are usually described in elementary books, both of which are represented in the figure.

In fig. (1) each pulley is supported by a separate string, one end

Fig. 1.





Fig. 2.



of which is attached to a fixed point of support, and the other to the pulley next in order. In fig. (2) the string resting on each pulley has one end attached to the weight and the other to the pulley next in order. The two systems resemble each other in the arrangement of the pulleys, but to a certain extent each is the inversion of the other.

Let  $w_1, w_2, \&c.$  be the weights of the pulleys  $M_1, M_2, \&c.$   $T_1, T_2, \&c.$  the tensions of the strings which pass over them. In the figures only the suffixes of  $M_1, M_2, \&c.$  are marked on the pulleys to save space.

Considering fig. (1), the tension  $T_1 = P$ . The tensions of the two parts of the string on each side of the pulley  $M_1$  support the weight of that pulley and the tension  $T_2$ , we have therefore

$$T_2 = 2T_1 - w_1 = 2P - w_1.$$

Considering the pulleys  $M_2, M_3$ , we have in the same way

$$T_3 = 2T_2 - w_2 = 2^2P - 2w_1 - w_2,$$

$$T_4 = 2T_3 - w_3 = 2^3P - 2^2w_1 - 2w_2 - w_3,$$

and so on through all the pulleys. It is evident that the right hand side of each equation is twice that of the one above with a  $w$  subtracted. We therefore have finally

$$Q = 2T_n - w_n = 2^nP - 2^{n-1}w_1 - 2^{n-2}w_2 - \&c. - 2w_{n-1} - w_n.$$

If all the pulleys are of equal weight this gives

$$Q = 2^nP - (2^n - 1)w.$$

The relation between the power and the weight follows easily from the principle of virtual work. If we suppose the lowest pulley to receive a virtual displacement upwards equal to  $q$ , each of the strings on its two sides is slackened by an equal space. To tighten these we must raise the next lowest pulley through a space equal to  $2q$ . In the same way, the next in order must be raised a space twice this last, i.e.  $2^2q$ , and so on. Hence the power  $P$  must be raised a space  $2^nq$ . Multiplying each weight by the space through which it has been moved, we have, by the principle of virtual work,

efore have  $T_2 = 2T_1 + w_1 = 2P + w_1$ . Taking the other pulleys in order, we see that we have the same results as before except that the  $w$ 's have opposite signs. We thus have

$$T_3 = 2T_2 + w_2 = 2^2P + 2w_1 + w_2,$$

$$T_4 = 2T_3 + w_3 = 2^3P + 2^2w_1 + 2w_2 + w_3,$$

so on. Since the pulleys are all attached to the weight we have  $T_1 + T_2 + \dots + T_n = Q + W$ , where  $W$  is the weight of the

Substituting the values of  $T_1, T_2$ , &c. in this last equation, we have  $Q + W = (2^n - 1)P + (2^{n-1} - 1)w_1 + (2^{n-2} - 1)w_2 + \dots + w_{n-1}$ .

If all the pulleys are of equal weight this reduces to

$$Q + W = (2^n - 1)(P + w) - nw.$$

When the pulleys are arranged as in fig. (1), the mechanical advantage is decreased by increasing the weights of the pulleys. In fig. (2) the reverse is the case, for the weights of the pulleys act to the power in sustaining the weight.

To deduce the relation between the power and the weight by the principle of virtual work, let us first imagine the bar to be held at rest and the highest pulley to be moved downwards through a space  $q$ . Each of the strings on the two sides of that pulley is equally slackened by the space  $q$ . To tighten the strings, the second highest pulley must be moved downwards through a space  $2q$ , and so on. The power must descend a space

To restore the upper pulley to its original position let us suppose the whole system to be moved upwards through a space equal to  $q$ , Art. 65. On the whole, the weight  $Q$ , together with the bar  $ABC$ , has ascended a space  $q$ ; the downward displacements of the several pulleys in order, counting from the top, are respectively  $0, (2 - 1)q, (2^2 - 1)q, \dots$ ; while the upward displacement of the power  $P$  is  $(2^n - 1)q$ . The principle of work at once yields the equation

$$Wq = w_{n-1}(2 - 1)q + w_{n-2}(2^2 - 1)q + \dots$$



we have  $AB = 2a_2 - a_1$ ,  $BC = 2a_3 - a_2$ , and so on. Taking moments about  $A$  we have

$$T_2 \cdot AB + T_3 \cdot AC + \&c. = Q \cdot AH + W \cdot AG.$$

This equation determines the position of  $H$ .

If the weights of the strings or ropes cannot be neglected, we may suppose the weight of the portion of string between the pulleys  $M_1, M_2$  included in the weight  $w_1$ , that of the portion between the pulleys  $M_2, M_3$  included in  $w_2$ , and so on. The portions of string which join the points  $A, B, C$ , &c. to the pulleys are supported by the fixed beam  $ABC$ , &c. in fig. (1), and may be included in the weight of the beam in fig. (2). The weight of the string wound on any pulley may be included in the weight of that pulley.

The system of pulleys represented in fig. (1) of Art. 532 is sometimes called the *first system*. That represented in Art. 529 is the *second system*; while the one drawn in fig. (2) of Art. 532 is the *third system*.

**535.** When the weights of the pulleys are neglected and each hangs by a separate string, we can easily find the relation between the power and the weight when the strings are not parallel.

Let  $2\alpha_1, 2\alpha_2, 2\alpha_3$ , &c. be the angles between free parts of the strings which pass over the pulleys  $M_1, M_2, M_3$ , &c. respectively. Let also  $T_1, T_2, T_3$ , &c. be the tensions. Then by the same reasoning as before


$$T_1 = P, T_2 = 2T_1 \cos \alpha_1, T_3 = 2T_2 \cos \alpha_2, \&c.$$

If there are  $n$  pulleys we easily obtain  $Q = 2^n P \cdot \cos \alpha_1 \cdot \cos \alpha_2 \cdot \&c. \cos \alpha_n$ .

**536.** Ex. 1. In that system of pulleys in which all the strings are attached to the weight, if the weight of the lowest pulley be equal to the power  $P$ , of the second  $3P$ , and so on...that of the highest moveable pulley being  $3^{n-2}P$ , the ratio  $P : W$  will be  $2 : 3^n - 1$ . [Math. Tripos, 1855]

Ex. 2. In that system of pulleys in which each hangs by a separate string from a horizontal beam the weights of the pulleys, beginning with the highest, are in arithmetical progression, and a power  $P$  supports a weight  $Q$ ; the pulleys are then reversed, the highest being placed lowest, and the second highest placed lowest but one, and so on, and now  $Q$  and  $P$  when interchanged are in equilibrium. Show that  $n(Q + P) = 2W$ , where  $W$  is the total weight of the pulleys, and  $n$  the number of pulleys. [Coll. Exam., 1883]

Ex. 3. In a system of  $n$  pulleys where a separate string goes round each pulley and is attached to the weight, if the string which goes over the lowest pulley have the end at which the power is usually hung, passed under another moveable pulley and then over a fixed pulley, and attached to the weight  $Q$ ; and if the weight of each pulley be  $w$  and no other power be used, prove that  $Q = (3 \cdot 2^{n-1} - n - 1)w$ , and find



the strings being vertical, if  $W$  be the weight supported, and  $w_1, w_2, \dots, w_n$  the weights of the moveable pulleys, there will be no mechanical advantage unless

$$W - w_n + 2(W - w_{n-1}) + 2^2(W - w_{n-2}) + \dots + 2^{n-1}(W - w_1)$$

be positive.

[Math. Tripos, 1869.]

Ex. 6. In the system of  $n$  heavy pulleys in which each hangs by a separate string,  $P$  is the power (acting upwards),  $Q$  the weight, and  $R$  the stress on the beam from which the pulleys hang: show that  $R$  is greater than  $Q(1 - 2^{-n})$  and less than  $(2^n - 1)P$ .

[Math. Tripos, 1880.]

Ex. 7. If there be two pulleys, without weight, which hang by separate strings, the fixed ends only of the string being parallel, and the power horizontal, prove that the mechanical advantage is  $\sqrt{3}$ .

[St John's Coll., 1883.]

Ex. 8. In that system of pulleys, in which all the strings are attached to the weight, if the power be made to descend through one inch, through what distance will the weight rise? Illustrate by reference to this system of pulleys the principle which is expressed by the words, "In machines, what is gained in power is lost in time."

[Math. Tripos, 1859.]

Ex. 9. In the system of pulleys in which all the strings are attached to the weight  $Q$ , prove that, if the pulleys be small compared with the lengths of the strings, the necessary correction for the weight of the strings is the addition to  $Q, w_1, w_2, \dots, w_{n-1}$  respectively, of the weights of lengths

$$h_1 + h_2 + \dots + h_{n-1} + h, \quad 2(h_1 - h), \quad 2(h_2 - h_1), \dots, 2(h_{n-1} - h_{n-2})$$

of string; where  $h_1, h_2, h_3, \dots, h_n$  are the heights of the  $n$  pulleys (whose weights are  $w_1, w_2, \dots, w_n$  respectively) above the line of attachment, supposed horizontal, of the strings to the weight  $Q$ , and  $h$  the height of the point of attachment of the power above the same line.

[Math. Tripos, 1877.]

Ex. 10. In that system of pulleys in which the strings are all parallel, and the weights of the pulleys assist the power, show that, if there are  $n$  pulleys, each of diameter  $2a$  and weight  $w$ , the distance of the point of suspension of the weight from the line of action of the power is equal to

$$n \frac{2^{n+1} Q + [(n-3) 2^n + n+3] w}{2(2^n - 1) Q} a,$$

where  $Q$  is the weight.

[Math. Tripos, 1883.]

Ex. 11. In a system of four pulleys, arranged so that each string is attached to a bar carrying the weight, the string which usually carries the power is attached to one end of the same bar, and the fourth string to the other end. The weight and diameter of each pulley are respectively double of those of the pulley below it, and the strings are all parallel. The weight being 33 times that of the lowest pulley, find at what point of the bar it is hung.

[Trin. Coll., 1885.]

Ex. 12. In the system of pulleys, in which each pulley hangs by a separate string with one end attached to a fixed beam, there are  $n$  moveable pulleys of equal weight  $w$ . The  $r$ th string, counting from the string round the highest pulley, cannot bear a greater tension than  $T$ . Prove that the greatest weight which

**537. The Inclined Plane.** *To find the relation between the power and the weight in the inclined plane.*

Let  $AB$  be the inclined plane,  $C$  any particle situated on it. Let  $CN$  be a normal to the plane and  $CV$  vertical; let  $\alpha$  be the inclination of the plane to the horizon, then the angle  $NCV = \alpha$ . Let  $Q$  be the weight of  $C$ ,  $P$  a force acting on  $C$  in the direction  $CK$ , where the angle  $NCK = \phi$ . It is supposed that  $CK$  lies in the vertical plane  $VCN$ .





Fig. 1.

If the plane is smooth the reaction  $R$  of the plane on the particle acts along the normal  $CN$ . We then have by Art. 35

$$\frac{P}{\sin \alpha} = \frac{Q}{\sin \phi} = \frac{R}{\sin (\phi - \alpha)} \dots \dots \dots (1).$$

It is necessary for equilibrium that  $R$  should be positive, for otherwise the particle would leave the plane. It follows from these equations that  $\phi$  must be greater than  $\alpha$ . This follows also from an examination of fig. (1), for  $Q$  acting along  $VC$  and  $R$  along  $CN$  cannot be balanced by a force  $P$  unless its direction lies within the angle formed by  $CV$  and  $NC$  produced. If  $P$  act up the plane,  $\phi = \frac{1}{2}\pi$  and  $P = Q \sin \alpha$ ,  $R = Q \cos \alpha$ . If  $P$  act horizontally,  $\phi = \frac{1}{2}\pi + \alpha$ , and  $P = Q \tan \alpha$ ,  $R = Q \sec \alpha$ .

**538.** If the plane is rough, let  $\mu = \tan \epsilon$  be the coefficient of friction. With the normal  $CN$  as axis describe a right cone whose semi-angle is  $\epsilon$ ; this is the cone of friction, Art. 173. The resultant action  $R'$  of the plane on the particle lies within this cone; let  $CH$  be its line of action and let the angle  $NCH = i$ ; then  $i$  lies between  $\pm \epsilon$ . Let the standard case be that in which  $\alpha$  is greater than  $\epsilon$ , and  $\phi$  greater than either; this is represented in fig. (2). We therefore have



When the force  $P$  is so great that the particle is on the point of ascending the plane, the reaction  $R'$  acts along  $CE$ , and  $i = -\epsilon$ . Let  $P_1$  be this value of  $P$ , then

$$\frac{P_1}{\sin(\alpha + \epsilon)} = \frac{Q}{\sin(\phi + \epsilon)} = \frac{R'}{\sin(\phi - \alpha)} \dots\dots\dots (3).$$

When the force  $P$  is so small that the particle is only just sustained, the reaction  $R'$  acts along  $CD$ , and  $i = \epsilon$ . Let  $P_2$  be the value of  $P$ , then

$$\frac{P_2}{\sin(\alpha - \epsilon)} = \frac{Q}{\sin(\phi - \epsilon)} = \frac{R'}{\sin(\phi - \alpha)} \dots\dots\dots (4).$$

If  $\alpha > \epsilon$  as in fig. (2), it is clear that the particle will slide down the plane if not supported by some force  $P$ , Art. 166. When the particle is just supported the reaction  $R'$  acts along  $CD$  and  $Q$  along  $VC$ ; it is clear that these forces could not be balanced by any force  $P$  unless its direction lay within the angle made by  $CV$  and  $DC$  produced. Accordingly we see from (4) that  $R'$  is negative unless  $\phi > \alpha$ . In the same way it is impossible to pull the particle up the plane (without pulling it off) by any force whose direction does not lie between  $CV$  and  $EC$  produced. Assuming  $\phi > \alpha$ , the least force required to keep the particle at rest is given by (4), and the greatest by (3).

If  $\epsilon > \alpha$  as in fig. (3), the particle will rest on the plane unless disturbed by some force  $P$ . To just pull the particle up the plane the force must act within the angle formed by  $CV$  and  $EC$  produced, and its magnitude is given by (3). In order that the particle may be just descending the plane the force must act within the angle formed by  $CV$  and  $DC$  produced, and its magnitude is given by (4).

**539.** Ex. 1. If a power  $P$  acting parallel to a smooth inclined plane and supporting a weight  $Q$  produce on the plane a pressure  $R$ , then the same power acting horizontally and supporting a weight  $R$  will produce a pressure  $Q$ . [Coll. Ex., 1881.]

Ex. 2. Find the direction and magnitude of the least force which will pull a particle up a rough inclined plane.

By (3) we see that  $P_1$  is least when  $\phi + \epsilon = \frac{1}{2}\pi$ , i.e. when the force makes an angle with the inclined plane equal to the angle of friction.

Ex. 3. Find the direction and magnitude of the least force which will just support a particle on a rough inclined plane.

Ex. 4. A given particle  $C$  rests on a given smooth inclined plane and is supported by a force acting in a given direction. If the inclined plane is without weight and has its side  $AL$  moveable on a smooth horizontal table, find the force which when acting horizontally on the vertical face  $BL$  will prevent motion. Find also the point of application of the resultant pressure on the table.

Ex. 5. A heavy body is kept at rest on a given inclined plane by a force making a given angle with the plane; show that the reaction of the plane, when it is smooth, is a harmonic mean between the greatest and least reactions, when it is rough.

[Math. Tripos, 1858.]

Ex. 6. A heavy particle is attached to a point in a rough inclined plane by a

equal angles with the vertical, show that the difference between the inclinations of the planes must be twice the angle of friction. [Math. Tripos, 1878.]

**540. Wheel and Axle.** *To find the relation between the power and the weight in the wheel and axle.*

Let  $a$  be the radius of the axle  $AB$ ,  $c$  that of the wheel. The power  $P$  acts by means of a string which passes round the wheel several times and is attached to a point on the circumference. The weight  $Q$  acts by a string which passes similarly round the axle. Taking moments round the central line of the axle, we have  $Pc = Qa$ . The mechanical advantage is equal to  $c/a$ .




Fig. 1.




Fig. 2.

If  $p, q$  be the spaces which the power and weight pass over while the wheel turns through any angle, we have

$$p/q = c/a = Q/P.$$

**541.** When a great mechanical advantage is required we must either make the radius of the wheel large or that of the axle small. If we adopt the former course the machine becomes unwieldy, if the latter the axle may become too weak to bear the strain put on it. In such a case we may adopt the plan represented in fig. (2). The two parts of the axle are made of different thicknesses, and the rope carried round both. As the power  $P$  descends, the rope which supports the weight is coiled on the thicker part of the axle and uncoiled from the thinner. Let  $a, b$  be the radii of these two portions of the axis. If  $Q$  be the weight attached to the pulley, the tension of the string is  $\frac{1}{2}Q$ . Taking moments about the central line of the axis, we have  $Pc = \frac{1}{2}Q(a - b)$ . The mechanical advantage is therefore equal to the radius of the wheel divided by half the difference of the radii of the axle. By making the radii of the two portions of the axis as nearly equal as we please, we can increase the mechanical advantage without decreasing the strength of the machine. This arrangement is called the *differential axle*.

**542. Ex. 1.** A rope passes round a pulley, and its ends are coiled opposite


13. When both the power and the weight act on the circumference of wheels are various methods of connecting the two wheels besides that of putting on a common axis. Sometimes, when the wheels are at a distance from each other, they are connected by a strap passing over their circumferences. In some cases one wheel works on the other by means of teeth placed on their rims.

**44. Toothed Wheels.** *To obtain the relation between the power and the weight in a pair of toothed wheels.*

Let  $A, B$  be the centres of two wheels which act on each other by means of teeth, the teeth on the axis of one wheel working into the teeth on the circumference of the other at the point  $C$ . Let  $a_1, a_2$  be the radii of the axes,  $b_1, b_2$  those of the wheels.

Let  $p, q$  be the virtual velocities of the power  $P$  and weight  $Q$ , then  $Pp = Qq$ . If the teeth

are small the average velocities of the points near  $C$  on the two wheels are equal, and the common direction is perpendicular to the straight line  $AB$ . If then  $\theta_1, \theta_2$  are the angles turned through by the wheels when the power receives a small displacement,



we have  $a_1\theta_1 = b_2\theta_2$ . But  $p = b_1\theta_1, q = a_2\theta_2$ . It follows that  $\frac{b_1b_2}{a_1a_2}$ . We have here omitted the work lost in overcoming friction at the teeth in contact and at the points of support.

**45.** Let a tooth on one wheel touch the corresponding tooth on the other in point  $D$ , and let  $EDF$  be a common normal to the two surfaces in contact at the point  $D$ . The point  $D$  is not marked in the figure because the teeth are not fully drawn, but is necessarily situated near  $C$ . The actual velocities of the points of the teeth in contact at  $D$  when resolved in the direction  $EDF$  are equal. If, then,  $h$  and  $k$  are the perpendiculars drawn from  $A, B$  on  $EDF$ , it is clear that  $\theta_1h = \theta_2k$ . As the wheels turn, the lengths  $h$  and  $k$  alter, and if the ratio  $h/k$  is not constant, there is more or less irregularity in the working of the machine. To correct this defect, the teeth are sometimes cut so that the normal at every point of the boundary of a tooth is a tangent to the circle to which the tooth is attached. When this is

circle. The two involutes are unwrapped from the circle in opposite directions and portions of each form the sides of the tooth.

When the centres of the toothed wheels are given, and the ratio of the angular velocities at which they are to work, we may determine their radii in the following manner. Let  $A, B$  be the given centres; divide  $AB$  in  $C$  so that  $AC \cdot \theta_1 = BC \cdot \theta_2$ . Through  $C$  draw a straight line  $ECF$ , which should not deviate very much from a perpendicular to  $AB$ . With  $A$  and  $B$  as centres describe two circles touching the straight line  $ECF$ . The sides of the teeth are to be involutes of these circles. By this construction the common normal to two teeth pressing against each other at  $D$  is the straight line  $ECF$ . As the wheels turn round, and the teeth move with them, the point of contact  $D$  travels along the fixed straight line  $ECF$ . The perpendiculars  $h$  and  $k$  are equal to the radii of these circles and are constant during the motion. Their ratio also is evidently equal to the ratio of  $AC$  to  $BC$ , i.e. of  $\theta_2$  to  $\theta_1$ .

It has already been shown that  $Pp = Qq$ , and  $p = b_1\theta_1$ ,  $q = a_2\theta_2$ . Since  $\theta_1 h = \theta_2 k$ , we find as before  $\frac{Q}{P} = \frac{b_1 b_2}{a_1 a_2}$ .

We may notice that, if the distance between the centres  $A$  and  $B$  is slightly altered, the pair of wheels will continue to work without irregularity and the ratio of the angular velocities will be the same as before. To prove this, we observe that the common normal to two teeth pressing against each other is still a common tangent to the two circles, though in their displaced positions. Thus, though the inclination to  $AB$  of the straight line  $ECF$  is altered, the lengths of the perpendiculars  $h$  and  $k$  are the same as before.

That the teeth should be made of the proper form is a matter of importance to the even working of the machine. Many other considerations enter into the theory besides that mentioned above. Thus defects may arise from the wearing of the teeth if the pressure be very great at the point of contact. There may also be jolts and jars when the teeth meet or separate. But the subject is too large to be treated of in a division of a chapter. The reader who is interested in this matter is referred to books on the principles of mechanism. In Willis' *Principles of Mechanism* (2nd edition, 1870) five different methods of constructing the teeth are described, in three of which epicycloids are used; the advantages and disadvantages of these constructions are also compared.


**546.** Ex. 1. In a train of  $n$  wheels, the teeth on the axle of each wheel work on those on the circumference of the next in order. Show that the power and weight are connected by the relation  $\frac{Q}{P} = \frac{b_1 b_2 \dots b_n}{a_1 a_2 \dots a_n}$ , where  $a_1, a_2$  &c. are the radii of the axles and  $b_1, b_2$  &c. those of the wheels.

Ex. 2. In a pair of toothed wheels show that, if the ratio of the power and weight is to be approximately constant, the height and breadth of the teeth must

47. **The Wedge.** To find the relation between the power and the weight in the wedge.

Let  $M, N$  be two obstacles which it is intended to separate by inserting a wedge  $ABC$  between them. For the sake of distinctness the obstacles are represented in the figure by two equal boxes placed on the floor, but it is obvious they may be of any kind.

We shall suppose that the wedge used is isosceles, and that its median line  $CN$  vertical. Let the angle  $ACB$  be  $2\alpha$ . Let



$C$  be the points of contact with the obstacles (not marked in figure),  $R, R$  the normal reactions at these points,  $F, F$  the frictions. When the wedge is on the point of motion we have  $R \tan \epsilon$ , where  $\tan \epsilon$  is the coefficient of friction.

Let  $P$  be a force acting vertically at  $N$  urging the wedge upwards. Supposing  $P$  to prevail, the frictions on the wedge along  $CA, CB$ ; we therefore find by resolving vertically

$$P = 2R (\sin \alpha + \tan \epsilon \cos \alpha) = 2R \sin (\alpha + \epsilon) \sec \epsilon.$$

The resultant reaction  $R'$  at  $D$  is then found by compounding  $R$  and  $\mu R$ .

If the obstacle  $M$  can only move horizontally, the whole of the reaction  $R'$  is not effective in producing motion. The horizontal component of  $R'$  tends to move  $M$ , but the vertical component presses the box on the floor and possibly tends to increase the sliding friction between the box and the floor. Let  $X$  be the horizontal component of  $R'$ ; we find

$$X = R \cos \alpha - R \tan \epsilon \cdot \sin \alpha = R \cos (\alpha + \epsilon) \sec \epsilon.$$

The mechanical advantage  $X/P$  is therefore equal to  $\frac{1}{2} \cot (\alpha + \epsilon)$ .

48. It may be noticed that the mechanical advantage of the wedge is increased by making the angle  $\alpha$  more and more acute. There is of course a natural limit to the acuteness of this angle, for that degree of sharpness only is given to the wedge which is consistent with the strength required for the use to which it is to be applied.

In examples of wedges we may mention knives, hatchets, chisels, nails, pins, &c. Generally speaking, wedges are used when a large power can be exerted through a narrow space. This force is usually applied in the form of an impulse.



It has not been considered necessary to consider separately the case in which the wedge is smooth, as the results obtained on so erroneous a supposition have practical bearing.

**549.** If the force is applied in the form of a blow so that the wedge is driven forwards between the obstacles, the problem to determine its motion is properly one in dynamics. Our object here is merely to find the conditions of equilibrium of a triangular body inserted between two rough obstacles and acted on by a force  $P$ .

When a series of blows is applied to the wedge, we may, however, enquire what happens in the interval between the impulses. The wedge may either stick fast, held by the friction, or begin to return to its original position, being pressed back by the elasticity of the materials. Assuming that these forces of restitution may be represented by two equal pressures  $R$ , acting on the sides of the wedge, let  $P_1$  be the force necessary to hold the wedge in position. The friction now acts to assist the power. To determine  $P_1$  we write  $-\epsilon$  for  $\epsilon$  in the equation of equilibrium. We therefore have

$$P_1 = 2R \sin(\alpha - \epsilon) \sec \epsilon.$$

If  $\alpha$  is greater than  $\epsilon$ ,  $P_1$  is positive and therefore some force is necessary to hold the wedge in position. If  $\alpha$  is less than  $\epsilon$ ,  $P_1$  is negative, thus the friction is more than sufficient to hold the wedge fast. A force equal to this value of  $P_1$  with the sign changed is necessary to pull the wedge out. The result is that the wedge will stick fast or come out according as the angle  $A$  is less or greater than twice the angle of friction.


Ex. 1. Referring to the figure of Art. 547, show that if either of the angles  $A$  or  $B$  of the wedge is less than the angle of friction, no force  $P$  however great could separate the obstacles  $M$ ,  $N$ .

If the angle  $A$  is less than  $\epsilon$ , we find that  $\alpha + \epsilon$  is greater than a right angle, therefore that  $X$  is negative. It is easy also to see that, if the angle  $A$  is equal to the resultant reaction between one side of the wedge and an obstacle is vertical. The wedge therefore merely presses the obstacle against the floor.

of Art. 547. Discuss the two cases in which (1) one obstacle is immovable  
(2) both move equally when the wedge makes an actual displacement.

**550. The Screw.** *To find the relation between the power and the weight in the screw.*

Let  $AB$  be a circular cylinder with a uniform projecting ridge running round its surface, the tangents to the directions of the ridges making a constant angle  $\alpha$  with a plane perpendicular to the axis of the cylinder. The screw thus formed fits into a hollow cylinder with a corresponding groove on its internal surface, in which the ridge works. The grooves on the hollow cylinder have not been sketched, but are included in the beam  $EF$ .



The position of the ridge on the cylinder is easily understood by the following construction. Let a sheet of paper be cut into the form of a right-angled triangle  $LMN$ , such that the altitude  $MN$  is equal to the altitude of the cylinder  $AB$  and the angle the base  $LM$  makes with the hypotenuse  $LN$  is equal to  $\alpha$ . Let this sheet of paper be wrapped round the cylinder  $AB$ ; if the base  $LM$  is long enough to go several times round the base of the cylinder, the hypotenuse will appear to gradually round the cylinder. The line thus traced by the hypotenuse is the line along which the ridge lies.

Let  $P$  be the power applied perpendicularly at the end of a lever  $CD$ . Let  $AC = a$ , and let  $b$  be the radius of the cylinder  $AB$ . Supposing the body  $EF$  in which the screw works to be fixed in space, the end  $B$  of the cylinder will be gradually moved round  $A$  as the lever describes a circle round  $A$ . Let  $Q$  be the force acting at  $B$ .

Let  $\sigma$  be any small length of the screw which is in contact with an equal length of the groove. Let  $R\sigma$  be the normal reaction between these small arcs,  $\mu R\sigma$  the friction.

In some screws the ridge is rectangular, so that it may be regarded as generated by the motion of a small rectangle moving round the cylinder with one side in contact with the surface

$\alpha$ . In other screws the section of the ridge has some other form, such, for example, as a triangle. In such cases the line of action of  $R$  makes some angle  $\theta$  with the tangent plane to the cylinder. We therefore resolve  $R$  into two components, one intersecting at right angles the axis of the cylinder and the other lying in the tangent plane. The magnitude of the latter is  $R \cos \theta$ , and its direction makes with the axis of the cylinder an angle equal to  $\alpha$ . Since the ridge is uniform the angle  $\theta$  will be the same throughout the length of the screw.

Let us suppose that the power  $P$  is about to prevail, then the friction acts so as to oppose the power. Resolving parallel to the axis of the cylinder and taking moments about it, we have

$$Q = \Sigma R \sigma \cdot \cos \theta \cos \alpha - \Sigma R \sigma \cdot \mu \sin \alpha,$$

$$P a = \Sigma R \sigma \cdot b \cos \theta \sin \alpha + \Sigma R \sigma \cdot \mu b \cos \alpha.$$

Dividing one of these equations by the other we have

$$\frac{Q}{P} = \frac{\cos \theta \cos \alpha - \mu \sin \alpha}{\cos \theta \cos \alpha + \mu \sin \alpha} \cdot \frac{a}{b}.$$

**551.** If it be possible to neglect the friction and treat the screw as smooth we put  $\mu = 0$ . We then find for the mechanical advantage the expression  $(a \cot \alpha)/b$ . If a point travelling along the ridge or thread of the screw make one complete revolution of the cylinder, it advances parallel to the axis a space equal to the distance  $h$  between the ridges. This distance is therefore  $h = 2\pi b \tan \alpha$ . Substituting for  $\tan \alpha$ , we find that the mechanical advantage of a smooth screw is  $c/h$ , where  $c$  is the circumference described by the power and  $h$  is the distance between two successive threads of the screw measured parallel to the axis.

**552.** We may easily deduce the relation between the power and the weight in a smooth screw from the principle of virtual work. When the power has turned the handle  $AC$  through a complete circle, the screw and the attached weight have advanced a space  $h$  equal to the distance between two threads of the screw measured parallel to the axis. When therefore friction is neglected and no work is otherwise lost in the machine, we have  $Pc = Qh$ , where  $c$  is the circumference of the circle described by  $P$ .

When the friction between the ridge and the groove is taken account of we see by Art. 550 that the efficiency of the machine is given by  $\frac{Qh}{Pc} = \frac{\cos \theta - \mu \tan \alpha}{\cos \theta + \mu \cot \alpha}$ .

When the thread of the screw is rectangular the angle  $\theta$  is zero. In that case the expression for the efficiency takes the simple form  $\frac{Qh}{Pc} = \frac{\tan \alpha}{\tan (\alpha + \epsilon)}$ , where  $\epsilon$  is the angle of friction.

If the weight  $Q$  is about to prevail over the power, we change the signs of  $\mu$  and  $\epsilon$  in these formulæ.

**553.** Ex. 1. What force applied at the end of an arm 18 inches long will produce a pressure of 1000 lbs. upon the head of a smooth screw when 11 turns cause the head to advance two-thirds of an inch? [Trin. Coll., 1884.]

Ex. 2. A screw with a rectangular thread passes into a fixed nut: show that no force applied to the end of the screw in the direction of its length will cause it to turn in the nut, if the pitch of the screw is not greater than  $\epsilon$ , where  $\epsilon$  is the angle of friction. [Coll. Exam., 1878.]

Ex. 3. A rough screw has a rectangular thread: prove that the least amount of work will be lost through friction when the pitch of the screw is  $\frac{1}{4}(\pi - 2\epsilon)$ , where  $\epsilon$  is the angle of friction. [St John's Coll., 1889.]

Ex. 4. The vertical distance between two successive threads of a screw is  $h$ , its radius is  $b$ , and the power acts perpendicularly to an arm  $a$ . If the thread be square and of small section, and the friction of the thread only be taken into account, show that if  $a$  and  $h$  are given, the efficiency of the machine is a maximum when  $2\pi b = h \tan (\frac{1}{4}\pi + \frac{1}{2}\epsilon)$ ,  $\epsilon$  being the limiting angle of friction. [Math. Tripos, 1867.]

Ex. 5. The axis  $AB$  of a screw is fixed in space and the beam  $EF$  through which the cylinder passes is moveable. The power  $P$ , acting at the end of a lever  $CD$ , tends to turn the cylinder, while a force  $Q$ , acting on  $EF$  parallel to the axis  $AB$ , tends to prevent motion. Show that the relation between  $P$  and  $Q$  is the same as that given in Art. 550.

Ex. 6. A weight is supported on a rough vertical screw with a rectangular thread without the application of any power. If  $l$  be the length and  $b$  the radius of the cylinder on which the thread lies, show that the screw has at least  $\frac{l \cot \epsilon}{2\pi b}$  turns.

# NOTE ON SOME THEOREMS IN CONICS REQUIRED IN ARTS. 126, 127.

THE following analytical proof of the two theorems in conics which are assumed in these articles requires a knowledge only of such elementary equations as those of the normal or of the chord joining two points.

Let  $\phi, \phi'$  be the eccentric angles of two points  $P, Q$  on the conic. Taking the principal axes of the curve as the axes of coordinates, the equations of the normals at these points are

$$\frac{a\xi}{\cos \phi} - \frac{b\eta}{\sin \phi} = a^2 - b^2, \quad \frac{a\xi}{\cos \phi'} - \frac{b\eta}{\sin \phi'} = a^2 - b^2.$$

The ordinate  $\eta$  of their intersection is therefore given by

$$\frac{b\eta}{a^2 - b^2} = -\frac{\sin \frac{1}{2}(\phi + \phi')}{\cos \frac{1}{2}(\phi - \phi')} \sin \phi \sin \phi' \dots\dots\dots (1).$$

The ordinate of the middle point of the chord  $PQ$  is

$$\begin{aligned} \bar{y} &= \frac{1}{2}b(\sin \phi + \sin \phi') = b \sin \frac{1}{2}(\phi + \phi') \cos \frac{1}{2}(\phi - \phi'), \\ \therefore \frac{b^2}{a^2 - b^2} \frac{\eta}{\bar{y}} &= \frac{-\sin \phi \sin \phi'}{\cos^2 \frac{1}{2}(\phi - \phi')} = \frac{\cos^2 \frac{1}{2}(\phi + \phi')}{\cos^2 \frac{1}{2}(\phi - \phi')} - 1 \dots\dots\dots (2). \end{aligned}$$

Again, the equation to the chord  $PQ$  is

$$\frac{x}{a} \cos \frac{1}{2}(\phi + \phi') + \frac{y}{b} \sin \frac{1}{2}(\phi + \phi') - \cos \frac{1}{2}(\phi - \phi') = 0 \dots\dots\dots (3).$$

If  $p, p'$  and  $q$  are the perpendiculars on the chord from the foci and the centre, we have the usual formula for the length of a perpendicular

$$\frac{pp'}{q^2} = \frac{\{\cos \frac{1}{2}(\phi - \phi') - e \cos \frac{1}{2}(\phi + \phi')\} \{\cos \frac{1}{2}(\phi - \phi') + e \cos \frac{1}{2}(\phi + \phi')\}}{\cos^2 \frac{1}{2}(\phi - \phi')}.$$

It follows by an easy reduction that

$$\left(\frac{\eta}{\bar{y}} - 1\right) \frac{b^2}{a^2} = -\frac{pp'}{q^2} \dots\dots\dots (4).$$

It is explained in the text that the corresponding form for  $\xi$  is an inconvenient one because the foci on the minor axis are imaginary. If the chord cut the axes in  $L$  and  $M$ , we find, from the equation to the chord  $PQ$  given above, that

$$\frac{CL}{a} = \frac{\cos \frac{1}{2}(\phi - \phi')}{\cos \frac{1}{2}(\phi + \phi')}, \quad \frac{CM}{b} = \frac{\cos \frac{1}{2}(\phi - \phi')}{\sin \frac{1}{2}(\phi + \phi')}.$$

Whence immediately from (2)

When the points  $P, Q$  coincide,  $\xi, \eta$  become the coordinates of the centre of curvature at  $P$ . We then deduce from (1) the well-known formulæ

$$-\frac{b\eta}{a^2-b^2} = \sin^3 \phi, \quad \frac{a\xi}{a^2-b^2} = \cos^3 \phi \dots\dots\dots (7).$$

The coordinates  $\bar{x}, \bar{y}$  of the middle point  $G$  of the chord being given, the chord itself is determinate. The equation to the chord is

$$\frac{(\xi - \bar{x})\bar{x}}{a^2} + \frac{(\eta - \bar{y})\bar{y}}{b^2} = 0.$$

We then readily find the intercepts  $CL, CM$ . We deduce from (2) or (5)

$$\left\{ \frac{b^2}{a^2-b^2} \frac{\eta}{\bar{y}} + 1 \right\} \left\{ \frac{\bar{x}^2}{a^2} + \frac{\bar{y}^2}{b^2} \right\}^2 = \frac{\bar{x}^2}{a^2} \left\{ -\frac{a^2}{a^2-b^2} \frac{\xi}{\bar{x}} + 1 \right\} \left\{ \frac{\bar{x}^2}{a^2} + \frac{\bar{y}^2}{b^2} \right\}^2 = \frac{\bar{y}^2}{b^2} \dots\dots\dots (8).$$

Let  $X, Y$  be the coordinates of the intersection  $T$  of the tangents at  $P, Q$ , then

$$\frac{X}{\bar{x}} = \frac{Y}{\bar{y}}, \quad \frac{\bar{x}X}{a^2} + \frac{\bar{y}Y}{b^2} = 1,$$

because  $G$  is the intersection of the straight line joining the origin to  $T$  with the polar line of  $T$ . We easily find  $\bar{x}, \bar{y}$  in terms of  $X, Y$ , and the equations (7) then become

$$\frac{\eta}{\bar{Y}} = \frac{(a^2-b^2)(X^2-a^2)}{a^2Y^2+b^2X^2}, \quad \frac{\xi}{\bar{X}} = -\frac{(a^2-b^2)(Y^2-b^2)}{a^2Y^2+b^2X^2} \dots\dots\dots (9),$$

which are the equations used in Art. 127.

Ex. 1. A uniform rod, whose ends are constrained to remain on a smooth elliptic wire, is in equilibrium under the action of a centre of force situated in the line of the axis of the ellipse, and varying as the distance, see Art. 51. Show that the centre of gravity  $G$  must be either in one of the axes or at a distance from the centre equal to  $CR/(a^2+b^2)^{\frac{1}{2}}$ , where  $CR$  is the semi-diameter drawn through  $G$ . Show that in the latter case half the length of the rod is equal to  $CD^2/(a^2+b^2)^{\frac{1}{2}}$ , where  $CD$  is the semi-conjugate to  $CR$ . Show also that the tangents at the extremities of the rod are at right angles. Find the lengths of the shortest and longest rods which could be in equilibrium.

Ex. 2. One extremity of a string is tied to the middle point of a rod whose other extremities are constrained to lie on a smooth elliptic wire. If the string is pulled in a direction perpendicular to the rod, show that there cannot be equilibrium unless the rod is parallel to an axis of the curve.

Ex. 3. When the conic is a parabola, show that the equations (5), (8), (9) take the simpler forms,

$$\eta = 2\bar{y} \cdot \frac{AR}{m} = \frac{2\bar{y}}{m} \left( \bar{x} - \frac{\bar{y}^2}{m} \right) = -\frac{2}{m} XY, \\ \xi = 2\bar{x} - AR + m = \bar{x} + \frac{\bar{y}^2}{m} + m = -X + \frac{2Y^2}{m} + m,$$

Ex. 5. Two chords of a conic are drawn parallel to any two conjugate diameters and touch a given confocal. Show that the sum of their lengths is constant.

Ex. 6. If the normals at four points  $P, Q, R, S$  meet in a point whose coordinates are  $(\xi, \eta)$ , prove that the middle points of the six chords which join points  $P, Q, R, S$  two and two lie on the conic

$$(a^2 - b^2)(a^2y^2 - b^2x^2) + a^2b^2(\xi x + \eta y) = 0.$$

This follows at once from (8).

Ex. 7. A heavy uniform rod is in equilibrium with both ends pressing against the interior surface of a smooth ellipsoidal bowl. If one axis of the bowl is vertical show that the rod must lie in one of the principal planes.

The ellipsoid being referred to its axes, the normals at the extremities of the rod are  $\frac{a^2}{x}(\xi - x) = \frac{b^2}{y}(\eta - y) = \frac{c^2}{z}(\zeta - z)$ ,  $\frac{a^2}{x'}(\xi - x') = \frac{b^2}{y'}(\eta - y') = \frac{c^2}{z'}(\zeta - z')$ .

It is necessary for equilibrium that each of these should be satisfied by  $\eta = \frac{1}{2}(y + \zeta) = \frac{1}{2}(z + z')$ . Substituting, we find that  $y'/y = z'/z$ , unless either both the  $y$ 's or both the  $z$ 's are zero. Putting  $y' = \rho y$ ,  $z' = \rho z$ , the equations become

$$\frac{2a^2}{x}(\xi - x) = b^2(\rho - 1) = c^2(\rho - 1), \quad \frac{2a^2}{x'}(\xi - x') = b^2\frac{1 - \rho}{\rho} = c^2\frac{1 - \rho}{\rho}.$$

Unless  $b^2 = c^2$ , these give  $\rho = 1$ . It easily follows that  $y' = y$ ,  $z' = z$ ,  $x' = x$  so that the two ends of the rod coincide. As this is impossible, we must have either both  $y$ 's or both the  $z$ 's equal to zero. The rod must therefore be in a principal plane.

END OF VOLUME I

# INDEX

*The numbers refer to the articles*

- AMONTONS. Experiments on friction, 170.
- ANCHOR RING. Surface and volume, 415. Centre of gravity of a portion, 425.  
Anchor ring slides on an axis, 269.
- ANTICENTRE. Defined, 460. Of a circle and ellipse, &c., 460.
- ARCHIMEDES. Parallelogram of forces founded on the lever, 31.  
Relation of sphere to the circumscribing cylinder, 420.
- AREAL COORDINATES. Defined, 53, Ex. 2. Trilinear equation of the resultant of any three forces acting along the sides of the triangle, 120. Central axis in terms of the moments about and resolutes along the sides, 278, Ex. 8.
- ASTATICS. Equilibrium defined, 70. Astatic triangle, 71, 73. Centre defined, 72, 160. Central point of two forces, 74. Of any forces in a plane, 160.
- ATOMS. Equilibrium of four repelling atoms, 130.  
Kelvin on the theory of Boscovich, 226. Two, three and four atoms in various arrangements, 227.
- AXIOMS. Newton's laws of motion, 13. Elementary statical axioms, 18. Other axioms necessary, 148. Frictional axiom, 164. Axiom on elasticity, 489.
- AXIS. See also CENTRAL AXIS. Of a couple, 97.  
Friction between wheel and axis, 179.  
Instantaneous axis always exists when a body moves in a plane, 180.  
Axis of initial motion, 185, 188, &c.  
Pressure on axis reduced to two forces, 268.  
Axis of revolution and Pappus' theorems, 413.
- BALANCE. Three requisites of the common balance, 519. False balances and other problems, 520. Roberval's balance, used to weigh letters, 517.
- BALL, SIR ROBERT. The cylindroid, 287. Reciprocal screws, 294. The sexiant, 326.  
The pitch conic, 288.
- BALL, W. W. R. History of mathematics. Parallelogram of forces, 31. Catenary, 443 note.
- BENDING COUPLE. Defined, 142. Of a plank bridge, 144. Of a rod acted on by forces shown graphically, 145. Heavy rod, 147, Ex. 1. Rotating wire, 147, Ex. 2. Crane, 147, Ex. 5. Gipsy tripod, 147, Ex. 6. Rod under centre of force, 147, Ex. 7. Townsend's theorem on a bridge, 147, Ex. 3. Found by graphics, 362.
- BERNOULLI. Discovers the catenary, 443. On the form of a sail, 458. String acted on by a centre of force, 475.
- BESANT. On roulettes, 244.
- BONNET. The catenary of equal strength for a central force which varies as the inverse distance, with a list of curves included, 477, Ex. 11.
- BOOLE. Envelope of an equilibrium locus, 224.
- BOSCOVICH. Theory of atoms, 226.
- BOW. System of lettering reciprocal figures, 340.



- CATENARY. *Centre of gravity of arc*, with a geometrical construction, 399, 445.  
*The suspended chain*, 443. Examples, 446. The parameter of a suspended catenary found, 447, 448. Catenary with a heavy ring fixed or moveable. Examples on smooth pegs, festoons, endless strings, &c., 448.  
*Stability of equilibrium* of a chain over two smooth pegs, 449.  
*Heterogeneous catenary*, 450. The cycloidal chain, 451. Parabolic when roadway is light, 452. Catenary of equal strength, equation, centre of gravity, span, &c., 453.  
*Examples*. Chain partly in water, partly in air, 456. Heavy string over rough catenary, 469, 471. A heavy string fits a tube without pressure. To cut find the pressure, 462. A heavy endless string hangs round a horizontal cylinder, 462. The catenary is the only homogeneous curve such that the centre of gravity is vertically over the intersection of the tangents, 448, 451.  
*Stability of a heavy rod sliding on two catenaries*, 243.  
*Spherical catenary*, 482. See STRINGS.  
*Calculus of variations*, 488.
- CAYLEY. The six coordinates of a line, 260. On four forces in equilibrium. Determinant of involution, 324.
- CENTRAL AXIS, defined and found in terms of  $R$ ,  $G$ , 270. Cartesian equation in terms of the six components, 273.  
 Central axis of forces  $A_1A_1'$ ;  $A_2A_2'$ ; &c., 278, Exx. 6, 7. Central axis in trilinear coordinates, 278, Ex. 8. Central axis of forces represented by the sides of a tetrahedron, 278, Ex. 5. Central axis in tetrahedral coordinates in terms of forces along the edges, 339. Central axis of conjugate forces, 285, 309. Problems on central axis, 278, 283, 310.
- CENTRE OF GRAVITY. Definition, 51, 374. Unique point, 375. Working rule, 380; with examples, 382. Triangular area, 383; equivalent points, perimeter, 386. Quadrilateral, 387; pentagonal area, trapezium, 388. Tetrahedron, 389; frustum, 391; faces and edges, 392; isosceles tetrahedron, double tetrahedra, 394. Pyramid and Cone, 390, 418.

Circular arc, 396, &c., other arcs and the curve  $r^n \sin n\theta = a^n$ , 399. Circular sectors, 400; quadrant, 401; segment, 402. Elliptic areas, 404; areas, 409, 412. Space bounded by four coaxials, 406; by four confocal

Pappus' theorems, 413, &c., with extensions when axis does not lie in the plane of the curve, 417.

Spherical surfaces, 420; hemisphere, segment, 423. Spherical triangles, 424. Spherical solid sector, segment, 426, 427. Ellipsoidal sectors, &c., 429. Ellipsoidal thin shells, both kinds, 430; also shell when the density varies as the inverse cube of the distance from a point, 430, &c.

Any volume and surface, 431. The solid  $\left(\frac{x}{a}\right)^n + \left(\frac{y}{b}\right)^n + \left(\frac{z}{c}\right)^n = 1$ . Octant of an ellipsoid when density is  $x^l y^m z^n$ , 434. Triangle of density, 434.

- CHASLES. Radius of curvature of a roulette, 242.  
 Invariants of two systems of forces, 280.  
 Characteristic of a plane, 314.  
 Four forces in equilibrium, 316.
- CIRCLE. Least force to move a hoop, disc, &c. placed on a rough plane, 189.
- CLARKE. Principles of Graphic statics, 340 note.
- CLAUSIUS. Virial, 157.
- CLEBSCH. Expresses the form of a heavy string on a sphere in elliptic in  
 482 note.
- COMPONENT. Defined, 40. In three dimensions, 257, 260.  
 The six components of a system of forces, 273, 276.
- CONE. Centre of gravity of volume, 390; of surface, 418; of cone on elliptic base  
 Cone of friction, 173.  
 Couple to turn a cone in a hole, 189, Ex. 12.
- CONIC. The relations of a chord to the normals at its extremities, 126 and 127.  
 Conic of closest contact, position found, 249.  
 Centre of inscribed and circumscribing conic, 440.  
 The pitch conic, 288.
- CONJUGATE FORCES AND LINES. A system can be reduced to two forces, one  
 action arbitrary, 303; other elements arbitrary, 313. Self-conjugate  
 306. Conjugate of a given line found, 308.  
 Arrangement of conjugate forces round the central axis, 309; arrangement  
 hyperboloids, 310; in planes, 311.  
 Theorems on conjugates, 312, 313. Two systems of forces with common  
 conjugate lines, 311.
- CONSERVATIVE SYSTEM. Definition and fundamental theorem, 211. See also 212.
- COORDINATES. Of a system defined, 206, 207.  
 The six coordinates of a line, 260.  
 Areal coordinates, 53. Tetrahedral coordinates, 339.
- COUPLE. Poinso't's theory of couples, 89, &c. Measure of couple, 96; and of  
 Laws of combination of forces and couples, 101. Tetrahedron of couples,  
 99. Any four axes being given, couples in equilibrium can be found  
 Forces represented by skew polygon are equivalent to a couple, 99.  
 Friction couple, 167. Least couple which can turn a table on  
 floor; a cone in a rough circular hole; and other problems, 188, 189.  
 Minimum couple of a system of forces, 277.
- CORIOLIS. Invents the catenary of equal strength, after Gilbert, 453.
- COULOMB. Experiments on friction, 170.
- CREMONA. The polar plane of a system of forces, 298. Double lines, 306.  
 Reciprocal figures, 342.
- CROFTON. On self-strained frames of six joints, 238.
- CULMANN. Graphical statics, 340. Method of sections, 366.
- CURTIS. Problem on two spheres in a paraboloid, 129.

n. The polygon of maximum area, 133.  
 On Lagrange's proof of virtual velocities, 256.  
 On the use of Jacobians in integration, 411.  
 e. Framework defined, 231.  
 c. Of a catenary, 443. Statical directrix of a heavy string on a smooth  
 ve, 460. Other cases, 482, 494, 500.  
 NES. Defined by Cremona, 306. See NUL LINES.  
 Proof of the parallelogram of forces, 27.  
 Defined by Plücker, 261. Relation to a wrench, 271.  
 raphical statics, 340.  
 y. Of a machine defined, 504. If a force  $P$  raise and  $P'$  support a  
 ght, the efficiency is  $(P + P')/2P$ , 505.  
 TRINGS. Hooke's law, 489. Heavy string (a) free, (b) on an inclined  
 ne, 492.  
 Work of stretching, 493. Various problems, 492, 493.  
 Heavy string on a smooth curve, tension, pressure, &c., 494. Light  
 ng on a rough curve, 495. See ENDLESS STRINGS. Various problems, 495.  
 General equations, 496.  
 Heavy string on various surfaces, 497.  
 String under central force, 498, 499.  
 Elastic catenary, equations, 500, geometrical properties, 501, Ex. 2.  
 See CONIC. Centre of gravity of sector, segment, &c., 405; of the space  
 nded by co-axials, 406; confocals, 412; of the space between ellipse and  
 tangents, 406.  
 Equilibrium of a rod in an ellipse, 126, 243.  
 s. Centres of gravity of the two kinds of thin shells, 430. Centre of  
 vity when the density varies as the cube of the distance from a point,  
 Centre of gravity of an octant, density  $x^l y^m z^n$ , 434.  
 Resultant of normal forces to an octant, 319.  
 TRINGS. Slipping of a band which works two wheels, 466, Ex. 5. Maxi-  
 m tension when string is slightly extensible, 495, Ex. 5. Festoons, 466,  
 10.  
 Strings which *just fit* a curve, 472. Examples of a circle, catenary,  
 oid, ellipse, &c., 473.  
 Twisted cords, 495, Ex. 3.  
 Slipping of cords round pegs, &c., 495, Ex. 4, &c.  
 m. Of a particle, 45. Of a rigid body in two dimensions, 109. In three  
 ensions, 259; problems on, 268.  
 Conditions deduced from the principle of work, 203. Altitude of the  
 re of gravity a max-min, 218. Stability defined, 70, 75; of three forces,  
 221; conditions of stability, 214, 220; of rocking stones, 244, &c.  
 Critical equilibrium, 246.  
 On the sufficiency of the six conditions, i.e.  $m$  moments and  $n$  resolutions  
 g zero, 331.  
 Condition of equilibrium found by Graphics, 353.  
 Condition that six wrenches of given pitches on six given axes can be

R. Quadrilateral of jointed rods, not acted on by external forces, tightened by strings, 132.

Relation between corners, faces and edges in a polyhedron, 351.

Form of the teeth of wheels, 545.

G. Experiments on friction, 170.

FORCES. Two straight lines can be drawn to cut five forces in equilibrium, 320. Invariant, Central axis, &c., 323. Given the five lines of action, to find the forces, 323, &c.

MINING JENKIN. Practical use of reciprocal figures, 340.

E. Its characteristics, 5. Represented by a straight line, 7. How measured, 10, 16. Superposition, 15.

$n$  forces act along the generators of a hyperboloid, 316, 317.  $n$  forces intersect two straight lines, 320, 323. Forces represented by the sides of a skew polygon are equivalent to a couple, 103.

ES AT A POINT. Resultant, 42, 44, 46. Conditions of equilibrium, 45, 49. A force moved parallel to itself, 100.

FORCES. Their relations to (a) a skew quadrilateral, 103, 323; (b) a hyperboloid, 316; (c) a tetrahedron, 40, 318. Geometrical proofs, 316; analytical, 317.

Conditions of equilibrium of four forces acting at a point, 40. Rankine's theorem on four parallel forces in equilibrium, 86.

Four forces acting along tangents to a conic, 120, Ex. 5, 317, Ex. 4.

The invariants, 316, 317, 323.

Given the lines of action, to find the forces, 316, 317.

. Problem on the most stable position of the feet, 88.

IER. Proof of the principle of virtual work, 193.

NETWORK. Defined, 150. The number of rods necessary to stiffen a framework, 151. The reactions are determinate in a simply stiff framework, 153. The same deduced from the principle of work, 232; in an over stiff framework, indeterminate, 155, 235. Problems on hexagons, tetrahedra, polygons, &c., 234. Self-strained frameworks, 132, 238.

Reactions found by graphical methods, 363. Problems on graphical statics, 372.

KLIN. Extension of Lagrange's two theorems on centres of gravity, 438.

FRICION. Defined, 54; experiments, 164, 166; laws, 165; limiting friction, 165.

Coefficient and angle of friction, 166. Friction couple, 167. Cone, 173.

The two kinds of problems, 171, 181. Problems of the first kind, 176, 178, &c. The ladder, 177, 178. Tripos and College problems, 178. Wheel and axle, 179, &c. The indeterminateness of friction, 181. Limiting equilibrium, 182.

Problems of the second kind, 182, &c. The least couple or force which can move a triangular table, a rod, a lamina, a hoop, a disc, a cone in a hole and other bodies, 188, 189.

Two connected particles, 190: a string of  $n$  particles arranged in a circular

GILBERT. Invents the catenary of equal strength, 443, 453.  
 GIULIO. Centre of gravity of a spherical triangle, 424 ; also of a solid generated by a catenary, 424.

GOODWIN, HARVEY. Stability of a rod inside a spheroid, 126, 243.

GRAHAM. Graphic and Analytic statics, 340.

GREENHILL AND DEWAR. Construct a model of an algebraic spherical catenary, 482.

GREGORY. Solves the problem of the catenary, 443.

GULDIN. Centre of gravity of  $2n$  sides of a regular polygon, 397. Centre of gravity of the area of a right cone, 418.

Guldin's or Pappus' theorems on surfaces of revolution, 413.

HOOKE. Law on elastic strings, 489.

HYPERBOLA. Relation of the theory of projection to the hyperbola, 408.

HYPERBOLOID. Forces act along the generators, pitch, single resultant, central axis, &c., 317.

Locus of principal force of a given system, 277.

Locus of conjugate forces, 310.

INCLINED PLANE. Smooth, 537 ; rough, 538 ; problems, 539.

INDETERMINATE. Problems so called, if the elementary laws of statics are insufficient for their solution, 148. Additional laws derived from the elasticity of bodies, 148. Examples of such problems, weight on a table, the gallows problem, bars suspended by several strings, framework, &c., 149.

The reactions of a framework are not or are indeterminate according as it is simply or over stiff, 153, 155, 235.

Indeterminate tensions, 237, 368. Indeterminate friction, 181.

Indeterminate multipliers, 213.

Indeterminate reciprocal figures, 351.

INDEPENDENCE OF FORCES. Principle explained, 15.

INERTNESS OF MATTER. Explained, 14.

INFINITE FORCES. 154, 198, 306.

INITIAL MOTION. Of a body when acted on by a couple, 102.

Of a system is such that the initial work is positive, 200 ; and that the potential energy decreases, 216.

INVARIANTS. The two invariants defined, 279.

Meaning of the vanishing, 279.

Charles' invariants of two systems of forces, 280.

Rules to find the invariants of two forces, any number of forces, of couples, of wrenches, 281, 282.

Invariant of forces acting along  $n$  generators of a hyperboloid, 317. Of forces intersecting two directors, 323. Invariant of any forces along the edges of a tetrahedron, 339.

INVOLUTION. Forces in involution defined, 325.

Forces along the edges of a tetrahedron are not in involution, 339.

JACOBIAN. The Jacobian condition of equilibrium of a particle on a curve, 59.

Applied to centre of gravity of an area, 411.

- Proof of the principle of virtual work, 255.
- Two theorems on centre of gravity, 436, 437.
- AGE. Proof of the parallelogram of forces, 31.
- OR. Astatic equilibrium in two dimensions, 162. Critical equilibrium, 246.
- OF MOTION. Newton's, 13.
- NITZ. Theorem on the mean centre, 51. Solves the problem of the catenary, 443.
- ISCATE. Centre of gravity of the arc  $AP$  lies in the bisector of the angle  $AOP$ , 399. The locus of the centre of gravity of an arc of given length, 399. The centre of gravity of half the area of either loop, 412, string, 477.
- R. Three kinds, 511. Conditions of equilibrium, 507, pressure, 508.
- What is gained in power is lost in speed, 513.
- Examples from animal economy, 515.
- . *Statique Graphique*, on the reactions of frameworks, 150. His definitions, 231. Theorem on indeterminate tensions of a framework, 236, 368. Graphical statics, 340. Theorems on the force polygon, 357.
- ING. Friction, 165, equilibrium, 182.
- . Elementary statics, 41.
- INE. Mechanical advantage defined, 502; lever, 512; pulley, 527, 532, &c.; inclined plane, 537; wheel and axle, 540; wedge, 547; screw, 550.
- . The two systems of equal areas and of similarity, 421.
- VELL. On stiff jointed frameworks, 150, 151.
- Friction locus of a particle, 189.
- If  $R$  be the thrust of a rod in a framework,  $r$  its length,  $\sum Rr$  found in terms of the forces, 230.
- Theorem on reciprocal figures, 341, &c.
- CENTRE. See also CENTRE OF GRAVITY. Use of, in resolving and compounding forces which meet at a point, 51. Also other forces, 120.
- E. Application of centre of gravity to pure geometry, 439.
- NUM. Minimum method of solving friction problems, 185.
- The work is a max-min in equilibrium, 212.
- Altitude of centre of gravity a max-min, 218.
- Minimum couple of forces in three dimensions, 277.
- Minimum couples and forces to move a body, 188, 189. Minimum force at one end to move (a) a string of particles, 190, and (b) a heavy string in a circular arc on a rough floor, 487.
- IVS. The polyhedron of couples, 99.
- The nul plane, 298.
- Four forces in equilibrium lie on a hyperboloid, 316.
- Five forces intersect two directors, 320.
- Six forces in equilibrium, 324.
- ENT. Moment of a force defined in two dimensions, 113, in three dimensions, 263.
- Proved equal to  $dW/d\theta$  where  $W$  is the work, 209.
- Moment of a line in geometry, 265. Represented by the volume of a tetrahedron, 266. By a determinant, 266, 267. In tetrahedral coordinates,

MORIN. Experiments on friction, 170.

NEWTON. Laws of motion, 13. Proof of the parallelogram of forces, 25.

NORMAL FORCES. To a polygon, 133; to a tetrahedron, 318; to a polyhedron, to a closed surface, 319; to an octant of an ellipsoid, 319.

NUL. Nul plane defined, 298. Its Cartesian equation, 301. Its tetrahedral equation, 339. Theorems on the nul plane, 304.

The Cartesian condition that a given line is a nul line, 301. Nul plane of a given plane found geometrically and analytically, 302.

OBLIQUE. Resolution of forces, 40. Axes, 50.

PAPPUS. The surface and volume of a solid of revolution deduced from a centre of gravity sometimes called Guldin's theorems, 413.

PARABOLA. Centre of gravity of areas, bounded by an ordinate, 412; bounded by four parabolas, 412, &c.

Parabolic chain, tension, centre of gravity, &c., 452.

PARALLEL FORCES. Centre of parallel forces, 83, 373. Conditions of equilibrium,

A given force replaced by two parallel forces, 79; by three forces, 86.

Rankine on the equilibrium of four parallel forces, 86.

Theory of couples, 89.

PARALLELEPIPED OF FORCES. Theorem, 39.

PARALLELOGRAM. The parallelogram law, 7. Of velocities, 12. Of forces, 24.

PENTAGON. Centre of gravity of a homogeneous pentagon, 388, Ex. 5.

PITCH. Defined, 271. Pitch of an equivalent wrench found, 273.

PLÜCKER. The six coordinates of a line, 260. A dynamine, 261.

A proof of Moebius' theorem, 316.

POINSON. Theory of couples, 89.

Why some problems are indeterminate, 148.

Method of finding resultants, 104, 257.

Central axis, 270.

POLAR PLANE. Cremona's polar plane defined, 298.

Sylvester's defined, 325. Various theorems, 336, &c.

POTENTIAL. Defined, 59. Potential energy, 211. Decreases in initial motion,

POLYGON. The polygon of forces, 36. Forces at the corners, 37. Forces perpendicular to the sides, 37. Forces wholly represented by the sides in a couple, 103, Ex. 6. Forces proportional to the sides at an angle dividing the sides in a given ratio, 103, Ex. 9. Forces which join the corners of two positions of the same polygon, 120, Ex. 6.

Polygon of heavy rods, 134. Subsidiary polygon, 139.

On the number of conditions necessary to determine a polygon, 152.

POLYHEDRON. Polyhedron of forces, 47, 318.

Euler's relation between the number of corners, faces and edges, 351.

Reciprocal polyhedra, 341, 351.

Centre of gravity of polyhedron circumscribing a sphere, 392, Ex. 5.

PRATT. Treatise on Mechanical Philosophy, 502.

Analytical aspect of projections, 407.

PYRAMID. Centre of gravity of the volume, 390.

The five equivalent points of a pyramid on a quadrilateral base, 395.

QUADRILATERAL. Jointed with attracting particles at the corners, 130. With various strings, 132.

Centre of gravity when uniform, 387, 388. When heterogeneous, 434.

Some geometrical theorems deduced from statics, 439, 441.

Forces along the sides of a *skew* quadrilateral are not in equilibrium, for a couple or single resultant, 103. Their invariant, 323.

RANKINE. Equilibrium of four parallel forces, 86.

Force diagram, 140.

Moment of flexure or bending stress, 142.

Graphical statics, 340.

REACTIONS. Three rules (1) when two smooth rods press, 125; (2) when two rods are jointed, (a) line of symmetry, (b) one rod not acted on by a force, 132; (c) when more than two rods meet at the same point, 132; (3) when two rods are rigidly connected the reaction is a force and a couple, 142, 143.

Jointed quadrilaterals tightened up by various strings, 132.

Jointed polygons acted on by normal forces, 133. Reactions at the joints of a polygon of heavy rods, 134. Various problems on reactions at joints, 141.

Bending moment, 142. Weight on a light plank bridge, 144. Diagram of stress for a rod acted on by forces at isolated points, 145. Weight on heavy bridge, 147, Ex. 1. Bending moment for a rotating semicircular wire, 147, Ex. 2. Townsend's problem on a bridge, 147, &c.

Principle of work used to find reactions at the joints of a hexagon, tetrahedron, rhombus, tripods, &c., 234.

Reactions in three dimensions, at an axis, pressures, joints, &c., 268.

Reactions found by graphics, 361, 363, &c.

$n$  spheres in a cylinder, 129.

RECIPROCAL FIGURES. Defined, 340. Maxwell's theorem, 341; Cremona's, 342. To draw reciprocal figures, 343, 350. Mechanical property, 346.

RESOLUTE. Defined, 41. Equal to  $dW/ds$  where  $W$  is the work, 209.

RESOLUTION. Defined, 40. Resolved part or resolute, 41.

Three methods of oblique resolution, 40.

Use of the mean centre, 51.

Resolution in three dimensions, 260.

Along three lines by a tetrahedron, 53, Ex. 3.

Along six lines in space, 329.

Graphical method, 360.

RESULTANT. Resultant force defined, 22. Forces in a straight line, 23; at a point, 42.

Method of the mean centre, 51. With an extension, 53, Ex. 4.

Parallel forces, 78, 80.

Single resultant in two dimensions, 118. A trilinear equation, 120.

Resultant force and couple in three dimensions, 257. Single resultant, 257.



REYNOLDS, OSBORNE. Experiments on friction, 170.

RIGID BODY. Defined, 19. Rigidity of cords, 531.

ROBERTS, R. A. Theorem on the centre of gravity of the arc of a lemniscate, 3.

ROBERVAL. Method of finding envelopes, 242.

Balance, 517.

ROCKING BODIES. Condition of stability, 244.

Hollow bodies with fluid, 245.

Second approximations, 247, 249.

In three dimensions, 251.

ROD. Heavy rod in a bowl and cylinder, 125. In a spheroid, 126, 243. Two support an ellipse, 127. Jointed light rods forming quadrilaterals polygons, 131—133. Jointed heavy rods, 134. Friction problems, 178.

Bending couple due to a weight, 142, 144, &c.

Various problems, 141, 149. Stability, 221, &c.

Rod on rough wall in three dimensions, 269.

Pressure on supports of a rod found by graphics, 361. Stress at point, 362.

SAIL. Can a boat sail quicker than the wind? 53, Ex. 10. Form of a sail act by the wind and its best position, 458.

SALMON. The relation between the inclinations of any four lines in space, 48.

A leading theorem on determinants quoted, 49.

On roulettes, 244.

On the six coordinates of a line, 260.

Generalization of a theorem on the relations of a chord of a conic two normals, 126 and note.

SCOTT, R. F. Treatise on determinants, 267.

SCREWS. See also WRENCH. Pitch defined, 271. Right and left handed, 272.

Work of a wrench on a screw, 292.

Reciprocal screws, 294.

As a machine defined, 550. Mechanical advantage, 550. Various theorems, 551.

SHEAR. Defined, 142.

SIX FORCES. Analytical view, 324. Geometrical view, 334.

Two methods of describing the sixth line ( $a$ ) as a plane locus, ( $b$ ) nul line of two fixed forces, 334.

Only one way in general of reducing a system to six forces along straight lines, 329.

The case of involution, 328.

On the ratio of  $P_5$  to  $P_6$  and other theorems, 336. See also EQUILIBRIUM.

On six forces along the edges of a tetrahedron, 339. See also TETRAHEDRON.

SMITH, R. H. On graphics quoted, 364.

SMOOTH BODY. Defined, 54. Reactions, 55.

SPOTTISWOODE. The determinant of involution, 327.

STABILITY. Defined 70-75. Of two forces, 76. Of three forces, 77-221. Of four forces, 222-223. Of five forces, 224-225. Of six forces, 226-227. Of seven forces, 228-229. Of eight forces, 230-231. Of nine forces, 232-233. Of ten forces, 234-235. Of eleven forces, 236-237. Of twelve forces, 238-239. Of thirteen forces, 240-241. Of fourteen forces, 242-243. Of fifteen forces, 244-245. Of sixteen forces, 246-247. Of seventeen forces, 248-249. Of eighteen forces, 250-251. Of nineteen forces, 252-253. Of twenty forces, 254-255. Of twenty-one forces, 256-257. Of twenty-two forces, 258-259. Of twenty-three forces, 260-261. Of twenty-four forces, 262-263. Of twenty-five forces, 264-265. Of twenty-six forces, 266-267. Of twenty-seven forces, 268-269. Of twenty-eight forces, 270-271. Of twenty-nine forces, 272-273. Of thirty forces, 274-275. Of thirty-one forces, 276-277. Of thirty-two forces, 278-279. Of thirty-three forces, 280-281. Of thirty-four forces, 282-283. Of thirty-five forces, 284-285. Of thirty-six forces, 286-287. Of thirty-seven forces, 288-289. Of thirty-eight forces, 290-291. Of thirty-nine forces, 292-293. Of forty forces, 294-295. Of forty-one forces, 296-297. Of forty-two forces, 298-299. Of forty-three forces, 300-301. Of forty-four forces, 302-303. Of forty-five forces, 304-305. Of forty-six forces, 306-307. Of forty-seven forces, 308-309. Of forty-eight forces, 310-311. Of forty-nine forces, 312-313. Of fifty forces, 314-315. Of fifty-one forces, 316-317. Of fifty-two forces, 318-319. Of fifty-three forces, 320-321. Of fifty-four forces, 322-323. Of fifty-five forces, 324-325. Of fifty-six forces, 326-327. Of fifty-seven forces, 328-329. Of fifty-eight forces, 330-331. Of fifty-nine forces, 332-333. Of sixty forces, 334-335. Of sixty-one forces, 336-337. Of sixty-two forces, 338-339. Of sixty-three forces, 340-341. Of sixty-four forces, 342-343. Of sixty-five forces, 344-345. Of sixty-six forces, 346-347. Of sixty-seven forces, 348-349. Of sixty-eight forces, 350-351. Of sixty-nine forces, 352-353. Of seventy forces, 354-355. Of seventy-one forces, 356-357. Of seventy-two forces, 358-359. Of seventy-three forces, 360-361. Of seventy-four forces, 362-363. Of seventy-five forces, 364-365. Of seventy-six forces, 366-367. Of seventy-seven forces, 368-369. Of seventy-eight forces, 370-371. Of seventy-nine forces, 372-373. Of eighty forces, 374-375. Of eighty-one forces, 376-377. Of eighty-two forces, 378-379. Of eighty-three forces, 380-381. Of eighty-four forces, 382-383. Of eighty-five forces, 384-385. Of eighty-six forces, 386-387. Of eighty-seven forces, 388-389. Of eighty-eight forces, 390-391. Of eighty-nine forces, 392-393. Of ninety forces, 394-395. Of ninety-one forces, 396-397. Of ninety-two forces, 398-399. Of ninety-three forces, 400-401. Of ninety-four forces, 402-403. Of ninety-five forces, 404-405. Of ninety-six forces, 406-407. Of ninety-seven forces, 408-409. Of ninety-eight forces, 410-411. Of ninety-nine forces, 412-413. Of one hundred forces, 414-415.

STATICS. Defined as one case of mechanics, 1. As the science of force, 21.

STEELYARD. (a) Roman, 521, (b) Danish, 522. Comparison of a steelyard and balance, 523. Problems on steelyards, 524.

STEREOGRAPHIC PROJECTION. On the principle of similitude in Maps, 421.

STEVINUS. Enunciates the triangle of forces, 31.

STRESS. Defined, 142. See BENDING COUPLE.

STRING. See CATENARY, ELASTIC STRINGS, ENDLESS STRINGS.

Tension of a light string unaltered by passing over a smooth surface, 1.

*Intrinsic equations* of equilibrium, 454. Cartesian form, 455. Polar, 456.

*Constrained by a curve*, four cases, (a) string light, curve smooth, 457.

(b) string heavy, curve smooth, 459, (c) string light, curve rough, 460.

(d) string heavy, curve rough, 467, &c.

String with normal forces, 458.

The statical directrix, 460. Heavy string on a circle with hanging end and a catenary, 462.

Methods of integration in case (d), 468, 469.

Rope wound round thin rough posts and pegs, 466.

*One centre of force*, 474, 476. Force when the curve is a circle, Ex. 2, the curve  $r^n = a^n \cos n\theta$ , Ex. 3; infinite strings, Ex. 4, &c.; force the inverse square, Ex. 6; catenary of equal strength when the force varies as the inverse distance, Ex. 11; dynamic curves, Ex. 12.

*Two centres of force*, 477. The lemniscate, Ex. 2.

*Constrained by a surface*. General equation, 478. Geodesic strings, 480. Inflectional points, 480.

Solid of revolution, 481.

Spherical catenary form, tension, pressure, 482. Case of one end free case when directrix plane passes through the centre of the sphere, &c., 483. Instability, 482.

Cylindrical surface, if smooth and vertical the string when developed is catenary, 483; if rough, Ex. 3. Examples on a horizontal cylinder, 483.

Conical surface with centre of force at the vertex, 484.

*Rough surfaces*, general equation, 485. Geodesics, 485. Helix, 487.

*Minimum force* to move a circular heavy string on a rough horizontal plane, 487.

*Calculus of variations*. A string (a) suspended from two points, (b) on surface under any forces, 488.

SUPERPOSITION OF FORCES. A principle of statics, 15.

SURFACE. Particle on a smooth surface in equilibrium, 57. On a rough surface, 17. Resultant of normal forces, 319.

SUSPENSION. Of a heavy body, with examples on triangles, rods, cones, &c., 87.

Of a polygon of heavy rods, 134.

Of a heavy string, 447.

SUSPENSION BRIDGE. See CATENARY. When the main chain alone is heavy, 443.

When the roadway alone is heavy, 452.

When the vertical rods are heavy, 452. Other problems, 452.

SURFACE. On the equilibrium of six forces, 324. The determinant of involu-

TENDENCY TO BREAK. Defined, **142**, see BENDING COUPLE.

TENSION. Of a rod defined, **142**; of a string, **442**. See FRAMEWORKS AND STRING.

A bundle of heavy horizontal cylinders tied by a string, **129**, Ex. 7.

TETRAHEDRON. Used in two ways to resolve forces ( $a$ ) by sines of angles, **40**, ( $b$ ) the mean centre of the base, **53**, Ex. 3.

Volume found, **266**; used to measure moments, **266**, **267**.

Any six forces along edges are not in involution, **339**.

Central axis of the forces represented by the six sides, **278**.

Forces referred to tetrahedral coordinates, **267**, **339**.

Relation of four forces ( $a$ ) acting at the corners perpendicularly to opposite faces, ( $b$ ) at the centres of gravity of the faces, ( $c$ ) at middle points of the edges, **318**.

Centre of gravity of the volume, **389**; frustum, **391**; double tetrahedron, **394**; faces and edges, **392**; heterogeneous, **434**.

The isosceles tetrahedron, **393**.

Geometrical theorems deduced from the centre of gravity, **439**.

THOMSON AND TAIT, see KELVIN. Proof of the principle of virtual work, **199**.

THREE FORCES, see TRIANGLE. A system reduced to three forces acting at corners of an arbitrary triangle, ( $a$ ) in two dimensions, **120**, ( $b$ ) in three dimensions, **315**.

Parallel forces reduced to three, **86**.

THRUSTS. Defined, **364**, see FRAMEWORKS.

TIES. Defined, **364**, see FRAMEWORKS.

TOOTHED WHEELS. Small teeth, **544**. Involute of a circle, **545**; effect of rotating the wheels, **545**. Epicycloidal teeth, **545**. Problems, locking teeth, &c., **546**.

TOWNSEND. Bending moment of a bridge with a carriage of finite size, **147**.

Relation between the equilibrium of a string and the free motion of a particle, **476**.

TRANSMISSIBILITY OF FORCE. A principle of statics, **17**.

TRANSON. Radius of curvature of a roulette, **242**.

TRAPEZIUM. Centre of gravity of the area, **388**.

TRIANGLE. Triangle of forces, **32**, &c.; theorems, **103**; astatic triangle, **73**.

A heavy triangle suspended by strings and in other ways, **87**.

A system of forces reduced to three along the sides of an arbitrary triangle, **120**. A system in three dimensions reduced to forces at corners, **315**.

The least couple to move a triangular table on a rough floor, **188**.

Centre of gravity of area, **383**; various equivalent points, **385**; perimeters, **386**; heterogeneous density  $x^l y^m z^n$ , **434**.

Geometrical property of the product of the alternate segments of a circle on the sides, **132**. Centre of the nine points circle and the orthocentre of a triangle by centre of gravity, **440**.

TWO FORCES, see CONJUGATE FORCES. A system reduced to two forces ( $a$ ) in

- WALLIS. Centre of gravity of a circular arc, 396. Circular sector, 400. Cycloidal area, 412.
- WALTON. Centre of gravity of a spherical triangle, 424. Of the space between a parabola and two tangents, 412. Of the lemniscate, 399.
- WARREN GIRDER. Problem on, 372.
- WATSON. Problems of the reactions of the legs of a table supporting a weight, 149. On a case of neutral equilibrium, 88.
- WEDGE. Defined, 547; mechanical advantage, 548. Condition that a wedge stays in when struck, 549.
- WHEEL AND AXLE. Mechanical advantage, 540; differential axle, 541. Problems on the wheel and axle, 542.  
Friction between wheel and axle, 179.  
Work required to turn the wheel when the string is elastic, 493, Ex. 2.
- WHITE. A system of pulleys invented to diminish friction, &c., 530.
- WILLIS. His principles of mechanism, 502. On the form of toothed wheels, 545.
- WORK. Defined, 62; equilibrium of a particle, 66; rings on elliptic wires, &c., 69. Proof of the general principle, after Fourier, 194, 195. The converse after Thomson and Tait, 199. Work of forces equal to that of resultants, 194. List of forces which do not appear, 196.  
Work of a bent elastic string, 197, 493.  
Method of using the principle, 202, examples, semicircle, rods, &c., 205.  
Work function defined, 208; stability deduced, 214; application to frameworks, 229.  
Lagrange's proof of virtual velocities, 255.
- WRENCH. Defined, 271. See CENTRAL AXIS.  
Equivalent wrench (*a*) when *R* and *G* are given, 270, (*b*) when system is given by its six components, 273, (*c*) when the system is two wrenches, 285, (*d*) when the system is two forces, 284.  
Method of compounding wrenches by the cylindroid, 287.  
Problems on wrenches, 278.  
The work of a wrench, 292.  
Condition of equilibrium of six wrenches, the sexiant, 326.  
Used by Cremona for reciprocity, 342.
- YOUNG. Modulus of elastic strings, 490.